



Nagpur Metro Rail Project Trust

# DETAILED PROJECT REPORT FOR NAGPUR METRO RAIL PROJECT



Prepared By:



दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड  
DELHI METRO RAIL CORPORATION LTD.

NOVEMBER 2013

# CONTENTS



	<b>SALENT FEATURE</b>	1-11
	<b>EXECUTIVE SUMMARY</b>	LXXXIX
CHAPTER 1	INTRODUCTION	1-16
CHAPTER 2	TRAFFIC DEMAND FORECAST	1-22
CHAPTER 3	SYSTEM SELECTION	1-29
CHAPTER 4	GEOMETRIC DESIGNING PARAMETERS & ALIGNMENT DESCRIPTION	1-33
CHAPTER 5	CIVIL ENGINEERING	1-56
CHAPTER 6	STATION PLANNING	1-68
CHAPTER 7	TRAIN OPERATION PLAN	1-75
CHAPTER 8	ROLLING STOCK	1-83
CHAPTER 9	POWER SUPPLY, SYSTEM OF TRACTION AND POWER TARIFF	1-83
CHAPTER 10	MAINTENANCE DEPOTS	1-29
CHAPTER 11	SECURITY SYSTEM	1-6
CHAPTER 12	TELECOMMUNICATIONS & AUTOMATIC FARE COLLECTION	1-16
CHAPTER 13	DISABLED FRIENDLY FEATURES	1-23
CHAPTER 14	ENVIRONMENTAL IMPACT ASSESSMENT	1-32
CHAPTER 15	SAFETY MEASURES FOR A METRO SYSTEM	1-5
CHAPTER 16	DISASTER MANAGEMENT PLAN FOR A METRO RAIL SYSTEM	1-7
CHAPTER 17	MULTI-MODAL TRANSPORT INTEGRATION	1-7
CHAPTER 18	COST ESTIMATES	1-12
CHAPTER 19	FINANCING OPTIONS, FARE STRUCTURE AND FINANCIAL VIABILITY	1-13
CHAPTER 20	ECONOMIC APPRAISAL	1-18
CHAPTER 21	IMPLEMENTATION STRATEGY	1-18
CHAPTER 22	CONCLUSION	1-4

## SALIENT FEATURE



1. GAGE
2. DESIGN SPEED
3. ROUTE LENGTH
4. NUMBER OF STATIONS
5. TRAFFIC FORECAST - RIDERSHIP
6. TRAIN OPERATION
7. TRACTION POWER SUPPLY
8. ROLLING STOCK
9. MAINTENANCE FACILITIES
10. SIGNALING, TELECOMMUNICATION & TRAIN CONTROL
11. FARE COLLECTION
12. CONSTRUCTION METHODOLOGY
13. PROJECT COST
14. FINANCIAL INDEXES



### SALIENT FEATURES

1. GAUGE (STANDARD) - 1435 mm
2. MAX. PERMISSIBLE SPEED - 80kmph
3. ROUTE LENGTH (END TO END OF STATION)

Description	Elevated (km)	At Grade (km)	Total (km)
Line 1 - North-South Corridor: Automotive Square to MBAN	15.558	4.520	19.658
Line 2 - East West Corridor: Pragathi Nagar to Lokmanya Nagar	18.557	000	18.557
<b>Total</b>	<b>33.815</b>	<b>4.520</b>	<b>38.215</b>

#### 4. NUMBER OF STATIONS

Description	Elevated	At grade
Line 1 - North-South Corridor: Automotive Square to MBAN	10	2
Line 2 - East West Corridor: Pragathi Nagar to Lokmanya Nagar	10	0
<b>Total</b>	<b>14</b>	<b>2</b>

**E. TRAFFIC FORECAST - RIDERSHIP**

BOARDING/RIDERSHIP (DAY)	2016	2021	2026	2031	2036	2041
ON LINE 1(AUTOMOTIVE-KHAPRO)	168361	185531	203720	224318	245419	277734
ON LINE 2(PRAJAPATI-LOKMANYA)	104881	137908	215415	234577	263257	298631
<b>TOTAL OF BOTH</b>	<b>273242</b>	<b>323439</b>	<b>419135</b>	<b>458895</b>	<b>508676</b>	<b>607365</b>
AVERAGE TRIP LENGTH IN KM	6.418	6.453	6.484	6.533	6.521	6.522
MAXIMUM PHDPT ON LINE 1	10089	10936	11815	12934	14286	16729
MAXIMUM PHDPT ON LINE 2	1748	3460	9104	3500	10748	11882

**E. TRAIN OPERATION****A) TRAIN FREQUENCY****Line 1: North - South Corridor**

Sections	2016		2021		2026		2031		2036		2041	
	Peak Hour P/W	Lean Hour P/W	Peak Hour S/W	Lean Hour S/W	Peak Hour P/W	Lean Hour P/W	Peak Hour S/W	Lean Hour S/W	Peak Hour P/W	Lean Hour P/W	Peak Hour S/W	Lean Hour S/W
Automotive Bore to Congress Nagar Station	8 min	10 to 30 min	3 min	8 to 20 min	4, 5, 6 min	9 to 23 min	4 min	8 to 20 min	3, 3 min	5 to 15 min	3 min	5 to 15 min
Congress Nagar to Khajri Station Section	12 min	20 to 60 min	10 min	15 to 40 min	8 min	12 to 40 min	8 min	12 to 40 min	7 min	10 to 30 min	6 min	10 to 30 min

Line 2: East-West Corridor

Sections	2016		2021		2026		2031		2036		2041	
	Peak Hour %/w	Lean Hour %/w	Peak Hour %/w	Lean Hour %/w	Peak Hour %/w	Lean Hour %/w	Peak Hour %/w	Lean Hour %/w	Peak Hour %/w	Lean Hour %/w	Peak Hour %/w	Lean Hour %/w
Prayagraj Nagar to Agrasen Chowk Section	13 min	20 to 30 min	12 min	20 to 30 min	10 min	16 to 42 min	8 min	12 to 40 min	8 min	12 to 40 min	7 min	10 to 33 min
Agrasen Chowk to Subhash Nagar Section	4.5 min	10 to 20 min	4 min	10 to 20 min	5 min	9 to 23 min	4.5 min	6 to 20 min	4 min	6 to 20 min	3.5 min	5 to 15 min
Subhash Nagar to Ushermanya Nagar Section	13 min	20 to 30 min	12 min	20 to 30 min	10 min	16 to 43 min	8 min	12 to 40 min	8 min	12 to 40 min	7 min	10 to 33 min

**B) RAKE REQUIREMENT**

Corridor	Year	No. of Rakes	Rake Config	No. of Cars
North - South Corridor	2016	11	3 car	33
	2021	12	3 car	36
	2031	16	3 car	51
	2041	20	3 car	60
East - West Corridor	2016	12	3 car	36
	2021	13	3 car	39
	2031	17	3 car	51
	2041	20	3 car	60

**7. TRACTION POWER SUPPLY**

- |                       |                                    |
|-----------------------|------------------------------------|
| a) Voltage            | 25 KV AC                           |
| b) Current Collection | Overhead Current Collection System |
| c) SCADA system       | Provided                           |



**POWER DEMAND (MVA)**  
Power Demand Estimation (MVA)

Corridor		Year			
		2016	2021	2031	2041
North-South Corridor – 1 Automotive Sgri to Depot Station. (21,833 kms : 18 elevated Stations & 1 LIG Station)	Traction	4.32	5.21	5.84	7.10
	Auxiliary	7.72	7.84	8.14	11.43
	Total	12.04	12.85	14.98	18.53
East West Corridor – 2 Pragathi Nagar to Lokmanya Nagar (18,266 kms : 19 Elevated Stations)	Traction	4.24	4.57	5.23	7.01
	Auxiliary	8.34	8.46	9.08	12.45
	Total	12.58	13.03	15.31	19.46

## 8. ROLLING STOCK

### i. Coach Size

Particular	Length*	Width	Height
Driving Motor Car (DMC)	21.84 m	2.8 m	3.9 m
Trailer Car (TC)/Motor Car (MC)	21.34 m	2.8 m	3.5 m

\*Maximum length of coach over couplers/buffers: 22.8 m  
(depending upon Kinematic Envelope)

- Train Composition: 3- Car train: DMC+TC+ DMC
- Seating Arrangement: Longitudinal
- Passenger Carrying Capacity (Coach @ 8 persons/m<sup>2</sup>)

PARTICULAR	SEATED	STANDING	TOTAL
DMC	43	304	347
TC/MC	50	230	279
S.CAR	130	628	754



v. Axle load	16T
vi. Max Acceleration	1.0 m/s <sup>2</sup>
vii. Max Deceleration	1.0 m/s <sup>2</sup> (Normal Brake) > 1.3 m/s <sup>2</sup> (Emergency Brake)
viii. Maximum Design Speed	80 kmph
ix. Maximum Operating Speed	80 kmph
x. Schedule Speed (as per train operator in following limits)	
a. Corridor I : North-South Corridor	33-34 kmph
b. Corridor II : East-West Corridor	30 kmph

## 9. MAINTENANCE FACILITIES

Depot cum workshop near Khajuri Station (MKDC Land) and near Lokmanya Nagar Station (SRP Land)

## 10. SIGNALLING, TELECOMMUNICATION & TRAIN CONTROL

- a) Type of Signaling : Cab signaling and continuous automatic train control with Automatic Train Protection (ATP)
- b) Telecommunication :  
 i) Integrated System with Fibre optic cable, SCADA, Train Radio, PA system etc.  
 ii) Train information system, Control telephones and Centralised Deck System.

## 11. FARE COLLECTION

Automatic Fare collection system with PGM and Smart card etc.

## 12. CONSTRUCTION METHODOLOGY

- i. Viaduct : Pre-stressed concrete 'Box' shaped Diers/Double U-Diers on Single pier with pile / Open foundations.





### 13. PROJECT COST Total Estimated/Completion Cost

(Rs. Crore)

Corridor No	Name of Corridor	Distance (KM)	Estimated Cost without Central taxes at June-2012 Price Level	Estimated Cost with Central taxes at June-2012 Price Level	Completion Cost
I	North-South Corridor	10.028	3013.00	3,425.00	8600
II	East-West Corridor	18.557	2954.88	3,427.00	
Total		28.585	5967.88	6852.00	

### 14. FINANCIAL INDICES

- I. FRR: (Cost with central taxes) 19.35 %
- II. CRR: 17.75 %

# EXECUTIVE SUMMARY



0.1	INTRODUCTION
0.2	TRAFFIC DEMAND
0.3	SYSTEM SELECTION
0.4	GEOMETRIC DESIGN NORMS
0.5	ENV. ENGINEERING
0.6	STATION PLANNING
0.7	TRAIN OPERATION PLAN
0.8	ROLLING STOCK
0.9	POWER SUPPLY, SYSTEM OF TRACTION AND POWER TARIFF
0.10	MAINTENANCE DEPOT
0.11	SIGNALING SYSTEM
0.12	TELECOMMUNICATION & AUTOMATIC FARE COLLECTION
0.13	ROADSIDE FRIENDLY FEATURES
0.14	ENVIRONMENTAL IMPACT ASSESSMENT
0.15	SAFETY MEASURES FOR A METRO RAIL SYSTEM
0.16	DISASTER MANAGEMENT PLAN FOR A METRO RAIL SYSTEM
0.17	MULTI-MODAL TRANSPORT INTEGRATION
0.18	COST ESTIMATES
0.19	FINANCIAL OPTIONS, FARE STRUCTURE AND FINANCIAL VIABILITY
0.20	ECONOMIC ANALYSIS
0.21	IMPLEMENTATION STRATEGY AND PROJECT IMPLEMENTATION
0.22	CONCLUSION AND RECOMMENDATIONS

## TABLES

TABLE 0.1A	ALIGNMENTS PROPOSED BY S&B/C
TABLE 0.1B	FINAL ALIGNMENTS
TABLE 0.2	SUMMARY OUTPUT - TRAFFIC
TABLE 0.3	DESIGNER'S INPUT PARAMETERS
TABLE 0.4	SUMMARY OF TRACK CONFIG. - ALL CORRIDOR
TABLE 0.5	SUMMARY OF TRACK CONFIG. - ON CORRIDOR
TABLE 0.6	SEC. FILE INFORMATION DETAILS - ALL CORRIDOR
TABLE 0.7	OPEN POINTS TRACK DETAILS - ON CORRIDOR
TABLE 0.8	SEC. FILE INFORMATION DETAILS - ON CORRIDOR
TABLE 0.9	OPEN POINTS TRACK DETAILS - ON CORRIDOR
TABLE 0.10	SUMMARY OF TRACKS UNDER LAKE REQUIREMENT
TABLE 0.11A	ON CORRIDOR EQUIPMENT OF SYSTEM WITH CHARACTERISTIC AND OPERATIONAL & PLATFORM CHARACTERISTICS
TABLE 0.11B	ON CORRIDOR EQUIPMENT OF SYSTEM WITH CHARACTERISTIC AND OPERATIONAL & PLATFORM CHARACTERISTICS FOR
TABLE 0.12	ENTRY CAPACITY PROVIDED
TABLE 0.13	YEAR WISE RAIL REQUIREMENT
TABLE 0.14	SIZE OF THE CLASH
TABLE 0.15	CARRYING CAPACITY OF PROPOSED RAIL TUNNELS
TABLE 0.16	PROPOSED STATION CONFIGURATION (PVA)
TABLE 0.17	DETAILS OF SIGNALING SYSTEM
TABLE 0.18	TECHNOLOGIES PROPOSED FOR TELECOMMUNICATION SYSTEMS
TABLE 0.19	TECHNOLOGIES PROPOSED FOR AFC SYSTEMS
TABLE 0.20	PROFILES LIST
TABLE 0.21	FORMING PATTERNS UNDER PVA MODES
TABLE 0.22	SIGNALING PATTERN UNDER RAIL MODES (WITH CENTRAL TOWER)
TABLE 0.23	YEAR WISE INVESTMENT WITH CENTRAL TOWER
TABLE 0.24	ROBUST EMPLOYMENT DATA UNDER PVA

## FIGURES

FIG. 0.1	EXT PLAN OF RAILWAY NETWORK
----------	-----------------------------



## EXECUTIVE SUMMARY

### 2.1 INTRODUCTION

#### 2.1.1 General

**Nagpur** is the third largest city of Maharashtra and also the winter capital of the state. With a population of approximately 20 lakhs, Nagpur Metropolitan Area is the 12th largest urban conglomerate in India. It has also recently been ranked as the cleanest city and the second greenest city of India. In addition to being the seat of annual winter session of Maharashtra state assembly "Vidhan Sabha", Nagpur is also a major commercial and political center of the Vidarbha region. It is also known as "Orange City" for being a major trade center of oranges that are cultivated in the region.

Nagpur lies precisely at the center of the country with the Zero Mile Marker indicating the geographical center of India. The city was founded by the Gondas but later became part of the Maratha Empire under the Shindeas. The British East India Company took over Nagpur in the 18th century and made it the capital of the Central Provinces and Berar. After the first reorganisation of states, the city lost its capital status but according to the informal "Nagpur Pact" between political leaders, it was made the second capital of Maharashtra. **Nagpur** is also declared, "Tiger Capital of India" as it contains many Tiger Reserves in India to the world.

Nagpur lies on the Deccan plateau of the Indian Peninsula and has a mean altitude of 310 meters above sea level. The underlying rock strata are covered with alluvial deposits resulting from the flood plain of the Kanhan River. In some places these give rise to granular sandy soil. In low lying areas which are poorly drained, the soil is alluvial clay with poor permeability characteristics. In the eastern part of city crystalline metamorphic rocks such as gneiss, schist and quartzites are found, while in the northern part yellowish sand stones and slates of the lower Gondwana formations are found.



Nagpur city is dotted with natural and man-made lakes with Ambazari lake being the largest. Other natural lakes include Borewade Lake and Taleghardi lake. Borewade lake and Taleghardi lake are man-made lakes created by the city's historical rulers. Nag river, Pili road along with holes form the natural drainage pattern for the city. Nagpur is known for its greenery, and was judged as the cleanest and second greenest in India. Recently, Government of India selected Nagpur as a Model City for National Clean Air Mission by allocating 25 cores for the plan. This project will be funded by Nagpur's own NEERI.

As it is located at centre of Indian peninsula far from the Bay of Bengal and the Arabian Sea, Nagpur has a tropical wet and dry climate with dry conditions prevailing for most of the year. It receives an annual rainfall of 1,288 mm (47.44 in) from monsoon rains during June to September. The highest recorded rainfall was 904 mm on 14 July 1984. Summers are extremely hot being from March to June, with maximum temperatures occurring in May. Winter lasts from November to January, during which temperatures can drop below 10 °C (50 °F). The highest ever recorded temperature in the city was 45°C, while the lowest was 2°C.

### 3.1.2 Study Area

In early 2012 Nagpur Improvement Trust (NIT) requested DMRC to provide Consultancy services for preparation of a Detailed Project Report for Metro Rail System in Nagpur, Maharashtra initially for 30 Km which was revised to 42 Km in July 2012. Thereafter, DMRC conducted Traffic Surveys, Topographical Surveys, Geotechnical Investigations and Environment Impact Assessment Survey.

The study area consisted of Nagpur Municipal Corporation Area. The study area totalled to approximately 217 sq km.

Based on the different types of surveys done by DMRC, main alignments were finalized after detailed inspection of the road network, intersections, passenger traffic flow, traffic congestion, connectivity to important and uses. Alignment of routes proposed by DMRC were as follows:

Table 3.1A: Alignments Proposed by DMRC (in July 2012)

Alignment (Proposed by DMRC)	Detail Route
<b>Alignment-1</b> North-South Corridor (24.833 Km, 17 stations)	Automotive Square, along Kamotee Road, Wardha Road, Vardoli Square to Ashyankar Road, along Nag River alignment will fall on Humpyare Road, Rohda Colony Road, Wadga Road, Khamb Road, Airport, MBHAN Area
<b>Alignment-2</b> East - West Corridor (18.286 Km, 15 stations)	From Prapatti Nagar, along Central Avenue Road, Railway Feeder Road, Mula Chok, Jhansi Rahis Chok, North Ambazari Road, Hingra Road, Laksharya Nagar



## FINAL ALIGNMENT FOR NAGPUR METRO

On 23.06.2013, a meeting presided by Shri S.K. Lohia, JS-MOUD,Govt was held at Nagpur to discuss the DPR. In that meeting, JS-MOUD,Govt expressed that the FIRR of the project should be of least 8%. Recently, MOUD has also issued advisory that FIRR of Metro Project should not be below 8%.

On 1.10.2013, a presentation on the DPR was made by MS NIT to The Chief Minister, Government of Maharashtra. He was of the opinion to avoid underground alignment in MHAN and also construct Maintenance Depot in the land belonging to State Govt Land. Subsequently, on 21.10.2013, a joint inspection of the NS corridor was done by VC&MD-MADC, Chairman,NIT, and Director Business Development,CMRC.

The original alignment of Corridor-I proposed was passing through Kharia Road, Airport Area after Sahakar Nagar and finally was ending at MHAN. The alignment up to Old Airport Station was elevated, then for a length of 3.26 km, it was underground with one underground station named as New Airport Station and again elevated in MHAN Area. Since the cost of underground section of the alignment is much more than the elevated section or the section at grade, alternative alignment was suggested for cost reduction, enhancement in FIRR and to increase FIRR so that project becomes financially and economically viable.

The new proposed alignment suggested in the above inspection, was to pass through a 24m wide road adjacent to London Street after Sahkar Nagar Junction and was proposed to be taken to the east along 24m wide road and London Street up to Wartha Road. From the intersection of Wartha road, the elevated alignment was proposed to be on the central divider on the Wartha Road. After crossing existing intersection point of Wartha Road & Airport Road, the alignment was to be shifted to the MHAN area. Alignment in this portion was proposed to be at grade and to run parallel to Wartha road upto RCB and existing railway line transfer up-to proposed Car Depot.

But, while working on the modification of alignment, it was noticed that a very large number of properties were falling along the alignment due to sharp curve at the junction of Sahkar Nagar & 24 m wide road and also at the junction of 24m wide road & Wartha Road. Acquiring of these properties will be very tough and may delay the whole project.

Hence to avoid all such situation, it has been decided to take the alignment on Wartha Road only without going on Kharia Road.

Finally, NS Corridor will pass through Wartha Road after Congress Nagar Metro Station. After crossing existing intersection point of Wartha Road & Airport Road, the alignment will be shifted to the MHAN area. Alignment in this portion will be at grade and will run parallel to Wartha road upto RCB and parallel to railway line transfer up-to proposed Car Depot. 14m wide stretch of land between the railway boundary line and the road near



proposed Container Depot of Container Corporation of India Ltd. will be affected by this proposed alignment of the Metro Rail as the proposed alignment passes through this stretch of land. 73 Ha land is available on the west side of railway line and south of existing flyover near Khasari station. Average width of this land is about 80m and is about 1800m long. This MADC land may be utilised for Car Depot. Similarly, Depot of EW Corridor has also been shifted to GRP Land near proposed Lokmanya Nagar Metro Station.

This has caused closure of few earlier proposed metro stations on N5 Corridor and addition of new stations on the same.

Final alignment for both the corridors is as below.

**Table 9.12**  
**FINAL ALIGNMENT**

Alignment	Detail Route
<b>Alignment-1</b> North-South Corridor (13.608 km, 17 Stations)	Automotive Square, along Kamappa Road, Wazha Road, Variety Square to Annyankar Road, along Nag River alignment will fall on Humpyard Road, Rohata Colony Road, Wazha Road, Parallel to Railway Line, Khasari Station and finally in MBHAN Area near concert depot.
<b>Alignment-2</b> East - West Corridor (18.507 km, 19 Stations)	From Pappal Nagar, along Central Avenue Road, Railway Poshar Road, Murja Chowk, Jhara Kharve Chowk, North Ambahar Road, Hingra Road, Lokmanya Nagar

## 9.2 TRAFFIC DEMAND

9.2.1 Traffic Study and Ridership estimation are the first tasks in DPR which imply finalising a feasible alignment plan of the proposed metro network and then locating normal and interchange metro stations (if any). After that, Ridership Estimation is done. Estimating daily and peak hour boarding and alighting from each station, daily trip load and PMPDT trip loads (all together is called Ridership Estimation) are estimated. These estimates are primary inputs to other important estimates such as station design, train operation plan, estimate of revenue collection, benefits of metro, riding time and many other estimates including EIRR and FIRR.

### 9.2.2 Station Loading (Daily and Peak)

Total daily boarding ridership in 2016 is estimated as 3.52 lakh in which share of line 1 as 41% and line 2 as 59%. Average trip length is 6.41km. The daily and peak station



loads of the Metro System comprises of the following lines, are described as under in Table 0.2.

**Table 0.2: Summary Output - Traffic**

BOARDING/RIDERSHIP (DAY)	2018	2021	2028	2031	2038	2041
ON LINE 1(AUTOMATIVE-KHAPRI)	166361	165531	203720	224316	248419	277704
ON LINE 2(PRAJAPATI-LOKMANYA)	164081	157936	215415	234577	262237	286091
<b>TOTAL OF BOTH</b>	<b>330442</b>	<b>323467</b>	<b>419135</b>	<b>458893</b>	<b>510656</b>	<b>563795</b>
AVERAGE TRIP LENGTH IN KM	5.419	5.453	5.454	5.533	5.521	5.522
MAXIMUM PHPOD ON LINE 1	13088	9036	11915	12934	14286	15728
MAXIMUM PHPOD ON LINE 2	7748	8400	3104	8000	10748	11882

## 6.3 SYSTEM SELECTION

The population growth in cities and urban centers has put a lot of pressure on the infrastructure of these cities. In rapidly developing countries like India the urban infrastructure is stretched to limit and requires very effective solutions. The rapid development in India is not unprecedented and such development earlier took place in several nations of Europe, America and in Japan. So several modes of urban mass transit are now available for solution to the problem of Urban Transit.

### 6.3.1 Benefits of Mass Transport System

The main benefits addressed by mass transport are the mobility and freedom. The sustainability of mass transport has greater potential and major benefits occur through immediate means of helping the environment and conserving energy. In developing countries, like India, benefit through mass transit systems extend to urban poor with affordable fare structure when compared with costs incurred by private transportation on fuel, parking, congestion etc. The supply of planned and integrated mass public transport is the only way to relieve traffic congestion and reduce hours of delay on major travel corridors. Moreover, supply of metro rail system in Nagpur will mean a lot in terms of sustainable mode of transport that meets the mobility and accessibility needs of people.

### 6.3.1 Feasibility of Metro System.

From the Traffic Demand Forecast it can be seen that peak hour peak direction trips (PHPDT) on the North-South Corridor is 16089, 16936, 12934 and 15729 the year of 2016, 2021, 2031 and 2041 respectively. Similarly PHPDT on East-West corridor in the year of 2016, 2021, 2031 and 2041 is 7746, 8493, 9906 and 11892 respectively.

Radial systems can optimally carry up to a maximum of 8,000 PHPDT. Since the PHPDT assumed on the above corridors exceed 8,000, there can be two options namely 1) Metro Rail and 2) Light Capacity Metro. Metro rail can carry the PHPDT projected but the technology is not a tested one. The operation and maintenance cost is much higher than Light Metro. The capital cost of Metro rail is also almost same as that of Light Metro with no experience of Metro rail in India. Even in the other countries, the Metro rail is being adopted only for small lengths and as feeder to Metro. Hence, keeping in view the above disadvantages, it is recommended to adopt an stable, tested and reliable Metro technology. However, for Nagpur it will be Light Capacity Metro System.

## 6.4 GEOMETRIC DESIGN NORMS

The geometrical design norms are based on international practices adopted for similar metro systems with standard gauge on the assumption that the maximum permissible speed on the sector is limited to 85 kmph. Planning for any higher speed is not desirable as the average interstation distance (37 stations in approx. 40 km) is about 1.10 km and trains will not be able to achieve higher speed.

### 6.4.1 GEOMETRIC DESIGN PARAMETERS

#### (i) Horizontal Curves

Table 6.1: Horizontal Curve Parameters

Description	Underground section	Elevated section
Desirable Minimum radius	300 m	300 m
Absolute minimum radius	200 m (only on)	120 m
Minimum curve radius at stations	1000 m	1000 m
Maximum permissible cant (Ca)	125 mm	125 mm
Maximum desirable cant	110 mm	110 mm
Maximum cant deficiency (Cd)	55 mm	55 mm

#### (ii) Transition Curves





- Length of Transition of Horizontal curves (m)
  - Minimum : 0.44 times actual (art) or cant deficiency (m.m), whichever is higher.
  - Desirable : 0.72 times actual cant or cant deficiency, (m.m), whichever is higher.
- Overlap between transition curves and vertical curves not allowed.
- Minimum straight between two Transition curves (in case of reverse curves): either 25 m or 6L.
- Minimum straight between two Transition curves (in case of same flexure curves): either 25 m or both curves should be converted in to the compound curve by introducing single transition between the two circles.
- Minimum curve length between two transition curves: 25 m.

#### ii) Gradients

Normally the stations shall be on level stretch. In limited cases, station may be on a grade of 0.1 %. Between stations, generally the grades may not be steeper than 3.0 %. However, where existing road gradients are steeper than 2 %, or for Switch Over Ramps gradient as to 4% (compensated) can be provided in short stretches on the main line.

#### iii) Vertical Curves

Vertical curves are to be provided when change in gradient exceeds 0.4%. However, it is recommended to provide vertical curves at every change of gradient.

#### iv) Radius of vertical curves:

- On main line (steep side) : 2500 m
- (Absolute minimum) : 1000 m
- Other Locations : 1500 m
- Minimum length of vertical curve : 30 m

## 6.4.2 Route Alignment

Two Corridors have been identified for implementation in phase I of Nagpur Metro Rail Project network as per details given as under:-

- Corridor I: North-South Corridor : Automotive Square to KHAMRI
- Corridor II: East West Corridor : Prapast Nagar to Lokmanya Nagar

### 6.4.2.1 North-South Corridor: Automotive Square to KHAMRI

This corridor originates from Automotive Square on Karmotee Road, move along Karmotee Road and reach the intersection point of Aravali Road and Varaha Road.



then after crossing Fly Over moves towards Munja Square, moves towards Chantol and along this moves towards Entola/D. Munja Mang, leads towards Congress Nagar T-Point, then on Rajada Colony Road and then falls on Wartha Road, leads towards NEERL, then moves along Wartha Road and then west of Railway Track in MHAN area. And passes through 14th wide stretch of land between the railway boundary line and the road near proposed Container Depot.

Entire length (19.658 Km.) of this corridor is proposed as elevated except in 4.6 Km at grade after Airport Station and in MHAN area near Khajuri Railway Station. There are 17 stations on this corridor of which 15 stations are elevated and 2 stations are at track. Suburb station is an Inter-change station.

#### 8.4.2.3 East West Corridor - Pratapnagar to Lokmanya Nagar

This corridor originates from Pratapnagar and runs westwards. Through Vashoodari Chowk, Ambodkar Chowk, Telephone Exchange, Dhillar Of Chowk, Agaram Chowk, Daxar Vahya Chowk, Nappur Railway Station, Sitabardi, Jhansi Ram Square, Institute of Engineers, Shamshir Nagar Square, Lid Chowk, Champath College, Subhash Nagar, Radha (Ring road Junction), Vasudev Nagar, Baral Nagar to Lokmanya Nagar. The entire corridor is elevated.

The total length of the corridor is 18.537 kilometer. There are 19 stations on this corridor. All stations are elevated stations and Sitabardi station is an Interchange Station.

### 6.5 CIVIL ENGINEERING

#### 6.5.1 Elevated Section - Choice of Superstructure

The choice of superstructure has to be made keeping in view the ease of constructability and the maximum standardization of the framework for a wide span ranges.

The segmental construction has been chosen mainly due to the following advantages:

- Segmental construction is an efficient and economical method for a large range of span lengths and types of structures. Structures with steep curves and variable super elevation can be easily accommodated.
- Segmental construction permits a reduction of construction time as segments may be manufactured while substructure work proceeds and assembled rapidly thereafter.
- Segmental construction protects the environment as only space required for foundation and sub-structure is required at site. The superstructure is manufactured at a place away from busy areas and placement of superstructure is done with the system erected from piers at heights.



- Segments are easy to stack in the casting yard/stacking yard in more than one layer, thereby saving in requirement of space.
- It is easier to transport smaller segments by road trailers on city roads.
- It is easy to incorporate last minute changes in span configuration if the site situation so warrants.
- Interference to the traffic during construction is significantly reduced.
- Segmental construction contributes towards aesthetically pleasing structures and good finishes.
- The overall labour requirement is less than that for conventional methods.
- Better quality control is possible in the casting yard.
- During construction, the technique shows an exceptionally high record of safety.

### 6.3.2 Types of Superstructures for Elevated Section

- Pre-cast segmental box girder using external unbounded tendon.
- Pre-cast segmental U-Channel Superstructure with internal pre-casting.

### 6.3.3 CONSTRUCTION METHODOLOGY

For the elevated sections it is recommended to have pre-cast segmental construction for super structure for the viaduct. For stations also the superstructure is generally of pre-cast members. The pre-cast construction will have following advantages-

- Reduction in construction period due to concurrent working for substructure and superstructure.
- For segmental, pre-cast element (of generally 3.0m length), transportation from construction depot to site is easy and economical.
- Minimum inconvenience is caused to the public utilizing the road as the superstructure launching is carried out through launching girder requiring narrow width of the road.
- As the pre-cast elements are cast on production line in a construction depot, very good quality can be ensured.
- The method is environment friendly as no concreting work is carried at site for the superstructure.

### 6.3.4 Utility Diversion

It is suggested that all utilities falling within excavation area are diverted away in advance to avoid damage to such utilities during the excavation/ construction phase. The cross utilities, however, has to be well supported. It is suggested that pressure water pipelines crossing the proposed cut area are provided with valves on both sides of the cut so that the cut area can be isolated in case of any leakage to the pipelines to avoid flooding of the cut/strange to the work.



## 2.2.2 Geo-Technical Investigations

### 2.2.2.1 Physiography

Nagpur is situated at 21° 05' N latitude and 79° 05' E longitude and a mean altitude of 310 meters above sea level. Being located far away from any major water body at the centre of the Indian peninsula, the Nagpur's climate is dry or mostly humid for most of the year except for the rainy season. The highest ever recorded temperature in the city was 45 °C, while the lowest was 3°C. The geology of the Nagpur region is famous for the metamorphic rocks, which occur in all the districts in the Nagpur region except Wardha and some part of Nagpur district. The other geological formation, Deccan Trap occur in the Wardha and North and North West part of Nagpur District.

### 2.2.2.2 Objective of Geotechnical Investigation

The main objectives of Geo-Technical Investigation Services are:

- To determine the required strength characteristics of the underlying soil/rock strata to design the foundation of the structure proposed to be constructed at various locations.
- To determine the subsurface profile of the underlying strata.
- To decide the construction methodology.

### 2.2.2.3 Details of Bore Holes

#### Investigation Works

Geotechnical investigation work at sites was carried out to determine the existing soil/rock strata, proposed type & depth of foundations and safe bearing capacity of foundations required for the proposed two Metro Corridors in Nagpur based on the results of 06 boreholes. #1 bore holes were driven in AUTOMOTIVE SQUARE TO MIPHAN alignment & 05 boreholes were driven in Laksharya Nagar to Pratap Nagar alignment. However, due to the site condition, depth of drilling work ranging from 10.00m to 20m was carried out at the proposed locations.

**Table 0.4**  
**SUMMARY OF BORE HOLES**  
**N.S.CORRIDOR**

Bore No.	Location Details	Total depth	Soil	Soft Rock	Hard Rock	Water Table (m)
1	Automotive Chowk	20.00	10.00	10.00	-	7.20
2	Go Gas Pump	10.00	6.00	10.00	-	7.10
3	Wally Automobiles	17.00	7.00	10.00	-	7.20
4	Lal garden Chowk	15.00	5.00	10.00	-	6.00
5	New India Hind School	10.00	6.00	10.00	-	6.00
6	Opal, Jawant Tail Mill	10.00	6.00	10.00	-	7.10



Sl. No.	Location Details	Total Depth	Soil	Soft Rock	Hard Rock	Water Table (m)
7	Bhakti Power Pump (10 No. Poles)	14.50	4.50	10.00	-	5.48
8	Kohli Chowk	14.50	4.50	10.00	-	5.15
9	Chandwani (Palacey Lane Near)	20.00	10.00	10.00	-	3.88
10	Saddi Goddara Chowk	12.00	2.00	10.00	-	4.22
11	L.I.C. Chowk, ANM Church Campus	11.00	1.00	10.00	-	4.48
12	R.R.I. Rank Chowk	12.00	2.00	10.00	-	4.98
13	Montrose College, T. Post	11.00	1.00	10.00	-	3.85
14	Dia Burn Police Station	14.50	4.50	10.00	-	5.08
15	Rax Furniture, Opp. Nanga Traders	16.00	6.00	10.00	-	4.71
16	Yashraj Stadium	17.00	7.00	10.00	-	4.88
17	Chandni P.S. Opp. Green City Hotel	17.50	7.50	10.00	-	5.18
18	Mathuram Arts M. Printers	15.00	5.00	10.00	-	3.20
19	Aska Towers	14.50	4.50	10.00	-	3.98
20	Hardwar Chowk	14.00	4.00	10.00	-	3.40
21	Central Jail	15.00	5.00	10.00	-	3.88
22	Clock Tower Rajiva Gandhi Chowk	11.50	1.50	10.00	-	3.25
23	Sardar Vallabhbhai Patel School	12.50	2.50	10.00	-	4.98
24	Bhakti Creations/Sanjay Traders	13.00	3.00	10.00	-	4.18
25	Gowankar Chowk	10.50	2.50	10.00	-	3.98
26	Khatwa Bus Stop	12.50	2.50	10.00	-	3.88
27	Baba Hardwani/Vijay Trading	12.00	3.00	10.00	-	3.08
28	Arun Rao Furniture Chowk (Pulver)	13.00	3.00	10.00	-	2.18
29	Rohit/Sereno Food Area (Airport)	14.00	4.00	10.00	-	2.98
30	Parking Airport	14.50	4.50	10.00	-	2.18
31	Airport Baudry	14.50	4.00	10.00	-	3.78

**Table 3.5**  
**SUMMARY OF BORE HOLES**  
**E-W CORRIDOR**

Sl. No.	Location Details	Total Depth	Soil	Soft Rock	Hard Rock	Water Table (m)
1	Asst. Engineering Unit	11.00	1.00	5.00	5.00	3.30
2	C.R.P.P. Jodhpur No. 1	11.00	1.00	5.00	4.00	4.30
3	Mahindra Company	11.50	1.50	5.00	4.00	4.30
4	Andou Salt Chowk (Near Dheeran Surtta)	11.00	1.00	10.00	-	4.05
5	Toll Tax Naka	11.00	1.00	10.00	-	4.25
6	Super Indico, Opp. Prakash Trading	11.50	1.50	10.00	-	5.30
7	Hingra T. Post	11.50	1.50	10.00	-	4.70
8	Nataraj Hotel	11.00	1.00	10.00	-	4.80
9	Pump House (C.C.R.P.P.) Nagpur	10.00	0.00	10.00	-	5.10
10	Subhash Nagar Chowk	12.00	2.00	10.00	1.00	4.20
11	Nagar Improvement Trust, Crazy Castle	13.00	3.00	10.00	-	4.40
12	Tanwar Hotel	12.50	2.50	10.00	-	3.40
13	Leela House (Near Janghon T. Post)	12.00	2.00	10.00	1.00	3.80
14	L.A.D. Chowk	13.00	3.00	10.00	-	5.10
15	Shankar Nagar Chowk	12.00	3.00	10.00	-	5.15
16	Aashan S.S. High School	12.00	2.00	10.00	-	5.10
17	Dharampeth Vidyoday	14.00	4.00	10.00	-	4.30
18	A.M.I.E. (Nagar Local Center)	14.00	4.00	10.00	-	5.30



Sr. No.	Location Details	Top Soils	Soil	Left Pile	Right Pile	Water Table (m)
19	M.J College	14.55	4.55	10.30	-	4.95
20	Jhansi Raj Chowk	14.00	4.00	10.30	-	5.95
21	Muni Chowk	14.00	4.00	10.30	-	5.70
22	Railway Push Box	14.50	4.50	10.30	-	4.00
23	Nagpur Corporation extra lane - 12	14.00	4.00	10.30	-	4.20
24	Harid soda major	14.00	4.00	10.30	-	5.30
25	Muni Hospital	12.00	2.00	10.30	-	3.95
26	Devi Sagar Chowk	13.00	3.00	10.30	-	4.20
27	Ganesh Bagh (Bus Stop)	12.00	2.00	10.30	-	4.20
28	Chitrakoot Chowk	13.20	3.20	10.30	-	4.20
29	Condoner Chowk	13.15	3.15	10.30	-	4.00
30	Rahala Hospital	14.50	4.50	10.30	-	4.75
31	Telephone Exchange	10.00	5.00	10.30	-	7.20
32	Chhapra Nagar Chowk, Bhawal Purkhur	10.00	5.00	10.30	-	5.30
33	Ambedkar Chowk	17.50	7.50	10.30	-	4.00
34	All Electrical, Varanasi Nagar Chowk	10.00	5.00	10.30	-	7.40
35	Near Mahasam Collection	18.50	8.50	10.30	-	6.40
36	Sapna Bar & Restaurant	17.00	7.00	10.30	-	4.30
37	Rishi Krishna Hospital Chowk	17.50	7.50	10.30	-	7.30
38	Das Wine Shop	21.00	11.00	10.30	-	7.00
39	Govt Hotel, Near P & B Bank	25.00	15.00	10.30	-	7.30

#### TYPE OF FOUNDATION - NORTH - SOUTH CORRIDOR

##### A : Bored Cast in situ RCC Pile

Depending on the field and laboratory observations of subsoil strata, test results and the type of structures proposed at site, the most feasible soil-foundation system is recommended as natural bored cast in situ R.C.C. pile foundations of 0.80m & 1.0m diameter at different depths with cut-off level at 1.50m to 2.0m depth below existing ground level. The safe test carrying capacities of these piles are given in following table.

Table B4 : RCC PILE DETAILS FOR NORTH - SOUTH CORRIDOR

Borehole Nos	Dia. of Pile	Cut-off level	Depth, m	Pile Capacity		
				Compression	Uplift	Lateral
1	0.80	1.30	19.00	180.0	50.0	9.0
	1.00	1.30	19.00	500.0	120.0	12.0
2, 3	0.80	1.30	11.00	170.0	40.0	9.0
	1.00	1.30	11.00	290.0	50.0	12.0
4, 5	0.80	1.30	10.50	170.0	40.0	9.0



7.5	1.00	1.50	10.00	230.0	50.0	12.0
	0.80	1.30	10.00	190.0	35.0	9.0
	1.00	1.50	10.00	225.0	45.0	12.0
9	0.80	1.50	15.00	220.0	65.0	9.0
	1.00	1.50	15.00	320.0	100.0	12.0
14	0.80	1.00	10.00	150.0	35.0	9.0
	1.00	1.00	10.00	225.0	45.0	12.0
15.16	0.80	1.20	11.00	170.0	40.0	9.0
	1.00	1.20	11.00	230.0	50.0	12.0
17	0.80	1.50	12.00	180.0	45.0	9.0
	1.00	1.50	12.00	260.0	55.0	12.0
18 to 21	0.80	1.00	10.00	150.0	35.0	9.0
	1.00	1.00	10.00	225.0	45.0	12.0
22 to 28	0.80	1.20	10.00	140.0	33.0	9.0
	1.00	1.20	10.00	210.0	40.0	12.0
29 to 32	0.80	1.20	10.00	130.0	30.0	9.0
	1.00	1.00	10.00	225.0	45.0	12.0

**B: Open square footing**

Depending on the field and laboratory observations of subsoil strata, test results and the type of structures proposed at site, the type of foundations, depths and net safe bearing capacities recommended for design purposes are given in the following table. The net SBC(RP) in the following table are the lower of the values obtained from shear failure criterion as per IS: 5433 and settlement failure criterion as per IS: 6000, Part 4.

**Table 6.7 : OPEN FOUNDATION DETAILS FOR - NORTH - SOUTH CORRIDOR**  
For Permissible settlement = 40.0 (mm)

Type of Foundation	Depth of Foundation (m)	Size of Foundation (m)	Net safe Bearing Capacity/ Allowable Pressure intensity (ton/m <sup>2</sup> )
<b>For Square Hole Size : 10 to 15, 22 &amp; 23 to 41 :</b>			
Square footing	1.00 to 3.0	3.0 to 6.0	20.00

**Note:** For design purpose water table shall be considered at foundation level

**TYPE OF FOUNDATION - EAST - WEST CORRIDOR****A : Bored Cast in situ RCC Pile**

Depending on the field and laboratory observations of subsoil strata, test results and the type of structures proposed at site, the most feasible soil-foundation system is recommended as normal bored cast in situ R.C.C. pile foundations of 0.80m & 1.0m diameter at different depths with cut-off level at 1.50m to 2.0m depth below existing ground level. The safe load carrying capacities of these piles are given in following table.



Table 9.8 :RCC PILE DETAILS FOR EAST - WEST CORRIDOR

Borehole Nos	Dia. of Pile	CutOff level	Depth in	Pile Capacity		
				Compression	Uplift	Lateral
11	0.80	1.00	12.00	400.0	60.0	9.0
	1.00	1.00	12.00	600.0	90.0	12.0
17 - 22	0.80	1.00	14.00	130.0	50.0	9.0
	1.00	1.00	14.00	240.0	70.0	12.0
20 - 24	0.80	1.50	14.00	180.0	60.0	9.0
	1.00	1.00	14.00	250.0	70.0	12.0
25 - 26	0.80	1.50	12.00	150.0	40.0	9.0
	1.00	1.00	12.00	220.0	50.0	12.0
30 - 31	0.80	1.50	14.00	170.0	50.0	9.0
	1.00	1.50	14.00	240.0	70.0	12.0
32	0.80	1.50	12.00	170.0	40.0	9.0
	1.00	1.50	12.00	250.0	50.0	12.0
35 - 36	0.80	1.50	15.00	200.0	60.0	9.0
	1.00	1.50	15.00	300.0	100.0	12.0
30 - 37	0.80	1.50	15.00	190.0	70.0	9.0
	1.00	1.00	15.00	300.0	100.0	12.0
38	0.80	1.50	15.00	180.0	60.0	9.0
	1.00	1.50	15.00	250.0	100.0	12.0
39	0.80	1.50	20.00	200.0	60.0	9.0
	1.00	1.50	20.00	300.0	100.0	12.0

**Note:**

1. For design purpose, water table shall be considered at cut off level.
2. For design purpose, effective overburden pressure at pile tip should correspond to pile length equal to 10 times the diameter.
3. The above values should be confirmed through pile load tests in the field before adopting these values for design purposes.

**B : Open square footing**

Depending on the field and laboratory observations of subsoil strata, test results and the type of structures proposed at site, the types of foundations, depths and net safe bearing capacities recommended for design purposes are given in the following table. The net SBC/MP in the following table are the lower of the values obtained from shear failure criterion as per IS: 6400 and settlement failure criterion as per IS: 8009, Part I.





**Table J.9: OPEN FOUNDATION DETAILS FOR EAST WEST CORRIDOR**  
For Permissible settlement = 40.0 mm

Type of Foundation	Dimens No	Depth of Foundation (m)	Size of Foundation (m)	Net Safe Bearing Capacity/ Allowable Pressure Intensity (t/m <sup>2</sup> )
Square footing	1 - 9	2.30 - 3.0	5.0 to 6.0	25.00
	10 & 12	3.0	5.0 to 6.0	20.00
	12 - 13	3.0	5.0 to 6.0	20.30
	14 - 15	3.80 - 4.80	5.0 to 6.0	25.00
	16	3.0	5.0 to 6.0	20.00

**Note:** For design purpose water table shall be considered at foundation level.

## E.5.6 LAND

### Land Requirement for following Major Components

- MRTS Structure including Route Alignment, Station Building, Platforms, Entry/Exit Structures, Traffic Integration Facilities, Depots, etc.
- Receiving/Traction Sub-stations
- Radio Towers
- Temporary Construction Depots and work sites.
- Staff quarters, office complex and operation control centre(OCC)

**Table E.10: Summary of Permanent Land Requirement<sup>8</sup>**

LAND DETAILS	EAST-WEST CORRIDOR PRAJAPATI NAGAR TO LOPMANYA NAGAR		NORTH-SOUTH CORRIDOR AUTOMOTIVE SQUARE TO KHAPE DEPOT	
	GOVT. LAND (in sqm)	PVT. LAND (in sqm)	GOVT. LAND (in sqm)	PVT. LAND (in sqm)
STATIONS EXTERNTY	364.80	7769.40	7525.36	13812.80
RUNING SECTION	3225.30	5680.00	10382.00	10225.90
DEPOT AREA	29873.00		33000.00	
TRAFFIC INFORMATION/PARKING	8376.10	1483.70	6378.80	6176.20
<b>TOTAL</b>	<b>37482.20</b>	<b>14933.10</b>	<b>63218.16</b>	<b>26317.90</b>
<b>TOTAL GOVT LAND</b>	<b>7965.40</b>		<b>847 77.66 HECTARE<sup>9</sup></b>	
<b>TOTAL PVT LAND</b>	<b>62821.80</b>		<b>847 6.2 HECTARE<sup>9</sup></b>	

<sup>8</sup> Apart from this the State Government should provide 20 hectares land free of cost for PD activity. Also for construction depots, temporary land @2 hectares per 10 km. will be required on Temporary Basis.



## 9.8 STATION PLANNING

### Line -J (North-South Corridor) Automotive Square to KHAPRI Depot

A total of 17 Stations have been planned along the proposed NS Corridor. This corridor originates starts from Automotive square and runs southwards on NH-7 through Nar Road, Indora Chowk, Gadi Godan Square, Kasturba Park, Zam Mla, Salsund, Congress Nagar, Mahila colony, Air Sqre Station, Chhatrapati Sai Station, JapraKant Nagar, Ujjwal Nagar, Airport Station, New Airport Station and Khapri Station. The Corridor is partly elevated and partly at grade. Total Length of the corridor is 19.658 Km of which approximately 15.058 is elevated and 4.5 km is at grade. There are 17 stations on this corridor of which 15 stations are elevated and 2 stations are at grade. Salsund Station is an interchange station. Average interstation distance is 1.20km approximately varying from 0.54km to 2.4km depending upon the site, local and traffic requirements. The sequence of stations with their respective clearances and locational and platform characteristics is presented in Table 9.11A.

**Table 9.11A: NS Corridor :  
Sequence of Stations with Clearances and Locational & Platform Characteristics**

	Name of Station	Clearance (m or ft)	Distance from previous station (m or ft)	Rail level (m or ft)	Platform type	Alignment
	Auto Sq	-045.2				
1	AUTOMOTIVE SQRM	00	408.2	333.000	Isle	Elevated
2	NAR ROAD	075.0	075.0	338.000	Isle	Elevated
3	INDORA CHOWK	2736.7	1103.0	374.700	Isle	Elevated
4	KASTURBA CHOWK	3307.0	1047.0	378.600	Isle	Elevated
5	GADI GODAN SQRM	4300.0	1217.0	323.200	Isle	Elevated
6	KASTURBA PARK SQRM	6148.0	748.0	328.300	Isle	Elevated
7	ZAM MLA	0775.5	1020.0	373.000	Isle	Elevated
8	SALSUND	0700.0	000.7	375.000	Isle	Elevated
9	CHHATRAPATI SAIBAI	7007.0	1188.0	317.300	Isle	Elevated
10	MAHILA COLONY	3800.0	786.4	320.400	Isle	Elevated
11	AIR SQ	10184.7	1822.1	375.300	Isle	Elevated
12	CHHATRAPATI SAIBAI	11160.0	1047.0	373.000	Isle	Elevated
13	JAPRAKANT NAGAR	11071.5	96.2	320.000	Isle	Elevated
14	UJJWAL NAGAR	12000.0	1034.7	371.000	Isle	Elevated



	Name of Station	Chainage (m. m)	Distance from previous station (m. m)	Rail level (m. m)	Platform type	Alignment
15	AMPOLI	1174.9	336.2	371.00	Side	Existing
16	NEW AMPOLI	1834.4	236.0	368.00	Side	At-Grade
17	EMAKHOLI	1940.5	125.2	358.00	Side	At-Grade
	Dead End	1920.0				

#### Line -2 (East-West Corridor) Prapada Nagar to Lokmanya Nagar

A total of 13 Stations have been planned along the proposed EW Corridor. This corridor originates from Prapada Nagar and runs westwards, through Valachandri Chawk, Ambekar Chowk, Telephone Exchange, Dikkar Oil Chowk, Agrawal Chowk, Datar Valaya Chowk, Nagpur Railway Station, Sitaburi, Jhansi Ram Square, Institute of Engineers, Shankar Nagar Square, LAD chawk, Dharmash Collage, Subhash Nagar, Ratna (Ring road Junction), Vasudev Nagar, Baral Nagar to Lokmanya Nagar. The entire corridor is elevated. The total length of the corridor is 15.256 kilometers. All stations are elevated stations and Sitaburi station is an interchange station. Average inter-station distance is 1.00km approximately varying from 0.55km to 1.20km depending upon the site, operational and traffic requirements. The sequence of stations with their respective chainages and locations and platform characteristics is presented in Table 3.11B.

**Table 3.11 B: EW Corridor :  
Sequence of Stations with Chainages and Locations & Platform Characteristics**

	Name of Station	Chainage (m. m)	Distance from previous station (m. m)	Rail level (m. m)	Platform type	Alignment
	Dead End	-052.3				
1	Prapada Nagar	5.0	222.0	311.0	Side	Elevated
2	Valachandri Chowk	1229.3	1229.3	300.0	Side	Elevated
3	Ambekar Chowk	1347.3	118.0	302.0	Side	Elevated
4	Telephone Exchange	1717.8	370.5	311.8	Side	Elevated
5	Dikkar Oil Chowk	2080.3	362.5	311.5	Side	Elevated
6	Agrawal Chowk	2453.9	373.6	315.5	Side	Elevated
7	Datar Valaya Chowk	2580.4	126.5	321.0	Side	Elevated
8	Nagpur Railway Station	3484.4	904.0	315.7	Side	Elevated
9	Sitaburi Interchange	4717.7	1233.3	320.7	Side	Elevated
10	Jhansi Ram Square	5764.0	1046.3	313.0	Side	Elevated



Station No.	Name of Station	Distance (m)	Distance from previous station (km)	Head level (m a.s.l)	Platform type	Alignment
11	Section 21 Express	9117.2	763.2	315.4	Side	Ground
12	Automotive Nagar Station	13234.0	917.7	318.0	Side	Ground
13	Deopet	13875.1	741.2	323.7	Side	Ground
14	Congress Nagar	12325.1	1147.8	320.8	Side	Ground
15	Section 22	12347.1	221.9	328.0	Side	Ground
16	Section 23	14225.1	1878.0	328.0	Side	Ground
17	Section 24	14172.0	812.0	340.2	Side	Ground
18	Section 25	15131.0	959.0	328.0	Side	Ground
19	Section 26	17752.0	2621.0	325.4	Side	Ground
	Grand total	18180.0	3724			

Site specific plans for the stations were prepared and put up in the respective chapter.

## 8.7 TRAIN OPERATION PLAN

### 8.7.1 Operation Philosophy

The underlying operation philosophy is to make the BRT System more attractive and economical, the main features being:

- Selecting the most optimum frequency of Train services to meet additional capacity requirement during peak hours or most of the sections.
- Economical & optimum train service frequency not only during peak period, but also during off-peak period.
- A short train consists of 3 coaches.
- Multitasking of train operator and maintenance staff.

### 8.7.2 Train Operation Plan

#### 8.7.2.1 Salient Features

- Running of services for 12 hours of the day (5 AM to Midnight) with a station dwell time of 30 seconds. No services are provided between 00.00 hrs to 0.05 hrs, which are reserved for maintenance of infrastructure and rolling stock.
- Make up time of 5-10% with 5-12% coasting.
- Scheduled speed for these corridors has been assumed as:
  - 'Automotive Nagar to Congress Nagar' section: 32 kmph
  - 'Congress Nagar to Deopet Station' section: 35 kmph

**Line-2, East-West Corridor**

- Prapatti Nagar to Lakshmiya Nagar section, 30 kmph
- Agrasen Chowk to Subhash Nagar section, 25 kmph

**8.7.2.2 Train formation**

To meet the above projected traffic demand, the possibility of running trains with composition of 3 cars with different headway has been examined.

**Composition**

DMC - Driving Motor Car

TC - Trailer Car

Capacity @ 6 passengers per square meter of standing area

Driving Motor Car (DMC) - 247 (63 seated + 204 standing)

Trailer Car (TC) - 279 (50 seated + 220 standing)

3 Car Train - 764 (136 seated + 626 standing)

**8.7.2.3 PHDT capacity provided****Table 8.12: PHDT capacity provided**

Description	YEAR			
	2014	2021	2031	2041
<b>North - South Corridor</b>				
Carstairs	3	3	3	3
Head way (Minutes)	6.0/12	5/10	4/8	3/6
Max. PHDT Demand	10089	10036	12604	10725
PHDT Capacity Available	7640 (8736 <sup>*</sup> )	9168 (1678 <sup>*</sup> )	11468 (14366 <sup>*</sup> )	12283 (13483 <sup>*</sup> )
<b>East - West Corridor</b>				
Carstairs	3	3	3	3
Head way (Minutes)	6.0/12	8/12	4.5/9	3.5/7
Max. PHDT Demand	7745	6450	8936	11682
PHDT Capacity Available	7052 (8362 <sup>*</sup> )	7640 (9736 <sup>*</sup> )	10167 (12072 <sup>*</sup> )	13087 (16683 <sup>*</sup> )

\* @ 6 persons per square meter of standing area



### 8.2.2.4 Year wise rake requirement

Based on Train formation and headway as decided above to meet Peak Hour Peak Direction Traffic Demand, Rake requirement has been calculated and enclosed as Attachment V in respective chapter & has been tabulated below:

Table 8.13 : Year wise rake requirement

Corridor	Year	No. of Rakes	Rake Config	No. of cars
North – South Corridor	2016	11	3 car	33
	2021	12	3 car	36
	2031	18	3 car	54
	2041	20	3 car	60
East – West Corridor	2016	12	3 car	36
	2021	13	3 car	39
	2031	17	3 car	51
	2041	20	3 car	60

## 8.3 ROLLING STOCK

The required transport demand forecast is the governing factor for the choice of the Rolling Stock. The forecasted Peak Hour Peak Direction Traffic calls for a Light Capacity Main System (MRTS).

### 8.3.1 Coach Size

The following optimum size of the coach has been chosen for this corridor as mentioned in Table 8.14

Table 8.14: Size of the coach

	Length*	Width	Height
Driving Motor Car (DMC)	21.64 m	2.8 m	3.8 m
Traction Car (TC)/Motor Car (MC)	21.34 m	2.8 m	3.9 m

\*Maximum length of coach over couplers/buffers = 22.8 m

### 8.3.2 Passenger Carrying Capacity

In order to maximize the passenger carrying capacity, longitudinal seating arrangement shall be adopted. The whole train shall be vestibuled to distribute the passenger evenly in all the coaches. Criteria for the calculation of standing passengers are 3 persons per square meter of standing floor area in normal state and 6 persons in crush state of peak hour.

Therefore, for the Medium Rail Vehicle (MRV) with 2.8 m maximum width and longitudinal seat arrangement, conceptually the crush capacity of 40 seated, 204 standing thus a total of 247 passengers for a Driving motor car, and 30 seated, 220



standing thus a total of 270 for a trailer motor size is envisaged. Following train composition is recommended:

3-car Train: DMC + TC + DMC

**Table 6.16: Carrying Capacity of Medium Rail Vehicles**

3 car Train Composition	DMC + TC + DMC
Train Carrying Capacity of 3 Car Train (60 passengers per square meter of stowage area)	- 704 passengers @ 0 standardton

NORMAL - 3 Persons/m<sup>2</sup> of stowage area, CRUSH - 5 Persons/m<sup>2</sup> of stowage area

## 8.9 SYSTEM OF TRACTION AND POWER TARIFF

The power requirements of a metro system are determined by peak-hour demands of power for traction and auxiliary applications. Broad estimation of auxiliary and traction power demand is made based on the following requirements:-

- Specific energy consumption of rolling stock - 75kWh/1000 GTRM
- Regeneration by rolling stock - 30%
- Elevated station load - Initially 2000kW, which will increase to 400 kW in the year 2041
- Underground Station load - Initially 2000 kW, which will increase to 2500 kW in the year 2041
- Depot auxiliary load - Initially 1000 kW, which will increase to 2000 kW in the year 2041

Keeping in view of the train operation plan and demand of auxiliary and traction power requirements provided for the year 2016, 2021, 2031 and 2041 are summarized in **Table 6.16:-**

**Table 6.16: Power Demand Estimation (MVA)**

Corridor		Year			
		2016	2021	2031	2041
North-South Corridor - 1 Autonovo Gare to KHAPRI [19.668 kms ; 15 elevated Stations & 2 at Grade Station]	Traction	4.92	3.01	3.84	7.32
	Auxiliary	7.72	7.84	9.14	11.40
	Total	12.64	12.85	14.98	18.73
East West Corridor - 2 Pratap Nagar to Lokmatsya Nagar [18.557 kms ; 19 Elevated Stations]	Traction	4.26	4.57	5.73	7.01
	Auxiliary	8.34	8.46	9.88	12.45
	Total	12.60	13.03	15.61	19.46



## 8.10 MAINTENANCE DEPOT

### 8.10.1 Depot-cum-Workshop

It is proposed to establish one depot-cum-workshop near Khajuri Station in NADC Land for North-South Corridor and one depot-cum-workshop in the land belonging to DMF near Lokmanya Nagar for East-West Corridor with following functions:

#### **i) Depot-cum-workshop for North-South Corridor (Line 1)**

- (i) Major overhauls of all the trains of Line 1.
- (ii) All minor schedules and repairs of Line 1.
- (iii) Lifting for replacement of heavy equipment and testing thereof of Line 1.
- (iv) Repair of heavy equipments of Line 1.

#### **ii) Depot-cum-workshop for East-West Corridor (Line 2)**

- (i) Major overhauls of all the trains of Line 2.
- (ii) All minor schedules and repairs of Line 2.
- (iii) Lifting for replacement of heavy equipment and testing thereof of Line 2.
- (iv) Repair of heavy equipments of Line 2.

**8.10.2** The Depot planning near Khajuri Station for North-South Corridor and near Lokmanya Nagar for East-West Corridor is based on following assumptions:

- (i) Enough space should be available near Khajuri Station for North-South Corridor and near Lokmanya Nagar for East-West Corridor for establishment of a Depot-Cum-workshop.
- (ii) All inspection, workshop lines and stabling lines are designed to accommodate two trains of 3-car each.
- (iii) All stabling lines are planned in the proposed depot-cum-workshop assuming adequate space availability. In case of space constraints, if any, stabling facilities may need to be created at terminal stations or elsewhere to cater to the required stabling facilities.
- (iv) Provision of transfer line from one corridor to another corridor.





In broad terms, based on the planned Rolling Stock requirements, this chapter covers conceptual design on following aspects and will work as a guide for detailed design later:

- Layout of Stabling-shed, Inspection-shed, minor repairs and heavy repair overhauling workshop and cleaning of Rolling Stock.
- Operational and functional safety requirements.
- Ancillary buildings for other maintenance facilities.
- Electrical & Mechanical Services, power supply and distribution system.
- Water Supply, Drainage & Sewerage.

## 2.11 SIGNALLING

The signaling system shall provide the means for an efficient train control, ensuring safety in train movements. It assists in optimization of major infrastructure investment and running of efficient train services on the network.

### 2.11.1 Standards

The following standards will be adopted with regard to the Signaling system.

Table 2.17: Standards of Signaling System

Description	Standards
• Interlocking	Computer based Interlocking adopted for station having switches and crossings. All related equipment as far as possible will be centralized in the equipment room at the station. The depot shall be interlocked except for lines heavily used for workshop lines, inspection shed etc. etc.
• Operation of Points	With Direct current 110V D.C. point machines or 380 volts 3 phase, 50 Hz. AC point machines.
• Track Circuit (Fitted)	Audit frequency Track circuits on running section, tail track and in depot.
• Signals at Stations with point & crossings	Line Side signals to protect the points (switches); LED type signals for reliability and reduced maintenance cost.
• UPS (uninterrupted power) at stations, as well as for OCC	For Signaling and Telecommunications



Description	Standards
• Train protection system	Automatic Train Protection system (CBTC based). The system architecture shall provide for redundancy.
• Train Descriptor System	Automatic Train Supervision system. Movement of all trains to be logged on to a central computer and displayed on workstations in the Operational Control Centre and at the SCR. Remote control of stations from the OCC. The system architecture shall provide for redundancy.
• Cables	Outdoor cables will be steel armoured as far as possible.
• Fail Safe Principles	SIL-4 safety levels as per CENELEC standard for signal application.
• Immunity to External Interference	All data transmission on telecom cables/GPRS/Radio. All Signaling and telecom cables will be separated from power cables. CENELEC standards to be implemented for EMC.
• Train Working under emergency	Running at side with line side signal with speed automatically restricted between 16-26 kmph.
• Environmental Conditions	As conditions for all equipment rooms.
• Maintenance philosophy	Philosophy of continuous monitoring of system status and preventive & corrective maintenance of Signaling equipments shall be followed. Card / module / sub-system level replacement shall be done in the field and repairs under test in the central laboratory/ manufacturer's premises.

## 8.12 TELECOMMUNICATION AND AUTOMATIC FARE COLLECTION

The telecommunication system acts as the communication backbone for Signalling systems and other systems such as SCADA, AFC etc and provides telecommunication services to meet operational and administrative requirements of metro network.

### 8.12.1 Technology

The Technologies proposed to be adopted for telecommunication systems are shown in Table 0.12 below:-

**Table 0.12: Technologies Proposed for Telecommunication Systems**

System	Standards
• Transmission Media	Optical Fibre system as the main bearer for bulk of the telecommunication network
• Telephone Exchange	EMPEX of minimum 30 ports is to be provided at all Stations, an Exchange of 60 Ports to be provided at Terminal Station. Larger exchange is required at OCC/Depot depending upon the actual users
• Train Radio System	Digital Train radio (TETRA) communication between members of moving cars, stations, maintenance personnel and control centre
• Train Destination Indicator System	LED/LCD based boards with adequate visibility to be provided at convenient location at all stations to provide bilingual visual indication of the status of the running trains, and also special messages in emergencies.
• Centralized clock system	Accurate display of time through a synchronization system of slave clocks driven from a master clock at the OCC and sub - master clock in station. This shall also be used for synchronization other systems.
• Passenger Announcement System	Passenger Announcement System covering all platform and concourse areas with local as well as Central Announcement.
• Redundancy (Major Systems)	Redundancy in Radio's in the Base Stations. Path Redundancy for Optical Fibre Cables by provisioning in ring configuration.
• Environmental Conditions	All equipment rooms to be air conditioned.
• Maintenance Philosophy	System to have, as far as possible, automatic switching facility to alternate route/circuits in the event of failure. Philosophy of preventive checks of maintenance to be followed. System interfaced with NMS for diagnosing faults and co-ordination. Continuative level replacement shall be done in the field and repair undertaken in the central laboratory/main contractor's premises.



### 9.11.2 Automatic Fare Collection

Metro Rail Systems handle large number of passengers. Ticket issue and fare collection play a vital role in the efficient and proper operation of the system. To achieve this objective, ticketing system shall be simple, easy to use/operate and maintain, easy on accounting facilities, capable of issuing single/multiple journey tickets, amenable for quick fare changes and require overall lesser manpower. In view of above, computer based automatic fare collection system is proposed.

#### 9.11.3 Automatic fare collection systems have the following advantages:

1. Less number of staff required.
2. Less possibility of leakage of revenue due to automatic ticket check by control gates.
3. Recycling of ticket fraudulently by staff avoided.
4. Efficient and easy to operate, faster evacuation both in normal and emergency.
5. System is amenable for quick fare changes.
6. Management information reports generation easy.
7. System has multi-operator capabilities. Same Smart Card can be used for other applications also, including in other lines of the Metro.
8. AFC systems are the worldwide accepted systems for LRT/Metro environment.

### 9.12.4 Technology

The technology proposed for AFC systems are as given under in **Table 9.19**.

**Table 9.19: Technologies Proposed for AFC Systems**

Standards	Description
<ul style="list-style-type: none"> <li>• Fare media</li> </ul>	a) Contactless smart card - For multiple journeys. b) Single Journey / Contactless Token
<ul style="list-style-type: none"> <li>• Gates</li> </ul>	Computer controlled retractable flap type automatic gates at entry and exit. There will be following types of gates: <ul style="list-style-type: none"> <li>• Entry</li> <li>• Exit</li> <li>• Reversible (if required as per final station layout) - can be set to entry or exit</li> <li>• Reversible Hand tapped Gate -gates for disabled people.</li> </ul>



Standards	Description
<ul style="list-style-type: none"><li>Station computer, Central computer and AFC Network</li></ul>	All the fare collection equipment shall be connected in a local area network with a station server controlling the activities of all the machines. These station servers will be linked to the central computer situated in the operational control centre through the optic fibre communication channels. The centralized control of the system shall provide real time data of earnings, passenger flow analysis, blockading of specified cards etc.
<ul style="list-style-type: none"><li>Ticket office machine (TOMEPO)</li></ul>	Manual Ticket office machine shall be installed in the stations for selling tickets to the passengers. Also TOMs shall be provided for Automatic Ticket Vending.
<ul style="list-style-type: none"><li>Ticket reader/face Machine, and portable ticket decoder</li></ul>	Ticket reader shall be installed near EPC for passengers to check information stored in the ticket. This shall also be used as a Add Value Machine to allow passenger to tap and add value to his card which has been topped up through internet.
<ul style="list-style-type: none"><li>UPS (uninterrupted power at stations as well as for GCC).</li></ul>	<b>Common UPS of BRT system will be utilized.</b>

### 8.13 DISABLED FRIENDLY FEATURES

The objective of making this chapter is to create a user-friendly mass transport system in India which can ensure accessibility to persons with disabilities, people traveling with small children or are carrying luggage, as well as people with temporary mobility problems (e.g. a leg in plaster) and the elderly persons.

The design standards for universal access to Public Transport infrastructure including related facilities and services, information, etc. would benefit people using public transport.

The access standards given here are extracted from Indian Roads Congress Code, IRC 102, 2012, Guidelines for Pedestrian Facilities, Model Building Bye-Laws, 2011 and National Building Code, 2005. Central Public Works Department's (CPWD) 'Space Standards for Barrier Free Built Environment for Disabled and Elderly Persons', 1998 and 2013 edition (under revision by MoUD), and International best practices / standards.



Further, it has also been attempted to provide guidelines/standards for sighting and boarding area, approach to station, car parking area, drop-off and pick-up areas, kerbside rickshaw stand, bus stations, footpath (sidewalk), kerb ramp, road intersection, median/pedestrian refuge, traffic signals, subway and foot over bridge etc. to achieve a seamless development around metro.

## 2.14 ENVIRONMENTAL IMPACT ASSESSMENT

### 2.14.1 Environmental Impacts

A total of 101 structures (74 in EW Corridor and 27 in NS Corridor) of various dimensions shall be affected by the proposed project. Majority of the structures are privately owned.

According to the results of the present study, it is found that about 517 trees are likely to be lost due to the project. Four trees have to be planted for each tree cut. Hence, 1348 trees to be planted. These trees would have occupied about 85 ha in the forest. No re-forest land is available, hence 85 ha have to be re-forested in degraded forests or around Nagpur.

**Utility/Drainage Problems:** The alignment will cross/dismantle large number of sub-surface, surface and utility services, viz. sewer, water mains, storm water drains, telephone cables, overhead electrical transmission lines, electric pipes, traffic signals etc. These utility services are essential and have to be maintained in working order during different stages of construction by temporary/permanent diversions or by supporting in position.

### 2.14.2 Positive Environmental Impacts

**Employment Opportunities:** Manpower will be needed in various activities during construction. If operated, about 40 persons per 100 meter length of the corridor, is (approx. 1,700 persons) will be employed for operation and maintenance of the proposed system. Thus the project would provide substantial direct employment, besides, more people would be indirectly employed in allied activities and trades.

**Enhancement of Economy:** The construction of Nagpur Metro will facilitate the population to move from one end of the city to another. The proposed transport facility will facilitate rural population to move quickly towards urban centres and return there from. With the development of Nagpur Metro, it is likely that more people will be involved in trade, commerce and allied services.



**Mobility:** Metro lines will facilitate people to move quickly towards urban centres and return from there. Any reduction in number of private vehicles will result in reduction of accidents which will involve savings from damage to vehicles and savings towards medical and insurance expenses to persons involved in accidents.

**Less Fuel Consumption:** On implementation of the project both petrol and diesel consumption will get reduced due to shift of passengers from road to rail and also due to decongestion on road.

**Less Air Pollution:** With the construction of metro, there will be less vehicular traffic on road, and consequently less air pollution, and hence the air quality will improve.

**Reduction in Traffic Congestion:** Metro will reduce the congestion and journey time on roads because of diversion of some traffic to Metro. Reduction in traffic congestion will save the necessary capital investment and vehicle operating cost as well as increase in time saving per vehicle.

**Environmental Management Plan:** The project will provide higher living standard, better quality of life, less travel time, better connectivity and transport facilities. The management plans are essential to ensure that stress loads on the systems are within carrying capacity. The management plan aims at maintaining the environmental quality of project area minimal in pre-project stage. An environmental management strategy plan was developed to mitigate the adverse impacts.

## 8.15 SECURITY MEASURES FOR A METRO SYSTEM

Metro is emerging as the most favoured mode of urban transportation system. The inherent characteristics of metro system make it an ideal target for terrorists and saboteurs. Metro systems are typically open and dynamic systems which carry thousands of commuters. Moreover the high cost of infrastructure, its economic importance, being the life line of city high news value, fear & panic and mass casualty does poses greater threat to its security. Security is a relatively new challenge in the context of public transport. It addresses problems caused intentionally. Security differs from safety which addresses problems caused accidentally. Safety problems or threats are caused by people whose actions aim to undermine or disturb the public transport system and/or to harm passengers or staff. These threats range from daily operational security problems such as disorder, vandalism and assault to the terrorist threat.

### 8.15.1 Necessity of Security

It is well known that public transportation is increasingly important for urban areas to prosper in the face of challenges such as reducing congestion and pollution. Therefore, security plays an important role in helping public transport system to become the mode of choice. Therefore, excellence in security is a prerequisite for Metro system for increasing its market share. Metro railway administration must ensure that security matter must keep pace rapid expansion of the metro and changing security scenario.



### 8.16.2 Three Pillars of Security

Security means protection of physical, human and intellectual assets either from criminal interference, removal of destruction by terrorists or criminals or incidental to technological failures or natural hazardous events. There are three important pillars of security as mentioned under:

- (i) The human factor;
- (ii) Procedures; and
- (iii) Technology

## 8.16 DISASTER MANAGEMENT PLAN FOR A METRO RAIL SYSTEM

A disaster is a tragic event, be it natural or manmade, which brings sudden and immense agony to humanity and disrupts normal life. It causes large scale human suffering due to loss of life, loss of livelihood, damages to property and persons and also brings untold hardships. It may also cause destruction to infrastructure, buildings, communication channels essential services, etc.

### 8.16.1 Need for Disaster Management Measures

The effect of any disaster spread over in operational area of Delhi Metro is likely to be substantial as DMRC deals with thousands of passengers daily in underground tunnels, viaducts and stations. Disaster brings about sudden and immense misery to humanity and disrupts normal human life in its established social and economic patterns. It has the potential to cause large scale human suffering due to loss of life, loss of livelihood, damage to property, injury and hardship. It may also cause destruction or damage to infrastructure, buildings and communication channels of Metro. Therefore there is an urgent need to provide for an efficient disaster management plan.

### 8.16.2 Objectives:

The main objectives of this Disaster Management Measures are as follows:

- Save life and alleviate suffering.
- Provide help to stranded passengers and arrange their prompt evacuation.
- Instil a sense of security amongst all concerned by providing accurate information.
- Protect Metro Rail property.
- Expedite restoration of train operation.
- Lay down the actions required to be taken by staff in the event of a disaster in





- Delhi Metro Rail Corporation in order to ensure handling of crisis situation in coordinated manner.

To ensure that all officials who are responsible to deal with the situation are thoroughly conversant with their duties and responsibilities in advance, it is important that these officials and workers are adequately trained in anticipation to avoid any kind of confusion and chaos at the time of the actual situation and to enable them to discharge their responsibilities with alacrity and promptness.

## 8.17 MULTI-MODAL TRANSPORT INTEGRATION

The Metro Transport Network in Noida will cover a length of approximately 38 kms. It will be augmented through enhanced facility of cross-mode interchanges to other modes and reduce the travel time of commuters. While Metro provides a high capacity corridor to carry the passengers, the need for integration of with other secondary/intermediate transport modes is getting highlighted more than ever to ensure a seamless transfer. This concept is to provide at least last mile or half mile connectivity to the commuters with in their pieces of day. Accordingly the priority in this issue, MUID has laid down policy guidelines to include the need and provisioning of all public, IPT and private modes in the DPRs for the Metro Systems. (Ref: MUID (Urban Transport Wing) Advisory Circular no. N-1491 V/12007-UT-FV dated 30.08.2013)

The state of various modes of secondary/intermediate modes of travel is complex and dynamic issue which is dependent on a large number of variables like available road width, generation in the residential areas, Road condition, distance from the existing Metro Stations, availability of parking and lay out and availability of circulating areas at the Metro Stations, Business centre or markets & existing traffic densities. These factors relate with each other and evolve with development of new roads, etc of transport, infrastructure and changes with the passage of time. Even though for a given urban transport scenario, optimal mode share may be determined from computer based models but actual optimal mode share is never achievable on the road due to dynamic nature of demand and supply of transport modes.

## 8.18 COST ESTIMATES

Cost estimates have been prepared based on the rates accepted for Delhi Metro by established up to June 2012 level.

### Corridor - 1: NORTH-SOUTH CORRIDOR (AUTOMOTIVE SQUARE TO KHAPRA)

The overall capital cost for Corridor 1) at June 2012 price level, works out to Rs. 2815 Crore, excluding taxes and duties, but including general charges & design charges @ 3% on all items except land and 3% contingencies on all items. Estimated total taxes & duties are Rs. 428Crore.

**Corridor 2: EAST WEST CORRIDOR (LOKMANYA NAGAR TO PRAJAPATI NAGAR)**

The overall capital cost for Corridor-2, at June 2012 price level, works out to Rs. 2564 Crore excluding taxes and duties, but including general charges & design charges @ 5% on all items except land and 3% contingencies on all items. Estimated total taxes & duties are Rs. 443Crore.

**8.15 FINANCING OPTIONS, FARE STRUCTURE AND FINANCIAL VIABILITY**

**8.15.1** The Nagpur Metro project- North South corridor (Alternative Square to KHAPRI) and East West corridor (Prajapati Nagar to Lokmanya Nagar), covering a total route length of 36.215 Kms is proposed to be constructed with an estimated cost as per details are shown in **Table 8.20** below:-

**Table 8.20: Completion Cost**

(Rs. Crore)					
Corridor No	Name of Corridor	Distance (KMs)	Estimated Cost without Central taxes at June-2012 Price Level	Estimated Cost with Central taxes at June-2012 Price Level	Completion Cost
1	North-South Corridor	13.808	3015.00	3433.00	<b>6500</b>
2	East-West Corridor	16.507	2564.00	3427.00	
<b>Total</b>		<b>30.315</b>	<b>5579.00</b>	<b>6860.00</b>	

The estimated cost at June-2012 price level also includes an amount of Rs.43 Crore as one-time charges of security personal towards cost of weapons, simulators, and hand held and door detector machine etc. However, the recurring cost towards salary and allowances of security personal have not taken in to account in PRR calculation.

**8.15.2 Financial Internal Rate of Return (FIRR)**

The Financial Internal Rate of Return (FIRR) and costs for 30 years business model including construction period is **13.34%**.

**8.15.3 Funding Pattern**

The funding pattern has been worked out under two models viz., SPV model and BOT Model.

**(A)** The proposed funding with Central Taxes assumed under the SPV model is given in Table 8.21 as under:-



Table 0.21: Funding pattern under SPV model

Particulars	[Rs/Crores]	
	With Taxes & Duties	
	Amount (Rs/Crores)	% of contribution
Equity by GOI	1114.00	52.83%
Equity by GOM	1114.00	52.83%
SD by GOM for central Taxes (50%)	441.00	5.08%
SD by GOI for Central Taxes (50%)	441.00	5.08%
SD by GOM to State Taxes	250.00	2.98%
SD by GOM for Land	644.00	7.42%
Nagpur Improvement Trust Contribution	421.00	4.85%
Nagpur Municipal Corporation Contribution	421.00	4.85%
JICA Loan @ 1.60% PA/Vestral Sewerage @ 12%	3825.00	44.88%
<b>Total</b>	<b>6690.00</b>	<b>100%</b>

b) The proposed funding with Central Taxes assumed under the BOT model is given in Table 0.22 as under:-

Table 0.22 Funding pattern under BOT model (with central taxes)

Particulars	Amount (Rs/Crores)	% of contribution
VGF by GOI	1033.40	20.00%
VGF by GOM	324.00	6.78%
Equity by Concessionaire	1033.00	24.42%
Concessionaire's cost @ 12% PA	3738.00	48.80%
<b>Total</b>	<b>7777.80</b>	<b>100.00%</b>
Land Fee by GOM	644.00	
State Taxes by GOM	250.00	
SD	440.00	
<b>Total/including SD</b>	<b>8136.80</b>	



### 8.18.4 Cost Investment Break Up

It is assumed that commercial operation shall start from April-2019. The Revenue Opening Date (ROD) has been assumed as 01.04.2019. The total completion costs duly estimated is shown in Finance Chapter, which has been taken as the initial investment. The cash flow of investments based on completion cost is in **Table 8.23** as below.

**Table 8.23: Year wise Investment-With Central Taxes**

Financial Year	Cost at June 2012 Price Level	Completion Cost
2013-14	667.00	452.00
2014-15	946.00	1001.00
2015-16	1020.00	1074.00
2016-17	1885.00	2412.00
2017-18	1420.00	1083.00
2018-19	497.00	743.00
2019-20	134.00	198.00
<b>Total</b>	<b>6582.00</b>	<b>3050.00</b>

## 8.20 ECONOMIC ANALYSIS

**8.20.1** The sources from where economic savings occur are identified first. Although there are many kinds of primary, secondary and tertiary benefits, only the quantifiable components can be taken to measure the benefits. These components are quantified by linking with the number of passengers shifted and the passenger km covered by the trips which are shifted from road/rail based modes to metro. It may be observed that first four benefit components given in **Table 8.24** are direct benefits due to shifting of trips to metro, but other benefit components are due to decongestion effect on the road. Benefit components were first estimated applying market values then were converted into respective Economic values by using separate economic factors which are also given in **Table 8.24**. Depending upon methodology of estimation, economic factors are assumed. Overall economic value of benefit components is 99% of the market value. Similarly economic value of the cost components are 85% of the market cost.

**Table 8.24: Benefit Components due to Metro**

	Benefit Components	Economic Factors
1	Construction Cost	85%
2	Maintenance Cost	85%
3	Annual Time Cost Saved by Metro Passengers	99%
4	Annual Fuel Cost Saved by Metro Passengers	99%



	<b>Benefit Components</b>	<b>Economic Factors</b>
5	Annual Vehicle Operating Cost Saved Saved by Metro Passengers	90%
6	Emission Saving Cost	90%
7	Accident Cost	90%
8	Annual Time Cost Saved by Road Passengers	90%
9	Annual Fuel Cost Saved by Road Passengers	90%
10	Annual Infra Structure Maintenance Cost	90%
11	Overall economic factor for the benefit components	90%

The project cost comprises capital cost, operation and maintenance cost including:

- Capital cost of infrastructure (civil engineering, land, track, power supply, station system, signaling and telecommunications, etc.) and rolling stock.
- Operating cost of metro.

The benefit stream that has been evaluated and quantified includes:

- Capital and operating cost (in present congestion norms) of carrying the total volume of passenger traffic by existing bus system and private vehicles in case metro project is not taken up.
- Savings in operating costs of all buses and other vehicles due to de-congestion including those that would continue to use the existing transport network even after the metro is introduced.
- Savings in time of commuters using the metro over the existing transport modes because of faster speed of metro.
- Savings in time of those passengers continuing on existing modes, because of reduced congestion on roads.
- Savings on account of prevention of accidents and pollution with introduction of metro.
- Savings in road infrastructure and development costs that would be required to cater to increase in traffic, in case metro is not introduced.
- Savings in fuel consumption on account of less number of vehicles on road and decongestion effect with introduction of metro are included in those of vehicle operating cost.

The Economic Internal Rate of Return (EIRR) it worked out as 17.76% for this project.



## 8.21 IMPLEMENTATION STRATEGY AND PROJECT IMPLEMENTATION

8.21.1 To ensure that the project is implemented as targeted in this report it has to get the visible positive support from Nagpur Administration, CoM and CoJ. To enable Nagpur Metro project to be implemented without any loss of time and cost over-run, effective institutional arrangements would need to be set up. Presently, Nagpur Improvement Trust (NIT) is dealing with this Project but there is need to have an SPV responsible entirely for the project.

### 8.21.2 Special Purpose Vehicle

Special Purpose Vehicle (SPV) is a legal entity established for implementation of specific projects and is used to isolate the governing authority / stakeholder company from operational and financial risk. SPV has a management dedicated to the accomplishment of the specific objective. The SPV also allows securitization of assets without disturbing the managerial relationship. Under the arrangement, any profitable income stream generated by secure assets can be securitized. Three models have been analyzed and summarized below:-

#### a) Implementation through Government

Under this model, the entire project development, implementation and operation is undertaken and financed by the government authority. Some recent examples of metro rail projects implemented directly through Government agencies are as under:-

- Delhi
- Bangalore
- Chennai
- Jaipur
- Kolkata

#### b) Implementation through BOT model

BOT approach assumes that the metro is given to a private partner (Concessionaire) to develop and operate over the concession period. The private partner brings requisite funds and the efficiency of private sector management in the implementation as well as operation of the project. MMRC's role in this option is limited to that of a regulatory authority. Thus MMRC would monitor the implementation of the project such as laying down the passenger fares, targets for the minimum number of services to be run by the private partner, frequency, punctuality and reliability of these services, etc. There are only two projects namely Hyderabad and Mumbai being implemented through BOT model. The success of this mode in India is still to be known.

#### c) Implementation through PPP model

Under this mode, the government entity undertakes all civil works and the associated station work, while all other works like rolling stock, signaling and telecom, track laying work are undertaken by the private partner along with management of the metro service over the concession period. This enables the client to monitor and adhere to quality and construction timelines for the project in a better way. Implementation of a part express line in Delhi is the only example of this model in India.

**d) Proposed Implementation Model**

Due to very low FIRR and uncertainties of getting the agencies for taking up this work on BOT/PPP model, it is proposed that implementation of Nagpur Metro should be done on DBM/DBMC model.

**8.18 CONCLUSIONS AND RECOMMENDATIONS**

- i) It has been established that a Light Capacity Metro System (LCMTS) with carrying capacity of about 20,000 PHPDT would be adequate to meet not only the present Metro demand but also cater to the demand for the next 33 years.
- ii) After examining the various options for execution of Nagpur Metro Rail Project, it is recommended that the project be implemented through government funding. Implementing through an SPV namely "Nagpur Metro Rail Corporation (NMRC)" registered under the Companies Act, 1956. This SPV should be a PSU of GoM and Govt. After the approval of State Government, DPR to be sent to the Secretary, Ministry of Urban Development, Government of India, advising GOI of the State Government's intention to take up the Project on government funding basis and requesting for the latter's "In Principle" clearance to go ahead with the Project.



Key plan of Nagpur Metro is shown in Fig-0.1

FIG : 0.1





# CHAPTER 1

## INTRODUCTION



### 1.1 BACKGROUND

- 1.1.1 FACTS ABOUT NAGPUR
- 1.1.2 DEMOGRAPHY
- 1.1.3 VEHICLE POPULATION IN NAGPUR CITY
- 1.1.4 NAL AND AIR TRANSPORT IN NAGPUR CITY
- 1.1.5 POINTS FROM OTHER FEASIBILITY STUDY DONE FOR NAGPUR ALIGNMENTS PROPOSED BY IORIC
- 1.1.6

### 1.2 STRUCTURE OF THE PROJECT REPORT

#### TABLES

- TABLE 1.1 a DEMOGRAPHY, POPULATION OF NAGPUR CITY IN 2011
- TABLE 1.1 b DEMOGRAPHY, POPULATION OF NAGPUR METROPOLITAN IN 2011
- TABLE 1.1 c REGISTRARS REPORTS DATA BY NAGPUR CITY FOR LAST FIVE YEARS
- TABLE 1.2 MICRO VEHICLE POPULATION OWNED IN NAGPUR CITY
- TABLE 1.3 MICRO VEHICLE POPULATION FOR VARIOUS ALIGNMENTS
- TABLE 1.4 BASIS OF THE STUDY DONE BY I&T BARRIDGE CONSULTING ENGINEERS LIMITED
- TABLE 1.5 FINAL ALIGNMENT

#### FIGURES

- FIG. 1.1 LOCATION OF THE PROPOSED NAGPUR MICRO RAIL
- FIG. 1.2 ALIGNMENT 1 OF METRO RAIL LINES PROPOSED BY I&T BARRIDGE CONSULTING ENGINEERS LIMITED
- FIG. 1.3 ALIGNMENT 2 OF METRO RAIL LINES PROPOSED BY I&T BARRIDGE CONSULTING ENGINEERS LIMITED
- FIG. 1.4 ALIGNMENT 3 OF METRO RAIL LINES PROPOSED BY I&T BARRIDGE CONSULTING ENGINEERS LIMITED
- FIG. 1.5 ALIGNMENT 4 OF METRO RAIL LINES PROPOSED BY I&T BARRIDGE CONSULTING ENGINEERS LIMITED



## CHAPTER-1

### INTRODUCTION

#### 1.1 BACKGROUND

##### 1.1.1 FACTS ABOUT NAGPUR

**Nagpur** is the third largest city of Maharashtra and also the winter capital of the state. With a population of approximately 25 lakhs, Nagpur Metropolitan Area is the 13th largest urban conglomeration in India. It has also recently been ranked as the cleanest city and the second greenest city of India. In addition to being the seat of annual winter session of Maharashtra state assembly 'Yashwantrao Chavan Sanstha', Nagpur is also a major commercial and political center of the Vidarbha region. It is also known as "Orange City" for being a major trade center of oranges that are cultivated in the region.

Nagpur lies precisely at the center of the country with the Zero Mile Marker indicating the geographical center of India. The city was founded by the Gondas but later became part of the Maratha Empire under the Bhonsles. The British East India Company took over Nagpur in the 18th century and made it the capital of the Central Provinces and Berar. After the first reorganisation of states, the city lost its capital status but according to the informal "Nagpur Pact" between political leaders, it was made the second capital of Maharashtra. **Nagpur** is also declared, "Tiger Capital of India " as it connects many Tiger Reserves in India to the world.

#### Etymology

The Nag River, a tributary of the Karmali River, flows in a serpentine path and is therefore named "Nag", the Marathi word for snake. And hence, the river and city is named as Nagpur. During British times the city used to be referred to as Nagpore. While others say that the river flows through the old city of Nagpur and hence the city is named after the river. "Pur" is a common suffix given to cities, villages and towns across India, and is after simply translated "city". The seal of Nagpur Municipal Corporation depicts a cobra in the water of a river.



## Geography and Climate

### Geography

Nagpur lies on the Deccan plateau of the Indian Peninsula and has a mean altitude of 310.0 meters above sea level. The underlying rock strata are covered with alluvial deposits resulting from the flood plain of the Karmali River. In some places these give rise to granular sandy soil. In low lying areas which are poorly drained, the soil is alluvial clay with poor permeability characteristics. In the western part of city crystalline metamorphic rocks such as gneiss, schist and granites are found, while in the northern part yellowish sand stones and clays of the lower Gondwana formations are found.

Nagpur city is dotted with natural and man-made lakes with Amazzal lake being the largest. Other natural lakes include Gorewadi Lake and Taralghat lake. Soneganj lake and Dandhalegaon lake are man-made lakes created by the city's historical turn. Nag river, Pich hadi along with canals form the natural drainage pattern for the city. Nagpur is known for its greenery, and was judged as the cleanest and second greenest in India after Chandigarh. Recently, Government of India selected Nagpur as a Model City for National Clean Air Mission by allocating 25 crores for the plan. This project will be handled by Nagpur's own NEERI (National Environmental Engineering Research Institute).

### Climate

As it is located at centre of Indian peninsula far from the Bay of Bengal and the Arabian Sea, Nagpur has a tropical wet and dry climate with dry conditions prevailing for most of the year. It receives an annual rainfall of 1,266 mm (49.84 in) from monsoon rains during June to September. The highest recorded rainfall was 384 mm on 14 July 1994. Summers are extremely hot lasting from March to June, with maximum temperatures occurring in May. Winter lasts from November to January, during which temperatures can drop below 10 °C (50 °F). The highest ever recorded temperature in the city is 49°C, while the lowest is 3°C.

#### 1.1.2 DEMOGRAPHICS

As per provisional reports of Census India, population of Nagpur in 2011 is 2,400,421; of which male and female are 1,226,812 and 1,173,611 respectively. Although Nagpur city has population of 2,431,421, its urban UA / metropolitan population is 2,437,777 of which 1,275,750 are males and 1,222,027 are females<sup>1</sup>. Details of population of Nagpur city and Nagpur Metropolitan Area are given in Table 1.1 A, 1.1B

<sup>1</sup> <http://www.censusindia.co.in/censuscity353/nagpur.html>



Table 1.1 A : Census India, population of Nagpur City in 2011

Nagpur City	Total	Male	Female
Population	2,495,421	1,226,613	1,178,211
Literate	2,812,698	1,360,333	998,239
Children (0-6)	237,386	123,951	114,014
Average Literacy (%)	90.12	96.19	85.29
Sex ratio	961		
Child Sex ratio	921		

Table 1.1 B : Census India, population of Nagpur Metropolitan in 2011

Nagpur Metropolitan	Total	Male	Female
Population	2,437,777	1,275,790	1,222,027
Literate	2,695,419	1,102,638	992,781
Children (0-6)	248,679	129,522	119,158
Average Literacy (%)	93.17	98.20	90.02
Sex ratio	958		
Child Sex ratio	920		

The population growth rate of Nagpur City for last five decades is given in Table 1.1 C below:

Table 1.1 C

Year	Population Nagpur City	Growth Rate (%)
1971	866330	34
1981	1317000	43
1991	1622818	34
2001	2001330	24
2011	2405421	17



### 1.1.3 VEHICLE POPULATION IN NAGPUR CITY (As per Motor Transport Statistics of Maharashtra)

Motor Vehicles Population on Road as on 31st March, 2011 & 31st March, 2012 in Nagpur City are as below:

**Table-1.5\***  
**Motor Vehicles Population in Nagpur City**

S.No.	Category	31st March, 2011	31st March, 2012
1	Motor Cycles	306102	423037
2	Scoters	253320	318889
3	Motoros	283810	283771
<b>TOTAL OF TWO WHEELERS</b>		<b>843232</b>	<b>1025707</b>
4	Motor Cars	89478	99233
5	Jeeps	25244	25727
6	Station Wagons	842	842
7(A)	Taxi motor Rfid	0	0
7(B)	Taxi Tourist Cabs	2881	2907
8	Autocostars	16417	17140
9	Stage Carriages	1741	1741
10	Charred Carriages	730	893
11	School Buses	375	613
12	Private Service Vehicles	1327	1314
13	Ambulances	520	667
14	Art. & M.M.Ven.	806	825
15	Trucks & Lorries	12078	13024
16	Tankers	2275	2500
17	Delivery Van (4 Wheelers)	12878	14183
18	Delivery Van (3 wheelers)	6161	6864
19	Tractors	5385	5400
20	Trailers	5243	5346
21	Others	1153	1345
<b>TOTAL OF ALL TYPES</b>		<b>1157024</b>	<b>1227998</b>

\*MTO Nagpur Figure

### 1.1.4 RAIL AND AIR TRANSPORT IN NAGPUR CITY

A total of 190 trains from various destinations halt at Nagpur. These include various passenger, express, mail Duronto, Rajधान, Duris, Full train. Of these 26 train terminate from Nagpur. Almost 1.3 lakh passengers board/alight daily at different stations in Nagpur. Of which Nagpur Central Station alone is used by approximately 100,000 passengers. Ajni, Beal and Kalamna are other important railway stations within Nagpur. Nagpur Central is mainly used for long distance travel, whereas Ajni, Beal station are used for commuting nearby areas such as Suburb.



**Ramtek etc.** The city is the Divisional Head Quarters for the Central Railway and South East Central Railway Zone of Indian Railways.

The Airport handles around 4,000 passengers per day and caters to 8 Domestic Airlines connecting Nagpur to 12 domestic destinations including Mumbai, Delhi, Pune, Kolkata, Hyderabad, Raipur etc and a few (connecting flights) International Airline to Singapore etc.

### 1.1.5 POINTS FROM OTHER FEASIBILITY SURVEY DONE FOR NAGPUR

**1.1.5.1** The Nagpur Municipal Corporation (NMC) had awarded the project titled "**Preparation of Master Plan/Perspective Plan for Transportation System of Nagpur City 2011**" to L&T-Ramboll Consulting Engineers Limited in June 2007. The study aims to update the long-term transportation strategy for NMC and identify a practicable and effective investment programme up to 2031. Consultants commenced the study in the month of June,2007 and completed in June,2008. L&T-Ramboll Consulting Engineers Limited had carried out the Comprehensive Traffic and Transportation Study and prepared Transportation Master Plan for Nagpur city commissioned by NMC. As a part of study consultants had

1. Reviewed all the relevant secondary data related to landuse, travel pattern and demographics, supply of transport infrastructure and road safety etc. Major traffic generators such as MHAH (Multinodal International Cargo Hub and Airport at Nagpur), Industrial Areas such as Bhatnagar and High etc were taken into account to forecast future population and employment.
2. Conducted primary traffic surveys including household surveys (2% of sample households)
3. Developed Travel demand models using the TRIPS/CUBE Software and calibrated for the base year and using the validated software forecasted travel demand for 2011,2021 and 2031 for two scenarios (do nothing) and do something (improved public transportation scenario)
4. Based on the outputs of travel demand models and studying the availability of present transportation infrastructure consultants have recommended short term,medium term and long term improvement projects to be implemented from 2008-2031.

### 1.1.5.2 Salient Features of Nagpur Current Traffic and Transportation Scenario (L&T-Ramboll study) :

- Nagpur is the second capital of Maharashtra and is located in the geo-geographical centre of India with good road and rail network.
- Nagpur acts as transportation place for areas like Chhattisgarh and Eastern Maharashtra.
- 2008 population of NMC as 24.47 lakhs and average density as 112/sq.ft. (as per report)



- Main public transport providers are MRTC DOT bus operator (Star Bus).
- Poor public transportation system (less than 5% of the total trips).
- Non-motorised modes walk and bicycle constitutes 56% of total trips.
- Motorised transport is dominated by two wheelers (29%).
- Predominant on-street parking and absence of off-street parking facilities.
- Current Vehicle Ownership is 11.57 lakh in which 5.57 lakh are two wheelers.
- Poor mobility in some of the areas such as Nagpur.
- Absence of truck terminals at Nagpur is proposed as Future Road Corpn hub.
- Development of Multi-Modal Hub Airport in Nagpur (MHN) @ 4254 hectares is underway.

#### 1.1.5.3 Some of the important findings of the L&T-Ramboll study are as follows :

- Forecasted population of NMC by for 2021 and 2031 is 23.4 lakh and 42.7 lakh respectively.
- Forecasted Employment of NMC by for 2021 and 2031 is 12.4 lakh and 16.8 lakh respectively.
- MHN is going to generate around 2.6 lakh employment by 2015 (fully operational) and 4.3 lakh by 2031.
- Total trips made by the residents of Nagpur in 2007 is 25.57 lakh (without intra-zonal) and expected to increase to 55 lakh by 2031.

#### 1.1.5.4 Transportation improvement proposals (L&T-Ramboll study) are broadly classified into three categories based on the time horizon:

- Short Term Improvement Proposals (2008-2009)
- Medium Term Improvement Proposals (2009-2021)
- Phase-I (2009-2011)
- Phase-II (2012-2018)
- Phase-III (2017-2021)
- Long Term Improvement Proposals (2020-2031)

#### 1.1.5.5 Some of the important proposals recommended by L&T-Ramboll Consulting Engineers Limited are:

- Improved bus system with a fleet consisting of Standard buses and Mini-buses. Standard buses will serve the major corridors whereas mini-bus services act as a feeder services and low demand corridors. In Short term (with in a year) fleet size of 375 buses (225 Standard buses and 50 mini-buses) needs to be deployed to serve 2.5 lakh passengers per day. In medium term (with 2 to 3 years) 500 buses needs to be deployed to serve 5 lakh passengers/day. In long term say by 2010, 750 buses needs to be deployed to serve 7.5 lakh passengers/day. Coverage Area of Buses should be improved to 90% (At present it is less than 40%).
- Improved pedestrian facilities with min 2.5 m footpaths and FCBs/Subways.
- Bicycle lanes on pilot scale on several wide roads.



- Off-street parking facilities near important areas such as commercial areas, office areas, special generators such as religious places etc on PPP model especially in District, Dabur areas, Transport terminals and at Ganaspeth bus terminal.
- Construction of ROBU/RT/BRT/Buses across the city/town.
- Development of Inner Circle ring road and Alternative north-South corridor to take predominately north-south demand.
- Improvement of Radial Roads such as Warcha Road to 6-lane configuration from existing 4-lane configuration by 2016.
- Inner Ring Road to be improved to 6-lane configuration with service road by 2016.
- Outer ring road to be planned after 2015. It will be funded by State and Central Governments.
- Construction of MRTS in phases 2012-16 and 2017-2021. It is envisaged 85 km of MRTS and 20 km commuter rail by 2031.
- Development of Truck Terminal at War place on PPP basis at Inner Outer Ring Road.
- Creation of public transport infrastructure bus terminals/depot/flow procurement etc.
- Environment friendly policies such as use of CNG, favourable policies for public transport, more conducive environment for walking and bicycles.
- Development of Bus Terminal/Transport Terminal at Outer ring road.
- Additional BRTS/ MRTS Corridors in long term.
- Road Corridor parallel to Railway line to come north-south traffic (feasibility to be ascertained)
- Development of Commuter rail system from Nagpur city to Buldhur on the similar lines of Multi-Modal Transport System (MMTS) in Hyderabad.
- Rural Area redevelopment.

#### 1.1.2.6 MRTS Corridors Proposed by L&T/Ramboll Consulting Engineers Limited

Several corridors of MRTS were studied and presented by L&T/Ramboll Consulting Engineers Limited, in their report.

Four different MRTS options were considered. The description of each alignment was presented in Chapter 4 of their report. Four different MRTS alignment options considered are:

**Alignment-1** - Ford Naka to Dahagpur ( 24.54 km with 25 Stations). The alignment option -1 starts at Ford Naka and ends at Dahagpur. It passes through Central Avenue road, Central railway station, Ganaspeth Bus stand, Medical Chowk, Manikwada Jn etc. (Fig-1.2)

**Alignment-2** - Automotive Square to Dahagpur ( 23.54 km with 24 Stations). The alignment option -2 starts at Automotive Square and ends at Dahagpur. It





passes through Kamptee road, Inam railway station, Central Avenue road, Medical Chowk, Manawada Jn etc. (Fig -1.3)

**Alignment-5** : Transport Plaza to Dohgaon predominantly on NH-7 ( 27.3 km with 26 Stations) The alignment option 3 starts at Automotive Square and ends at Dohgaon. It passes through Indira, LIC Square, Raathurichand Park, Central railway station, Zero mile, Sitabul, NEERI, Chhatrapati Square, Manawada Jn etc. (Fig -1.4)

**Alignment-6** : Transport Plaza to Dohgaon partially on NH-7 ( 24.2 km with 24 Stations) The alignment option 4 starts at Transport Plaza and ends at Dohgaon. This alignment option is combination of options 2 & 3. It passes through Mahendra Nagar, Indira, Gadigodam, Central railway station, CRSI Depot, Medical Chowk, Manawada Jn etc (Fig -1.6)

- 1.1.2.7 From the study done by L&T-Rambol Consulting Engineers Limited : Ridership for four MRTS alignments are worked out and presented in Table below. It can be observed that Alignment -1 is giving highest ridership compared to other three options. The nearby estimation for option 3 is 1.55 lakh in 2011.

**Table-1.3 Ridership Estimation for various Alignments**

(Based on the study done by L&T-Rambol Consulting Engineers Limited)

Year	Alignment -1	Alignment -3	Alignment -2	Alignment -4
2011	115400	12000	177200	131347
2021	230000	19000	300040	218013
2031	325746	279640	489170	311738

### 1.1.8 ALIGNMENTS PROPOSED BY DMRC IN JULY-2012 DPR

In early 2012 Nagpur Improvement Trust (NIT) requested DMRC to provide Consultancy services for preparation of a Detailed Project Report for Metro Rail System in Nagpur, Maharashtra initially for 30 Km which was revised to 42 Km in July 2012. Thereafter, DMRC has conducted Traffic Surveys, Topographical Surveys, Geotechnical Investigations and Environment Impact Assessment Survey.

Based on the different types of surveys done by DMRC, main alignments has been finalized after repeated inspection of the road network, intersections, passenger traffic flow, traffic congestion, connectivity to important landuses.

Alignment of routes proposed by DMRC were as follows



Table 1.4 Alignment Proposed by DMRC

Alignment	Detail Route
Alignment-1 North-South Corridor (21.859 km, 17 Stations)	Automotive Square, along Kharoloo Road, Wartha Road, Variety Square to Abhyankar Road, along Nag River alignment will fall on Hurlpyard Road, Kanaka Colony Road, Wartha Road, Khoria Road, Airport, MHAN Area
Alignment-2 East-West Corridor (18.265 km, 10 Stations)	From Prajapati Nagar, along Central Avenue Road, Railway Feeder Road, Munje Chowk, Jhansi Ramesh Chowk, North Ambekar Road, Hingla Road, Lakshmi Nagar

## 1.2 FINAL ALIGNMENT FOR NAGPUR METRO

On 23.08.2013, a meeting presided by Shri S R Lohia, JS-MOUD/GOI was held at Nagpur to discuss the DPR. In that meeting, JS-MOUD/GOI expressed that the FIRR of the project should be at least 8%. Recently, MUCD has also issued advisory that FIRR of Metro Project should not be below 8%.

On 1.10.2013, a presentation on the DPR was made by M/s MIT to The Chief Minister, Government of Maharashtra. He was of the opinion to avoid underground alignment in MHAN and also construct Maintenance Depot in the land belonging to State Govt Land. Subsequently, on 21.10.2013, a joint inspection of the NS corridor was done by UCAMD-MUCD, Chairman MIT, and Director Business Development-DMRC.

The original alignment of Corridor-1 proposed was passing through Khoria Road, Airport Area after Sahakar Nagar and finally was ending at MHAN. The alignment up to Old Airport Station was elevated, then for a length of 3.30 km, it was underground with one underground station named as New Airport Station and again elevated in MHAN Area. Since the cost of underground section of the alignment is much more than the elevated section or the section at grade, alternative alignment was suggested for cost reduction, enhancement in RFPCT and to increase FIRR so that project becomes financially and economically viable.

The new proposed alignment suggested in the above inspection, was to pass through a 24m wide road adjacent to London Street after Sahakar Nagar Junction and was proposed to be taken to the east along 24m wide road one London Street up to Wartha Road. From the intersection at Wartha road, the elevated alignment was proposed to be on the central divider on the Wartha Road. After crossing existing intersection point of Wartha Road & Airport Road, the alignment was to be shifted to the MHAN area. Alignment in this portion was proposed to be at grade and to run parallel to Wartha road upto ROB and existing railway line thereafter up-to proposed Car depot.



B.U. while working on the modification of alignment, it was noticed that a very large number of properties were falling along the alignment due to sharp curves at the junction of Bahadur Nagar & 24 m wide road and also at the junction of 24m wide road & Wardha Road. Acquiring of these properties will be very tough and may delay the whole project.

Hence to avoid all such situation, it has been decided to take the alignment on Wardha Road only without going on Khemta Road.

Finally, NS Corridor will pass through Wardha Road after Congress Nagar Metro Station. After crossing existing intersection point of Wardha Road & Airport Road, the alignment will be shifted to the MHAN area. Alignment in this portion will be at grade and will run parallel to Wardha road upto ROG and parallel to railway line thereafter upto proposed Cor-depot. 4km wide stretch of land between the railway boundary line and the road near proposed Container Depot of Container Corporation of India Ltd. will be affected by the proposed alignment of the Metro Rail as the proposed alignment passes through this stretch of land. 73 Ha land is available on the west side of railway line and south of existing flyover near airport station. Average width of this land is about 80m and is about 1800m long. This MOC land may be utilized for Car Depot. Similarly, Depot of EW Corridor has also been shifted to SRP Land near proposed Lokmanya Nagar Metro Station.

This has caused creation of few water processed metro stations on NS Corridor and addition of new stations on the same.

Final alignment for both the corridors is as below :

Table 1.8 FINAL ALIGNMENT

Alignment	Detail Route
<b>Alignment-1</b> North-South Corridor (16.658 km, 17 Stations)	Subhash Square, along Kamptee Road, Wardha Road, Vasthi Square to Abhyankar Road, along Nag River alignment will fall as Hampden Road, Rahata Colony Road, Wardha Road, Parallel to Railway Line, Khemta Station and finally in MHAN Area near cancer depot
<b>Alignment-2</b> East - West Corridor (18.567 km, 10 Stations)	From Pimpri Nagar, along Central Avenue Road, Railway Paster Road, Mynda Chowk, Jhansi Kames Chowk, North Anandhar Road, Hingra Road, Lokmanya Nagar

Index Plan of the Proposed Nagpur Metro Rail is put up at Pg. No. 1.1



### 1.3 THE STRUCTURE OF THE DETAILED PROJECT REPORT

The report contains the chapters as mentioned below:

CHAPTER NO.	DESCRIPTION
Chapter-1	Introduction
Chapter-2	Traffic Demand Forecast
Chapter-3	System Selection
Chapter-4	Geometric Designing Parameters & Alignment Description
Chapter-5	Civil Engineering
Chapter-6	Station Planning
Chapter-7	Train Operation Plan
Chapter-8	Rolling Stock
Chapter-9	Power Supply, System of Traction And Power Toff
Chapter-10	Maintenance Depot
Chapter-11	Signaling System
Chapter-12	Telecommunication & Automatic Fare Collection
Chapter-13	Disabled Friendly Features
Chapter-14	Environmental Impact Assessment
Chapter-15	Security Measures for a Metro System
Chapter-16	Disaster Management Plan for a Metro Rail System
Chapter-17	Multi-modal Transport Integration
Chapter-18	Cost Estimate
Chapter-19	Financing Options, Fare Structure And Financial Viability
Chapter-20	Economic Appraisal
Chapter-21	Implementation Strategy
Chapter-22	Conclusion



**Fig : 1.1**  
**Index Plan of the Proposed Nagpur Metro Rail**





Fig. 1.2

Alignment 1 of MRT4 Corridors Proposed by L&E-Ramboll Consulting Engineers Limited






Fig. 1.0  
Alignment 2 of MRT3 Corridors Proposed by LRT Ramboll Consulting Engineers Limited






Fig-1.4

Alignment-3 of MRT3 Corridor Proposed by LST-Ramboll Consulting Engineers Limited








Fig -1.6

Alignment 4 of MRT3 Corridor Proposed by LST Ramboll Consulting Engineers Limited



# CHAPTER 2

## TRAFFIC DEMAND FORECAST



2.1	INTRODUCTION
2.2	POPULATION OF NAGPUR
2.3	ECONOMY OF NAGPUR
2.4	CARGO HUB AND AIRPORT AT NAGPUR (MHAN)
2.5	TRAFFIC VOLUME COUNT (TVC) AND PASSENGER OCCUPANCY SURVEYS (PCS)
2.6	MODE SHARE
2.7	TERMINAL SURVEY RESULTS
2.8	TERMINAL PASSENGER INTERVIEW
2.9	WORK PLACE SURVEY
2.10	INTERVIEW OF WORKERS
2.11	TRIP FORECASTING USING TRAFFIC MODELS
2.12	TRIP END ESTIMATION
2.13	TRIP DISTRIBUTION
2.14	MODAL SPLIT
2.15	WHEEL SANDON MODAL SPLIT AND DISTRIBUTION
2.16	TRIP ASSIGNMENT
2.17	DAILY RIDERSHIP ESTIMATION
2.18	NAGPUR METRO ALIGNMENT PLAN
2.19	REMARKS OUTPUT
2.20	DAILY RIDERSHIP
2.21	NOTE ABOUT MHRN
2.22	EFFECT OF MHRN ON PROPOSED METRO RIDERSHIP
2.23	FUTURE DEVELOPMENTS
2.24	ESTIMATION OF RIDERSHIP FOR FINAL ALIGNMENTS
2.25	TAJ BOARDING AND FARE

### TABLES

TABLE 2.1A	CENSO 2011, POPULATION OF NAGPUR CITY IN 2011
TABLE 2.1B	CENSO 2011, POPULATION OF NAGPUR METRO POLITICAL REGION
TABLE 2.2	VEHICULAR TRAFFIC DETAILS AT 40 DIFFERENT LOCATIONS - NAGPUR
TABLE 2.3	FAST BUSSEY PASSENGER DETAILS AT 40 DIFFERENT LOCATIONS - NAGPUR
TABLE 2.4	TRAFFIC FLOW IN PULL ON NORTH - NORTH DIRECTION
TABLE 2.5A	TRAFFIC FLOW IN PULL ON EAST - WEST DIRECTION
TABLE 2.5B	TRAFFIC FLOW IN PULL ON EAST - WEST DIRECTION
TABLE 2.6	STATIONING MODAL SPLIT ON THE BOARDING AND ALIGHTING PASSENGERS
TABLE 2.7	EXTERNAL TRIPS IN NAGPUR CITY
TABLE 2.8	DAILY VARIATION OF TRIP FOR NAGPUR METRO SYSTEM
TABLE 2.9	DAILY VARIATION OF TRIP FOR NAGPUR METRO SYSTEM
TABLE 2.10	MODE SHARE BY EXTERNAL PASSENGER
TABLE 2.11	FREQUENCY OF TRIP MADE BY EXTERNAL PASSENGER
TABLE 2.12	DISTRIBUTION OF EXTERNAL PASSENGER
TABLE 2.13	FUTURE OF THE EXTERNAL TRIP

TABLE 1.17	TRIP LENGTH FREQUENCY OF WORKERS
TABLE 1.18	WORKERS INCOME BY WORKERS
TABLE 1.19	MODE LOSS BY THE WORKERS
TABLE 1.20	POPULATION GROWTH AND EMP PRODUCTION IN LAHSI URBAN DEVELOPMENT REGION YEAR
TABLE 1.21	URBAN MODE SHARE
TABLE 1.22	SUBURBAN OUTPUT (I)
TABLE 1.23	SUBURBAN OUTPUT (II)
TABLE 1.24	URBAN EMPLOYED
TABLE 1.25A	DAY BOARDING ON LINE 1 FROM AJITHA/VALE TO MEGAN
TABLE 1.25B	DAY BOARDING ON LINE 2 FROM PULJAPATI NAGAR TO LOKMANYU NAGAR
TABLE 1.26	YEAR WISE BOARDING ON LINE 1 AND LINE 2
TABLE 1.27	PERIT LINE LOAD ON LINE 1 FROM AJITHA/VALE TO MEGAN
TABLE 1.28	PERIT LINE LOAD ON LINE 2 FROM PULJAPATI NAGAR TO LOKMANYU NAGAR
TABLE 1.29	ANNUAL POPULATION AND EMPLOYMENT IN MEGAN
TABLE 1.30	REVENUE FROM HUMAN STATIONS
TABLE 1.31	SAPUR METRO RAIL PROJECT'S OVERVIEW
TABLE 1.32	SIMILARITY OF ADDRESS OF (A) LINE 1 AND LINE 2
TABLE 1.33	DAY BOARDING ON LINE 1 AND LINE 2 STATIONS
TABLE 1.34	LINE 1 PERIT FROM AJITHA/VALE TO MEGAN
TABLE 1.35	LINE 2 PERIT FROM PULJAPATI NAGAR TO LOKMANYU NAGAR
TABLE 1.36	COMPARISON OF SALIENT FEATURES BETWEEN TWO ALTERNATIVES (YEAR 2021)

## FIGURES

FIG. 1	VIEW OF SAPUR, IS THE GEOGRAPHICAL CENTER OF MEGA
FIG. 2	BUILDING UNDER CONSTRUCTION MEGAN
FIG. 3	MEGAN ADMINISTRATIVE OFFICE
FIG. 4A	VIEW FROM SAPUR
FIG. 5	NORTH-SOUTH DIRECTIONAL FLOW (I)
FIG. 6	EAST-WEST DIRECTIONAL FLOW (I)
FIG. 7	PROPOSED PLANS AT DIFFERENT LOCATIONS IN SAPUR (I) (MILLER)
FIG. 8	OVERALL NORTH-SOUTH DIRECTIONAL FLOW
FIG. 9	PLANS FOR SITE NORTH WEST OF CHANDRANA (COLLEGE REGIONAL ROAD)
FIG. 10	PLANS FOR SITE NORTH WEST OF VERDANT (TECHNOLOGICAL REGION)
FIG. 11	PLANS FOR SITE NORTH WEST OF HILL OF PARADE (RECREATIONAL REGION)
FIG. 12	MODE SHARE USING PAVEMENT VEHICLES BY TYPE OF MOTOR
FIG. 13	MODE SHARE BETWEEN PUBLIC AND PRIVATE PAVEMENTS VEHICLES WITH METRO
FIG. 14	ALIGNMENT OF SAPUR METRO PROJECT (YEAR 2021)
FIG. 15	FINAL ALIGNMENT



## CHAPTER 2

### TRAFFIC DEMAND FORECAST

#### 2.1 INTRODUCTION

Nagpur Improvement Trust (NIT) has entrusted the job of preparing Detail Project Report (DPR) for Nagpur Metro Rail<sup>1</sup> to Datta Metro Rail Corporation (DMRC).

Traffic Study and Ridership estimation are the first tasks in DPR which imply finalizing a feasible alignment plan of the proposed metro network and then locating terminal and interchange metro stations (if any). After that, Ridership Estimation is done. Estimating daily and peak hour boarding and alighting from each station, daily link load and PMPDT, the loads put together is called Ridership Estimation<sup>2</sup> are estimated. These estimates are primary inputs to other important estimates such as station design, train operation plan, estimate of revenue collector, benefits of metro, rolling stock and many other estimates including DPR and PRR.

Alignment is finalized after repeated inspection of the road network, intersections, passenger traffic flow, traffic congestion, connectivity to important edifices, Road roads

<sup>1</sup> The Nagpur Metro Rail project is sanctioned by the state government of Maharashtra for the city with the estimate of ₹ 3,000 Cro and ₹ 200 Cro. Budget for its two phases of 21 km (from Datta Road to Nagpur and Nagpur to Airport) and 10 km (Datta Road to Chhatrapati Square in Nagpur) respectively. Consultant Datta Metro Railways Corporation (DMRC) will study the alignment and submit a detailed project report.

The site inspection for a study begun in March 2011 with the initiative from Nagpur Improvement Trust (NIT). The ₹ 10,000 crore project will be executed by a new company called Nagpur Metro Transport Co Ltd (NMTC), formed under the NIT, BMC, Maharashtra Urban Development Corporation (MUCD) i.e. that is currently developing the Metro project – BMC and MUCD are the other participating organizations. Source:

[http://www.bmcnagpur.org/links/nagpurmetro\\_mmr03112011.pdf](http://www.bmcnagpur.org/links/nagpurmetro_mmr03112011.pdf)

are normally avoided for alignment to avoid relocation, land purchase and demolition of buildings. Sharp bends are avoided. Underground construction is considered only when necessary space for elevated link is not available or such construction is prohibited in the area.

Stations are located near large road intersections so that passenger from all directions can access the station. In general, interstation gap is kept between 0.5 to 1.5 km. Engineering feasibility of the alignment is considered simultaneously.

In this particular (Nagpur) study, a few traffic and land use related physical surveys were undertaken. These are (1) Traffic Volume Count (TVC) and Passenger Occupancy Survey (POC) at mid block sections, screen lines and major corridor points, (2) Bus and Rail Mode passenger Terminal Survey and (3) Work Place Survey. Several important outputs were derived which will be shown in subsequent paragraphs.

Secondary data which were collected include past and present population of Nagpur Urban Agglomeration, ward wise population of Nagpur City, Road and Rail Network within Nagpur and Future Land Use Map of Nagpur. For verification purpose, Google Earth website has been used.

Road Network and Landuse Map of Nagpur were geo coded and digitised layers were created using TransCad Software.

## 2.2 POPULATION OF NAGPUR

As per provisional reports of Census India, population of Nagpur in 2011 is 2,405,421, of which male and female are 1,226,610 and 1,178,811 respectively. The sex ratio of Nagpur city is 965 per 1000 males. In education sector, total literates in Nagpur city are 2,018,598 of which 1,065,395 are males while 953,203 are females. Average literacy rate of Nagpur city is 93.13 percent of which male and female literacy was 96.16 and 89.86 percent. Total children (0-6) in Nagpur city are 207,865 as per figure from Census India report on 2011. There were 125,661 boys while 114,014 are girls. Child sex ratio of girls is 921 per 1000 boys. Nagpur city is governed by Municipal Corporation which comes under Nagpur Urban Agglomeration. Although Nagpur city has population of 2,405,421; its urban / metropolitan population is 2,497,777 of which 1,275,796 are male and 1,222,027 are female<sup>1</sup>.

Another positive outcome for Nagpur region is the Decadal Growth Rate of population. It has come down from 23.74 in the last decade (1991-2001) to 14.36 in 2001-2011. Nagpur region added the least number of people in its population in the decade than any other<sup>2</sup>.

<sup>1</sup> <http://www.census2011.co.in/data/ward/pop300-nagpur.htm>

<sup>2</sup> <http://www.mh.21.com/nagpur/about-nagpur/nagpur-general-485-population-census-2011/>

In 2011, the urban population was 2,129,303, and there were around 418,000 households in the city. 728,664 people lived in slums making Nagpur second-most slum-populated city in Maharashtra after Mumbai. Scheduled Caste and Scheduled Tribes accounted for around 9% of the population<sup>1</sup>.



Figure 2.1:

Zero Mile Nagpur, is the Geographical center of India

## 2.3 ECONOMY OF NAGPUR<sup>2</sup>

Nagpur has been the main center of commerce in the Vidarbha region since early days and is an important trading location. However, Nagpur's economic importance had gradually declined relative to Mumbai and Pune after the merging of Vidarbha into the Maharashtra because of a period of neglect by the state government. During the slowdown, state and central government offices were a major source of employment in the city. Nagpur's economy is now recovering from just slowdowns and city has attracted Rupees 5,000 crore in investment in 2008. The city is important for the banking sector as it hosts the regional office of **Reserve Bank of India**, which was opened on September 12, 1956. **Shabud** market in central Nagpur, known as the Heart of the city, is the major commercial market area of city.

The **Subbari** industrial area is the largest in all of Asia in terms of area. The world's largest unit is of Indo Rama Synthetics, which manufactures synthetic polyester yarn. Other units in Subbari include the power transmission company KEC, Hyundai Unilack, ACC Nilkar Castings Ltd, Koradi Thermal Power Station and Kharakhada Thermal

<sup>1</sup> <http://en.wikipedia.org/wiki/Nagpur>

<sup>2</sup> <http://www.eco-economy.com>

**Power Station** are the two major thermal power stations located near Nagpur and operated by MPPCL.

The Hingra Industrial estate located on the western fringe of the city is made up of around 600 small and medium industrial units. The major ones among them are tractor manufacturing plant of **Manindra and Manindra**, casting units of **NECO Ltd.** (the country's largest casting group), units of **International Combustion**, **Rajaj Auto group**, **Cordeo** (the **SECOND** largest confectionery manufacturing plant in India ), **Apna** stationery and **Sanyoj Group** (largest steel wire group of companies for long products in Central India). Nagpur is home to top-brand manufacturer **Dishdale**, Indian dry food manufacturer **Hatsimom's** and **Ajwa** water product company **Vest**.

## 2.4 CARGO HUB AND AIRPORT AT NAGPUR (MHAN)

Nagpur is witnessing an economic boom as the "Multi-modal International Cargo Hub and Airport at Nagpur (MHAN)" is being developed. MHAN will be used for handling heavy cargo coming from south east Asia and the Middle East. The project will include Indian rupee ₹10,000 crore (US\$2.17 billion) Special Economic Zone (SEZ) for Information Technology (IT) companies. **Parasoft Systems** has one of the software development centres at Nagpur.

**MHAN - Multi-modal International Cargo Hub and Airport at Nagpur** is the biggest economical development project currently underway in India in terms of investment. **MHAN** is spread over an area of 4354 Hectares. **MHAN** is an ideal business hub, located in **Nagpur**, the geometrical centre of India and easily accessible to all the major cities of India as well as the world.

**MHAN** Project consists of two parts namely **International airport** to act as a **cargo hub** and a **Special Economic Zone SEZ** with residential zone covering a total area of 40.28 sq. km on the southern end of Nagpur. Maharashtra Government formed a special purpose entity in the name of **Maharashtra Airport Development Company (MADC)** for development of **MHAN**. The project is financed by multiple Indian banks with total loan amount of **₹4R 3,000 million** along with investment from state government and Airport Authority of India. With a projected target of serving 14 million passengers and handle 0.07 million tones of cargo this is one of largest aviation project in India. The estimated capital cost of the project is **₹4R 200 crore** (by year 2030) and is supposed to generate revenues **₹4R 220 crore** (**Nagpur**).

A new **Nagpur SEZ** of 2080 hectares, largest multi-product SEZ in India, would be built along side the airport. Out of 2080 hectares, 1470 hectares would be used by various processing units to be set-up and remaining 610 hectares for service sector unit. Like all SEZs it will have financial incentives and soft taxation policy to attract investment. The initial set-up material for these units and later use material will be duty-free.



Figure 2.2:  
Buildings under construction MIHAN



Figure 2.3: MIHAN Administrative Office



## 2.5 TRAFFIC VOLUME COUNT (TVC) AND PASSENGER OCCUPANCY SURVEYS (PCS)

To understand traffic characteristics in terms of vehicular, passenger and PCU, 40 traffic count stations were identified, some of which are mid block sections, some locations were fixed as screen line points and some were as outer vordon points<sup>6</sup>. In table 2.1, total traffic flow for all 40 locations and for both direction in terms of PCU is given. In table 2.2, a grouped vehicular traffic volume of fast, slow (NMT) and goods vehicles for all 40 locations is given. Nagpur being located at a central position, many inter-city and inter-state bus routes pass, an separate column is given for such trips (axial bus routes). In figure 2.4, TVC locations are shown.



Figure 2.4 TVC points in Nagpur

Table 2.1  
Direction wise PCU Traffic details at Nagpur

Lic.No.	Lic. Name		Direction	Traffic PCU	Peak PCUs	Peak Hour (%)
1	Wireless land ringra road	E-W	Nagpur to Hingna	5,480	680	9.92%
1	Wireless land ringra road	W-E	Hingna to Nagpur	5,233	630	9.67%
2	Ambedkar Tera North	E-W	Nagpur to	8,964	717	9.99%

<sup>6</sup> Screen line points are given in Appendix

Loc.No	Loc. Name		Direction	Traffic PCU	PCAR PCUs	Peak Hour (%)
			Hingna			
2	Ambabhai Tank North	W-E	Hingna to Nagpur	8,204	740	10.00%
3	CA road near Fly off	E-W	Bhandara to Nagpur	12,440	1,074	8.10%
3	CA road near Fly off	W-E	Nagpur to Bhandara	13,800	1,002	8.12%
4	Roadside Road Control Jct	E-W	Am to Wartha	13,496	1,141	10.01%
4	Roadside Road Control Jct	W-E	wartha to am	14,300	1,342	11.22%
5	Wireless - Amravati Road	E-W	nagpur to amravati	12,424	1,300	12.77%
3	Wireless - Amravati Road	W-E	amravati to nagpur	11,500	1,001	9.92%
6	Grid Road - near subhead rd intersection	N-S	nagpur to wartha	13,300	1,180	9.87%
6	Grid Road - near subhead rd intersection	S-N	wartha to nagpur	11,848	1,381	11.42%
7	Kisor road - near slabsud	E-W	greshpath to zero mile	13,300	1,304	12.00%
7	Kisor road - near slabsud	W-E	zero mile to greshpath	15,939	1,389	10.20%
8	Bus stand - Wartha road	N-S	zero mile to mumbai	10,074	1,303	9.99%
8	Bus stand - Wartha road	S-N	mumbai to zero mile	14,916	1,469	10.49%
9	Roadside north Tagers Bldg	N-S	vco to mahalsdigh	5,022	526	9.79%
9	Roadside north Tagers Bldg	S-N	mahalsdigh to vco	7,080	704	12.01%
10	Hotel pad - Wartha road	N-S	dahli to zero mile	10,502	1,400	9.70%
10	Hotel pad - Wartha road	S-N	zero mile to dahli	17,040	1,483	10.00%
11	Old secretariat - Palm road	E-W	nagpur to amravati	6,614	800	12.00%
11	Old secretariat - Palm road	W-E	amravati to nagpur	6,977	670	9.69%
12	Mahachowda - Kabi road	E-W	nagpur to kabi	8,000	500	9.01%
12	Mahachowda - Kabi road	W-E	kabi to nagpur	7,180	592	9.00%
13	Kasturba park - palm road	N-S	nagpur et to mumbai	8,300	740	9.49%
13	Kasturba park - palm road	S-N	mumbai to nagpur et	8,000	800	10.00%
14	Moly crane - Road along	E-W	nagpur et to vco	11,374	870	9.40%

Loc.No	Loc. Name		Direction	Traffic PCU	PCAR PCUs	Peak Hour (%)
	Kastur zone					
14	Holy cross - Road along Kastur zone	W-E	cast to nagpur	12,002	874	8.03%
15	Chandwara Road and Mount Road E	N-S	cast to nagpur	17,269	1,157	8.93%
16	Chandwara Road and Mount Road K	S-N	nagpur to cast	10,520	1,237	9.38%
16	Chandwara Road Raj Shaver	N-S	cast to nagpur	11,509	943	9.09%
16	Chandwara Road Raj Shaver	S-N	nagpur to cast	13,200	1,199	10.09%
17	Near Rly stn - Gundwara Kamplax road	N-S	nagpur to nagpur	13,166	1,210	9.01%
17	Near Rly stn - Gundwara Kamplax road	S-N	nagpur to kamplax	13,794	2,010	14.44%
18	Cradock road - mohinpur	E-W	chandwara to nagpur	5,301	340	9.17%
18	Cradock road - mohinpur	W-E	nagpur to chandwara	6,290	494	9.32%
19	Indore - Kamplax road	E-W	chandwara to nagpur	10,733	1,130	9.08%
19	Indore - Kamplax road	W-E	nagpur to kamplax	10,634	1,035	7.98%
20	Adarsh Vidya Mandir society-CA Road	E-W	chandwara to nagpur	13,094	1,032	8.99%
20	Adarsh Vidya Mandir society-CA Road	W-E	nagpur to chandwara	13,900	1,094	7.95%
21	Before intersection of CA Road and Factory	E-W	chandwara to nagpur	12,932	1,232	11.34%
21	Before intersection of CA Road and Factory	W-E	nagpur to chandwara	11,012	940	9.72%
22	Jawahar Nagar - West Boundary road	E-W	chandwara to nagpur	9,008	1,216	14.61%
22	Jawahar Nagar - West Boundary road	W-E	nagpur to chandwara	11,037	900	9.07%
23	Ayu College - UNRED Road	E-W	unred to nagpur	9,000	700	9.00%
23	Ayu College - UNRED Road	W-E	nagpur to unred	7,997	790	10.49%
24	Somwarpath - Roge Road	E-W	unred to ajpi	11,741	771	9.31%
24	Somwarpath - Roge Road	W-E	ajpi to unred	13,889	1,000	11.08%
25	Railway quarters - Ajpi Road	E-W	unred to ajpi	17,430	1,290	10.99%
25	Railway quarters - Ajpi	W-E	ajpi to unred	15,141	1,132	10.27%

Loc. No.	Loc. Name		Direction	Traffic PCU	PCAN PCUs	Peak Hour (%)
	Road					
26	Rohasli colony - Wartha Road	N-S	negaur to wartha	16,641	1,204	7.20%
26	Rohasli colony - Wartha Road	S-N	wartha to negaur	14,979	1,397	10.24%
27	Near 661 ATM - North Ambahani Road	E-W	negaur to tingra	13,912	1,000	10.34%
27	Near 661 ATM - North Ambahani Road	W-E	tingra to negaur	14,898	984	6.59%
28	Gonzaga - AMRAWATI road	E-W	negaur to arnavat	14,303	1,175	8.42%
28	Gonzaga - AMRAWATI road	W-E	arnavat to negaur	14,500	3	0.00%
29	Hindustan colony - Arnavat road	E-W	negaur to arnavat	8,909	750	8.18%
29	Hindustan colony - Arnavat road	W-E	arnavat to negaur	8,211	673	8.09%
30	PKD quarters - Kato road	E-W	negaur to kato	9,348	721	8.44%
30	PKD quarters - Kato road	W-E	kato to negaur	10,000	621	6.05%
31	Manta Hospital - Chindwara road	N-S	rahi to negaur	8,066	695	8.60%
31	Manta Hospital - Chindwara road	S-N	negaur to rahe	11,329	1,099	10.74%
32	Mankapur - Chindwara road	N-S	rahi to negaur	7,267	630	8.67%
32	Mankapur - Chindwara road	S-N	negaur to rahe	8,946	734	8.62%
33	Before intersection between Kumbha Road	E-W	simples to negaur	19,231	1,800	9.37%
33	Before intersection between Kumbha Road	W-E	negaur to simples	12,493	1,491	10.29%
34	Dampansay Garden - CA road	E-W	rahaibara to negaur	10,750	790	8.21%
34	Dampansay Garden - CA road	W-E	negaur to rhaibara	9,723	800	8.80%
35	Tasbagh - United Road	E-W	united to negaur	7,100	630	8.75%
35	Tasbagh - United Road	W-E	negaur to united	8,080	627	8.82%
36	Vivekanandnagar - Wartha road	N-S	negaur to wartha	19,134	1,491	8.82%
36	Vivekanandnagar - Wartha road	S-N	wartha to negaur	17,939	1,591	10.89%
37	Aerodrome - Wartha Road	N-S	negaur to wartha	13,710	1,062	10.54%
37	Aerodrome - Wartha	S-N	wartha to	12,300	1,062	8.59%

Loc.No	Loc. Name		Direction	Traffic PCU	PEAK PCUs	Peak Hour (%)
	Road		nagpur			
38	Vivekanand Nagp-Khanna Road	N-S	nagpur to khanna	7,208	594	10.03%
38	Vivekanand Nagp-Khanna Road	S-N	khanna to nagpur	7,078	594	9.99%
39	Unkhana- Nag Road	E-W	aji to khanna	8,960	1,283	10.73%
39	Unkhana- Nag Road	W-E	khanna to aji	8,773	699	9.99%
4E	Rosary College-Hingra Road	E-W	Nagpur to Hingra	10,347	676	8.40%
4E	Rosary College-Hingra Road	W-E	Hingra to Nagpur	9,000	710	9.97%

**Table 22**  
vehicular Traffic details at 40 different locations - Nagpur

TVC Location No	DIRECTION	EAST-BOUND TRAFFIC WITH EXTERNAL BUSES	EAST-BOUND TRAFFIC WITHOUT EXTERNAL BUSES	WEST BOUND TRAFFIC WITH EXTERNAL BUSES	WEST BOUND TRAFFIC WITHOUT EXTERNAL BUSES	EXCESS VEHICLE
1	WHEELS LAND HINGRA ROAD	15,521	13,889	14867	14,220	647
2	JAMBHARI TANK NORTH	14,333	13,398	13940	12,545	1,395
3	CA ROAD NEAR RLY STATION	24,654	22,648	23971	22,147	1,824
4	C D/A RAJWADA ROAD	25,461	23,816	24936	23,403	1,533
5	WHEELS - ANKURATI ROAD	22,523	22,049	19858	18,848	1,010
6	GHAT ROAD NEAR SUBHASH ROAD INTERSECTION	21,840	20,455	20909	18,937	1,972
7	ANSARI ROAD - NEAR STA BULDI	26,531	24,828	26166	24,669	1,497
8	BUS STAND - WARDHAI ROAD	27,831	25,825	27540	25,367	2,173
9	RAJWADA WITH TADKHE MARG	11,051	9,153	20763	10,348	415

TVC L&E #/Box No	DIRECTION	FAST+SLOW TRAFFIC WITH EXTERNAL BUSES	FAST+SLOW TRAFFIC WITHOUT EXTERNAL BUSES	FAST MODE TRAFFIC WITH EXTERNAL BUSES	FAST MODE TRAFFIC WITHOUT EXTERNAL BUSES	GOODS VEHICLE
10	HELIPAD- WARDHA ROAD	31,498	29,279	30745	27,878	2,867
11	OLD SECRETARIAT- PILM ROAD	14,532	13,600	14105	13,779	327
12	BEKARDHODA- KATOL ROAD	12,772	11,781	12331	11,539	792
13	KASTUR CHIND PARK/PALM ROAD	12,090	10,929	11785	11,325	461
14	HOLY CROSS ROAD-ALONG KASTUR PARK	20,794	18,290	20629	19,879	550
15	CHINDWARA AND MOUNT ROAD X	29,996	27,782	29544	27,705	1,839
16	CHINDWARA ROAD RUBHWAN	20,930	18,728	20534	19,154	1,380
17	NEARLY STN. GUJDIRAMA KAMPTER ROAD	21,733	19,390	20767	18,351	2,394
18	CHADDOCK ROAD- MOMIPURA	8,531	8,426	8519	8,493	26
19	NEORA- KAMPTER ROAD	27,413	25,408	26132	25,180	952
20	ADARSH VEDA MANOR SOCIETY-CA ROAD	22,538	21,324	21536	20,822	714
21	INTERSECTION OF CA ROAD AND FACTORY	17,336	16,688	16604	15,858	746
22	JAWAHAR NORTH-WEST BOUNDARY ROAD	18,489	17,898	17740	16,708	1,032
23	AVU COLLEGE- UMRRO ROAD	14,146	12,995	13458	12,505	953
24	SEEMRUPETH- RODE ROAD	21,985	20,893	21605	21,160	440

TVC L&E #/Box No	DIRECTION	FAST+SLOW TRAFFIC WITH EXTERNAL BUSSES	FAST+SLOW TRAFFIC WITHOUT EXTERNAL BUSSES	FAST MODE TRAFFIC WITH EXTERNAL BUSSES	FAST MODE TRAFFIC WITHOUT EXTERNAL BUSSES	GOODS VEHICLE
25	RAILWAY QUARTERS-ANI ROAD	28,083	27,236	27559	27,074	485
26	RAHATEY COLONY- WAREHA ROAD	37,369	33,019	26561	25,888	873
27	NEAR SSIATMA NORTH AMBALJHRE ROAD	25,739	24,753	25624	24,734	890
28	GOERPATH- JANNUATH ROAD	25,455	22,275	25008	23,743	1,265
29	HINDUSTAN COLONY- JANNUATH ROAD	14,124	12,173	13530	12,040	885
30	PVD QUATERS- KATOURD ROAD	17,050	15,555	16539	15,387	1,152
31	HEALTH HOSPITAL- CHINDIVRA ROAD	18,007	17,075	17623	16,720	903
32	MINAKPUR CHANDWARA ROAD	13,668	13,038	13320	12,623	897
33	BEFORE INTERSECTION BETWEEN KAMPTEE ROAD	23,210	20,797	19897	17,394	2,503
34	DESHRAJEEV GARDEN CA ROAD	15,089	12,634	14064	13,513	551
35	TABACH- UNNED ROAD	10,820	10,176	10244	9,199	1,043
36	VIVEKANAND NAGAR- WAREHA ROAD	34,778	32,478	33875	32,066	1,809
37	ABRODIA WAREHA ROAD	24,603	22,466	22663	20,753	1,010
38	VIVEKANAND NAGAR-ANMALA ROAD	11,344	10,720	10957	10,520	37

TVC Line Station No	DIRECTION	FAST+SLOW TRAFFIC WITH EXTERNAL BUSES	FAST+SLOW TRAFFIC WITHOUT EXTERNAL BUSER	FAST MODE TRAFFIC WITH EXTERNAL BUSES	FAST MODE TRAFFIC WITHOUT EXTERNAL BUSES	GOODS VEHICLE
00	UNTHANUR NAG ROAD	14,776	13,557	14003	12,077	1,926
40	HINDIA ROAD RICHON COLLEGE	16,732	15,057	16197	15,069	528

In table 2.3 passengers covered on fast modes, passenger vehicle flow and number of vehicles per passenger is given.

**Table 2.3:**  
**Fast Mode Passenger Details at 40 different locations - Nilgiri**

TVC Location No	DIRECTION	FAST MODE PASSENGER TRAFFIC WITH EXTERNAL BUSES	FAST MODE VEHICULAR TRAFFIC WITH EXTERNAL BUSES	VEHICLE / PASSENGER
1	WIRELESS LANE-HINDIA ROAD	93647	14867	6.188
2	AMBADHARI TANK NORTH	33016	13040	2.230
3	CA ROAD - NEAR RLY STATION	127139	21871	5.189
4	C DILE RAUBARA ROAD	117720	24896	4.212
5	WIRELESS JARAWATI ROAD	61180	16858	3.325
6	GHAT ROAD NEAR SUBHASH ROAD INTERSECTION	64166	20809	3.224
7	ANSARI ROAD - NEAR SITA BUILD	117806	26190	4.222
8	BUS STAND- WARDHA ROAD	148390	27540	5.183
9	RAJNENDRANATH TAGORE MARG	36211	10763	3.113
10	HELIPAD-WARDHA ROAD	128621	30745	4.223
11	OLD SECRETARIAT-PALM ROAD	80080	14100	5.211
12	MAWRENKONDA-KITOL ROAD	60463	12321	4.183
13	KASTUR CHAND PARK-PALM ROAD	78044	11780	6.151
14	HOLY CROSS ROAD-ALONG KASTUR PARK	162681	26429	6.134
15	CHINOWARA AND KOLINI ROAD A	141838	26545	5.288
16	CHINOWARA ROAD	126751	26534	4.153



TVC Location No	DIRECTION	FAST MODE PASSENGER TRAFFIC WITH EXTERNAL BUSES	FAST MODE VEHICULAR TRAFFIC WITH EXTERNAL BUSES	VEHICLE / PASSENGER
	RAJBHAVAN			
17	NEAR RLY STG DUREWADA KAMPTEE ROAD	135805	20747	6.153
18	CRADDOCK ROAD- NOMMURA	20387	8518	2.418
19	INDORA-KAMPTEE ROAD	145835	28132	5.183
20	ADARSH VIDYA MANDIR SOCIETY-CA ROAD	167100	21500	3.261
21	INTERSECTION OF CA ROAD AND FACTORY	67343	18804	3.247
22	JEWANR NAGAR-WEST BOUNDARY ROAD	61051	17740	3.285
23	AVU DOLL ROAD-LARGO ROAD	73056	13438	5.183
24	SOMWAR PETH-RODGE ROAD	78767	21800	3.274
25	RAILWAY QUARTERS-ANI ROAD	93028	27000	3.332
26	RAHITEY COLONY-BARDHI ROAD	234228	28951	8.113
27	NEAR DBS ATM-NORTH AMBAJHERI ROAD	87031	25624	3.291
28	COOPERATIVE MARKET ROAD	151285	25008	3.131
29	HINDUSTAN COLONY- AMBKATHE ROAD	112385	13530	8.128
30	PWD QUARTERS-KATOL ROAD	30850	18030	3.171
31	MENTAL HOSPITAL/ CHINWARA ROAD	84058	17823	3.267
32	SHANKARJI DABKOWARI ROAD	67447	13320	3.197
33	BEFORE INTERSECTION BETWEEN KAMPTEE ROAD	136750	19887	6.145
34	DESH-PAWDEY GARDEN-CA ROAD	128243	14354	8.111
35	TAZBAGH-UMRED ROAD	33218	10244	3.204
36	VIDYANAGAR NAGAR-VIDYAR ROAD	167881	33875	3.213
37	AERODROME-VIDYAR ROAD	128320	22883	5.187
38	VIDYANAGAR NAGAR-KAMLA ROAD	30163	10807	3.219
39	UNIKAWANAGAR ROAD	70822	14000	5.182
40	HINDIA ROAD-ROBOM	37585	18137	5.183

TVC Location No	DIRECTION	FAST MODE PASSENGER TRAFFIC WITH EXTERNAL BUSES	FAST MODE VEHICULAR TRAFFIC WITH EXTERNAL BUSES	VEHICLE / PASSENGER
	COLLEGE			

In table 2.4 peak hour details of Vehicle, Passenger and PCU are shown.

Table 2.4  
PEAK HOUR details at 40 different locations - Nagpur

TVC Location No	DIRECTION	VEH	PASS	PCU
1	WIRELESS LAND-HINDHA ROAD	6.80%	0.07%	8.32%
2	AMBADHARI TANK NORTH	11.30%	0.00%	9.34%
3	CA ROAD NEAR RLY STATION	8.98%	0.86%	7.71%
4	C ZAIL RAJABABA ROAD	9.48%	0.86%	8.48%
5	WIRELESS JMRALATI ROAD	11.27%	0.83%	10.10%
6	GHAT ROAD NEAR SUSHMISH ROAD INTERSECTION	9.81%	10.52%	8.87%
7	ANSARI ROAD - NEAR SITA BULDI	11.20%	0.00%	9.36%
8	BUS STAND- WARDHA ROAD	9.43%	0.00%	9.38%
9	RAVINDRANATH TAGORE MARG	10.07%	0.22%	10.00%
10	HELIPAD-WARDHA ROAD	9.30%	0.40%	9.38%
11	OLD SECRETORIAL-PALM ROAD	11.10%	11.40%	10.52%
12	BEKARACHONKARPOL ROAD	8.28%	0.93%	8.19%
13	KASTUR CHAND PARK PALM ROAD	8.70%	0.80%	9.08%
14	RDLY CROSS ROAD ALONG KASTUR PARK	9.20%	0.82%	9.60%
15	CHANDWARA AND MOUNT ROAD X	9.00%	0.17%	8.34%
16	CHANDWARA ROAD RAJSHIVWAN NEAR RLY STN-GURDWARA	9.07%	0.37%	8.07%
17	KAMPTEE ROAD	11.01%	12.30%	12.34%
18	CRADDOCK ROAD-NOMINPURA	8.50%	10.80%	8.71%
19	INDORA-KAMPTEE ROAD	8.31%	0.50%	7.81%
20	ADARSH VIDYA MANDIR SOCIETY, CA ROAD	7.78%	0.84%	7.71%
21	INTERSECTION OF CA ROAD	8.81%	10.04%	8.20%

TVC Location No	DIRECTION	VEH	PASSE	PCU
	AND FACTORY			
22	JYOTIHAR NAGAR-WEST BOUNDARY ROAD	9.11%	8.70%	10.00%
23	AYU COLLEGE-UMBRE ROAD	9.11%	8.70%	8.79%
24	SOMWARI PETH-REDGE ROAD	10.00%	10.66%	9.31%
25	RAILWAY QUARTERS-ANIR ROAD	10.70%	10.40%	9.76%
26	RAHATEY COLONY-WARDHA ROAD	9.11%	9.60%	9.00%
27	NEAR DBI-ATM-NORTH AMBAJHERI ROAD	9.00%	10.81%	9.29%
28	GOREPATH-AMRATH ROAD	9.12%	10.00%	8.67%
29	HINDUSTAN COLONY-AMRATH ROAD	9.00%	10.70%	8.54%
30	PWD QUARTERS-KATOL ROAD	8.48%	8.01%	8.23%
31	MENTAL HOSPITAL-CHINDWARA ROAD	9.20%	7.80%	8.72%
32	MANKAPUR-CHINDWARA ROAD	7.70%	8.42%	7.93%
33	BEFORE INTERSECTION BETWEEN KAMPTEE ROAD DEDHPANDEY GARDEN, CA ROAD	9.00%	9.34%	10.42%
34	ROAD	9.07%	7.80%	8.79%
35	TAZBACH-UMBRE ROAD	7.87%	9.90%	8.10%
36	VIVEKANAND NAGAR-WARDHA ROAD	10.00%	8.54%	9.67%
37	AERODROM-WARDHA ROAD	9.07%	10.00%	9.47%
38	VIVEKANAND NAGAR-KHAMLA ROAD	10.20%	9.81%	10.11%
39	UNTKHANA NUG ROAD	8.90%	8.42%	8.16%
40	HINDSI ROAD ROSHNI COLLEGE	8.77%	8.70%	8.48%

Through Nagpur, Delhi to Hyderabad National Highway has passed in North-South direction, and Kolkata to Mumbai National Highway has passed in East-West direction and for that reason lot of goods traffic pass through Nagpur. In tables 2.5A and 2.5B Traffic Flow in PCU on NORTH-SOUTH and EAST-WEST direction are given. Connecting bar diagrams are shown in figures 2.5 and 2.6.

**Table 2.5A**  
**Traffic Flow in PCU on NORTH-SOUTH direction**

TVC Location	Name of Location	EAST-BLOW TRAFFIC WITH EXTERNAL BUSES	EAST-BLOW TRAFFIC WITHOUT EXTERNAL BUSES	FAST MODE TRAFFIC WITH EXTERNAL BUSES	FAST MODE TRAFFIC WITHOUT EXTERNAL BUSES	00000 VEHICLES
32	MAKAPUR CHINDWARA ROAD	13793	11457	13458	10593	2965
31	MENTAL HOSPITAL-CHINDWARA ROAD	17159	14829	16905	13802	3104
16	CHINDWARA ROAD RAJAWAN CHINDWARA	22961	17341	22667	17999	4668
15	AND MOUNT ROAD X	27028	22093	27363	21746	5616
13	HELIPAD WIRDHA ROAD	30571	25028	30003	20965	6009
8	BUS STAND- WIRDHA ROAD	29991	23976	29770	22305	8465
25	RAJWADI COLONY- WIRDHA ROAD	31183	20568	30787	28180	2607
36	VISKHAND NAGAR- WIRDHA ROAD	31065	25915	31060	24785	6265
37	APRODIAL WIRDHA ROAD	24008	19263	23030	18701	6529




Figure 2.5 North-South Directional Flow (PCU)

(The Horizontal axis 1 stands for location 32 and 9 stands for location 37 as given in table 2.4)

**TABLE 2.5B**  
Traffic Flow in PCU on EAST→WEST direction

T/C Location #	Name of Location	FAST-SLOW TRAFFIC WITH EXTERNAL SLABS	FAST-SLOW TRAFFIC WITHOUT EXTERNAL SLABS	FAST MODE TRAFFIC WITH EXTERNAL SLABS	FAST MODE TRAFFIC WITHOUT EXTERNAL SLABS	GOODS-VEHICLE
34	DEHPANDEY GARDEN-CA ROAD	16279	13142	16757	13908	1845
21	INTERSECTION OF CA ROAD AND FACTORY ADARSH	19403	13802	14090	12600	2340
20	WONA BHOIR SOCIETY-CA ROAD	21282	18296	20586	18125	2375
9	CA ROAD NEAR RLY STATION	24088	18003	24276	19088	1080
10	HELIPAD WARDH-CA ROAD	30571	24004	30383	20995	9309
7	ANSARI ROAD -NEAR DTA BUILDI	24915	20662	24859	19466	5194
5	WIRELESS -ABRAWATI	17027	14602	16596	13238	3208

	ROAD					
24	SCIBURI PETHADDE ROAD	14040	13930	15864	14447	1397
2	ABBAZARI TRAK NORTH	14561	12493	14406	9854	4573
1	WIRELESS LAND-INDRA ROAD	14843	10763	16488	12500	1886
40	COLLEGE	15437	11346	15149	13459	1647




Figure 2.6 Road Hourly Directional Flow (PCU)

(\*) Horizontal axis 1 stands for location 34 and 11 stands for location 40 as given in table 2.5) Finally passenger traffic flow observed in all 40 locations is shown in figure 2.7. Highest counts are observed at Wanda Road Raffle Colony (Loc. 28), Annavel Road (Loc. 29).



Figure 2.7 Passenger flow at different locations in Nagpur (10 hrs VC)

## 2.6 Mode Share and Modal Split within Nagpur City

### 2.6.1 Mode Share

In figure 2.8, average mode share observed on roads in terms of Vehicle, Passenger and PCU are shown. If external passenger is included, public mode share is high. However, if external trips are excluded different scenario will emerge.




Figure 2.8 Overall Mode Share observed on Roads

In table 2.8, mode share of passenger trips observed on all 40 points are given.





Year	Revenue		Expenses		Profit		Total	Growth	Market	Share
	Q1	Q2	Q1	Q2	Q1	Q2				
2017	10000	12000	8000	9000	2000	3000	10000	10%	15%	10%
2018	12000	15000	9000	11000	3000	4000	12000	12%	18%	12%
2019	15000	18000	11000	13000	4000	5000	15000	15%	22%	15%
2020	18000	22000	13000	15000	5000	7000	18000	18%	28%	18%
2021	22000	28000	16000	19000	6000	9000	22000	22%	35%	22%
2022	28000	35000	20000	24000	8000	11000	28000	28%	45%	28%
2023	35000	45000	25000	30000	10000	15000	35000	35%	55%	35%
2024	45000	60000	32000	38000	13000	22000	45000	45%	70%	45%
2025	60000	80000	42000	50000	18000	30000	60000	60%	90%	60%

### 2.4.2 Modal Split within Nagpur City

In tables 2.1, 2.2, 2.3 and 2.4 Vehicular and Passenger Traffic volume and Peak hour counts are shown which may reflect on the road traffic situation but the corresponding modal splits shown in table 2.7 does not reflect real modal split within the city. The reason is given as under:

Geographically Nagpur is not only the center of India, but also the center of commercial and economic activities of a vast area surrounding the city. In this area, smaller towns such as Bhandara, Urmil, Buldh, Wartha, Hingna, Nisadi, Karanewar, Amravati, Kamptee, Kantak, Dholi, Raipur, Kalso, Chhindwara etc. (all town names are not given) and villages in between Nagpur and these towns are included.

Naturally therefore, external trips to and from Nagpur are significant. To bypass these trips, very good regional bus services exist apart from the Railways. Also long distance interstate bus services are available from different bus stands in Nagpur. In TVC survey, standard buses captured are mostly regional bus services<sup>1</sup>. In terminal survey, (table 2.6), it is seen 2.32 lakh trips are external trips out of which 62% were made by bus. Many of these bus passengers board and alight bus at city bus stands and not from the terminals. Train passengers usually walk or take shared auto to go and return from their destination. It was also noted that at present there is very limited city bus services<sup>2</sup>. Therefore these external services are excluded from the TVC internal picture of Nagpur City passenger mode share will emerge.

To show the difference, average passenger trip modal splits between public, private and NMT are shown below. In this, Public mode includes local bus, auto, shared auto, taxi and shared taxis. Private mode includes Scooters, Motorcycles and cars. NMT includes cycles and cycle rickshaws. Intra-city passenger trip mode share of Nagpur excluding inter-city bus trips will be **44.91%** by private mode and **22.66%** by public mode and **3.15%** by slow mode. A pie diagram is shown in figure 2.8.

<sup>1</sup> We will in table 2.12, see that significant number of internal trips for work and bus

<sup>2</sup> On total, there are 470 buses on PPT lanes (a mix of 44 water and 28 water in Nagpur but most of these buses are 300 are provided due to low revenue generation.




Figure 2.8 Public Private Modal split of passengers (excluding regional buses)

Out of the **64.91%** private mode passenger trips, about **52.76%** are two-wheeler trips and **51.16%** are trips made by cars. Out of **32.00%** public trips, **32.00%** are made by Auto-Rickshaws and **10.00%** are made by local buses. Vehicle-wise modal split of vehicles is shown in Figure 2.10.




Figure 2.10 Public Private Modal split of vehicles (excluding regional buses)

In terms of vehicles, out of the **74.32%** private mode trips, about **55.2%** are two-wheeler trips and **16.12%** are trips made by cars. Out of **15.41%** public trips, **14.3%** are made by Auto-Rickshaws and **1.01%** are made by local buses.




Figure 2.11 Public Private Model split of PCU of vehicles (excluding regional buses)

In terms of vehicle PCUs, out of the 55.3% private mode trips, about 34.3% are two-wheeler trips and 21.2% are trips made by cars. Out of 19.10% public trips, 16.9% are made by Auto Rickshaws and 2.2% are made by local buses.

Analysis of data collected from TVC survey was for understanding the traffic flow characteristics on the Road Network. To determine amount of trip which may be diverted to Metro, Generalized cost based LOGIT model has been used. Details are given in section 4.4 and 4.5.

## 2.7 TERMINAL SURVEY RESULTS

Bus and Rail Terminal stations were surveyed mainly to understand the magnitude of external trips. There are 3 railway stations and 7 bus terminals. A summary of incoming and outgoing passengers is given in table 2.7.

Table 2.7  
External Trips of Nagpur City

Terminal Name	In coming Passengers	In coming %	Out going Passengers	Out going %	Total
Nagpur Main Railway Station	52652	53.1	32757	45.9	85409
Agrl Railway Station	2263	27.9	3850	72.1	6113
Itean Railway Station	5932	37.9	9601	62.1	14533

Terminal Name	In coming Passengers	In coming %	Out going Passengers	Out going %	Total
Shiloh Bus Stand	8380	45.0	10200	55.0	18580
Gandhinagar Bus Terminal	32100	49.9	32280	50.1	64380
Ravi Nagar Bus Stand	5803	52.2	5373	47.8	11176
Chhatrapati Square	3720	33.2	7488	66.8	11208
Gandhinagar Bus Stand	1750	06.2	1308	43.8	3058
Indira Bus Stand	3985	55.0	3777	45.0	7762
Moti Choker Bus Stand	10000	62.0	6482	38.0	16482
MP Bus Stand	2884	54.8	2433	45.4	5317
	<b>110334</b>	<b>49.84</b>	<b>118840</b>	<b>51.58</b>	<b>229174</b>

Above data shows that 2.32 visits/trips are external trips (which could be more as there are many boarding and alighting bus stops except main bus terminals) out of which 38% are by train and 62% are by regional and interstate bus service. Above data is for 10 hours (5AM-10PM). Many trips are purely external to external (incoming by bus and outgoing by train and vice versa). Quantum of external trips is about 10% which is expected for a city like Nagpur.

Heavily variation of incoming and outgoing passenger flow for Nagpur Railway Station is shown same in table 2.8.

**Table 2.8**  
Hourly variation of traffic for Nagpur Railway Station

Time	IN	OUT	TOTAL
6:00 - 7:00	4.41%	4.23%	4.51%
7:00 - 8:00	7.54%	3.99%	5.69%
8:00 - 9:00	5.81%	7.23%	6.52%
9:00 - 10:00	5.72%	9.38%	7.54%
10:00 - 11:00	5.75%	3.88%	5.07%
11:00 - 12:00	4.74%	3.42%	5.08%
12:00 - 1:00	5.90%	5.74%	5.36%
1:00 - 2:00	5.53%	5.44%	5.48%
2:00 - 3:00	4.78%	3.89%	5.10%
3:00 - 4:00	5.07%	3.18%	5.08%

Time	IN	OUT	TOTAL
4:00 - 5:00	8.87%	5.08%	8.17%
5:00 - 6:00	8.38%	5.57%	8.97%
6:00 - 7:00	7.81%	7.48%	7.70%
7:00 - 8:00	7.66%	5.96%	6.90%
8:00 - 9:00	6.72%	6.94%	6.83%
9:00 - 10:00	5.77%	4.70%	5.23%

Hourly variation of incoming and outgoing passenger flow are not much and morning peaks for incoming and outgoing passengers are 7am-8am and 8am-10am respectively. Evening peaks for both incoming and outgoing are same at 5pm-6am. Picture is totally different for Ajni and Itanagar Railway stations as may be seen in table 2.0.

**Table 2.0**  
Hourly variation of traffic for AJNI & ITANAGAR Railway Stations

Time	AJNI		ITANAGAR	
	IN	OUT	IN	OUT
6:00 - 7:00	9.89%	1.32%	17.81%	2.59%
7:00 - 8:00	18.48%	5.54%	7.91%	4.62%
8:00 - 9:00	9.50%	21.70%	3.18%	5.05%
9:00 - 10:00	3.87%	23.32%	4.62%	4.32%
10:00 - 11:00	3.21%	11.20%	8.09%	10.22%
11:00 - 12:00	2.41%	2.87%	6.58%	6.59%
12:00 - 1:00	1.68%	8.83%	8.45%	5.94%
1:00 - 2:00	1.81%	0.88%	5.18%	4.30%
2:00 - 3:00	2.83%	3.28%	3.06%	12.17%
3:00 - 4:00	5.88%	1.03%	4.36%	5.39%
4:00 - 5:00	9.28%	4.27%	4.27%	10.38%
5:00 - 6:00	14.58%	6.32%	6.73%	7.26%
6:00 - 7:00	11.05%	6.56%	7.30%	3.61%
7:00 - 8:00	4.83%	1.82%	7.09%	6.28%
8:00 - 9:00	4.89%	0.87%	3.64%	4.53%
9:00 - 10:00	3.43%	0.85%	2.41%	5.05%

Peak hours for inbound passenger are early morning (16.48% between 8am-9am for Ajni) and 17.81% between 8am-9am for Itanagar) and basically are factory workers. Outgoing passengers for Ajni are between 8am-10am and between 10 am -11 am for Itanagar. Ajni rail station may be considered as an extended part of Nagpur Rail Station and many passenger interchange there too as per their convenience and train stoppage times. However, Itanagar station carry mostly commuters.

## 2.8 TERMINAL PASSENGER INTERVIEW

10881 passengers were interviewed at 8 main bus stands for knowing their travel characteristics. While most of the passengers use city bus for access and disposal to and from bus stand large number of Auto Rickshaw users are also observed. Other mode users are insignificant. For rail passengers, for access and disposal, auto rickshaw is used and few use of other modes (except taxi) indicates, people directly goes to their destination on foot.

**Table 2.10**  
**Mode used by external passengers**

MODE	BUS		RAIL	
	Access	Disposal	Access	Disposal
1 - Two Wheeler	9.1%	3.3%	8.4%	1.0%
2 - Auto Rickshaw	23.2%	12.1%	23.7%	11.3%
3 - Shared Auto Rickshaw	1.4%	1.0%	3.4%	0.5%
4 - Car	2.8%	0.8%	5.9%	1.4%
5 - Taxi	1.1%	0.7%	3.9%	0.6%
6 - Mini Bus (Public)	0.8%	1.3%	1.0%	0.5%
7 - Mini Bus (Regional)	0.1%	0.0%	0.0%	0.1%
8 - Bus (Public)	48.5%	80.1%	12.1%	2.1%
9 - Bus (Regional)	8.5%	17.1%	0.8%	0.2%
10 - Cycle Rickshaw	0.3%	0.2%	0.2%	0.4%
11 - Cycle	0.2%	0.1%	0.4%	0.0%
12 - Train	3.6%	2.0%	32.2%	81.3%
13 - Walk	2.3%	0.7%	1.4%	0.1%

By bus, 33% passenger trips are daily and by rail, it is 15.3%, signifying a large number of persons living outside the city commutes work by bus and other purposes.

**Table 2.11**  
**Frequency of trip mode by external passengers**

33.1%	15.6%	D - Daily
14.8%	10.0%	W - Weekly
34.3%	40.7%	M - Monthly
17.8%	32.0%	O - Occasionally

Regarding occupation, revealing part of the table 2.12, is over 65% are working in small establishments such as Shops, Hotels and Restaurants or labor or non permanent workers. Showing types of job which are available in the city. About 20% are employees of Government and Private Establishments.

**Table 2.12**  
Occupation of external passengers

BUS	RAIL	OCCUPATION
1.4%	0%	0 - Not stated
6.8%	3.8%	1 - Government Employee
9.1%	8.3%	2 - Private Employee
8.9%	5.1%	3 - Institute Employee
19.7%	19.9%	4 - Shop/ Mall/ Street
31.2%	43.4%	5 - Hospitality
12.3%	3.8%	6 - Services (Bank/ restaurant)
0.1%	0.1%	7 - Health
0.7%	1.1%	8 - Other (Mention)
10.9%	5.8%	9 - Student
0.1%	0%	Unemployed

Purpose wise trip made shows (in table 2.13) that more than 50% trips are work trips.

**Table 2.13**  
Purpose wise external trips

BUS	RAIL	PURPOSE
6.1%	3.0%	0-Not Stated
41.2%	41.4%	1 - Work
10.0%	10.5%	2 - Business
11.9%	8.0%	3 - Education
2.2%	2.3%	4 - Social
4.3%	2.3%	5 - Shopping
3.1%	4.0%	6 - Recreation
1.2%	3.3%	7 - Religious
24.0%	26.7%	8 - Other

## 2.3 WORK PLACE SURVEY

Workplace survey was conducted in Nagpur City to know the concentration and type of workplaces and workers socio-economic conditions. In all 60 thousand workplaces were investigated whereof 94 lakh people are working. For a population of 24 lakh, assuming 30% are workers, total workers are 72lakh 8 lakh. In this manner, about 29% workers were recorded during the survey. This survey was aimed mainly to identify main work centers within the city and not for preparing an exhaustive list of workplaces. This survey has given a number of valuable information which is presented in the following tables:



Table 2.14 Type of work Establishments

Type of Establishments	Samples	Percent
Office (Private, Agency)	3008	5.95%
Factory (Small Scale Manufacturing )	238	0.47%
Institute (School, College, Coaching Center, Training Institute )	1028	1.77%
Shopping (Retail and Wholesale Merchant)	47654	79.32%
Hospitality (Hotel, Restaurants, Eatery, Diner, fast food etc.)	3155	5.52%
Services (Garage, Automobile Repair, Spare Parts, Mobile, Kiosk store )	2624	4.38%
Health (Hospital, Nursing Home, Clinic, Medical Store, Gyn.)	2031	3.38%
Others (Marriage Hall, Ghatgriha, Temple)	101	0.32%
	50673	

Table 2.14 shows that overwhelming number (85%) of work places are shopping and hospitality business. This survey has depicted the status of retail type employment and not the status of basic type employments such as employments in Government Offices and Railways.

Table 2.15  
Work Places as per number of employees

1	2	31106	51.26%
3	5	23201	38.62%
8	10	4197	6.98%
11	20	1200	2.15%
21	30	211	0.35%
51	100	17	0.03%
>100		8	0.01%

Classification as per employee size given in table 14 shows + 90% establishments have less or equal to 5 employees.

## 2.10 INTERVIEW OF WORKERS

10000 workers were interviewed and several interesting information were extracted from the interview. From table 2.15, it is observed 40.00% is one earning member family and 30% has two earners. From the table it is deduced workers' population ratio is 0.35. It is also seen student / population ratio is 0.12 (with in sample). But it is not possible to know whether all these workers make work trips using vehicle.

**Table 2.16**  
Family details of workers

WORKERS IN FAMILY	NUMBER	PERCENT	FAMILY MEMBERS	STUDENT IN FAMILY
1	6877	45.66%	27742	15220
2	3887	30.05%	30008	5842
3	2098	13.65%	12989	3415
4	240	1.59%	1813	628
ALL	13000		73552	23314

From sample data, trip length frequency is constructed and shown in table 2.17. Average trip length of workers was computed as 8.47 km.

**Table 2.17**  
Trip length frequency of workers

FROM KM	TO KM	PERCENT
1	5	28.8%
6	10	43.4%
11	15	16.2%
16	20	4.3%
21	25	1.4%
26	30	1.3%

**Table 2.18**  
Monthly income of workers

Rs	Rs	Percent
0	10000	49.5%
10000	20000	20.7%
20000	30000	19.2%
30000	100000	8.8%
100000	200000	1.3%

As reported, 50% have income less than Rs. 10,000 per month. Average monthly income was deduced as Rs. 20000.

As far as vehicle used for coming to work place is concerned, it is found 50% use two wheeler. Nearly 15% use public transport system. Frequency distribution is given in table 2.19.

**Table 2.19**  
Mode used by the workers

Vehicle Type	Sample %
Two Wheeler	48.24%
Auto Rickshaw	35.17%
Shared Auto Rickshaw	3.41%

Vehicle Type	Sample %
Car	8.12%
Taxi	2.26%
Mini Bus (Public)	3.86%
Mini Bus (Regional)	1.23%
Bus (Public)	6.42%
Bus (Regional)	0.48%
Cycle Rickshaw	0.32%
Cycle	1.81%
Trish	0.36%
Walk	0.47%
TOTAL	100%

Average journey time (as reported) is 26.6 minute. Average expenditure on travel per day is Rs. 24.58.

As far as location of work place is concerned, 60% employment is concentrated in DHANTOLI, COTTON MARKET, ZERO MILE, SITABDIJI areas which are within the core area of the city. Another 26% employment is in MANAKPUR, MINAL, LAW COLLEGE, BHADARA ROAD, MANEHWDA, PORT, QANESHIPETH, SAGAR and LAKADAMJI areas. There are also a few isolated places such as MOORA, SHARLA, ITNARI and KALMANA where work places exist. This is an important finding for being work trip attraction zones for trip distribution purpose.

## 2.11 TRIP FORECASTING USING TRAFFIC MODELS

Four stage modeling procedure has been adopted which are known as trip generation, trip distribution, modal split and trip assignment. Many books and research papers are available in which basic theory and application are well explained. Depending upon the situation, different variations of the above stages are applied. A few references<sup>3</sup> are given in the footnote. To start with, a few basic data such as Traffic Zone System (TAZ), Road and Other Transport Network, Land use data are prepared.

<sup>3</sup> Ben-El-Mechaieq and Workman, I. 2003 Estimation of Travel Demand Models from Multiple Data Sources, Transportation and Traffic Theory, Georgia, U.S., 2003 Transportation Systems Engineering: Theory and Methods, Elsevier Academic Publishers, Burlington, September, I. 2016 Guidelines for Aggregate Level Pedestrian Using Disaggregate Data Models Transportation Research Board 603

National Research Council (NRC) Transportation Research Board (2000) Highway Capacity Manual, National Research Council (NRC) Transportation Research Board

Sheff, Y (198) Urban Transportation Networks: Evaluation Analysis with Mathematical Programming Methods, Englewood Cliffs, N.J., Prentice Hall

Waller, A.L. 2004 Urban and Regional Models in Geography and Planning, Wiley London, New York  
M.S. Bell & I. Jones, 2003, Transport Network Analysis, John Wiley & Sons, England

## 2.12 TRIP ENDS ESTIMATION

After collecting necessary inputs from primary survey, secondary data as available were also investigated. Several rounds made in the city to physically verify concentration of residential population, work places and education centers and their connecting routes. A list of wards (136), list of group zones (defined as ZONES numbering 1-10) and ward wise population of 2001 was available. In 2001, total population of Nagpur 136 wards was 20,52,988 with average population density 247/haector. Maximum population of any ward was found to be 10886, minimum population was 12,531 and average 15,090. From this it appears, wards were fixed on the basis of uniform population and not according to landuse activities.

Such wards cannot be successfully used as traffic analysis zones (TAZ) for estimating demands on proposed mass network. A map of Nagpur city was available where future allocation of landuses was clearly marked. This map became very helpful for creating TAZs. Nagpur and its adjoining areas were brought under new traffic zone system which had 368 internal and 10 external zones. These zones were classified as RESIDENTIAL, COMMERCIAL, MIXED, PUBLIC, GREEN and OTHER. From the names assigned to the classes, characteristics of the zones should be understood. Examples of MIXED zones are MOHNPURA, GANDHIBAG, MIDDLE, BAGADGANI, BASTI, AZMESHAH, DHARWOLI, DADA LAYOUT, MOHAN NAGAR, SADAR, TEMPLE ROAD, VJAY CLUB, NAVI NAGAR, HINDONA RD etc. which have both resident population and commercial activities. PUBLIC zones have mostly government offices, educational institutes, hospitals, courts etc. OTHER zones are Railway Stations & Yards, Government Lands, Bus Depots, Godowns, Wholesale Markets etc. GREEN zones are lakes, zones, forests, agriculture lands etc. Residential zones have highest population. With this classification, it became logical to allocate population and to identify the attraction zones. Ward wise population of 2001 was reallocated among the zones after verifying their geographical location and ZONES. External TAZs are entry points to the city namely the Roads: WARDHA, HINDONA, AMRAVATI, KATOL, KICRADI, KAMPTEE, BHANDARA, and UMRED.

Total Population of the study area and estimated daily vehicular trip production from all the internal and external zones during different horizon years are given in table 2.21. Employment locations (Zones) were identified from work place survey and 'Per Capita Trip Rate' for 2012 was also derived from the Workplace Survey Data. Concentration of educational institutes, and medical facilities were identified from map and physically verified. In this manner, trip attraction zones were identified for different purposes (work, education and other) and were assigned ranks. Zone attraction weights were then derived by multiplying zone rates with zone areas and then by normalizing it. Total trip for different purposes (work, education and other) trips attracted to zones were then by multiplying total purpose wise trips with zonal weights. Trips to be attracted for other horizon years were also estimated. Estimate of total population and trip produced of the study area are shown in table 2.20.

Table 2.20  
Population and Trip Production in lakhs during different horizon years

	2011	2016	2021	2026	2031	2036	2041	2046
POP	21.87	23.01	24.77	26.62	28.55	30.40	32.27	34.20
TRIP	17.53	18.01	22.27	24.44	26.85	28.73	30.83	33.29
TRIP RATE	0.80	0.826	0.894	0.916	0.935	0.946	0.959	0.973

## 2.13 TRIP DISTRIBUTION

Trip ends are then distributed (using gravity model) among traffic zones according to the distance (or by GC). Inner philosophy of trip distribution is that a trip is originated due to population and is attracted to another zone due to facility available in that zone. Also if the cost of travel to that zone is higher than the cost of travel to another zone having the same facility, the trip will be attracted to another zone. Trip distribution (Gravity Model) model formula is given as under:

$$T_{ij} = A_i P_j C_{ij}^{-\alpha} / \sum_j P_j C_{ij}^{-\alpha} \quad (1)$$

where  $T_{ij}$  are trips from zone  $i$  to  $j$ ,  $c_{ij}$  is cost of travel from  $i$  to  $j$ ,  $P_j$  = trips produced from zone  $j$ ,  $A_i$  = trips attracted to zone  $i$ ,  $R_i = 1 / \sum_j P_j C_{ij}^{-\alpha}$  &  $C_{ij}^{-1} = 1 / \sum_j A_j C_{ij}^{-\alpha}$  and  $\alpha$ ,  $\beta$  are difference constants.  $A_i$ ,  $C_{ij}$  are model constants which are fixed through iterative process.

## 2.14 MODAL SPLIT

Economics based modal share model is developed to determine realistic share between public and private transport for two options namely with metro and without metro. Utility cost or the generalized cost of travel for each mode is derived by computing certain values of the parameters which constitute the vehicle wide total economic cost (generalized) cost. Items which are used for constructing the utility function are given in the top row of table 3. All items are converted to money cost by using value of time. These values are obtained from sample survey.

Table 2.11: Utility Model inputs

Parameter/Variable	Without Metro/No Metro	With Metro/With Metro	Without Metro/No Metro	With Metro/With Metro	In time cost delay/ per sec in sec	In time cost delay/ per sec	Personal appearance	Personal appearance	Personal appearance	Personal appearance
Bus	30	10	10	18%	10%	1%	3	3	0.4	0.3
Car	40	0	0	0%	15%	1%	15	3	2	3.5
Taxi	40	0	0	0%	15%	1%	20	2	5	3.0
2 Wheeler	40	0	0	0%	15%	10%	2	3	1	3.5
Auto	30	0	0	0%	15%	1%	10	2	3	3.0
Metro	30	10	2.0	10%	3%	-10%	0	2	0.3	3.0

Discomfort cost is subjective which depends upon energy loss while availing the service of that particular mode. 10% is allotted to 2 wheelers due to the physical torsion and safety of the driver.

(-) 10% to metro passengers is indicative of comfort for hassle free journeys. For without metro situation, Metro is not considered in the model, and for with metro situation the same is considered. Logit model formulation is given by:

$$P_{ik} = \frac{e^{U_{ik}}}{\sum_j e^{U_{ij}}}$$

Where  $U_{ik}$  is utility function for mode  $k$  and  $P_{ik}$  is share of mode  $k$  when number of competitive modes are  $1, k$ .

In figure 5 mode share is shown for without metro situation. In figure 6 mode share between public and private modes is shown.




Figure 2.12: Mode share among passenger vehicles without metro




Figure 2.10 Mode share between public and private passenger vehicles with metro

## 2.15 SIMULTANEOUS MODAL SPLIT AND DISTRIBUTION

Trips between each zone pair are divided into public and private modes using logit model (Para 2.4.4). Car and Two Wheelers together are private modes. All types of Buses, Auto Rickshaws and Taxis together are considered as Public Modes. Private mode trips use road only network while public modes trips use other mode network also. Rail and Metro both fall under public mode.

Trips for every zone pair for which distance is available are divided into public and private modes as per the distance for using Logit Model and distributed by using public and private network which are already separated from the complete transport Network. Before distribution, distribution parameters ( $\theta, \beta$ ) are determined from observed average trip length (from work place to home average trip length was found as 8.47 km-see para 2.3.2). Thus Origin - Destination passenger trip matrices for all horizon years.

## 2.16 TRIP ASSIGNMENT

Several traffic assignment techniques such as capacity restrained, incremental loading, user equilibrium, dynamic assignment etc. are available. All of them are developed by considering (or hypothetically assuming) different kind of passenger behavior.

In this study, incremental loading assignment technique is used where OD matrix is partly assigned (10%-20% each time) and link cost is modified on the basis of the part assignment. Link loads obtained from each part assignment are added.

As metro is a part of the public network, a portion of the public trip matrix is separated for loading on metro network. If both origin and destination zone of a trip has at least one metro station, it is assumed that from other modes to metro will be from 10%-20%

(consider the mutual distance if the OD pair, lighter will be the shift to metro) from public OD. It is also assumed that trips from private OD will be shifted to metro OD.

This distribution cum assignment exercise will finally produce four OD matrices (1) private mode to use road only network, (2) public mode to use road and rail only network, (3) public mode to use road, rail and metro network and (4) metro mode to use metro and road only network], assigned trips and routes for each OD pair.

## 2.17 DAILY RIDERSHIP ESTIMATION

Estimation of trips on metro line is done by using a special computer program which scans routes between each zone-pair which are generated from traffic assignment mode during incremental loading traffic assignment algorithm. Each metro station is uniquely defined in the network and a continuous path from one metro station to another metro station crossing several metro stations on the way defines a metro route. Entry to and Exit from any other type of nodes (Road or Zone or Rail) are regarded as Boarding and Alighting of the concerned metro station.

## 2.18 NAGPUR METRO ALIGNMENT PLAN

For Nagpur city, two separate lines have been suggested with an interchange facility at SITABULDI. Length of line-1 (Automotive-Bihar) is 20.5 km and the length of line-2 (Pratapal-Colmánya) is 10.0 km. Alignments have been finalized after many considerations which include, traffic flow path, core area, connectivity, future land-use development plan and existing infrastructure. Line-1 shall connect two important gateways (Kamptee and Wardha). When and International Airport and Cargo HUB are dream projects will also be connected to this line. Line-2 will also connect another two gateways (Bhandara and Hingna) of the city. The line is passing through populated residential zones, business and education centers.





Figure 2.14 Alignment of Nagpur Metro

## 2.15 SUMMARY OUTPUT

Table 2.20: Summary Output<sup>1)</sup>

YEAR	2018	2021	2026	2031	2036	2041
Population <sup>2)</sup>	2162358	2859852	3029832	3226854	3428976	3617938

<sup>1)</sup> Zone wise population was projected from the population density (PD) of the zone observed in 2018. Different growth rates (GR) were applied on PD of the zone according to the class of the zone as per PD. For industrial, if PD of a residential zone is below 300, GR=1.000%, if PD is between 300 and 350, GR is 2.5% and so on. The

YEAR	2010	2021	2026	2031	2036	2041
Overall ANNUAL GROWTH	1.92%	1.48%	1.26%	1.13%	1.13%	1.10%
All trips	2718683	3951773	5129872	5882517	6719258	7995388
Trip rate	1.02	1.03	1.05	1.07	1.08	1.10
Motorists	325838	562399	409236	462918	529291	598183
% Of all trips	11.99%	12.20%	12.33%	13.45%	14.27%	14.72%

In NMC area, in 2011, 17.26% decadal growth rate of population is assumed which was lower than previous decadal growth rate (26%) - LRT-Railway Report.

Table 2.25: Summary Data of B

NO. OF PASSENGERS (per hr)	2010	2021	2026	2031	2036	2041
ON LINE 1 (MUTOMATIKA TO KAN)	144368	161171	180991	201180	240366	267617
ON LINE 2 (TRAHATI LOMBANYA)	179500	189028	211140	233728	280027	320588
<b>TOTAL OF BOTH</b>	<b>323868</b>	<b>350199</b>	<b>402136</b>	<b>462918</b>	<b>529291</b>	<b>598183</b>
AVERAGE TRIP LENGTH IN KM	6.273	6.284	6.297	6.283	6.258	6.207
MAXIMUM PASSENGER ON LINE 1	7145	8134	9624	10987	12881	14811
MAXIMUM PASSENGER ON LINE 2	8387	8792	10170	11700	13468	15364

Total daily boarding ridership in 2010 is estimated as 324 buses in which share of line 1 as 40% and line 2 as 60%. Average trip length is 6.27 km. Interesting observation is that between the lines are about 30%. As a standalone line, line 1 will carry 95 thousand and line 2 will carry 1.22 lakhs bus.

estimate is applied for projecting population of different future years. total CF was adjusted to match population of 2011. In the table overall annual growth rate was shown.

Ambitious plan of creating New Nagpur International Airport & Bypass City has also been incorporated and it is seen about 20 thousand trips will be counted from these two station in 2010.

Table 2.24: Summary Output(3)

	2018	2021	2026	2031	2036	2041
TRIPS WITHIN LINE 1	95401	109096	126996	141776	164030	182700
TRIPS WITHIN LINE 2	320340	344001	401340	436031	512380	550064
INTERCHANGING TRIP AT SIBABULDI-RETAJ MARKET	55100	60880	70700	76400	88310	95070
TOTAL RIDERSHIP/DAY	370841	413977	499036	544207	644720	707834
PEAK HR RIDERSHIP	35634	39884	46630	50201	58211	64700
TRIPS FROM NEW AIRPORT & BYPASS	25412	27640	31700	33870	39400	42120
TO LINE 1	20030	22801	26570	28800	33400	35810
TO LINE 2	5400	5839	6930	7460	8600	9210

## 2.15 DAILY RIDERSHIP

TABLE 2.25A- DAY BOARDING ON LINE 1 FROM AUTOMATIVE TO BHAM

STATION	2018	2021	2026	2031	2036	2041
AUTOMATIVE	12008	14163	16621	18131	21028	22766
NARI RD	7006	8007	9102	10000	11423	12027
INDRA	6008	6870	7956	8615	9820	10348
KADVI CHH	7100	7904	9070	9874	11242	11800
BADLI GODAM RD	600	717	800	860	970	1017
KASTURCHAND PARK	8000	8802	10100	10801	12320	12807
ZERO MILE	5131	5772	6640	7000	7912	8303
SIBABULDI	24103	27000	31000	33000	38003	40000
CONGRESS NAGAR	33000	36801	41807	47100	54000	57000
RAHATE COLONY	3400	3800	4307	4670	5300	5600

STATION	2018	2021	2026	2031	2036	2041
NEERI	2209	2451	2826	4518	6338	6926
DEV NAGAR	2138	2425	2744	3435	4253	5273
MAYURESH APTMENT	2365	2625	2851	3122	3683	3838
SAHAKAR NGR	3547	3765	4816	5320	6518	7888
OLD AIRPORT	1340	1402	1608	1732	1888	2040
NEW AIRPORT	8174	8922	9420	8894	10343	10738
MINA CITY	12740	13877	14922	16010	17225	18423
METRO DEPOT	4038	4840	5300	5800	6025	7392

TABLE 2.25B: DAY BOARDING ON LINE 2 FROM PRAJAPATI NAGAR TO LOKMANYA NAGAR

STATION	2018	2021	2026	2031	2036	2041
PRAJAPATI NGR	529	1007	1074	1202	1326	1433
VASHISHT DEVI CHK	1204	1289	1381	1522	1675	1810
AMBEDKAR CHK	2653	3208	3581	3788	4212	4621
TEL EXCHANGE	10872	12385	10758	20264	20378	20477
DHITAR CLI CHK	3754	4568	7382	8367	11478	13834
AGRAZIEN CHK	7571	9328	10502	11218	13078	14733
MAYO HOSPITAL	7543	11288	13848	18595	20907	18835
MAGPUR METRO ST	30688	34008	40413	45532	52026	58645
METAJI MKT	26481	28503	33189	36457	39813	43290
JIWANGI RAM GD	17144	18372	22388	23374	29477	34376
INST OF ENGINEER	21395	22328	23306	24675	26085	27590
BANK OF INDIA	12493	13672	14401	15297	16301	17573
LAD CHK	3558	3381	4234	4002	4088	3434
DPC OF SCIENCE	8875	9576	10475	11345	12227	12140

STATION	2010	2021	2026	2031	2036	2041
SUBHAS NGR	1008	1924	2023	2155	2396	2574
RACHANA	1004	2223	2470	2740	3000	3454
VASUDHY NGR	2030	2272	2477	2746	3029	3346
BANSI NGR	1636	1907	2173	2440	2832	3179
MAHENDRASMAHENDR	4300	4731	5115	5482	5837	6273
LOKMANYA NAGAR	7702	8362	9091	10074	10574	11003

TABLE 3.26-PEAK HOUR BOARDING ONLINE 1 FROM AUTOMATVE TO MMAN

STATION	2010	2021	2026	2031	2036	2041
<b>LINE-1</b>						
AUTOMATVE	1343	1629	1928	2187	2533	2909
NARS RD	890	1001	1311	1580	1698	1818
BODRA	600	767	947	948	1000	1171
KADVI CHK	782	858	985	1064	1182	1320
SADDI GOSAV SQ	72	85	98	118	140	148
KASTURCHAND PARK	575	1078	1187	1298	1455	1585
ZERO MILE	504	580	643	732	793	888
SITABULDI	2081	3040	3442	3857	4421	4958
CONGRESS NAGAR	3058	4057	4807	5187	5950	6682
RAHATE COLONY	388	388	401	613	630	1027
NEERI	243	273	311	497	697	792
DEV NAGAR	230	287	302	380	400	581
MAYURESH APPTMENT	250	280	314	343	392	429
SAHAKAR NGR	300	415	508	585	717	868
OLD AIRPORT	148	161	177	191	209	228
NEW AIRPORT	890	961	1030	1080	1130	1178
MMAN CITY	1401	1520	1640	1762	1880	2027
METRO DEPOT	480	613	660	685	704	870

STATION	2018	2021	2028	2031	2038	2041
<b>LINE-2</b>						
PRILAPATI NGR	102	111	118	132	146	163
VAISHNO DEVI CHK	132	141	163	167	184	200
AMBEDKAR CHK	323	333	385	417	463	508
TEL EXCHANGE	1196	1364	1734	2220	2701	3372
CHITAROLI CHK	833	700	808	1030	1203	1500
AGRASEN CHK	833	1048	1155	1294	1538	1621
MAYO HOSPITAL	833	1242	1694	1715	2303	2182
KADIPUR METRO ST	3370	3756	4445	3000	5622	6383
NETAJI MKT	2132	3245	3645	4610	4378	4753
JHANSI RANI SQ	1886	2038	2463	2601	3343	3803
INSTIT OF ENGINEER	2353	2406	2564	2714	2869	3020
BANK OF INDIA	1374	1480	1584	1683	1800	1933
LAD CHK	381	438	468	500	540	594
OPC OF SCIENCE	876	1084	1152	1246	1346	1446
SUBHAS NGR	186	212	223	241	254	283
RACHANA	219	246	272	302	337	380
VASUDEEV NGR	224	238	272	302	333	368
BANSI NGR	180	210	236	260	300	330
MAHENDRA BHSHNDR	483	520	563	603	649	690
LOKMANYA NAJIB	848	925	1000	1108	1207	1300

TABLE 2.27: PAPDT LINK LOAD ON LINE 1 FROM AUTOMATIVE TO BHWAN

STATION	STATION	2018	2021	2028	2031	2038	2041
AUTOMATIVE	NARI RD	2814	2434	2742	2185	3930	4459
NARI RD	INDORA	3333	4008	4708	5530	6345	7225
INDORA	KADVI CHK	4344	5141	5950	6831	7910	8958
KADVI CHK	GADDI GODAM SQ	5432	6320	7264	8385	9516	10701
GADDI GODAM SQ	KASTURCHAND PARK	5411	6287	7220	8300	9400	10737

STATION	STATION	2018	2021	2026	2031	2038	2041
RASTURDHAM PARK	ZERO MILE	5475	7433	8448	9071	10000	12234
ZERO MILE	SITABURDI	6028	7831	8871	10136	11409	12804
SITABURDI	CONGRESS NAGAR	7545	9529	9618	10997	12541	14332
CONGRESS NAGAR	RAHATE COLONY	3687	2939	3290	3564	4588	5442
RAHATE COLONY	NEERI	2203	2433	2708	3218	3884	4247
NEERI	DEV NAGAR	1944	2188	2312	2504	2932	3311
DEV NAGAR	MAYURESH APRTMNT	1040	1788	1920	2007	2380	2319
MAYURESH APRTMNT	SAHAKAR NGR	1318	1386	1517	1548	1790	1853
SAHAKAR NGR	OLD AIRPORT	1856	2041	2279	2327	2885	3237
OLD AIRPORT	NEW AIRPORT	1661	1818	2034	2263	2577	2948
NEW AIRPORT	MHAN CITY	3024	3004	3320	3007	3044	4320
MHAN CITY	METRO DEPOT	739	730	885	974	1121	1309

TABLE 3.26- PHDPT LINK LOAD ON LINE 2 FROM PRAJAPATI NAGAR TO LOKMANYU NAGAR

STATION	STATION	2018	2021	2026	2031	2038	2041
PRAJAPATI NGR	VASHNO DEVI CHK	142	154	185	185	203	220
VASHNO DEVI CHK	AMBEDKAR CHK	338	301	331	434	478	522
AMBEDKAR CHK	TEL EXCHANGE	818	881	980	1048	1183	1274
TEL EXCHANGE	CHITAR GLI CHK	2358	2871	3562	4328	5288	6338
CHITAR GLI CHK	AGRASEN CHK	3380	3708	4372	5422	6663	8035
AGRASEN CHK	MAYO HOSPITAL	4371	5034	5767	6733	8125	9484
MAYO HOSPITAL	NAGPUR METRO ST	4834	5767	6572	7537	9064	10090
NAGPUR METRO ST	SITABURDI	8087	8902	10370	11753	13405	15000
SITABURDI	JHANSI RANI SQ	5740	6356	7008	8857	9825	11307
JHANSI RANI SQ	INSTT OF ENGINEER	3310	4002	4301	5301	5881	6627

STATION	STATION	2016	2021	2026	2031	2036	2041
INSTT OF ENGINEER	BANK OF INDIA	6830	7462	8375	8758	9495	10244
BANK OF INDIA	LAD CHK	5960	6543	6340	6955	7199	7822
LAD CHK	DPC OF SCIENCE	4537	4998	5415	5827	6486	7026
DPC OF SCIENCE	SUBHAS NGR	3154	3609	3755	4162	4565	4964
SUBHAS NGR	RACHANA	2905	3184	3487	3838	4211	4624
RACHANA	VASUDEV NGR	2587	2838	3004	3403	3725	4054
VASUDEV NGR	BANSI NGR	2258	2471	2624	2868	3230	3513
BANSI NGR	MAHINDRAMAHENDR	1906	2164	2344	2568	2783	2995
MAHINDRAMAHENDR	LODMANYA NAGAR	1272	1380	1501	1662	1811	1964

## 2.21 More About MHAN

Some description about MHAN project is already given in section 2.4. SEZ and International Cargo HUB are two important projects in MHAN. NIT and GMR they are working hard to make the project successful.

L&T-Ratsoi (see Study Report submitted by them) has worked out population and Employment for MHAN when the project will be operational. Shown below are the salient points from that study report.

1. Population density of Nagpur mc is 94/hectare in 2001
2. Only 10 zones had population density over 600/ hectare
3. Residential area allocated in MHAN = 414 hectare
4. SEZ area in MHAN = 1475 hectare
5. Total area = 4354 hectare
6. Assumed to be operational in 2015
7. Employment in 2015 = 1.56 lakh
8. Employment in 2021 = 2.60 lakh
9. Employment in 2031 = 4.30 lakh
10. 40% employees will commute from Nagpur
11. Employment growth 2015-2021 = 4.5% (cumulative)
12. Employment growth 2021-2031 = 5.2% (cumulative)
13. Maximum Population density assumed = 600/ hectare
14. Maximum population in MHAN which can be accommodated is 2.40 lakh



According to I&T/RAMBOLL report, a maximum of 2.6 lakh population (PC+GSD factors) is expected to live in MHAN and due to GIZ and Airport Domestic activity, employment that will be generated in 2010 is 1.06 lakhs.

As per data, there is hardly any population living in MHAN and economic activity has not started. Therefore keeping a modest view, most likely population and employment figures are worked out by assuming Population density as 100/hectare and Employment density as 40/hectare in 2010 and shall grow with 5% growth rate. In MHAN, Population and Employment that are expected are given as under:

Table 2.28: Expected Population and Employment in MHAN

	2010	2021	2026	2031	2036	2041
<b>POPULATION</b>	63630	77644	94731	119869	149793	185258
<b>EMPLOYMENT</b>	83440	106405	130933	170465	211391	262037

If, however, project is further reduced, these figures will be shifted towards right.

### 2.22 EFFECT OF MHAN ON PROPOSED METRO RIDERSHIP

According to I&T/RAMBOLL report, 40% employees will commute here from outside MHAN including Nagpur city but there is no mention of people who would likely to commute from MHAN to Nagpur. Therefore, when completed, MHAN will be a self sufficient industrial city where people will live and work.

It is expected there will be overall 30% commuting of both resident population and due to employment which will make an impact on the daily riding of Metro.

This has been included in the forecasting process. Daily ridership projected from MHAN stations are given in table 2.30 (already shown in bottom of table 2.38).

Table 2.30: Ridership from MHAN Stations

STATIONS	2010	2021	2026	2031	2036	2041
<b>NEW AIRPORT</b>	4624	5252	6467	8161	9463	1219
<b>MHAN CITY</b>	14111	14989	16585	18772	20964	21779

### 2.23 FURTHER DEVELOPMENTS

On 01.08.2013, a meeting presided by Shri S.K. Lopa, JS-MOUD,GoI was held at Nagpur to discuss the DPR. In that meeting, JS-MOUD,GoI expressed that the FRR of the project should be at least 8%. Recently, MoUD has also issued advisory that FRR of Metro Project should not be below 8%.

On 1.10.2013, a presentation on the DPR was made by M/s NIT to The Chief Minister, Government of Maharashtra. He was of the opinion to avoid underground alignment in MMAN and also construct Maintenance Depot in the land belonging to SMMI Govt Land. Subsequently, on 21.10.2013, a JOM inspection of the NS corridor was done by VC&MD-MDC, Engineer-NIT, and Director Business Development,DMRC. In the inspection, as decided by M/s NIT, NS corridor was slightly modified to move along Wardha Road and then west of Railway Track in MMAN area. Location of Depot of NS Corridor has also been modified and now, depot has been located in MADC Land near Khajuri Railway Station. Similarly, Depot of EW Corridor has also been shifted to SRP Land near proposed Lokmanya Nagar Metro Station.

This has caused deletion of few earlier proposed metro stations on NS Corridor and addition of new stations on the same.

### 2.24 ESTIMATION OF RIDERSHIP FOR FINAL ALIGNMENTS

After going through the DPR, NIT requested DMRC to provide an estimate of the daily ridership for the alternative alignment of line 1 (Alternative to Khajuri). The new alignment of line 1 is same up to Aji Chowk as before but now will go straight along Wardha Road up to Khajuri Rail Station (instead of going along Khoria Road towards Mher). A diagram of the new alignment is shown in figure 2.14.

List of station names, chainage (m) and inter-station-distance (m): between the stations are given in the table 2.31 (Chainage and inter-station distances are shown as per map. Station names are given as per local area names).

Table 2.31: Nagpur Metro Rail Project NS Corridor

S.No	Station Name	Chainage(m)	Inter Distance Between Two Stations in KM
	DEAD END	438.2	
1	AUTOMOTIVE SURF	53	439.2
2	NARI ROAD	975.8	975.8
3	BODMA CHOWK	2139.7	1163.9
4	KADVI CHOWK	3181.2	1041.5
5	GADDI GODAM SOURCE	4099.0	917.8
6	KASTURBHAND PARK	5148.0	749.0
7	JERO MILE	6175.5	626.5
8	GITABURDI	6709.2	533.7
9	CONGRESS NAGAR	7907.2	1198.0
10	KARATE COLONY	8662.5	755.4
11	AJI SOURCE	10104.7	1422.1
12	DHATRAPATI SOURCE	11140.3	1041.6

S.No	Station Name	Chainage (m)	Inter Distance between Two Stations in KM
13	JAYRAKSHI NAGAR	11811.2	881.1
14	LUMAL NAGAR	12692.3	1081.2
15	AIRPORT	13784.3	1361.1
16	NEW AIRPORT	15184.4	2781.1
17	KHAPRI	18465.5	2117.9
	DEAD END	19250.0	

In the above list it is seen that after NEERI station (not alignment), the line is going straight along Wartha Road up to Khapri. The alignment along Khapri Road is now modified to Wartha Road for the reason that earlier it was taken to Airport but now it is not considered necessary due to heavy small ridership from Airport and high construction cost of Underground section. Hence the ridership has also got modified and given in the tables 2.32- 2.33. The modified phase-I metro network of Nagpur Metro is shown in fig 2.14

Figure 2.14  
FINAL ALIGNMENT




TABLE 2.22 SUMMARY OF RIDERSHIP ON LINE 1 AND LINE 2

BOARDING RIDERSHIP (DAY)	2018	2021	2028	2031	2038	2041
ON LINE 1(AUTOMATIVE-KHARSI)	162361	180531	203728	224316	248418	277704
ON LINE 2(PRAJAPATI-LAKHMANA)	164081	157966	215413	234377	260237	286031
TOTAL OF BOTH	326442	338497	419141	458693	508655	563735
AVERAGE TRIP LENGTH IN KM	6.419	6.455	6.484	6.533	6.521	6.522
MAXIMUM PHDOT ON LINE 1	30089	30936	11513	12934	14286	15729
MAXIMUM PHDOT ON LINE 2	7748	8460	9154	9906	10748	11682
TRIPS WITHIN LINE 1	104350	117020	128883	141988	158191	178897
TRIPS WITHIN LINE 2	120074	125402	140059	152203	170010	187224
INTERCHANGE TRIP AT SITABULDI-RETAJI MARKET	128018	137010	140718	184850	180438	187812
TOTAL TRIPS	352442	380437	410134	458891	508657	563733

### 2.25 DAY BOARDING AND PHDOT

Day boarding on line 1 and line 2 stations estimated for different horizon years are shown in table 2.23.

TABLE 2.23 DAY BOARDING ON LINE 1 AND LINE 2 STATIONS

STATION	2018	2021	2028	2031	2038	2041
	DAY	DAY	DAY	DAY	DAY	DAY
AUTOMATIVE	18528	18734	20941	24527	27996	31877
NARI RD	7241	8823	10380	11619	13257	15445
INDORA	8866	7903	8833	8871	11188	12417
KADY CHR	8021	8978	8855	10874	12137	13300
GADGI DODAM SDR	1227	1894	1558	1793	2145	2582
KARJURCHAND PARK	18198	18708	12188	14288	18888	17688
ZERO MILE	8886	9886	8867	8784	10436	10888
SITABULDI	29382	32982	35888	38182	42980	47138
CONGRESS NAGAR	35331	38283	41307	44414	48844	53300
RAHATE COLONY	8119	8880	8882	10889	12281	13488
GUNI SDR	5028	5729	6283	6882	7843	8429
CHHATRAPATI SDR	3123	3448	3743	4357	4413	4733
JESPRAKASH NAGAR	2028	2233	2387	2888	3875	3158
UJWAL NAGAR	9841	1224	1588	1881	4387	4781
AIRPORT	1788	1836	2038	2238	2441	2834
NEW AIRPORT	1474	1888	2383	3827	7488	9514
KHARSI	18488	17218	18828	20888	22843	26488

LINE 2	DAY	DAY	DAY	DAY	DAY	DAY
PRAJAPATI NGR	3308	3542	3793	4011	4293	4528
WISHVO DEV. CHK	2979	3195	3438	3637	3893	4152
AMBEKAR CHK	3390	3614	3867	4142	4439	4731
TEL EXCHANGE	51400	11813	12858	14210	15876	18778
CHITAR OL CHK	3379	3787	10514	11341	12737	14849
AGRASEN CHK	8332	8791	7280	7829	8301	8347
MAYO HOPITAL	4798	5107	5522	5970	6712	10497
MAGPUR METRO ST	21637	24026	26863	30659	35430	40545
NETAJI MKT	23787	24807	27273	29958	32621	34899
JHANSI RANI SGR	17051	17851	19833	21944	24245	26991
INSTIT. OF ENGINEER	29862	25423	27198	28890	30440	31749
BANK OF INDIA	57778	10026	20876	23215	25991	28584
LAD CHK	3508	3803	4110	4413	4777	5136
DPC OF SCIENCE	9811	10759	11893	12714	13772	14853
SUBHAS NGR	1318	2120	2287	2472	2881	2888
RACHANA	2173	2450	2729	2997	3473	3944
VASUDEV NGR	4818	5366	5820	6326	6821	7480
BANSI NGR	3083	3441	3771	4121	4481	4820
MAHENDRANAGAR	4737	5154	5548	6006	6382	6817
LOKMANYA NAGAR	8863	9629	10489	11300	12098	13734

Change about the boarding pattern is also investigated. On line 1, boarding from Automotive to Kasturba Chk is increased from 43663 to 50100 (+6437), from Zero mile to Congress Nagar is increased from 82791 to 88822 (+11011), from Rajula Colony to Khajuri is increased from 43017 to 48028 (+4911). Total increase is 22100.

On line 2, boarding from Prajapati to Agrasen Chowk is increased from 33791 to 38742 (+4951), from Mayo Hospital to Netaji Market boarding is decreased from 76299 to 68864 (-21315), from Jhansi Rani Sgr to DPC of science boarding is increased from 68489 to 77063 (+8574) and from Subhash Nagar to Lokmanya Nagar boarding is increased from 21448 to 28129 (+6681). Increase of boarding at Sitabuldi is 5212 and decrease at Netaji Market is 4946.

PHFOT of line 1 is increased from 8526 to 10838 (between Sitabuldi and Congress Nagar) while on line 2 PHFOT is decreased from 8552 to 7970 (between Netaji Market and Nagar Railway Station) as the stretch will not be used by line 1 passengers as it is old alignment. Maximum PHFOT of line 2 is between Institute of Engineers and Bank of India Station. PHFOT is 8400 (old alignment PHFOT was 7402 on this stretch). Interchange trip is increased from 33875 to 68505 (one way).

It is seen that in old alignment (via Khamdi Road) case, trips from line 1 were diverting to line 2 via Sitabuldi-Naraj Market Interchange and in new alignment (via Worcha Road) trips are going straight to Sitabuldi and beyond due to change of interchanged areas. Hence the drop of PHFDT on this stretch is expected. The stretches on line 1 from Zero Mile to Sitabuldi and on line 2 from Mayo Hospital to Naraj Market are parallel with average distance between them is 0.8 km. Traffic zones lying in this zone are commercial and office areas including Nagpur rail station.

PHFDT load on line 1 (from Automotive to Khapri) is given in table 2.34.

TABLE 2.34 LINE 1 PHFDT FROM AUTOMATIVE TO KHAPRI

STATION	STATION	2010	2021	2020	2031	2030	2041
AUTOMOTIVE	NARI RD	2001	3010	2433	4040	4811	3274
NARI RD	INDORA	3754	4478	5113	3960	6752	7810
INDORA	KADVI CHK	4885	5767	6647	7062	8908	9833
KADVI CHK	GADDI GODAM SOR	6039	7042	7940	3088	9025	11718
GADDI GODAM SOR	KASTURCHAND PARK	6059	7021	7814	9060	9033	11743
KASTURCHAND PARK	ZERO MILE	7329	8313	9373	10804	12132	13724
ZERO MILE	SITABULDI	8272	9205	10287	11631	13002	14872
SITABULDI	CONGRESS NAGAR	10000	10930	11910	12334	14280	15728
CONGRESS NAGAR	RAHATE COLONY	3288	3728	4330	4918	7588	8477
RAHATE COLONY	AJMI SOR	4513	4878	5338	5854	6478	7140
AJMI SOR	CHHATRAPATI SOR	3005	4241	4641	5084	5607	6180
CHHATRAPATI SOR	JYPRAKASH NAGAR	8561	3802	4185	4560	5073	5838
JYPRAKASH NAGAR	LIJWAL NAGAR	3289	3020	3891	4241	4880	5170
LIJWAL NAGAR	AIRPORT	2939	3136	3441	3787	4177	4624
AIRPORT	NEW AIRPORT	2730	2911	3193	3513	3878	4332
NEW AIRPORT	KHAPRI	2140	2207	2483	2740	3049	3690

PHOT line on line 2 (from Prajapati nagar to Lokmanya nagar) is given in table 2.26.

**TABLE 2.26 LINE 2 PHOT FROM PRAJAPATI NAGAR TO LOKMANYA NAGAR**

STATION	STATION	2016	2021	2026	2031	2036	2041
PRAJAPATI NGR	VASIND DEVI CHK	481	517	549	585	621	659
VASIND DEVI CHK	AMBEDKAR CHK	503	571	633	697	764	830
AMBEDKAR CHK	TEL EXCHANGE	1378	1479	1578	1685	1800	1923
TEL EXCHANGE	CHITAR OLI CHK	2819	3084	3353	3627	3909	4201
CHITAR OLI CHK	AGRASEN CHK	4300	4556	4793	5024	5262	5508
AGRASEN CHK	MAYO HOSPITAL	4843	5197	5572	6007	6504	7066
MAYO HOSPITAL	WASPUR METRO ST	5298	5649	6027	6510	7003	7517
WASPUR METRO ST	SITA BURDI	7341	7770	8254	8800	9418	10112
SITA BURDI	JHANSI RANI SOR	8141	8651	9218	9858	10573	11364
JHANSI RANI SOR	INSTIT OF ENGINEER	4336	4488	4642	4808	5001	5212
INSTIT OF ENGINEER	BANK OF INDIA	7746	8458	9154	9956	10776	11628
BANK OF INDIA	LAD CHK	6114	6693	7275	7899	8610	9314
LAD CHK	DPC OF SCIENCE	5601	6147	6684	7250	7930	8688
DPC OF SCIENCE	SUBHAS NGR	4372	4472	4579	4691	4809	4937
SUBHAS NGR	RACHANA	3787	4157	4530	4924	5410	5871
RACHANA	VASUDEV NGR	3404	3628	4133	4527	4932	5341
VASUDEV NGR	BANSI NGR	3714	3960	4217	4504	4819	5136
BANSI NGR	MAHENDRA MAHENDR	2212	2400	2603	2833	3082	3349
MAHENDRA MAHENDR	LOKMANYA NAGAR	1430	1550	1688	1852	2042	2250

Salient features of the two alternatives are shown in table 2.26.

**TABLE 2.26 COMPARISON OF SALIENT FEATURES BETWEEN TWO ALTERNATIVES (Year 2021)**

SUMMARY	NEW ALIGNMENT (STRAIGHT ALONG WARDAHA ROAD)	OLD ALIGNMENT (ALONG KHAMLA ROAD)
LINE 1 LENGTH	19.200 KM	21.900 KM
LINE 2 LENGTH	18.057 KM	18.296 KM
BOARDING/RIDERSHIP (DAY)	YEAR 2021	YEAR 2021
ON LINE 1 (AUTOMATIVE- MISANKHAPSI)	185331	163371
ON LINE 2 (PRALAPAT), LOHMANVA)	197936	199328
TOTAL OF BOTH	383439	362709
AVERAGE TRIP LENGTH IN KM	6.453	6.264
MAXIMUM PH/PDT ON LINE 1	10306	8526
MAXIMUM PH/PDT ON LINE 2	9400	8900
TRIPS WITHIN LINE 1	117025	109036
TRIPS WITHIN LINE 2	129432	146000
INTERCHANGE TRIP AT SITABULDHETA, MARKET	137910	108989
AVERAGE TRIP LENGTH IN KM	6.45	5.78

It is observed that boarding wise there shall be no loss (rather a net gain of 20786 trips). On line-1 maximum PH/PDT will increase but on line 2 maximum PH/PDT will be on another link. Maximum PH/PDT will decrease on previous link (old alignment) due to shift of boarding from line 2 to line 1 in the CBD area as explained before. Some trips from/to Khamsi side (stations from Dev Nagar to Old Airport) will now use line-1 stations from Chhatrapati Square to Airport. In 2021, average trip length will be 6.45 km for new alignment as against of 5.78 km in old alignment. Length of line-1 will decrease by around 2.5 km and also there will be road reduction due to avoidance of the underground portion. Original alignment of line 1 was planned on the assumption of full development of Mihan Industrial Area, Cargo Hub and International Airport and if these projects are not completed in time, original alignment of line 1 via old air-port may not be so useful and economically not viable. Hence pragmatically speaking, the new alignment of line-1 is better.



# CHAPTER 3

## SYSTEM SELECTION



- 3.1 GENERAL
- 3.2 BENEFITS OF MASS TRANSPORT SYSTEM
- 3.3 METRO SYSTEM WORLD WIDE
- 3.4 WORLD METRO GRAPH
- 3.5 FAMOUS METRO SYSTEMS
- 3.6 OPTIONS FOR PUBLIC TRANSPORT SYSTEM
- 3.7 CHARACTERISTICS OF URBAN TRANSIT SYSTEM

### TABLES

- TABLE 3.1 SPREAD OF WORLD METRO RAIL SYSTEMS
- TABLE 3.2 PASSENGER CARRYING CAPACITY PER TRAIN (TYPICAL) FOR DIFFERENT TRANSIT SYSTEMS
- TABLE 3.3 SUSTAINABILITY MODEL OF PUBLIC TRANSPORT MODES

### FIGURES

- FIG. 3.1 TRANSPORT CAPACITY OF DIFFERENT MODES AS A FUNCTION OF HEADWAY
- FIG. 3.2 GRAPHICAL COMPARISONS OF THE MOST IMPORTANT CHARACTERISTICS WORLD WIDE IN THE SELECTION OF DIFFERENT TRANSPORT MODES

**Chapter - 3****SYSTEM SELECTION****3.1 GENERAL**

The population growth in cities and urban centres has put a lot of pressure on the infrastructure of these cities. In rapidly developing countries like India the urban infrastructure is stretched to limit and requires very effective solutions. The rapid development in India is not unprecedented and such development earlier took place in several nations of Europe, America and in Japan. So several modes of urban mass transit are now available for solution to the problem of Urban Transit in Nagpur.

L&I Ramboll Consulting Engineers Limited had carried out the Comprehensive Traffic and Transportation Study and prepared Transportation Master Plan for Nagpur city commissioned by NMC. As a part of study they also recommended four Metro Corridors which have been discussed in Chapter-1 of this DPR.

**3.2 BENEFITS OF MASS TRANSPORT SYSTEM**

The main benefits addressed by mass transport are the mobility and freedom. The sustainability of mass transport has greater potential and major benefits occur through inevitable means of helping the environment and conserving energy. In developing countries, like India, benefit through mass transit systems extend to urban poor with affordable fare structure when compared with costs incurred by private transportation on fuel, parking, congestion etc. The supply of planned and integrated mass public transport is the only way to relieve traffic congestion and reduce hours of delay on major travel corridors. Moreover, supply of metro rail system in Nagpur urban complex will mean a lot in terms of sustainable means of transport that meets the mobility and accessibility needs of people.



### 3.2 METRO SYSTEM WORLD WIDE

Metro system is used in metropolitan areas to transport large number of people at high frequency. Rapid transit evolved from railways during the late 19th Century. The first system opened was the Metropolitan Railway (London) which connected most of the main railway termini around the city. The technology swiftly spread to other cities in Europe and then to United States and other parts of the world. At present, more than 180 cities have built rapid transit systems, and about twenty five have new systems under construction. The system is seen as an alternative to an extensive road transport system with many motorways. The capital cost is high, with public financing normally required.

India is experiencing a rapid growth in both population and rate of urbanisation. Travel demand is increasing by 5% annually on average, leading to sharp increase in personal vehicles and overwhelming the limited transport infrastructure. A need was therefore felt to develop mass rapid transit systems in metro cities of India to reduce the burden of normal railways as well as road transport service providers. Major cities were facing a situation of rising population and increasing vehicles which had led to problems like congestion and pollution. To overcome these problems, Indian Railways took an initiative towards development of urban mass transit system by starting metro rail. Metro rail systems are operational in Delhi, Kolkata and Bangalore. Metro projects are taken in various cities like, Mumbai, Chennai, Hyderabad, Jaipur, Kolkata, Kochi.

A summary of metro network developed worldwide is given below in Table 3.1.

**Table 3.1: Spread of World Metro Rail Systems**

City	Country	Continent	Commencement	Network Length (km)	Daily Ridership (million)
Aachen	Europe	Europe	15-May-05	13.5	
Amsterdam	Netherlands	Europe	15-Oct-77	32.7	0.232
Ankara	Turkey	Asia	20-Aug-08	22.1	0.21
Antwerp	Belgium	Europe	25-Mar-75	7.6	
Athens	Greece	Europe	1984	42.0	0.077
Austin	USA	America	20-Jul-93	79.2	0.0992
Baku	Azerbaijan	Asia	6-Nov-07	32.0	0.432
Baltimore	USA	America	21-Nov-82	24.0	0.0358
Bangkok	Thailand	Asia	5-Jan-03	14.3	0.164
Barcelona	Spain	Europe	20-Oct-04	119.4	1.1
Beijing	China	Asia	1-Oct-09	337.0	3.89
Belo Horizonte	Brazil	America	1-Aug-88	26.1	
Berlin	Germany	Europe	15-Jul-02	127.4	1.33
Birmingham	Germany	Europe	21-Sep-77	9.2	
Bilbao	Spain	Europe	11-Nov-00	40.8	0.228
Bonn	Germany	Europe	28-May-78	27.6	
Bonn	Germany	Europe	23-Mar-76	9.0	
Boston	USA	America	1-Sep-1987	30.5	3.4
Braşov	Romania	America	21-Nov-01	42.0	0.0428
Brussels	Belgium	Europe	20-Sep-78	32.2	0.389
Bucharest	Romania	Europe	16-Nov-75	87.7	0.304



City	Country	Contract	Commencement	Network Length (km)	Delivery Mileage (miles)
Budapest	Hungary	Europe	2 May 1998	33.0	0.814
Buenos Aires	Argentina	America	5 Jan '11	46.1	1.162
Buffalo	USA	America	19 May '01	8.4	
Bursa	Turkey	Asia	10 Apr '02	25.4	
Buenos	South Korea	Asia	16 Jun '01	56.0	0.734
Caen	France	Europe	27 Sep '81	66.5	1.62
Caracas	Venezuela	America	27 Jun '01	60.5	1.25
Casaca	Italy	Europe	27 Jun '08	3.8	
Changshu	China	Asia	11 '02	17.0	
Cherbourg	Belgium	Europe	21 Jun '79	17.6	
Chengde	China	Asia	27 Sep '11	18.6	
Chennai	India	Asia	18 Oct '07	27.0	
Chiba	Japan	Asia	20 Jun '88	15.3	
Chicago	USA	America	6 Jul 1998	146.0	0.642
Chongqing	China	Asia	25 Jun '09	18.5	
Cleveland	USA	America	15 Sep '05	31.0	0.813
Cologne	Germany	Europe	11 Oct '06	49.0	
Copenhagen	Denmark	Europe	10 Oct '02	21.0	0.128
Daejeon	South Korea	Asia	26 Apr '01	61.0	0.301
Damascus	South Korea	Asia	16 Sep '08	22.8	0.178
Davao	China	Asia	7 May '01	68.0	
Delhi	India	Asia	24 Oct '02	187.2	0.608
Detroit	USA	America	27 '87	4.8	
Düsseldorf	Germany	Europe	25 Dec '08	7.1	0.034
Düsseldorf	Germany	Europe	17 May '79	28.5	
Duba	United Arab Emirates	Asia	8 Sep '08	12.1	
Düsseldorf	Germany	Europe	4 Oct '87	8.8	
Düsseldorf	Germany	Europe	7 Jul '02	14.3	
Durham	Canada	America	20 Apr '78	20.4	
Düsseldorf	Germany	Europe	5 Oct '97	25.2	
Düsseldorf	Germany	Europe	4 Oct '88	20.0	
Fukuoka	Japan	Asia	26 Jun '81	20.8	0.34
Gelsenkirchen	Germany	Europe	1 Sep '84	6.5	
Gera	Italy	Europe	13 Jun '00	5.2	
Glasgow	United Kingdom	Europe	14 Dec 1998	10.8	0.2411
Guadalajara	Mexico	America	1 Sep '89	24.0	
Guangzhou	China	Asia	26 Jun '08	231.8	1.38
Guangzhou	South Korea	Asia	20 Apr '04	20.1	0.0488
Hala	Israel	Asia	1992	7.8	
Hamburg	Germany	Europe	1 Oct '72	130.7	0.618
Hamburg	Germany	Europe	26 Sep '75	18.8	
Helsinki	Finland	Europe	3 Aug '82	21.0	0.128
Hiroshima	Japan	Asia	20 Aug '89	18.4	0.0482
Hong Kong	China	Asia	1 Oct '78	188.7	0.82
Houston	South Korea	Asia	4 Oct '09	20.6	0.2
Ilford	UK	Europe	10 Sep '00	18.3	0.328
Ilford	UK	Asia	22 May '00	11.3	0.022
Jacksonville	USA	America	10 May '83	6.0	
Kanagawa	Japan	Asia	3 Mar '71	8.8	
Karlsruhe	France	Asia	5 Mar '00	42.7	0.022



City	Country	Contract	Commencement	Network Length (km)	DRY Rating (million)
Kiev	Ukraine	Europe	27-Aug-05	10.0	0.210
Kievko	Ukraine	Europe	27-Aug-05	17.2	0.362
Kiel	Germany	Europe	22-Oct-05	82.7	1.78
Koblenz	Germany	Asia	2-Jan-05	8.0	
Kyoto	Japan	Asia	15-Mar-77	10.8	0.232
Kyoto	Japan	Asia	24-Oct-83	22.6	0.474
Kyryi Hill	Ukraine	Europe	26-Dec-05	16.0	
Kuala Lumpur	Malaysia	Asia	0-Dec-08	94.0	2.00
Kyoto	Japan	Asia	7-Aug-07	11.3	0.246
Las Vegas	USA	America	16-Jul-04	8.0	
Laxenburg	Austria	Europe	24-May-07	13.7	
Lille	France	Europe	25-Apr-03	40.0	0.822
Lima	Peru	America	05-Jan-02	10.0	
Lisbon	Portugal	Europe	20-Dec-05	41.0	0.868
Lisbon	United Kingdom	Europe	07-Jun-00	438.0	2.34
Los Angeles	USA	America	24-Jun-07	50.0	0.125
Ludwigshafen	Germany	Europe	28-May-03	4.0	
Lyon	France	Europe	26-Apr-78	30.7	0.660
Madrid	Spain	Europe	17-Oct-78	288.0	1.78
Madrid	Philippines	Asia	5-Dec-84	11.0	0.240
Maastricht	Netherlands	America	8-Jul-08	8.0	
Marseille	France	Europe	28-Mar-77	27.8	0.100
Miami	United States	Asia	13-Jun-70	18.1	
Manila	Philippines	America	01-Jun-05	28.8	0.425
Manila City	Philippines	America	2-Sep-05	231.7	3.88
Manila	USA	America	27-May-89	80.0	0.240
Milan	Italy	Europe	1-Nov-04	10.8	0.600
Minsk	Belarus	Europe	26-Jul-04	10.0	0.778
Moscow	Russia	America	25-Apr-07	11.0	
Moscow	Russia	America	14-Oct-08	80.0	0.8
Moscow	Russia	Europe	16-May-04	100.0	6.44
Munich	Germany	Europe	5-Jun-79	8.0	
Munich	Italy	Asia		171.0	
Munich	Germany	Europe	04-Oct-77	94.2	0.202
Nagoya	Japan	Asia	16-Nov-87	80.0	1.17
Naha	Japan	Asia	03-Aug-05	12.8	
Nagoya	China	Asia	27-Aug-05	64.7	0.4
Nairobi	Kenya	Europe	25-Mar-02	11.8	0.378
New York	USA	America	27-Oct-04	280.0	4.21
Newark	USA	America	28-May-04	0.0	
Norwalk	United Kingdom	Europe	7-Aug-05	18.0	0.124
Norwich (England)	Ukraine	Europe	20-Apr-05	15.0	0.094
Norwalk	Ukraine	Asia	7-Jan-08	18.8	0.102
Nuremberg	Germany	Europe	1-Mar-72	18.8	0.376
Osaka	Portugal	Europe	7-Dec-02	21.7	
Osaka	Japan	Asia	27-May-23	157.0	2.38
Ottawa	Germany	Europe	22-May-08	82.0	0.274
Palma de Mallorca	Spain	Europe	20-Apr-07	8.0	
Paris	France	Europe	16-Jul-05	213.0	4.06
Parigi	Italy	Europe	24-Jun-08	0.0	




City	Country	Contract	Commencement	Network Length (km)	DrV (Millions)
Hialeah	USA	Aerovia	4-Mar-07	62.0	6.100
Metairie	USA	Aerovia	3-Jul-05	2.0	
Paris-Rueil	Spain	Aerovia	2-Sep-00	22.0	
Paris	France	Europe	7-Apr-07	6.1	
Prague	Czech Republic	Europe	9-May-18	66.1	1.8
Vordingborg	Norway	Asia	8-Sep-13	22.5	0.050
Roske	Spain	Aerovia	14-Sep-05	36.7	
Rosno	France	Europe	19-Sep-02	6.0	0.002
Rosno-Jarvis	Spain	Aerovia	8-Mar-10	62.0	0.07
Rosno	Spain	Europe	10-Jul-08	36.0	0.007
Rotterdam	Netherlands	Europe	10-Jul-08	47.0	0.238
Rouen	France	Europe	17-Dec-04	2.2	
Salt Lake	USA	Aerovia	21-Jun-01	12.4	
Saint-Petersburg	Russia	Europe	16-Mar-08	110.0	0.35
Saintes	France	Europe	26-Dec-07	10.2	0.028
San Francisco	USA	Aerovia	11-Sep-12	188.0	0.200
San Juan	Puerto Rico	Aerovia	8-Jul-05	17.2	0.047
Santiago	Chile	Aerovia	15-Sep-10	102.4	1.67
Santo Domingo	Dominican Republic	Aerovia	30-Jun-08	14.6	0.2
San Pedro	Spain	Aerovia	14-Sep-04	56.7	1.01
Sapporo	Japan	Asia	18-Dec-11	48.0	0.071
Sao Paulo	USA	Aerovia	18-Jul-08	62.2	
Saitama	Japan	Asia	16-Jul-07	14.6	0.190
Saudi	Saudi Arabia	Asia	16-Aug-14	288.0	0.67
Savona	Spain	Europe	2-Apr-08	18.0	
Shanghai	China	Asia	11-Apr-00	423.0	0.08
Shenyang	China	Asia	27-Sep-10	27.4	
Shenzhen	China	Asia	26-Dec-04	65.1	0.360
Singapore	Singapore	Asia	7-Nov-07	126.7	1.67
Sofia	Bulgaria	Europe	20-Jun-08	18.0	0.078
Stockholm	Sweden	Europe	1-Oct-01	186.7	0.667
Strasbourg	Germany	Europe	11-Jul-08	24.0	
Sydney	Australia	Oceania	1998	21.1	
Taipei	Taiwan	Asia	20-May-00	100.0	0.27
Tama	Japan	Asia	27-Nov-00	16.0	
Taipei	Taiwan	Asia	8-Jun-17	66.0	0.100
Tokyo	Germany	Asia	11-Jun-06	28.3	0.250
Toronto	Asia	Asia	27-Jul-00	60.0	1.28
The Hague	Netherlands	Europe	09-Oct-04	22.0	
Tientsin	China	Asia	26-May-08	72.0	0.0411
Tokyo	Japan	Asia	01-Dec-12	204.0	0.7
Toronto	Canada	Aerovia	01-Apr-04	11.0	0.190
Toulouse	France	Europe	28-Jun-00	27.0	0.170
Toronto	Spain	Europe	4-Jul-06	6.6	
Vancouver	Vancouver	Aerovia	16-Jul-08	6.2	0.040
Vancouver	Spain	Europe	20-Oct-08	21.8	
Vladivostok	China	Aerovia	20-Nov-00	40.0	
Vancouver	Canada	Aerovia	3-Jun-08	60.0	0.200
Vienna	Austria	Europe	26-Feb-10	14.8	1.2
Vladivostok	Russia	Europe	5-Nov-04	3.0	



City	Country	Continent	Commencement	Network Length (km)	Daily Ridership (million)
Warsaw	Poland	Europe	1-Apr-09	22.8	0.340
Washington	USA	America	21-Mar-09	171.2	0.811
Rabat	Tunisia	Asia	25-Sep-04	28.0	0.016
Wuppertal	Germany	Europe	1-Mar-01	13.1	
Yokohama	Japan	Asia	26-Apr-01	8.5	0.128
Yaroslavl	Russia	Asia	1-Mar-01	12.1	0.048

#### 3.4 WORLD METRO GRAPH





3.6 FARDUS METRO SYSTEM:-



London



Medellin



Taipei



Paris



Delhi



Kolkata





## 3.2 OPTIONS FOR PUBLIC TRANSPORT SYSTEM

3.2.1 The following systems are mainly available for Urban Mass Transit:


- (i) **Metro System:** Metro system is a grade separated dedicated system for high peak hour traffic densities exceeding 40,000 PMPDT. It is characterized by short distances of stations spaced at 1 km, high acceleration and deceleration and scheduled speeds of 30-35 kmph.
- (ii) **Light Rail Transit:** Modern Semi-Steel Cars running on Rails at grade or elevated with sharp curves of 24m radius. These are extremely popular and operating in large number of European countries. Generally the stations are spaced at 500m to 1 km and have high acceleration and deceleration characteristics. In most of the countries, they are operating at-grade with prioritized signaling at road intersections.
- (iii) **Ray Train:** This is an experimental rail based system under development by Korean Railway.
- (iv) **Other Rail Based Systems:** A number of options are available but have not been introduced in India. Some of these are very briefly mentioned below:
  - (a) **Maglev:** This is an advanced Rail based transit system in which Magnetic Levitation is used to raise the vehicles above the rail surface. Rail wheel interaction is thus avoided and very high speeds are attainable. Maglev Levitation can either be due to attractive force or due to repulsive forces.
  - (b) **Linear Induction Motor (LIM) Train:** This is also an advanced Rail based transit system in which propulsion is through a Linear Induction Motor whose stator is spread along the track. The rotor is a magnetic material provided in the under frame of train. In the technology the tractive force is not transmitted through rail-wheel interaction, and so there is no limitation on account of adhesion. The technology is most appropriate for tunnels, as the height of the tunnel can be reduced to lower height of cars.
- (v) **Monorail:** Monorail trains operate on grade separated dedicated corridors with sharp curves of up to 70m radius. This is a rubber tyred based rolling stock, electrically propelled on concrete beams known as guideways. The system is extremely suitable in narrow corridors as it requires minimum right of way on existing roads and permits light and air and is more environmental friendly. This is prevalent in several countries for traffic densities of over 20,000 PMPDT.
- (vi) **Bus Rapid Transit System:** This system involves operation of buses on a dedicated corridor (except of traffic integration) at a high frequency to achieve PMPDT.



For providing a very high transport capacity say 20,000 PHPT, about 200 buses shall be required per hour i.e., at headway of 20 seconds. Such a high PHPT can be achieved by providing two lanes of traffic in each direction and elimination of traffic intersection on the route.

- (vi) **Automated Guide way Transit System:** The term is used for systems other than conventional rail-based system on grade separated guide ways. The systems can be rail based or rubber tire based but fully automated guided systems with driver less operation.

3.3.2 - The salient features of the various Transit Systems are summarized as under:-

System	LRT (Light Rail Transit) (Elevated)	AOT (Automated Guide way Transit)	Straddle type Monorail
Labels of Vehicle	 It is a transport system that runs on the exclusive beam and track mostly built over highways.	 It is a rail transport system that runs on the exclusive track built on elevated structure with highway vehicle.	 It is a rail transport system that runs straddling on the exclusive beam track mostly built over highways.
Trailing wheel			
Length (m)	30.0 (articulated type)		
Width (m)	2.3		
Height (m)	3.7		
Number of doors	2		
Wheel arrangement	2-2-0		
Weight (tons) (m)	44		
Axle load (tons)	10.1		
Type of rail used	Concentrated load	Concentrated load	Concentrated load
Powering gear and track structure			
Traction system	Flange Motor and steel wheel	Flange Motor and rubber tire	Flange Motor and rubber tire
Drive system	Electric drive and for traction, brake	Electric brake and air brake	Electric brake and air brake
Guideway System	Steel rail	Laminated prestressed Concrete	Guide Wheel (Rubber)
Power collector	Catenary	Conductor rail	Conductor rail
Voltage	D.C. 750 V	A.C. 750 V (Three phase)	D.C. 1,000 V
Track	Steel rail	Concrete slab	Track beam



System	LRT (Light Rail Transit) (planned)	AOT (Automated Drive way Transit)	Straddle (eye Horizontal)
Track			
Construction	Grade and crossing	Lateral platform with	Flange track beam
The Operative Characteristics			
Maximum speed	80 km/h	80 km/h	80 km/h
Service speed	30 km/h	30 km/h	30 km/h
Minimum curve radius	20m	20m	70m
Maximum gradient	4 %	6 %	6 %
Acceleration	1 km/h/s	1 km/h/s	1 km/h/s
Deceleration: Service trails	1 km/h/s	4 km/h/s	4 km/h/s
Emergency trails	4 km/h/s	6 km/h/s	4 km/h/s
Automatic train operation	There is low example of it	It has been developed writing for automatic operation. There are many examples of automatic operation including intensive operation	There are three cases of ATC operation in Japan.
Energy/vehicle capacity			
1 car seat	80		40
standing	30		40
total	110 (30m)	80 (1+0m)	100 (3+70m)
4 car seat	120		160
standing	180		240
total	300 (30m+30m)	280 (8-car L+04m)	400 (L+60m)
5 car seat	200		300
standing	300		400
total	500 (30+30m+30m+30m)	420 (12 car L+70m)	640 (L+120m)
6 car 190/217 (110% , between 2+ m)	24,480	17,300 (100%)	24,300
	It is possible to deal with over 24,480 190/217 of demand. (train length 120m)	It is possible to deal with up to 17,300 190/217 of demand. (train length 100m)	It is possible to deal with over 24,300 190/217 of demand (train length 120m)
Structure			
Superstructure	Concrete slab	Concrete slab	Track beam
Net and foundation	Concrete	Concrete	Concrete
Maintenance and cost			
Track	In addition to grinding of surface of rails, track maintenance work will require	It has small maintenance of track.	It has small maintenance of track.



System	LRT (Light Rail Transit) (proposed)	AOT (Automated Guided way Transit)	Shinkansen (High Speed Rail)
	short time		
Vehicle	Maintenance of rotary motor and greasing of steel wheels shall be necessary.	Maintenance of rotary motor and exchange of rubber tire after every 125,000 km running shall be necessary.	Maintenance of rotary motor and exchange of rubber tire after every 125,000 km running shall be necessary.
Effect on ambient surrounding and behavior with other vehicles			
Effect on ambient surrounding	No impact of wheels noise as steel wheels on rubber tire track.	Low running between AGV and steel is not available. The system with rubber tire makes steel noise and vibration. Because its running surface is made of concrete slab, there remain problems like existence of cracks or holes (discrepancy).	This system will reduce the noise steel noise and vibration.
visual landscape	This system is inferior to other systems in terms of landscape because overhead wires for power collection must be installed.	Because its superstructure is made of concrete slab, depressing feeling of view is an issue.	This system is superior to AGV or LRT from a view of landscape because its superstructure consists of only track beams that have small section.
Disruption associated			
	Evacuation after train (pass to end or side by side)	Evacuation after train (pass to end or side by side)	Evacuation after train (pass to end or side by side)
	Walk way	Walk way	Evacuation shelter
	In case of emergency, supporting vehicles will engage in rescue activities. If supporting vehicles cannot do that, it is possible for passengers to evacuate to nearest stations through evacuation passage by walk.	In case of emergency, supporting vehicles will engage in rescue activities. If supporting vehicles cannot do that, it is possible for passengers to evacuate to nearest stations through evacuation passage by walk.	In this system, supporting vehicles are needed for passengers' emergency evacuation, which is inferior to other systems like Shinkansen. In addition, there is a safety concern of performance of running in Japan and has a established method for rescue.
Operation cost			
Construction			2.26M USD/km
Running cost			
Life			7.5 Years



System	Urban Massiv (MRT)	Metro/ Subway	Bus Rapid Transit
<p>    </p>	<p>                     It is a mass transport system that runs on the exclusive beam with track, mostly built over highways.                 </p>	<p>                     It is Metro or Heavy Rail Transit (HRT) is a specialized, essentially powered rail system carrying passengers within urban areas.                 </p>	<p>                     It is a bus system generally characterized by use of exclusive or reserved right-of-way (Buss lanes). But permit higher speeds and economies of scale to cater general traffic flows.                 </p>
Rolling stock			
Length (m)			16 (articulated bus)
Width (m)			2.5
Height (m)			3.5
Number of doors			2
Wheel arrangement	3 axle / 6 wheel	2/2 or 3/1	Independent drive
Weight (empty) (ton)	15.0	41	12 to 18
Area (sq. meter)	2,500sq.	170sq.	30 to 15.30
Type of track	dedicated track	Dedicated / rail	Dedicated track
Traction gear and track structure			
Traction system	Direct Traction Motor and Direct magnetic inductive system	Tractor Motor and steel wheel	Rubber tyre
Brake system	Electric Brake and air brake	Electric Brake and Hydraulic Brake and Regenerative Brake	Hydraulic Brake
Guidance System	Direct magnetic inductive system	Steel Rail	None, system guide wheels or kerbs
Power supply	Conductor rail	Catenary or Conductor rail	Not applicable
Voltage	D.C. 1,500V	D.C. 750V & A.C. 25kV	None
Track	Steel rail, Electromagnetic inductive system	Steel rail	Fixed
Signal			
Construction	Flexible track layout	Switch and crossing	Fixed Crossing
File Operation (Turn/switch)			
Maximum speed	80 km/h	80 to 100 km/h	80 km/h



System	Urban Metro (BRT)	Metro/ Subway	Bus Rapid Transit
Schedule speed	30 km/h	30 km/h	30 km/h
Minimum curve radius	50m	100m	50m
Maximum gradient	8 %	4 %	
Acceleration	1 km/h/s	1 km/h/s	
Deceleration - Service state	1 km/h/s	1 km/h/s	
Emergency brake	4 km/h/s	4 km/h/s	
Automatic train operation	There are cases of ATC operation in Tokyo/Japan	Automatic train operation	No
Transportation capacity			
1 car / rail	32	76	76
standing	40	120	40
total	74 (L=140)	300(L=300)	110(L=110)
4 car / rail	128	300	
standing	150	300	
total	300 (L=300)	600(L=300)	
3 car / rail	240	600	
standing	344	600	
total	600 (L=120)	1000(L=120)	
5 car / rail (100%) (100% / headway 2.5 min)	25,100 (near 100%)	55,000	
	It is possible to deal with over 25,100 (94%) of demand (train length 112m)	It is possible to deal with over 50,000 (94%) of demand (train length 112m)	It is possible to deal with over 4,000 (94%) of demand
Structure			
Superstructure	Concrete slab	Concrete slab	Roads
Fill and foundation	Concrete	Concrete	
Maintainability and cost			
Track	It has low maintenance of track as there is less physical movement.	It has low maintenance of track.	It requires maintenance of tracks.
Vehicle	As it has no entry point, it is excellent in maintenance.	Maintenance of entry point and greasing of steel wheels shall be necessary.	Maintenance of engine and other parts shall be necessary.
Effect on accident involving and handling with other vehicles			



System	Urban Negligé (RRT)	Metro/ Subway	Bus Rapid Transit
Effect on ambient surroundings	There remains problems like addition of overhead or radio infrastructure, because its supporting structures are made of concrete steel.	This system is better due to steel when underground.	Lower and Pollution free mode
Urban landscape	This system is better to other systems in terms of landscape. Because overhead wires for power collection must be installed.	Decision by infrastructure is made of concrete steel. Supporting facility of steel is not seen. This system is better to other systems in terms of landscape. Because overhead wires for power collection must be installed.	No such issues
Emergency evacuation			
	Evacuation other than (and to) exit or side by exit)	Evacuation other than (and to) exit or side by side)	No problems
	Walk way	Walk way	
	In case of emergency, supporting vehicles will engage in rescue activities. If supporting vehicles cannot do that, it is possible for passengers to evacuate in nearest stations through evacuation passage by walk.	In case of emergency, supporting vehicles will engage in rescue activities. If supporting vehicles cannot do that, it is possible for passengers to evacuate in nearest stations through evacuation passage by walk.	
Operation cost			
Electric energy	2.26 million/km		
Rolling stock cost			
Cost		6 to 10 Crores	Two lakhs

## 3.2 CHARACTERISTICS OF URBAN TRANSIT SYSTEM

### 3.2.1 Transport Capacity

It is product of passenger carrying capacity of a train and maximum per-minute frequency of train operation. The passenger carrying capacity is determined by number of cars (units/ coaches), which can be stubbed to form a train and dimensions of each car. To compare different systems uniform packing density is considered although for different systems different crush loading may be permissible. The passenger carrying capacity is dependent on the following:

- (i) **Dimensions of vehicle:** Length and breadth, useful area. The cars vary from about 9m to 24m for most of systems. The width varies from 2.5m to 3.0m.



- (b) **Passengers per m<sup>2</sup>:** The normal to crush loading of most systems varies from 4 to 7 passengers per m<sup>2</sup>.
- (c) **No of Cars per train:** The cars can be from 1 to 10 for most of the systems and the train length can be up to 300m.

**Table 3.2: Passenger carrying Capacity per Train (typical)  
for different Transit Systems**

S. No.	Transit System	Car Size (length m <sup>1</sup> x breadth m <sup>2</sup> )	Car Capacity (No. of passengers /car)	No of Cars /Train	Train Length m <sup>3</sup>	Train Capacity passenger /Train
1	Light-rail monorail	13 x 3	170	2 to 8	120	1400 for 6cars
2	Heavy Metro Rail	21 to 24 x 2.8 to 3.8	250	8 to 15	190 to 315	2000 for 8cars
3	Bus	18 x 2.5 to 3	70 to 100	1 to 2	18	100 per bus
4	AGT	8 to 13 x 2.5 to 3	88 to 120	2 to 12	105	720
5	LRT	18 <sup>4</sup> x 2.65	145 <sup>5</sup>	2 to 8	72	700 <sup>6</sup>
6	Maglev	18 x 2.8	170	2 to 8	120	1300 for 8 cars

(Standard Occupancy rate: 0.34 m<sup>2</sup>/passenger)

<sup>4</sup> Smallest combination of modules for an independent LRT

- (d) **Headway:** The headway and frequency of train operation depends on Signaling and Rolling Stock characteristics viz. control systems, acceleration (tractive effort) and maximum permissible speed (adhesion). A graph showing the carrying capacity of different modal and passenger capacity is given below (see next page).
- (e) **Train Signaling and Control Systems:** The various train signaling and control systems which help in increasing frequency of operation are:
- Automatic Train Operation and Control System (ATO)
  - Automatic Train Supervision System (ATS)



## ➤ Automatic Train Protection System (ATP)




Figure 3.1 Transport Capacity of Different Modes as a Function of Headway

- (f) **Traction effort and Acceleration:** By increasing the tractive effort and acceleration it is possible to increase transportation capacity both by improving the average speed and also by permitting higher frequency of train operation. The factors influencing tractive effort/acceleration speed are:

- Adhesion
- Ratio of Motor coaches to trailer coaches
- Traction Motor Rating
- No of Traction Motors per car
- Drive System

**3.1.2 Geometric Characteristics:**

- (i) **Minimum Radius:** varies from 25m minimum for LRT, 70m for Monorail to 120m for Metro.
- (ii) **Right of Way:** The right of way required for a Grade Separated (skewed) system is solely determined by the building line provided the cars can be accommodated on the central strip. For an At Grade system the Right of Way required is determined by lines required for motorized non motorized vehicles in

addition to width of road required for the mass transit system. The minimum right of way required is about 22.5m.

(iii) **Gradient:** Ruling gradient varies from system to system.

➤ **Environmental Characteristics Noise:**

Rubber tyre on road is less noisy as compared to steel wheels on rails.


➤ **Aesthetics, Air and Sunshine:** The at grade systems are least restrictive in exposing the corridors, buildings next to these corridors and people (on these corridors) inhabiting buildings next to these corridors) to natural air and sunshine.

The effect of elevated systems on the existing buildings and their inhabitants is the worst. Comparatively the best system as far as this factor is considered is underground metro rail system.

➤ **Pollution:** All electrically driven systems are better than diesel operated systems. This is where Rail based systems score over the Road based vehicles.

Graphical comparisons of the most important characteristics which influence selection of different technologies are depicted in the Figure 3.2 below:-

Fig-3.2



As shown, carrying capacity increases with the speed of the service and the cost to construct. The rail family can carry more passengers per hour at a faster speed, but most systems cost more to construct than do bus-based systems.



### 3.7.3 Need for a Grade Separated Transit System

- a) A large number of inter change points.
- b) High vehicular density.
- c) Excessive congestion and delays on the corridors, especially during peak hours.
- d) As the corridors are normally following busy areas of the city, it is not easy to find the required areas for depots, workshops.

Additional capacity needs to be created on the corridors to accommodate more traffic on the roads. More re-allocation of road space to provide for dedicated bus lanes for public transport may not serve the purpose due to presence of large number of private vehicles, which will continue to operate, and whole numbers will continue to rise. Further presence of large number of inter change points will severely restrict speed of operation of public transit system employing dedicated lanes. Considering projections of travel demand on those corridors it is essential to provide grade separated transit system for those corridors.

In view of levels of services that will be required to meet the travel demand on the corridors, a fixed guide way, grade separated system is unavoidable.

### 3.7.4 Discussions on suitability of various modes

The following shows the suitability of various modes of public transport in terms of parameters.

**TABLE 3.3: Suitability Matrix of Public Transport Modes**

Mode of transport	Not an Overcrowded	Not an Effect on Road Users	Not an Effect on the Environment	An effective Decision to Sustainable	An effective Effect on the Environment	Efficient	No Safety
Micro Rail elevated	✓	✓	✓	✓	✓	✓	✓
Micro Rail underground	✓	✓	✓	✓	✓	✓	✓
LRT elevated	✓	✓	✓	✓	✓	✓	✓
LRT at Grade	✓	✓	✓	✓	✓	✓	✓
Monorail	✓	✓	✓	✓	✓	✓	✓
Subway elevated	✓	✓	✓	✓	✓	✓	✓
AGT elevated	✓	✓	✓	✓	✓	✓	✓
Light Rail elevated	✓	✓	✓	✓	✓	✓	✓
Bus At Grade	✓	✓	✓	✓	✓	✓	✓
Bus Elevated	✓	✓	✓	✓	✓	✓	✓
✓	Adverse						
X	No Adverse Effect						



### 3.7.6 Feasibility of other systems:

Mopla is an energy guzzler and the AGT is primarily a proprietary system. Gay train is yet on experimental stages.

### 3.7.8 LRT and Monorail System:

From traffic point of view LRT and monorail systems appears to be good enough to meet requirement of traffic.

### 3.7.7 Feasibility of Metro system for Nagpur:

From the 'Traffic Demand Forecast' it can be seen that peak hour peak direction trip (PHPDT) on the North South Corridor is 7375, 8526, 10987 and 14332 the year of 2016, 2021, 2031 and 2041 respectively. Similarly PHPDT on East West corridor in the year of 2016, 2021, 2031 and 2041 is 8887, 9902, 11755 and 15060 respectively.

Road-based systems can optimally carry up to a maximum of 8,000 PHPDT. Since the PHPDT assumed on the above corridors exceed 8,000, there can be two options namely 1) Mono Rail and 2) Light Capacity Metro. Mono rail can carry the PHPDT projected but this technology is not a tested one. The operation and maintenance cost is much higher than Light metro. The capital cost of Mono rail is also almost same as that of Light Metro with no experience of Mono rail in India. Even in the other countries, the Mono rail is being adopted only for small lengths and as feeder to Metro. Hence, keeping in view the above disadvantages, it is recommended to adopt an stable, tested and reliable Metro technology. However, for Nagpur it will be Light Capacity Metro System.

# CHAPTER 4

## GEOMETRIC DESIGNING PARAMETERS & ALIGNMENT

### DESCRIPTION



- 4.1 GENERAL
- 4.2 GEOMETRIC DESIGN PARAMETERS
- 4.3 TRACK STRUCTURE
- 4.4 RAIL SECTION
- 4.5 BALLASTLESS TRACK ON MAIN LINES
- 4.6 BALLASTLESS/BALLASTED TRACK IN DEPOT
- 4.7 TURNOUTS
- 4.8 BUFFER STOPS
- 4.9 RAIL STRUCTURE INTERACTION
- 4.10 ROUTE ALIGNMENT
- 4.11 TECHNICAL FEATURES

### TABLES

TABLE 4.1	LIMIT PERMITTED SPEED AND MINIMUM TRANSITION LENGTH FOR CURVES
TABLE 4.2	TURNOUTS
TABLE 4.3	STATEMENT OF GRADIENTS & CURVES TO BE ADOPTED
TABLE 4.4	STATEMENT OF GRADIENTS TO BE ADOPTED
TABLE 4.5	STATEMENT OF GRADIENTS, CURVES & W/ GRADIENT
TABLE 4.6	STATEMENT OF GRADIENTS & W/ GRADIENT

**Chapter - 4****GEOMETRIC DESIGNING PARAMETERS AND  
ALIGNMENT DESCRIPTION****4.1 GENERAL**

The chapter deals with geometrical standards adopted for horizontal and vertical alignments, road description, etc. The proposed corridors under Nagpur Metro Rail Project network will consist of Standard Gauge (SG) lines. For underground corridors, track centres are governed by spacing of tunnels and box design.

The geometrical design norms are based on international practices adopted for similar metro systems with standard gauge on the assumption that the maximum permissible speed on the section is limited to 80kmph. Planning for any higher speed is not desirable as the average inter-station distance is about 1.30km and trains will not be able to achieve higher speed.

The elevated tracks will be carried on box-shaped elevated decking supported by single circular piers, generally spaced at 25-m centres and located on the median of the road. The horizontal alignment and vertical alignment are, therefore, dictated to a large extent by the geometry of the road and ground levels followed by the alignment.

The underground tracks will be carried in separate tunnels to be drilled by Tunnel Boring Machine. Stations will, however, be constructed by cut and cover method.

**4.2 GEOMETRIC DESIGN PARAMETERS**

The design parameters related to the Metro system described herewith have been worked out based on a detailed evaluation, experience and internationally accepted practices. Various alternatives were considered for most of these parameters but the best-suited ones have been adopted for the system as a whole.

**4.2.1 Horizontal Alignment**

As far as possible, the alignment follows the existing roads. This leads to introduction of horizontal curves. On consideration of desirable maximum cant of 112 mm and cant



efficiency of 85 mm on Metro tracks, the safe speed on curves of radii of 400 m or more is 60 km/h. On elevated sections minimum radius of 100 m has been used at one location having speed potential upto 40 km/h. However in underground section desirable minimum radius of curve shall be 300 m for ease of working of Tunnel Boring Machine (TBM). However in exceptional situation on this project curves of 200 m radius (safe speed of 30 km/h) have been adopted where New Austrian Tunneling Machine (NATM) shall be used.

For maximum permissible speed on curve with various radii, Table 4.1 may be referred.

#### Horizontal Curves

Description	Underground Section	Elevated Section
Desirable Minimum radius	300 m	200 m
Absolute minimum radius	200 m (only city)	100 m
Minimum curve radius at stations	1000 m	1000 m
Maximum permissible cant (Ca)	125 mm	125 mm
Maximum desirable cant	110 mm	110 mm
Maximum cant deficiency (Cd)	85 mm	85 mm

#### 4.2.2 Transition Curves

It is necessary to provide transition curves at both ends of the circular curves for smooth riding on the curves and to counter all centrifugal force. Due to change in gradient at various locations in the corridor, it is necessary to provide frequent vertical curves along the alignment. In case of tightest least track, it is desirable that the vertical curves and transition curves of horizontal curves do not overlap. These constraints may lead to reduced lengths of transition curves at certain locations. The transition curves have certain minimum parameters.

- Length of Transitions of Horizontal curves (m)
  - Minimum : 0.44 times actual cant or cant deficiency (in mm), whichever is higher.
  - Desirable : 0.72 times actual cant or cant deficiency (in mm), whichever is higher.
- Overlap between transition curves and vertical curves not allowed.
- Minimum straight between two Transition curves (in case of reverse curves) either 25 m or 60 m.
- Minimum straight between two Transition curves (in case of same flange curves) either 25 m or both curves should be converted in to the compound curve by introducing single transition between the two circles.
- Minimum curve length between two transition curves: 25 m



### 4.2.1 Vertical Alignment and Track Centre

#### (a) Elevated sections

The viaducts carrying the tracks will have a vertical clearance of minimum 3.0 m above road level. For meeting this requirement with the 'Box' shaped pre-stressed concrete girders, the rail level will be about 3.8 m above the road level. However, at stations which are located above central median, the rail level will be 13.3 m above the road level with concourse of mezzanine. These levels will, however, vary marginally depending upon where the stations are located.

The track center on the elevated section is kept as 4.1 m uniform throughout the corridor to standardize the superstructure, except at few stations, wherever sections crossovers are planned, it is kept 4.5 meter.

#### (b) Underground sections

Rail level at intersection in tunneling portion shall be kept at least 12.0 m below the ground level. At stations, the desirable depth of rail below ground level is 13.3 m, so that station concourse can be located above the piers/raja.

Track center in underground sections are follows:

Sections where stations are to be constructed

by cut & cover and running section by TBM to

Accommodate 12 m wide platform:

13.03 m (for

inner width of platform, track center to be reduced.)

Sections where stations are to be constructed

by NATM and running section by TBM to facilitate

Construction of stations

22.00 m

Sections where stations as well as running section

both are to be constructed by cut and cover method

4.50 m

#### (c) Gradients

Normally the stations shall be on level stretch. In limited cases, station may be on a grade of 0.1 %. Between stations, generally the grades may not be steeper than 3.0 %. However, where existing road gradients are steeper than 2 %, or for Switch Over Ramps gradient up to 4% (compensated) can be provided in short stretches on the main line.

#### (d) Vertical Curves

Vertical curves are to be provided when change in gradient exceeds 0.4%. However, it is recommended to provide vertical curves at every change of gradient.

#### (e) Radius of vertical curves:

- |                                    |        |
|------------------------------------|--------|
| • On main line (desirable)         | 2500 m |
| (Absolute minimum)                 | 1500 m |
| • Other Locations                  | 1500 m |
| • Minimum length of vertical curve | 20 m   |





#### 4.2.4 Design speed

The maximum sectional speed will be 85 km/h. However, the applied cant, and length of transition will be decided in relation to normal speeds at various locations, as determined by simulation studies of alignment, vertical profile and station locations. Computerized train simulation studies need to be conducted with proposed gradients at the time of selected design stage. This is with the objective of keeping down the wear on rails on curves to the minimum.

**Table 4.1: Cant, Permitted Speed & Minimum Transition Length for Curves**

RADIUS	CANT	MAXIMUM PERMISSIBLE SPEED	MINIMUM DISTANCE BETWEEN ADJACENT TRACKS	
			UNDIGROUND	ELEVATED AND AT-GRADE
meters	mm	kmph	mm	mm
8000	15	83	3500	3650
2000	15	83	3500	3650
2400	20	83	3500	3650
2000	20	83	3500	3650
1000	25	83	3500	3650
1500	30	83	3500	3650
1200	35	83	3500	3650
1000	45	83	3500	3700
800	55	83	3550	3750
600	70	83	3550	3750
500	85	83	3600	3750
400	95	83	3600	3800
400	105	83	3650	3800
350	110	75	3650	3800
300	110	70	3700	3850
200	110	55	3800	3950
150'	110	45	4000	4050
150'	0	33	4000	4050
120'	110	43	4000	4150
120'	0	23	4000	4150
100'	110	40		

- Note:**
- The track spacing is without any column/structure between two tracks and is with equal cant for both outer and inner tracks.
  - Track spacing shown is not applicable to stations which should be calculated depending on specific requirement.
  - Figures for any intermediate radius of curvature may be obtained by interpolating between two adjacent radii. For higher radii, values may be extrapolated.

#### 4.2.5 Station Locations

Stations have been located so as to serve major passenger destinations and to enable



convenient integration with other modes of transport. However effort has also been made to propose station locations, such that inter station distances are as uniform as possible. The average spacing of stations is close to 1.2 km.

#### 4.3 TRACK STRUCTURE

Track on Metro Systems is subjected to intensive usage with very little time for day-to-day maintenance. Thus it is imperative that the track structure selected for Metro Systems should be long lasting and should require minimum or no maintenance and at the same time, ensure highest level of safety, reliability and comfort, with minimum noise and vibrations. The track structure has been proposed keeping the above philosophy in view.

Two types of track structures are proposed for the systems under Nagpur Metro Rail Project network. The normal ballasted track in Depot (except inside the Workshops, Inspection lines and washing plant lines). The ballastless track is recommended on Viaducts and inside tunnels as the regular cleaning and replacement of ballast at such locations will not be possible.

For the depots, ballasted track is recommended as ballastless track or formation is not suitable due to settlement of formations. Ballastless track in depot is required inside the workshop or inspection lines and washing plant lines.

From considerations of maintainability, riding comfort and aim to contain vibrations and noise levels, the complete track is proposed to be jointless and for this purpose even the turnouts will have to be incorporated in LWR/CWR.

The track will be laid with 1 in 20 camber rails and the wheel profile of Rolling Stock should be compatible with the rail cant and rail profile.

#### 4.4 RAIL SECTION

Keeping in view the proposed axle load and the practices followed abroad, it is proposed to adopt UIC-60 (52 kg. m) rail section. Since on main lines, sharp curves and steep gradients would be present, the grade of rail on main lines should be 1080 Head Hardened as per IS-12-2000. As these rails are not manufactured in India at present, these are to be imported. For the Depot lines, the rails of grade 800 are recommended, which are available indigenously.

#### 4.5 BALLASTLESS TRACK ON MAIN LINES

On the viaducts, it is proposed to adopt pinch type ballastless track structure with RCC detachment guards integrated with the pinches. Further, it is proposed to adopt fastening system complying to performance criteria laid down by Indian Railways on ballastless track structures, with a base plate spacing of 60 cm. on viaducts.

In the underground sections, similar track structure with a base plate spacing of 75 cm is proposed on slab after 1<sup>st</sup> stage concrete.

#### 4.6 BALLASTLESS BALLASTED TRACK IN DEPOT

The ballastless track in Depot may be of the following types:

- Supported on steel pedestals for inspection Lane.
- Embedded rail type inside the Workshop.



- Finish type for flagging line.
- Track is to be laid on PRC sleepers with sleeper spacing of 33 cm. All the rails are to be converted HRG rail panels by doing fish bulb/thermit welding.

#### 4.7 TURNOUTS

All turn-out/sub-sleepers on the main lines and other running lines must be as under:

Table 4.2: Turn-Outs

S. No.	Description	Turn out Type
01	Main Line	1 in 9
02	Depot/Yard Lines	1 in 7

#### 4.8 BUFFER STOPS

On main line and Depot line, friction buffer stops with mechanical impact absorption (non-hydraulic type) will be provided. In elevated portion, the spans on which friction buffer stops are to be installed will be designed for an additional longitudinal force, which is likely to be transmitted in case of Rolling Stock hits the friction Buffer Stops.

#### 4.9 RAIL STRUCTURE INTERACTION

For continuing UAR/CAR on Viaduct, the elevated structures will be adequately designed for the additional longitudinal forces likely to be transmitted as a result of Rail-Structure interaction. Rail structure interaction study will determine the need and locations of Rail Expansion Joints (REJ) required to be provided.

#### 4.10 ROUTE ALIGNMENT

Two Corridors have been identified for implementation in phase I of Nagpur Metro Rail Project network as per details given underneath:-

- Automotive Square to KHAPRI
- Project Nagar to Lokmany Nagar

The main features of these corridors along with the details of route alignment have been described below:-

##### 4.10.1 Alignment from Automotive Square to KHAPRI

This corridor originates from Automotive Square on Kamptee Road, moves along Kamptee Road and reach the intersection point of Ahirvadi Road and Wardha Road, then after crossing Fly Over moves towards Munja Square, moves towards Debandil and along rail moves towards Empress/ Murja Mang, leads towards Congress Nagar T-Point, then on Rahula Colony Road and then falls on Wardha Road, leads towards NEERI, then moves along Wardha Road and then west of Railway Track in NHAN area. And passes through 14m wide stretch of land between the railway boundary line and the road near proposed Container Depot.

There are 17 Stations proposed on the alignments.



#### 4.10.2 Prajapati Nagar to Lokmanya Nagar

This Corridor originates from Prajapati Nagar (meeting point of GS Road and Ring Road), then along Central Avenue Road moves towards Vaidya Devi Chowk, then Maya Hospital and then takes left turn towards Nagpur Station Entry on Railway Feeder Road, then on Dhal Road alignment takes right turn and crosses over box culvert on existing railway line and sits on State Highway 255. Then after crossing Wartha Road alignment moves along North Ambahara Road upto Ambahara Lake and takes left State Highway 285. Then lies on Hingra Road and moves towards Lokmanya Nagar. There are 18 Stations proposed on this alignment.

#### 4.10.3 Main features of Alignment from Automotive Square to KHAPRI (North-South Corridor)

Main features of Alignment from Automotive Square to KHAPRI are detailed below:

- a) This corridor provides direct metro connectivity to Automotive Square, RBI, Vidyan Sadna, NIT, Zoro Mia, Nagpur University, Staburd, Yashwanth Stadium, Central Jai, NEERI, Wartha Road, Chhatrapati Shriji Chowk, Airport, Khapri, MBAN. Many other prominent places and Government offices are covered in this Corridor.
- b) Corridor is integrated with East West corridor at Staburd and this integration provides metro connectivity to new development at Lokmanya Nagar.
- c) Corridor integrates with other modes of transport, Bus Terminus near Jhandi Chowk.
- d) Entire length (19.655 Km.) of this corridor is proposed as elevated except in 4.6 Km. at grade after Airport Station and in MBAN area near Khapri Railway Station.
- e) Total 17 stations have been proposed on this corridor; out of these stations 15 stations are elevated and remaining 2 stations are at grade.
- f) Future extension of corridor in both directions is feasible.

#### 4.10.4 Main features of Alignment from Prajapati Nagar to Lokmanya Nagar (East-West Corridor)

Main features of Alignment from Prajapati Nagar to Lokmanya Nagar are detailed below:

- a) This corridor provides direct metro connectivity to Central Avenue Road and North Ambahara Road. This corridor covers many important location like Yashwanth Nagar, Mangalwadi, Maya Hospital, Nagpur Railway Station, Santara Market, Staburd, Jhandi/Ravi Chowk, LAD Square, Ambahara Lake, Hingra Road, Lokmanya Nagar.
- b) Corridor is integrated with North-South corridor at Staburd and through that integration prominent location falling on NS Corridor get connected.



- c) Corridor integrates with other modes of transport such as Bus Stand near Jhansi Road Square and Nagpur railway station.
- d) Entire length of the corridor is proposed as elevated.
- e) There are total 10 stations on this corridor and all are elevated.

#### 4.11 TECHNICAL FEATURES

##### 4.11.1 Automotive Square to KHAMRI (North-South Corridor)

(A) Horizontal Curves: Horizontal curve data is as per the table below:

Table 4.2: Statement of Horizontal Curves (North-South Corridor)

Curve No.	Station	Radius	Deflection Angle	Tangent Length	Offset	Curve Length	Free Curve Length	Sight Distance	Remarks
			SIR 1						Start of Alignment +0+17
1	Right	400.00	41.10 31.330	30.38	116.420	276.000	228.600	133.476	
2	Left	400.00	30.18 34.381	30.38	27.330	70.480	194.480	80.000	
3	Left	2000.00	30.07 34.382	31.14	49.717	30.980	30.980	188.800	
4	Right	600.00	30.11 37.380	31.14	30.11	80	80.000	208.800	
5	Right	2000.00	30.10 34.330	30.38	18.881	32.381	77.381	304.771	
6	Left	2000.00	30.10 34.330	31.14	30.317	30.980	30.980	307.130	
7	Left	1000.00	30.10 34.331	31.14	38.338	116.218	196.218	301.330	
8	Right	333.33	30.10 37.330	31.14	14.710	35.7	101.680	88.380	
9	Left	333.33	30.10 34.331	30.38	14.670	30.381	100.381	116.630	
10	Left	333.33	30.10 33.330	30.38	16.348	32.330	117.330	208.330	
11	Right	400.00	15.48 33.330	30.38	110.028	284.330	274.330	507.780	
12	Left	1400.00	31.10 34.330	30.38	15.904	27.880	77.880	139.880	
13	Left	300.00	30.00 30.110	30.38	14.110	34.380	106.380	87.380	
14	Left	1000.00	10.00 11.430	30.38	111.680	327.680	327.680	37.380	
15	Left	1000.00	31.10 30.940	30.38	16.207	31.110	70.110	138.670	
16	Right	300.00	30.10 31.130	30.38	13.889	32.788	32.788	112.870	
17	Left	333.33	30.10 34.330	30.38	14.870	30.980	108.980	141.980	
18	Right	1000.00	30.10 33.330	30.38	38.880	114.700	184.700	77.380	
19	Left	300.00	30.10 34.330	30.38	25.330	30.330	108.330	216.330	
20	Left	160.00	27.00 33.330	30.38	13.710	80.380	140.380	27.270	
21	Right	300.00	14.10 30.710	30.38	33.000	10.330	100.330	25.380	
22	Left	400.00	22.00 31.400	30.38	16.440	30.880	80.880	88.880	
23	Left	110.00	27.00 31.380	30.38	14.100	61.380	101.380	0	
24	Right	110.00	30.10 33.330	30.38	100.000	200.380	200.380	200.380	
25	Left	1000.00	30.10 30.330	30.38	33.780	100.380	170.380	170.380	
26	Right	160.00	30.10 30.330	30.38	100.000	107.240	107.240	121.780	
27	Left	160.00	30.10 30.330	30.38	113.000	80.380	190.380	118.780	



Curve No.	Direction	Radius	Entrance Length	Transition Length	Height	Lane Length	Total Curve Length	Weight Factor	Remarks
18	Left	-171.00	74.21.31.886	30	30	30.110	30.000	158.624	158.624
19	Right	1000.00	21.17.39.100	30	30	11.609	27.391	77.201	387.271
20	Right	800.00	30.18.31.886	30	30	17.966	31.166	71.980	317.298
21	Left	-800.00	32.11.31.782	30	30	11.873	148.626	166.424	335.697
22	Left	800.00	22.18.31.232	30	30	10.000	48.011	148.811	0
23	Right	800.00	22.18.31.606	30	30	12.833	30.989	120.999	179.999
24	Right	800.00	22.18.31.232	30	30	11.138	34.8	124.895	0
25	Left	200.00	22.21.21.751	30	30	17.914	38.922	124.832	200.00
26	Left	200.00	30.18.31.886	30	30	21.268	31.718	30.178	1731.988
27	Right	3000.00	30.03.31.333	15	15	-1.719	38.373	38.657	-630.31
28	Right	333.00	-15.18.31.830	31	31	22.875	30.311	173.211	0
29	Left	363.00	22.11.11.260	31	31	-8.473	22.967	143.967	127.537
30	Left	663.00	30.18.31.232	30	30	26.117	30.758	158.718	330.898
31	Right	663.00	-30.12.31.716	32	32	22.331	49.307	171.677	130.736
32	Left	663.00	30.18.31.782	32	32	20.270	32.368	160.238	0.1781
33	Right	-663.00	0.18.21.638	32	32	18.900	31.897	30.091	168.819
34	Left	663.00	31.18.19.000	32	32	11.138	38.873	38.873	179.643
35	Right	2000.00	30.21.31.717	30	30	15.179	31.131	37.131	158.791
36	Right	2000.00	30.21.31.343	11	11	38.991	31.99	33.990	168.211
37	Right	-200.00	30.21.31.691	30	30	36.171	111.026	151.838	112.891
38	Left	363.00	30.18.31.650	31	31	-10.000	30.964	128.964	0
39	Right	363.00	30.18.31.776	31	31	38.611	11.380	111.380	168.731
40	Left	-200.00	30.18.31.886	31	31	38.333	30.989	161.899	0
41	Right	200.00	30.18.31.777	32	32	11.261	34.380	114.681	381.380
42	Left	200.00	30.18.31.137	31	31	-1.333	32.338	121.338	167.664
43	Left	-200.00	30.18.31.664	31	31	22.666	48.331	30.331	161.731

214 of alignment is 2200

**Abstract of Horizontal Curves (N-S Corridor)**

S. No.	Radius (m)	No. of Curves	Curved Length (m)	% w. r. t. total curved length
1	>100m - <200m	0	1748.707	24.10%
2	>200m - <500m	10	1488.104	19.41%
3	>500m - <1000m	18	2894.028	38.80%
4	>1000m - <1500m	0	512.223	7.00%
5	>1500m - <2000m	1	67.798	0.89%
6	>2000m - <3000m	0	440.801	5.87%



T	=0000e	3	132.043	2.32%
<b>Total</b>		<b>33</b>	<b>7266.78</b>	<b>132.02%</b>

**(ii) Gradient**

A statement showing details of gradients provide along the N-S corridor is given in the following table No. 4.4.

**Table 4.4: Statement of Gradients (N-S Corridor)**

S. No.	Chainage		Length	Rd Level		Gradient	Remarks
	From	To		From	To		
1	435.2	370.2	75.112	303.8	303.9	0.00%	Level
2	369.2	468.2	199.008	303.8	303.9	-0.217%	Fall
3	482.2	640.2	258.000	303.8	303.9	1.340%	Rise
4	245.2	1118.2	873.000	303.8	303.9	0.000%	Level
5	1118.2	1818.2	700.000	303.8	303.9	0.200%	Rise
6	1818.2	1742.2	74.000	303.8	311.5	2.500%	Rise
7	1742.2	2220.4	478.202	311.5	314.4	1.004%	Rise
8	2220.4	2272.2	51.800	314.4	314.4	0.000%	Level
9	2272.2	2842.2	570.000	314.4	313.7	-1.367%	Fall
10	2842.2	2820.2	22.000	313.7	313.1	-0.194%	Fall
11	2820.2	3242.2	422.000	313.1	318.4	1.600%	Rise
12	3242.2	3112.2	130.000	318.4	318.4	0.000%	Level
13	3112.2	3692.2	580.000	318.4	318.3	-0.317%	Fall
14	3692.2	3818.2	126.000	318.3	323.9	1.700%	Rise
15	3818.2	4082.2	264.000	323.9	323.9	0.000%	Level
16	4082.2	4238.4	156.222	323.9	323.2	-1.200%	Rise
17	4238.4	4332.2	93.800	323.2	323.2	0.000%	Level
18	4332.2	4738.4	406.200	323.2	322.2	-0.300%	Fall
19	4738.4	5032.2	293.800	322.2	326.3	1.200%	Rise
20	5032.2	5382.2	350.000	326.3	326.3	0.000%	Level
21	5382.2	5882.2	500.000	326.3	323.4	-0.900%	Fall
22	5882.2	6182.2	300.000	323.4	313.8	-3.100%	Fall
23	6182.2	6382.2	200.000	313.8	313.8	0.000%	Level
24	6382.2	6872.2	490.000	313.8	313.5	-0.900%	Fall
25	6872.2	8032.2	1160.000	313.5	313.5	0.000%	Level
26	8032.2	7232.2	800.000	313.5	305.2	-2.500%	Fall
27	7232.2	7432.2	200.000	305.2	313.9	2.800%	Rise
28	7432.2	7782.2	350.000	313.9	317.8	1.240%	Rise
29	7782.2	8082.2	300.000	317.8	317.8	0.000%	Level
30	8082.2	8242.2	160.000	317.8	317.4	-0.120%	Fall
31	8242.2	8382.2	140.000	317.4	321.6	2.100%	Rise
32	8382.2	8882.2	500.000	321.6	321.6	0.000%	Level
33	8882.2	9121.7	239.500	321.6	322.4	0.250%	Rise
34	9121.7	9342.2	220.500	322.4	320	-1.500%	Fall
35	9342.2	9842.2	500.000	320	318.1	-1.147%	Fall
36	9842.2	9932.2	90.000	318.1	315.3	-0.884%	Fall
37	9932.2	10232.2	300.000	315.3	315.3	0.000%	Level



S. No.	Chainage		Length	Sd Level		Gradient	Remarks
	From	To		From	To		
38	1219.2	1219.2	545.000	315.3	319.9	0.00%	Flow
39	1219.2	1221.4	993.428	312.5	313.9	0.00%	Level
40	1221.4	1261.0	985.572	315.5	320	0.10%	Flow
41	1261.0	1262.0	281.000	320	320	0.00%	Level
42	1262.0	1266.0	493.000	320	311	-1.40%	Fall
43	1266.0	1268.0	401.000	311	311	0.00%	Level
44	1268.0	1219.0	140.000	311	307.1	-4.00%	Fall
45	1219.0	1228.0	281.000	307.1	307.2	0.03%	Flow
46	1228.0	1288.0	380.000	307.0	313.2	1.97%	Flow
47	1288.0	1408.0	410.000	313.2	313.2	0.00%	Level
48	1408.0	1410.0	271.000	313.2	307.8	-4.00%	Fall
49	1410.0	1422.0	360.000	307.8	309.8	0.60%	Flow
50	1422.0	1440.0	780.000	309.8	309.8	-1.70%	Flow
51	1440.0	1470.0	200.000	309.8	309.8	0.00%	Level
52	1470.0	1488.0	363.000	309.8	299	-3.00%	Flow
53	1488.0	1490.0	251.000	299	299	0.00%	Level
54	1490.0	1508.0	750.000	299	307.8	1.34%	Flow
55	1508.0	1524.0	244.821	307.8	318	3.40%	Flow
56	1524.0	1528.0	220.219	318	318	0.00%	Level
57	1528.0	1514.0	180.000	318	308.2	-3.04%	Flow
58	1514.0	1508.0	281.000	308.2	313.1	0.16%	Flow
59	1508.0	1500.0	212.000	308.1	308.1	-0.34%	Flow
60	1500.0	1487.1	576.100	308.1	308.1	0.00%	Level
61	1487.1	1524.0	432.900	308.1	302.9	-1.66%	Flow
62	1524.0	2074.2	1107.202	302.9	292	-3.64%	Flow

**Abstract of Gradients( N-S Corridor)**

S. No.	Description	Nos. Occurrences	Length (m)	% w. r. t. total Alignment length
1	Level	20	5233.013	28.82%
2	> 0% to < 1%	22	3040.247	45.66%
3	> 1% to < 2%	11	3340.933	16.99%
4	> 2% to < 3%	5	1108.730	5.84%
5	> 3% to < 4%	4	625.701	4.79%
<b>Total</b>		<b>62</b>	<b>18868.2</b>	<b>100.00%</b>




**4.11.2 Prajapati Nagar to Lokmanya Nagar (East-West Corridor)**

(a) Horizontal Curves: The details of horizontal curves is shown in Table 4.5

**Table 4.5: Statement of Horizontal Curves (East-West Corridor)**
**Table 4.5**

Curve No.	Direction	Radius	Deflection Angle	Stationing		Curve Length	Tangent	Curve Length	Total Curve Length	Sight Distance	Remarks
				Start	End						
1	Right	232.00	37.18.88.000	00	00	87.007	101.110	288.110	132.070	Start of Alignment -3rd	
2	Right	432.00	28.42.23.800	00	00	102.817	207.400	310.217	217.870		
3	Right	2602.00	00.16.18.100	12	00	12.207	27.627	39.834	387.270		
4	Right	1000.00	02.07.00.000	29	20	11.807	06.200	18.007	271.000		
5	Right	1180.00	00.09.07.000	29	20	0.000	0.000	0.000	20.900		
6	Left	1702.00	00.54.07.000	19	00	15.4	28.100	43.500	262.900		
7	Right	10000.00	00.12.40.200	10	00	0.000	0.000	0.000	200.000		
8	Left	1000.00	00.12.10.400	10	00	-1.000	47.100	46.100	60.000		
9	Right	1000.00	00.10.36.000	00	00	10.000	00.000	00.000	1000.100		
10	Right	900.00	00.00.27.000	00	00	0.000	0.000	0.000	40.000		
11	Left	1012.00	01.25.23.000	25	25	12.000	25.100	37.100	200.000		
12	Right	300.00	00.00.12.000	00	00	0.000	0.000	0.000	00.0		
13	Left	300.00	00.17.10.000	00	00	14.000	20.000	34.000	100.000		
14	Right	200.00	00.00.00.000	00	00	0.000	0.000	0.000	0.000		
15	Right	3000.00	00.30.00.000	00	00	00.000	00.000	00.000	100.000		
16	Left	2000.00	00.40.17.100	00	00	-1.000	20.000	19.000	10.000		
17	Left	1000.00	00.40.04.000	20	20	22.000	00.100	22.100	10.000		
18	Right	600.00	02.00.04.000	00	00	10.000	30.000	40.000	200.000		
19	Right	600.00	02.00.00.000	00	00	14.000	20.000	34.000	30.000		
20	Left	600.00	00.40.20.000	00	00	4.000	20.000	24.000	30.000		
21	Left	600.00	01.04.10.000	00	00	10.000	20.000	30.000	400.000		
22	Left	1000.00	01.00.00.000	20	20	14.000	20.000	34.000	0.000		
23	Right	1200.00	01.00.00.000	20	20	10.000	20.000	30.000	100.000		
24	Right	200.00	00.07.42.000	00	00	00.000	10.000	10.000	100.000		
25	Right	200.00	00.27.10.000	00	00	14.000	20.000	34.000	100.000		
26	Left	200.00	00.07.00.000	00.1	00.1	0.000	0.000	0.000	00.000		
27	Left	1000.00	00.00.00.000	20	20	11.000	00.000	11.000	100.000		
28	Right	600.00	02.00.10.000	00	00	20.000	40.000	60.000	60.000		
29	Left	600.00	01.00.34.000	00	00	14.000	20.000	34.000	200.000		
30	Left	1000.00	01.07.10.000	20	20	10.000	24.000	34.000	10.000		
31	Right	1000.00	02.00.00.000	20	20	22.000	40.000	62.000	100.000		
32	Right	600.00	02.07.00.000	00	00	14.000	20.000	34.000	200.000		
33	Left	1702.00	00.00.27.000	20	20	100.000	200.000	300.000	600.000		
34	Right	200.00	00.07.40.000	00.7	00.7	0.000	0.000	0.000	100.000		
35	Right	200.00	14.20.13.400	00	00	20.000	00.000	20.000	20.000		



Chain No.	Direction	Station	Deflection Angle	Transition Length	Target	Curve Length	Total Curve Length	Design Speed	Remarks
38	Left	112.00	73.28.20.753	60	60	260.871	221.130	225.700	400.000
37	Right	102.00	11.47.20.862	60	60	19.8	27.487	167.687	20.410
36	Right	102.00	37.9.25.272	60	60	45.37	66.475	136.475	254.307
35	Left	222.00	81.02.50.074	60	60	5.389	5.18	150.70	317.500
40	Left	20000.00	00.07.55.174	15	15	17.701	24.212	84.212	200.000
39	Left	8302.00	00.00.00.222	15	15	12.208	45.177	36.177	871.110
42	Left	400.00	07.45.08.064	60	60	27.767	36.215	154.210	600.000
43	Right	202.00	73.12.12.962	55	55	21.284	49.592	156.962	50.253
44	Left	202.00	25.23.05.503	55	55	49.501	59.527	189.527	309.270
45	Right	242.00	04.30.22.460	55	55	14.602	20.948	120.948	240.00
46	Left	502.00	02.20.48.900	60	60	14.800	20.327	130.327	181.207
47	Left	1000.00	00.00.00.000	20	20	80.000	180.27	270.27	0

Abstract of Horizontal Curves (E-W Corridor)				
S. No.	Radius (m)	No. Occurrences	Curved Length (m)	% w.r.t total curved length
1	+1500 - 2000	3	673.881	10.64%
2	+2000 - 5000	17	2918.441	45.72%
3	+5000 - 10000	13	1455.44	22.77%
4	+10000 - 15000	3	720.731	11.37%
5	+15000 - 20000	3	125.172	1.92%
6	+20000 - 50000	1	119.887	1.84%
7	+50000	0	357.555	5.60%

### (iii) Gradient

A statement showing details of gradients provide along the corridor is given in the following Table No. 4.6 :-

Table 4.6: Statement of Gradients (East-West Corridor)

S. No.	Change		Length	Rail Level		Gradient	Remarks
	From	To		From	To		
1	-592.00	390.00	872.000	391	391	0.00%	Level
2	180.00	430.00	250.000	391	287.2	-1.32%	Fall
3	430.00	730.00	270.000	297.2	300.5	1.12%	Rise
4	730.00	1087.35	357.348	300.5	305.9	1.78%	Rise



S. No.	Chainage		Length	Rail Level		Gradient	Remarks
	From	To		From	To		
1	1887.35	1920.00	32.652	305.3	305.3	0.00%	Level
2	1920.00	1970.00	50.000	305.3	304.8	-0.28%	Fall
3	1970.00	1920.80	49.200	304.8	305.3	1.47%	Rise
4	1920.80	2078.76	157.960	304.8	304.8	0.00%	Level
5	2078.76	2440.00	361.240	304.8	305.3	0.16%	Rise
6	2440.00	2640.00	200.000	305.3	305.7	0.40%	Rise
7	2640.00	3020.00	380.000	305.7	311.8	2.00%	Rise
8	3020.00	3235.00	215.000	311.8	311.8	0.00%	Level
9	3235.00	3384.00	149.000	311.8	310.5	-0.47%	Fall
10	3384.00	3772.00	388.000	310.5	311.0	0.16%	Rise
11	3772.00	4180.00	408.000	311.0	311.5	0.00%	Level
12	4180.00	4340.00	160.000	311.5	311	-0.22%	Fall
13	4340.00	4652.53	312.525	311	319.5	2.72%	Rise
14	4652.53	4922.00	269.467	319.5	319.5	0.00%	Level
15	4922.00	5190.00	268.000	319.5	318.7	-0.24%	Fall
16	5190.00	5490.00	300.000	318.7	321.8	1.57%	Rise
17	5490.00	5750.00	260.000	321.8	321.8	0.00%	Level
18	5750.00	5940.00	190.000	321.8	325.5	1.89%	Rise
19	5940.00	6300.00	418.000	325.5	319.7	-1.81%	Fall
20	6300.00	6580.00	280.000	319.7	319.7	0.00%	Level
21	6580.00	6890.00	310.000	319.7	313.1	-2.12%	Fall
22	6890.00	7130.00	240.000	313.1	313.1	0.00%	Level
23	7130.00	7290.00	160.000	313.1	310.2	-1.87%	Fall
24	7290.00	7610.00	320.000	310.2	320.1	3.04%	Rise
25	7610.00	7895.90	285.900	320.1	320.1	0.00%	Level
26	7895.90	8200.00	304.100	320.1	313.5	-2.08%	Fall
27	8200.00	8525.50	325.500	313.5	313.5	0.00%	Level
28	8525.50	8770.00	244.500	313.5	311.8	-0.52%	Fall
29	8770.00	8960.00	190.000	311.8	313.4	1.54%	Rise
30	8960.00	9241.43	281.430	313.4	313.4	0.00%	Level
31	9241.43	9490.00	248.567	313.4	312.8	-1.32%	Fall
32	9490.00	9770.00	280.000	312.8	313.9	0.25%	Rise
33	9770.00	9960.00	190.000	313.9	310.8	-1.84%	Rise
34	9960.00	10190.00	230.000	310.8	316.5	2.00%	Level
35	10190.00	10500.00	310.000	316.5	314.8	-0.57%	Fall
36	10500.00	10793.00	293.000	314.8	313.1	-0.52%	Rise



S. No.	Change		Length	Rail Level		Gradient	Remarks
	From	To		From	To		
41	13750.00	13750.00	220.000	319.1	319.1	0.00%	Level
42	13800.00	14300.00	370.000	319.1	318.8	-0.93%	Fall
43	14300.00	14840.00	480.000	318.8	320.3	2.20%	Rise
44	14840.00	12130.00	380.000	320.5	320.5	0.00%	Level
45	12130.00	12370.00	240.000	320.5	320	-1.57%	Fall
46	12370.00	12710.00	340.000	320	320	0.00%	Level
47	12710.00	13160.00	450.000	320	320	0.00%	Level
48	13160.00	13550.00	390.000	320	323.2	9.71%	Fall
49	13550.00	14000.00	450.000	323.2	326.8	1.09%	Rise
50	14000.00	14200.00	200.000	326.8	326.8	0.00%	Level
51	14200.00	14580.00	380.000	326.8	329.4	0.74%	Fall
52	14580.00	14870.00	290.000	329.4	340.4	3.33%	Rise
53	14870.00	15050.00	170.000	340.4	345.2	2.44%	Rise
54	15050.00	15270.00	220.000	345.2	345.2	0.00%	Level
55	15270.00	15532.00	262.000	345.2	342.5	-1.25%	Fall
56	15532.00	15770.00	238.000	342.5	330.2	-1.28%	Fall
57	15770.00	16020.00	250.000	330.2	330.3	-1.00%	Fall
58	16020.00	16289.74	269.742	330.3	336.3	0.00%	Level
59	16289.74	16500.00	210.258	336.3	332.4	-1.00%	Fall
60	16500.00	16800.00	300.000	332.4	332.2	-0.57%	Fall
61	16800.00	16960.00	160.000	332.2	323.3	-2.68%	Rise
62	16960.00	17160.00	200.000	323.3	320.4	-1.40%	Fall
63	17160.00	17496.75	336.756	320.4	320.4	0.00%	Level

**Abstract of Gradients (E-W Corridor)**

S. No.	Description	No. Occurrences	Length (m)	% w.r.t. total Alignment length
1.	Level	20	6754.412	55.51%
2.	+ 0% to + 1%	16	4519.547	24.80%
3.	+ 1% to + 2%	21	5642.563	31.67%
4.	+ 2% to + 3%	4	1282.525	7.04%
5.	+ 3% to + 4%	2	645	3.08%
	<b>Total</b>	<b>63</b>	<b>12165</b>	<b>100.00%</b>

# CHAPTER 5

## CIVIL ENGINEERING



5.1	GENERAL
5.2	CIVIL STRUCTURES
5.3	CONSTRUCTION METHODOLOGY
5.4	PRE-CAST CONSTRUCTION
5.5	STRUCTURAL SYSTEM OF VIADUCT
5.6	CONSTRUCTION OF STATIONS
5.7	GEO-TECHNICAL INVESTIGATIONS
5.8	LAND
5.9	UTILITY DIVERSION

### TABLES

TABLE 5.1	STRATEGICAL PLAN TYPE IN RAJASTHAN REGION
TABLE 5.2	DETAILS OF LABORATORY TESTS ON FILL WITH COARSE
TABLE 5.3	DETAILS OF LABORATORY TESTS ON SOIL SAMPLES
TABLE 5.4	FORMARY OF EMBANKMENT - C/SECTION
TABLE 5.5	FORMARY OF EMBANKMENT - C/C/SECTION
TABLE 5.6	ILL FILL DETAILS FOR BRICK - SANDY CLAY SOIL
TABLE 5.7	OPEN FOUNDATION DETAILS FOR NORTH - SOUTH CORRIDOR
TABLE 5.8	ILL FILL DETAILS FOR EAST WEST CORRIDOR
TABLE 5.9	OPEN FOUNDATION DETAILS FOR EAST WEST CORRIDOR
TABLE 5.10	DETAILS OF LAKE REQUIRED FOR NORTH SECTION
TABLE 5.11	DETAILS OF LAKE REQUIRED FOR NORTH SECTION - ON CORRIDOR
TABLE 5.12	DETAILS OF LAKE REQUIRED FOR NORTH SECTION - ON CORRIDOR
TABLE 5.13	DETAILS OF LAKE REQUIRED FOR STATION
TABLE 5.14	DETAILS OF LAKE REQUIRED FOR PARKING
TABLE 5.15	ABSTRACT OF LAND REQUIREMENT
TABLE 5.16	STATE RESPONSIBILITY DISTRIBUTION
TABLE 5.17	LOT OF AFFECTED WATER SUPPLY LINES - ON CORRIDOR
TABLE 5.18	LOT OF AFFECTED WATER SUPPLY LINES - ON CORRIDOR
TABLE 5.19	LOT OF AFFECTED BY LINES - ON CORRIDOR
TABLE 5.20	LOT OF AFFECTED BY POLES ON - ON CORRIDOR
TABLE 5.21	LOT OF AFFECTED BY LINES ON CORRIDOR
TABLE 5.22	LOT OF AFFECTED BY POLES ON - ON CORRIDOR

### FIGURES

FIG. 5.1	GENERAL ARRANGEMENT OF STATION WITH
FIG. 5.2	TYPICAL SECTION OF VIADUCT WITH 1 GURD
FIG. 5.3	TYPICAL SECTION OF VIADUCT WITH DOUBLE GURD
FIG. 5.4 & 5.5	LANDING SCHEDULE FOR EAST WEST AND NORTH SOUTH SECTION OF

FIG. 5	MEMBERSHIP OF TOWNS VECTOR
FIG. 5.1	YIP SWYEN KOTHEE - CAT AND CATS (CENTRAL TOWN)
FIG. 5.2	WONG TUNGWAI AND LAI SIANGTUN - CATS (KANGAROO NORTH TOWN)
FIG. 5.3	WONG TUNGWAI AND LAI SIANGTUN - CATS (KANGAROO SOUTH TOWN)
FIG. 5.4	WONG TUNGWAI AND LAI SIANGTUN - CATS (KANGAROO WEST TOWN)



## CIVIL ENGINEERING

### 6.1 GENERAL

The chapter deals with civil underground and elevated structures, Geotechnical investigation, construction methods, and requirements, Utility services and Traffic diversion during construction etc.

### 6.2 CIVIL STRUCTURES

#### 6.2.1 Underground Section

Presently, there is no "Underground Section" and as such this para is not required. But, there may be some underground section at a later stage. Keeping in view of the same, this has been included.

Tunnel excavation for underground section is generally carried out by Tunnel Boring Machines. Tunnel boring machines (TBM) capable of drilling in soft and hard rocks can be successfully employed for boring tunnels through the rocky stratum.

#### 6.2.2 Underground Stations

The underground station has been proposed as cut and cover with top-down method. The diaphragm walls for such station constructions would be 80 to 100 cm. thick and will function as a permanent side wall of the station. It is, therefore, necessary to construct the diaphragm walls absolutely watertight and with the required concrete strength. By resorting to top-down method the surface could be restored quickly and further excavations and construction of the station will not hamper the surface activity.

#### 6.2.3 Cut and Cover Method of Construction of Underground Station

Cut and Cover mainly consists of following steps:

1. Diversion of utilities
2. Construction of support walls
3. Excavation between the support walls along with the installation of struts between the two walls to hold them in position.
4. Construction of final structure and removal of temporary struts.



## 5. Back filling and restoration of the surface

### 6.2.4 Utility Diversion:

It is suggested that all utilities falling within excavation area are diverted away in advance to avoid damage to such utilities during the excavation/ construction phase. The cross utilities, however, need to be kept supported. It is suggested that pressure water pipelines crossing the proposed cut areas are provided with valves on both sides of the cut so that the cut area can be isolated in case of any leakage to the pipeline to avoid flooding of the cut/ damage to the works.

### 6.2.4 Support Wall:

Most commonly used support wall is RCC Diaphragm Wall. The advantage of diaphragm wall is that the same can be used as part of permanent structure. The modern techniques are now available where waterstop can be inserted at the joints of two diaphragm wall panels to avoid seepage through the joints. It is also now possible to ensure the verticality of the diaphragm wall panels to avoid any infringement problem later on. Typically the diaphragm wall of 80 cm to 1 meter thickness is sufficient to do the cut and cover construction. The various advantages of diaphragm wall are as follows.

- It is rigid type of support system and therefore ensures the maximum safety against settlement in the adjacent structures.
- Can be used as part of the permanent structure and, therefore, considered economical.
- With diaphragm wall it is possible to construct an underground structure by top down method. In this method top slab is cast once the excavation is reached to the top slab level with rigid connectors to the diaphragm wall which can be achieved by leaving couplers in the diaphragm wall reinforcement at appropriate level. This top slab then acts as strut between the two support walls and gives much more rigidity and safety to the construction. Excavation thereafter can be completed. This slab helps in restoration of the surface faster without waiting for full structure to be completed.

The other support walls which can be used depending on the site conditions are as follows:

- Sheet Piles** - 'Z' 'U' sheet pile can be used as temporary support wall. This can be advantageous where it is possible to reuse the sheet pile again and again and therefore, economy can be achieved. However the main concern remains, driving of sheet piles causes vibrations due to the adjacent buildings. This may sometimes lead to damage to the building and most of the time causes inconvenience to the





occupants of the building. Situation becomes more critical if sensitive buildings are adjacent to the alignment like hospitals, schools, laboratories, etc. Sheet pile driving equipments however are now available and can be used where such problems are articulated.

- (i) **Retaining Casing Piles:** This is suitable for situation where the cut and cover is to be done in partly soil and partly rock. The soil retaining structure can be done with the help of Casing pile which is then grouted with cement slurry. This is considered suitable in case of shallow level, non-uniform, uneven strata of rock head surface which render the construction of sheet pile/diaphragm wall impracticable. These are suitable up to 7-metre depth. The common diameter used for such casing pile is 2.00-2.50 m dia.
- (ii) **Solder Pile and Lagging:** Steel piles (H Section or I section) are driven into the ground at suitable interval (normally 1-1.5 m) centre-to-centre depending on the section and depth of excavation. The gap between two piles is covered with suitable lagging of timber planks/shel-creting steel sheets/CI sheets during the process of excavation.
- (iii) **Secant Piles:** are cast-in-situ bored pile constructed contiguous to each other so that it forms a rigid continuous wall. This is considered an alternative to diaphragm wall where due to soil conditions it is not advisable to construct diaphragm wall from the consideration of settlement during the working operation. 600 to 1000 mm dia piles are commonly used. Two alternate soft piles are driven and cast in such a way that the new pile partly cuts into earlier constructed piles. This new pile is constructed with suitable reinforcement. With this, alternate soft and hard pile is constructed. This has got all the advantages of diaphragm wall. However, this wall cannot be used as part of permanent structure and permanent structure has to be constructed in side of this temporary wall.

### 5.2.3 Anchors:

As an alternative to the struts, soil-rock anchors can be used to keep these support wells in position. This gives additional advantage as clear space is available between two support wells and progress of excavation & construction is much faster as compared to the case where large number of struts is provided which create hindrance to the movement of equipments and material & thus affects the progress adversely.

The combination of all the type of retaining walls, struts/anchors may be necessary for the project to suit the particular site. Based on the above broad principle, the support walls system for cut and cover shall be chosen for particular locations.



### 5.2.7 Elevated section - Choice of Superstructure

The choice of superstructure has to be made keeping in view the ease of constructibility and the maximum standardization of the formwork for a wide span ranges.

The segmental construction has been chosen mainly due to the following advantages:

- Segmental construction is an efficient and economical method for a large range of span lengths and types of structures. Structures with sharp curves and variable super elevation can be easily accommodated.
- Segmental construction permits a reduction of construction time as segments may be manufactured while substructure work proceeds and assembled rapidly thereafter.
- Segmental construction protects the environment as only space required for foundation and sub-structure is required at site. The superstructure is manufactured at a place away from busy areas and placement of superstructure is done with the system erected from piers at heights.
- Segments are easy to stack in the casting yard/stacking yard in more than one layer, thereby saving in requirement of space.
- It is easier to transport smaller segments by road trailers on city roads.
- It is easy to incorporate last minute changes in span configuration if the site situation so warrants.
- Interference to the traffic during construction is significantly reduced.
- Segmental construction contributes towards aesthetically pleasing structures and good finishes.
- The overall labour requirement is less than that for conventional methods.
- Better quality control is possible in the casting yard.
- During construction, the technique shows an exceptionally high record of safety.

### 5.2.8 Types of Superstructures for Elevated section

- (a) Pre-cast segmental box girder using external unbounded tendons
- (b) Pre-cast segmental U-Channel Superstructure with internal pre-stressing.

Comparative advantages/advantages of the above two types are given below:

#### A. Precast Segmental Box Girder using External Unbounded Tendon.

This essentially consists of precast segmental construction with external pre-stressing and dry joints and is by far most preferred technique in fast track projects. In such construction the pre-stressing is placed outside the structural concrete.



(inside the box section) and protected with high density polyethylene tubes, which are grouted with special wax or cement. The match cast joints at the interface of two segments are provided with shear keys as in traditional segmental construction. However, epoxy is dispensed with because water tight seal at the segment joints is not required because tendons are laid externally & protected by special wax or cement.

The main advantages of dry-cast external pre-stressed precast segmental construction can be summarized as follows:-

- + Simplification of all post-tensioning operations, especially installation of tendons.
- + Reduction in structural concrete thickness as no space is occupied by the tendons inside the concrete.
- + Good corrosion protection due to tendons in polyethylene ducts, the grout inspection is easier and leaks, if any, can be identified during the grouting process.
- + Simplified segment casting. There is no concern about alignment of tendons: increased speed of construction.
- + The elimination of the epoxy from the match-cast joints reduces costs and increases speed of construction further.
- + Replacement of tendons in case of distress is possible and can be done in a safe and convenient manner.
- + Facility for inspection and reaming of tendons during the entire service life of the structure.

Precast Segmental Box Girder using internal tendon is also used.

#### **B. Precast Segmental U-Channel Superstructure with Internal Pre-stressing.**

The single U type of viaduct structure is also a precast segmental construction with internal pre-stressing and requires grouting and temporary pre-stressing of segments. The match cast joints at the interface of two segments are also provided with shear keys. The main advantages for this type of structural configuration of superstructure are:

1. Built in sound barrier.
2. Built in cable support and system function.



3. Possibility to lower the longitudinal profile by approximately 1m compared to conventional design.
4. Built in structural elements capable to maintain the trains on the bridge in case of derailment (a standard barrier design allow this)
5. Built in maintenance and evacuation path on either side of the track.

## 6.3 CONSTRUCTION METHODOLOGY

For the elevated sections it is recommended to have pre-cast segmental construction for super structure for the viaduct. For stations also the superstructure is generally of pre-cast members. The pre-cast construction will have following advantages:-

- + Reduction in construction period due to concurrent working for substructure and superstructure.
- + For segmental, pre-cast element (of generally 3.0m length), transportation from construction site to site is easy and economical.
- + Minimum inconvenience is caused to the public utilizing the road as the superstructure launching is carried out through launching girder requiring narrow width of the road.
- + As the pre-cast elements are cast on production line in a construction depot, very good quality can be ensured.
- + The method is environment friendly as no concreting work is carried at site for the superstructure.

## 6.4 PRE-CAST CONSTRUCTION

### 6.4.1 Casting of segments

For viaducts segmental pre-cast construction requires a casting yard. The construction depot will have facilities for casting beds, curing and stacking area, batching plant with storage facilities for aggregates and cement, site testing laboratories, reinforcement steel yard and fabrication yard etc. An area of about 2.5 Ha. To 3.0 Ha. is required for such construction depot.

For casting of segments both long line and short line method can be adopted. However the long line method is more suitable for spans curved in plan while short line method is good for straight spans. A high degree of accuracy is required for setting out the curves on long line method for which pre calculation of offsets is necessary. Match casting of segments is required in either method. The cast segments are cured on the bed as well as in stacking yard. Ends of the segments are to be made rough through sand blasting so that joining of segments can be effective.



The cast segment will be transported on trailers and launched in position through launching girders.

#### 5.4.2 Launching Scheme

Launching girder is specially designed for launching of segments. The suggested launching scheme is designed in such a way that initially the launching girder is erected on pier head at one end of the work. The segments are lifted in sequence and when the lifting is over, they are dry matched while hanging from the launching girder. After dry matching, the

segments are grout with epoxy and pre-stressed from one end. The girder is lowered on the temporary / permanent bearings after pre-stressing. The launching girder then moves over the launched span to next span and the sequence continues.

### 5.5 STRUCTURAL SYSTEM OF VIADUCT

#### 5.5.1 Superstructure

The superstructure of a large part of the viaduct comprises of simply supported spans. However at major crossing/over or along scaling bridge, special steel or continuous unit will be provided.

Normally the U-Channel girder having a width of 3.0 m (approx) accommodates the two tracks situated at 3.7m (Tangent & upto 150m curvature) to 4.0m (90m curvature) c/c. The U-Channel superstructure for almost all the simply supported standard spans will be constructed by pre-cast pre-stressed segmental construction with epoxy bonded joints.

The main spans c/c of piers of standard simply supported spans constructed by pre-cast segmental construction technique has been proposed as 28.0m. The usual segments shall be 3.0m in length except the Diaphragm segments, which shall be 1.0m each. The other standard spans (c/c of pier) comprises of 25.0m, 31.0m, 22.0m, 19.0m & 18.0m, which shall be made by removing/adding usual segments of 1.0m each from the center of the span. Depth of the superstructure is so chosen that top of flange of U-Channel will be used as a evacuation walkway in an emergency.

The dimensions of end diaphragm will be finalized based on simply supported span of 31.0m and the same will be also kept for all simply supported standard span. The top level of both the end diaphragms of adjoining spans on the same pier is kept same so that expansion joint can be installed at top and continuity of profile of end diaphragm on the same pier can be maintained. The arrangement has been selected from aesthetic considerations.

The economical span (i.e. with optimum pre-stressing ratio) will be designed for the 25m situation.



Standard span up to 35.0m will be provided through out the viaduct as far as possible. At crossings, where spans require to be increased upto 31.0m, simply supported spans will be provided.

The location where the span foundations are possible, the spans of 15m will be provided.

For major crossing having spans greater than 31.0m, special units normally of 3 –span construction or steel girder have been envisaged.

All these continuous units (if case provided at obligatory location) will be constructed by cast-in-situ, balanced cantilever construction technique. The top profile of superstructure of continuous unit for the full length will be retained the same as for standard spans so that evacuation vehicles will be available even in continuous units. The increase in depth of U-chamber will be accomplished by thickening the soffit slab (downside downwards). At the end of continuous unit, the profile and thickness of soffit slab will be done to the extent that it will match with the profile and depth of end diaphragm of adjoining simply supported spans. The thickness of soffit slab will be increased smoothly toward penultimate support. In order to reduce the dead weight of the girder, voids will be also provided in the thickened soffit slab at bottom. These will be circular near the end of continuous unit and oblong near the penultimate support.

### 5.5.2 Substructure

The viaduct superstructure will be supported on single cast-in-place RCC pier. The shape of the pier follows the flow of forces. For the standard spans, the pier gradually widens at the top to support the bearing under the box webs. At the preliminary design stage, the size of pier is found to be limited to 1.8m to 2.0 m diameter of circular shape for most of its height so that it occupies the minimum space at ground level where the alignment often follows the contour verge of existing roads.

To prevent the direct collision of vehicle to pier, a Jersey Road crash barrier of 1.0 m height above existing road level has been provided all around the pier. A gap of 25 mm has also been provided in between the crash barrier and outer face of pier. The shape of upper part of pier has been so dimensioned that a required clearance of 5.5 m is always available on road side beyond vertical plane drawn on outer face of crash barrier. In such a situation, the minimum height of rail above the existing road is 8.4 m.

The longitudinal center to center spacing of abutment/cant bearing over a pier would be about 1.8 m. The space between the abutment bearings will be utilized for placing the lifting jacks required for the replacement of abutment bearing. An outward slope of 1:200 will be provided at pier top for the drainage due to spilling of rainwater, if any. The horizontal spacing between bearings would be 3.2 m (to be studied in more detail). The orientation and dimensions of the piers for the continuous units or steel girder (simply supported spans) have to be carefully selected to ensure minimum occupation of



ground level traffic. Since the vertical and horizontal loads will vary from pier to pier, this will be catered to by selecting the appropriate structural dimensions.

### 5.3.3 Foundation Recommendation

Depending on the nature of soil, type of proposed structure and expected loads on foundations, the recommended type of foundation is generally pile foundation except for a few locations where sand strata was located close to ground level. Pile capacities have been calculated as per IS 2811 Part 2 and IRC 79 while allowable bearing capacity for shallow open footing has been computed from the equation as per IS 6400 - 1981.

#### • PILE FOUNDATION

Pile foundation is a feasible foundation scheme that may be designed where the loadings are heavy/medium, upper strata are loose/soft or filled up, and depth of water table is less. The pile load bearing capacity is calculated as per IS 2811 Part 2 & IRC 79-2000.

#### • OPEN FOUNDATION

For the prevailing soil conditions and type of structures, it was observed that shallow open footings can be provided at certain locations. Allowable bearing capacity for shallow open footing has been computed from the equation as per IS 6400 - 1981 & Settlement shall be determined for unit pressure for a specified width of footing based on Corrected SPT values between the level of base of footing and the depth equal to 1.5 to 2.0 times the width of footing. Conditions shall be applied as applicable. Refer: IS 3009 (Part-I).

### 5.3.4 Deck - Simple Spans

#### 5.3.4.1 Deck - Simple Spans 'U' Order

Salient features of the precast segmental construction method technique as envisaged for the project under consideration are indicated below:

Salient features of the pre-cast segmental construction method technique as envisaged for the project under consideration are indicated below:

The superstructure shall be constructed "span by span" sequentially, starting at one end of a continuous stretch and finishing at the other end. Nos. of launching girders may be required so as to work on different stretches simultaneously to enable completion of the project in time.

The number of "breaks" in the stretch can be identified by nos. of continuous units.

The suggested method of erection will be detailed in drawings to be prepared. The launching girder (or, more accurately, the "assembly truss") is capable of supporting the



entire dead load of one span and transferring it to the temporary brackets attached to the pier. The governing weight of the segments will be of the order of 100 kN (to be finalized). The launching girder envisaged will be slightly greater than two span lengths. It must be able to negotiate curves in conjunction with temporary brackets.

Transportation of segments from casting yard to the point of erection will be effected by appropriately designed low-bedded trailers (fly-mounted). The segments can be lifted and erected using erector portal gantry moving on launching girder.

U-girder segments shall be match cast at the casting yard before being transported to location and erected in position. Post-tensioned cables shall be threaded in-situ and tensioned from one end. It is emphasized that for pre-cast segmental construction only one-end pre-stressing shall be used.

The pre-stressing steel and pre-stressing system steel accessories shall be subjected to an acceptance test prior to their actual use on the works. The tests for the system shall be as per FIP Recommendations as stipulated in the special specifications. Only multi-strand jacks shall be used for tensioning of cables. Draw and interest rope measurement device (e.g. Prestole Gauge) shall be attached in consultation with system manufacturer.

The Contractor shall be responsible for the proper handling, lifting, storing, transporting and erection of all segments so that they may be placed in the structure without damage. Segments shall be maintained in an upright position at all times and shall be stored, lifted and/or moved in a manner to prevent torsion and other undue stress. Members shall be lifted, hoisted or stored with lifting devices approved on the shop drawings.

#### **5.3.4.2 Deck – Simple Span Box Order**

The superstructure shall be constructed "span by span" sequentially, starting at one end of a continuous stretch and finishing at the other end. Nos. of launching girders may be required to do so work on different stretches simultaneously to enable completion of the project in time.

The number of "bays" in the stretch can be identified by Nos. of continuous units & spans.

The suggested method of erection will be detailed in drawings to be prepared, at the time of detailed design. The launching girder (or, more accurately, the "assembly truss") is capable of supporting the entire dead load of one span and transferring it to the temporary brackets attached to the pier. The governing weight of the segments will be of the order of 50t (to be finalized). The launching girder envisaged will be slightly longer than two span lengths. It must be able to negotiate curves in conjunction with temporary brackets.





Transportation of segments from casting yard to the point of erection will be effected by appropriately designed low-bedded trailers (pre-mounted). The segments can be lifted and erected using erection portal gantry moving on launching girder.

Box girder segments shall be match cast at the casting yard before being transported to location and erected in position. Post-tensioned cables shall be threaded in-situ and tensioned from one end. It is emphasized that for precast segmental construction only one-end pre-stressing shall be used.

The pre-stressing steel and pre-stressing system steel accessories shall be subjected to an acceptance test prior to their actual use on the works. The tests for the system shall be as per FIP Recommendations as stipulated in the special specifications. Only multi-strand jacks shall be used for tensioning of cables. Direct and indirect force measurement device (e.g. Pressure Gauge) shall be attached in consultation with system manufacturer.

The Contractor shall be responsible for the proper handling, lifting, storing, transporting and erection of all segments so that they may be placed in the structure without damage. Segments shall be maintained in an upright position at all times and shall be stored, lifted and/or moved in a manner to prevent torsion and other undue stress. Members shall be lifted, hoisted or stored with lifting devices approved on the shop drawings.

### 6.5.5 Epoxy Bonded Joints and Shear Keys

A minimum compressive stress of 3 kg/cm<sup>2</sup> shall be provided uniformly over the cross-section for the closure stress on the spliced joint until the epoxy has set. The curing period for application of the compressive stress, method of mixing and application of epoxy and all related aspects including surface preparation shall be as per approved manufacturer's specifications.

The purpose of the epoxy joint, which is about 1mm on each mating surface, shall be to serve as lubricant during segment positioning, to provide:

Waterproofing of the joints for durability in service conditions and to provide a seal to avoid cross-leak of grout during grouting of one cell into other ducts.

The epoxy shall be special purpose and meet requirements of relevant provision of FIP (International Federation of Pre-stressed Concrete).

The temporary compressive stress during the curing period shall be applied by approved external temporary bar pre-stressing (such as Maccloy or Dwidag bar systems or approved equivalent).



## 5.2 CONSTRUCTION OF STATIONS

It is proposed to construct the elevated stations with elevated concrete over the road at most of the stations to minimize land acquisition. To keep the rail level low, it is proposed not to take viaduct through the stations. Thus a separate structure configuration is required (although this may necessitate the break in the launching operations at each station location).

Sub-structure for the station portion will also be similar to that of viaduct and will be carried out in the same manner. However, there will be single viaduct column in the station area, which will be located on the median and supporting the concrete girders by a cantilever arm so as to eliminate the columns on right of way.

### 5.2.1 Grade of Concrete

It is proposed to carry out construction work with design mix concrete through computerized automatic Batching Plants with following grade of concrete for various members as per design requirement/durability considerations.

i) Pile	-	M-35
ii) Pile cap and open foundation	-	M-35
iii) Piers	-	M-40
iv) All precast element for viaduct and station	-	M-45
v) Cantilever pier and portal	-	M-40
	-	M-30
vi) Other miscellaneous structure	-	M-30

For all the main structures, permeability test on concrete sample is recommended to ensure impermeable concrete.

### 5.2.2 Reinforcement and pre-stressed steel

It is proposed to use HYSD 500 or TMT steel as reinforcement bars.

For pre-stressing work, low relaxation high tensile steel strands with the configuration 12 K 12 and or 10K 10 is recommended (conforming to IS 14288).

### 5.2.3 Road width required during construction

As most of the construction is to be carried out on the middle of the road, central fee lanes including median will be required for construction activities. During piling and open foundation work, a width of about 5 m will be required for construction and the same will be sanctioned. It is proposed that fee lanes are provided for traffic on either side during construction by widening of roads, if necessary. In certain cases, one way traffic may be resorted to.



All these actions will require a minimum period of about 4 to 6 months. During this period, the implementing agency can go ahead with the following preliminary works:

- i) Preliminary action for diversion of utility and preparation of estimates thereof.
- ii) Reservation of land along the corridor, identification and survey for acquisition.

The new SPV for the implementation of Nagpur metro rail project has to take action for appointment of consultant for Project Management and cost checking including preparation of tender documents. Simultaneously, action is also to be taken for detailed design for structures for elevated corridor.

## 6.7 GEO-TECHNICAL INVESTIGATION

The geological investigation was carried out by DMRC aiming to understand the geology of areas along with their alignment. The purpose of doing the geotechnical investigation is to identify the soil type with a view of design the safe & economical foundations for their structures and to propose the ground improvement methods in known troublesome spots like swampy areas, soft ground and peat land etc., if found any.

Prior to construction, it is necessary to ascertain the geological phenomena, based on interpretation of geological information such as boring log, physical and mechanical property. Accordingly, quality and quantity of geological investigation highly affect to civil engineering work.

### 6.7.1 Physiography

Nagpur is situated at 21° 00' N latitude and 75° 00' E longitude and a mean altitude of 315 meters above sea level. Being located far away from any major water body at the centre of the Indian peninsula, the Nagpur's climate is dry or mildly humid for most of the year except for the rainy season. The highest recorded temperature in the city was 48.6 °C, while the lowest was 3°C.

### 6.7.2 General Geology and Related Characteristics

The Geo technical site investigation carried out from AUTOMOTIVE SQUARE TO MH-Alignment A & B1 corridors were done in Utkarsha Nagar to Pimpri Nagar alignment with in the Nagpur City of Maharashtra.

Nagpur lies on the Deccan plateau of the Indian Peninsula and has a mean altitude of 315.5 meters above sea level. The underlying rock strata are covered with alluvial deposits resulting from the flood plain of the Karanla River. In some places these give rise to granular sandy soil. In low lying areas which are poorly drained, the soil is alluvial clay with poor permeability characteristics. In the eastern part of city crystalline (metamorphic) rocks such as granite, schist and gneisses are found, while in the northern part yellowish sand stones and clays of the lower Gondwana formations are found.



Latitude : 78°15' to 88°45' E, Longitude 18°45' to 21°35' N.

**Physiography and Climate:** The city is generally having warm tropical climate with the temperatures in summer varying between 41°C to 46°C and in winter between 32°C to 37°C. The period between January to April and May to December is generally dry whereas in June to October it is rainy season. The city has an average annual rainfall of 1152.8 mm.

**SEISMICITY:** According to studies, Nagpur region lies in between Zone 1 and Zone 2 of Earthquake Zones in the country. It means that Nagpur has close to zero chances of getting a major earthquake which may cause huge devastation. Recent history also supports the fact that Nagpur region is relatively very safe as far as earthquakes are concerned. Though city has not recorded any seismic activity of magnitude above 4 on Richter scale since 1008 and falls under safest earthquake zone area, the possibility of a low to moderate earthquake cannot be ruled out completely. A study of active faults conducted by the Geological Survey of India (GSI), central region in city in last ten years, has shown presence of predominant features of neo-tectonic activity in vicinity (200 plus km) of Nagpur which could reactivate and trigger low to moderate quakes in the area. Active faults studies conducted by GSI department from 2002 to March 2010 has shown that the entire stretch starting from Shadol district in Madhya Pradesh in the Son near basin to Narmada banks in Jabalpur, the Son Narmada South Fault (SNDF) which continues westward to become Dandarghat fault north of Parbhani in Maharashtra has shown presence of paleozoic-mesozoic rocks along the banks of the rivers which are known for tectonic activity.





**6.7.3 FIELD INVESTIGATION**

Field investigation at the site were planned to determine the required strength characteristics of the underlying soil/rock strata to design the foundations of the proposed structure to be constructed. The geotechnical investigation work includes:

1. Drilling of 150mm diameter boreholes in all kind of soil including gravels and cobbles and 60 size borehole in boulders and rock strata. All boreholes shall be bored upto depths of 30 m in soil (up to N=100) or 10 m in weathered rock (RQD <=50%) or 5 m in hard rock (RQD>50%).

However the maximum depth of bore hole does not exceed 30 m. If strata having a standard Penetration Test value greater than 100 with characteristics of rock are met earlier, the borehole shall not be advanced further. When the boreholes are to be terminated in soil strata, the Standard Penetration Test shall be carried out at the termination depth and recorded.

2. Conducting Standard penetration test (SPT) at every 1.5m interval starting from 1.5m from natural ground level at every change of stratum as per IS:2131.
3. Collection of disturbed, undisturbed soil samples and water sample as per IS: 2132, IS: 1892 & IS: 3025 should be followed.
4. The following laboratory tests were conducted on collected soil/water samples.

**Table 6.2 : LABORATORY TESTS-SOIL/WATER**

SL. NO.	PARTICULARS OF PROPERTIES	DISTURBED SOIL SAMPLE	UNDISTURBED SOIL SAMPLES
1.	Slime Analyse	✓	✓
2.	Hydrometer Analysis	✓	✓
3.	Natural Moisture Content		✓
4.	Bulk / Dry Density		✓
5.	Specific Gravity	✓	✓
6.	Atterberg's Limit	✓	✓
7.	Direct Shear Test (for non cohesive soils)		✓
8.	UU Tests (for cohesive samples)		✓
9.	UCS Tests (for cohesive samples)		✓
10.	Flow permeability test in soil		✓
11.	Chemical test on soil & water sample for pH value, carbonate, sulphate (SO <sub>4</sub> ) and SO <sub>2</sub>		✓



5. The following laboratory tests were conducted on collected rock sample.

**Table 5.3 : LABORATORY TESTS/ROCK SAMPLES**

SL. NO.	PARTICULARS OF PROPERTIES
1.	Permeability test by Packer method
2.	Density Test
3.	Water absorption
4.	Porosity
5.	Hardness
6.	Abrabergs Limit
7.	Unconfined compression test
8.	Flare test index
9.	Modulus of elasticity
10.	Acid test

## 6.7.4 DETAIL OF GEOTECHNICAL INVESTIGATION

### 6.7.4.1 GENERAL

Six boring rigs were deployed with all requisite equipments and accessories at project sites. Total 88 boreholes have been drilled at an average distance of 0.5 km each, all along the length of the proposed Metro corridor.

41 bore holes were drilled in AUTOMOTIVE SQUARE TO MBU alignment & 30 boreholes were drilled in Lakhmeya Nagar to Prapada Nagar alignment. However, due to the site condition, depth of drilling work ranging from 10.50m to 23m was carried out at the proposed locations. Details of Boreholes are given below in Table no 5.4 & Table no 5.5

### 6.7.4.2 DETAIL FOR NORTH - SOUTH CORRIDOR

Necessary plant, equipment and personnel for conducting the requisite field work were mobilized to the site. These were shifted from one test location to another location during execution of the field work and demobilized on satisfactory completion of the entire field work.



Forty one bore holes (SH-1 to SH-41) carried out.

The bore holes were bored at the site using Rotary drilling method as per IS: 1852-1975. Casing as required was used to retain the bore holes.

Standard penetration tests were conducted in the above bore holes at every 1.00 m interval & at change of strata as per specifications. The bore were cleaned up to the desired depths. Standard split spoon sampler attached to lower end of 16 mm rods was driven in the bore holes by means of standard hammer of 63.50 kg falling freely from a height of 75 cm. The sampler was driven 45 cm as per specifications & the numbers of blows required for each 15 cm penetration were recorded. The numbers of blows for the first 15 cm penetration were not taken into account. This was considered as seating drive. The numbers of blows for next 30 cm penetration were designated as SPT 'N' value. Whenever the total penetration was less than 45 cm, the number of blows & the depth penetrated is incorporated in respective bore logs. Disturbed soil samples obtained from standard split spoon sampler for all the above standard penetration tests were collected in polythene bags of suitable size. These samples were properly sealed, labelled, recorded and carefully transported to the laboratory for testing.

Undisturbed soil samples were collected from the bore holes at every 3.0 m interval in depth & at change of strata as per sampling specifications, in 60 mm dia sampling tubes of 100 mm dia and 400 mm length fitted to an adapter with bail and socket arrangement. These sampling tubes after retrieval from the bore holes were properly waxed and sealed at both ends. These were carefully labeled and transported to the laboratory for testing. Undisturbed soil samples whenever slipped during lifting, were duly marked in the field bore logs as well as in the soil profile.

Disturbed soil samples were also collected from the bore holes at suitable depth/intervals to supplement the boring records. These samples were collected in polythene bags of suitable size. These samples were properly sealed, labeled, recorded & carefully transported to the laboratory for testing.

Conducting field permeability test in same bore holes in overburden using falling head and in rock with packer.

The depth of ground water table was checked / measured in all bore holes. The ground water table was encountered in some bore holes during the boring activity.





Summary of Bore Holes for this corridor is as below :

**Table 5.4 – SUMMARY OF BORE HOLES  
N. S. CORRIDOR**

BH No.	Location Details	Total depth	Oil	Sub. Rock	Hard Rock	Water Table (m)
1	Automotive Chowk	25.00	15.00	10.00	-	7.20
2	Go Gas Pump	10.00	0.00	10.00	-	7.10
3	icoby Automobile	17.00	7.00	10.00	-	7.20
4	Lal golden Chowk	15.00	5.00	10.00	-	6.00
5	New Indira Hindi School	10.00	0.00	10.00	-	5.90
6	Doct. Jaiswar Tur(Mo)	10.00	0.00	10.00	-	7.10
7	Bharat Patel Pura (E) M. Pura	12.00	4.00	10.00	-	5.40
8	Kabali Chowk	14.00	4.00	10.00	-	3.70
9	Gurudwara (Railway Line Near)	20.00	10.00	10.00	-	5.00
10	Gaddi Gaddan Chowk	12.00	2.00	10.00	-	4.20
11	L.I.C. Chowk, AM Church Campus	11.00	1.00	10.00	-	4.40
12	R.S.J Bank Chowk	12.00	2.00	10.00	-	4.00
13	Maharaja College, T. Point	11.00	1.00	10.00	-	3.80
14	Ita Bani Police Station	14.00	4.00	10.00	-	5.00
15	Raj Furniture, Opp. Nanga Traders	10.00	0.00	10.00	-	4.70
16	Vaswani Stadium	17.00	7.00	10.00	-	4.60
17	Dharam P.S, Opp. Green City Hotel	17.00	7.00	10.00	-	5.10
18	Mahipal Arts (M. Printers)	10.00	0.00	10.00	-	3.20
19	Asha Towers	14.00	4.00	10.00	-	3.90
20	Handlor Chowk	14.00	4.00	10.00	-	3.40
21	Central Jail	10.00	0.00	10.00	-	3.80
22	Crack Tower Rajive Gandhi Chowk	11.00	1.00	10.00	-	3.20
23	Sanskar Vidya Nagar School	12.00	2.00	10.00	-	4.00
24	Bharat Creation/Genity Traders	13.00	3.00	10.00	-	4.10
25	Sewaraj Chowk	12.00	2.00	10.00	-	2.90
26	Khanta Bus Stop	12.00	2.00	10.00	-	3.60
27	Basa Hardware/Vijay Trading	13.00	3.00	10.00	-	3.00
28	Arun Rao Punjwar Chowk (Poly)	13.00	3.00	10.00	-	2.10
29	Park/Dance Forest Area (Vijay)	14.00	4.00	10.00	-	2.90
30	Parking Airport	14.00	4.00	10.00	-	2.10
31	Ajmer Shunty	14.00	4.00	10.00	-	3.70
32	Mihan Entry	11.00	1.00	10.00	-	2.60
33	Mihan Road	11.00	1.00	10.00	-	2.00
34	Mihan Road	11.00	1.00	10.00	-	3.70
35	Mihan Road	10.00	0.00	10.00	-	3.20
36	Mihan Road	11.00	1.00	10.00	-	3.10
37	Mihan Road	10.00	0.00	10.00	-	3.20
38	Mihan Road	11.00	1.00	10.00	-	4.00
39	Mihan Road	10.00	0.00	10.00	-	4.00
40	Mihan Dood	11.00	1.00	10.00	-	3.10
41	Mihan Dood	11.00	1.00	10.00	-	2.40



### 5.7.4.3 DETAILS FOR EAST - WEST CORRIDOR

Thirty nine bore holes (BH-1 to BH-39) were carried out. The bore holes were bored at this site using Rotary drilling method as per IS: 1052-1970. Casing as required was used to retain the bore holes.

Standard penetration tests were conducted in the above bore holes at every 1.50 m interval & at change of strata as per specifications. The bores were cleaned up to the desired depth. Standard split spoon sampler attached to their end of 1/4" drill rods was driven in the bore holes by means of standard hammer of 63.50 kg falling freely from a height of 75 cm. The sampler was driven 45 cm as per specifications & the number of blows required for each 15 cm penetration were recorded. The numbers of blows for the first 15 cm penetration were not taken into account. This was considered as seating drive. The numbers of blows for next 30 cm penetration were designated as SPT 'N' value. Whenever the total penetration was less than 45 cm, the number of blows & the depth penetrated is incorporated in respective bore logs. Disturbed soil samples obtained from standard split spoon sampler for all the above standard penetration tests were collected in polythene bags of suitable size. These samples were properly sealed, labeled, recorded and carefully transported to the laboratory for testing.

Undisturbed soil samples were collected from the bore holes at every 3.0 m interval in depth & at change of strata as per sampling specifications. In thin walled sampling tubes of 300 mm dia and 400 mm length fixed to an adapter with bit and socket arrangement. These sampling tubes after retrieval from the bore holes were properly wiped and sealed at both ends. These were carefully labeled and transported to the laboratory for testing. Undisturbed soil samples wherever stopped during lifting, were duly marked in the field bore logs as well as in the soil profile.

Disturbed soil samples were also collected from the bore holes at suitable depth/interval to supplement the boring records. These samples were collected in polythene bags of suitable size. These samples were properly sealed, labeled, recorded & carefully transported to the laboratory for testing.

Conducting field permeability test in some bore holes in overburden using falling head and in rock with packer.

The depth of ground water table was checked / measured in all bore holes. The ground water table was encountered in some bore holes during the boring activity.

Summary of Bore Holes is given in Table : 5.3.



**Table 5.1 - SUMMARY OF BORE HOLES  
E W CORRIDOR**

BH No.	Location Details	Total depth	SD	Soil Desc.	Hard Rock	Water Table (m)
1	AM Engineering Limited	11.00	1.00	5.31	5.01	1.90
2	C.R.P.F Gate No-1	11.00	1.00	6.00	4.00	4.20
3	Mehrota Company	11.00	1.00	6.00	4.00	4.30
4	Arbit. Salt Chok (Near Dhoram kanta)	11.00	1.00	6.00	-	4.05
5	Tot Tai Naka	11.00	1.00	6.00	-	4.25
6	Super Enclave, Opp. Pashant Trading	11.00	1.00	6.00	-	1.30
7	Hingra T. Point	10.00	0.00	6.00	-	4.70
8	Kanoria Hotel	11.00	1.00	6.00	-	4.00
9	Puro House (S.C.C.R.P.F) Nagar	10.00	0.00	6.00	-	5.30
10	Sudesh Nagar Chok.	12.00	2.00	5.00	1.00	4.20
11	Nagar Improvement Trust, Datta Galla	13.00	3.00	6.00	-	4.40
12	Tanwar Road	12.00	2.00	6.00	-	1.40
13	Leela house (Near Ambajhari T Point)	12.00	2.00	8.00	1.00	1.00
14	L.A.D. Chok	13.00	3.00	6.00	-	5.90
15	Mansar Nagar chok	13.00	3.00	6.00	-	5.15
16	Aashish S.S High School	12.00	2.00	6.00	-	5.30
17	Dharampeth Vidyapeeth	14.00	4.00	6.00	-	4.90
18	A.M.I.E (Nagar Local Center)	14.00	4.00	6.00	-	3.00
19	M.J. College	14.00	4.00	6.00	-	4.90
20	Jangam Road Chok	14.00	4.00	6.00	-	5.30
21	Murto Chok	14.00	4.00	6.00	-	5.70
22	Railway Push Box	14.00	4.00	6.00	-	4.00
23	Nagar Corporation sector Naka - 02	14.00	4.00	6.00	-	4.20
24	Haveli kanta nagar	14.00	4.00	6.00	-	5.30
25	Mayan Hospital	13.00	3.00	6.00	-	1.90
26	Sewa Solor Chok	13.00	3.00	6.00	-	4.90
27	Gandhi Bagh (Bus Stop)	12.00	2.00	6.00	-	4.35
28	Chhambawal Chok	13.00	3.00	6.00	-	4.70
29	Dandekar Chok	13.10	3.10	6.00	-	4.60
30	Richia Hospital	14.50	4.50	6.00	-	4.75
31	Telephone Exchange	16.00	6.00	6.00	-	7.30
32	Cham Nagar Chok, Bhata Furniture	16.00	6.00	6.00	-	5.30
33	Arbada Chok	17.00	7.00	6.00	-	4.90
34	All Electrical, Vardman Nagar Chok	16.00	6.00	6.00	-	7.40
35	Near Mohaloni Collection	16.00	6.00	6.00	-	6.60
36	Ising Bar & Restaurant	17.00	7.00	6.00	-	4.30
37	Rajha Krishna Hospital Chok	17.00	7.00	6.00	-	7.30
38	Des Wire Shop	21.00	10.00	6.00	-	7.00
39	Domt Hotel, Near P & B Barn	20.00	10.00	6.00	-	7.30

**5.7.4.4 TYPE OF FOUNDATION :****TYPE OF FOUNDATION :NORTH – SOUTH CORRIDOR****A : Bored Cast in situ RCC Pile**

Depending on the field and laboratory observations of subsist strata, test results and the type of structures proposed at site, the most feasible soil-foundation system is recommended as normal bored cast in situ R.C.C. pile foundations of 0.80m & 1.0m diameter at different depths with cut-off level at 1.50m to 2.0m depth below existing ground level.

The safe load carrying capacities of these piles are given in following table.

**Table :5.6 RCC PILE DETAIL S FOR NORTH – SOUTH CORRIDOR**

Borehole Nos	Dia. of Pile	Cutoff level	Depth, m	Pile Capacity		
				Compressio n	Uplift	Lateral
1	0.80	1.50	18.00	185.0	80.0	9.0
	1.00	1.50	18.00	300.0	100.0	12.0
2,3	0.80	1.50	11.00	170.0	40.0	9.0
	1.00	1.50	11.00	250.0	50.0	12.0
4,5,6	0.80	1.50	18.00	170.0	45.0	9.0
	1.00	1.50	18.00	250.0	50.0	12.0
7,8	0.80	1.50	18.00	190.0	35.0	9.0
	1.00	1.50	18.00	225.0	45.0	12.0
9	0.80	1.50	18.00	220.0	80.0	9.0
	1.00	1.50	18.00	320.0	100.0	12.0
14	0.80	1.50	18.00	190.0	30.0	9.0
	1.00	1.50	18.00	220.0	40.0	12.0
15,16	0.80	1.50	11.00	170.0	40.0	9.0
	1.00	1.50	11.00	250.0	50.0	12.0
17	0.80	1.50	12.00	180.0	45.0	9.0
	1.00	1.50	12.00	260.0	55.0	12.0
18 to 21	0.80	1.50	18.00	190.0	30.0	9.0
	1.00	1.50	18.00	220.0	40.0	12.0
21 to 28	0.80	1.50	18.00	140.0	30.0	9.0
	1.00	1.50	18.00	210.0	40.0	12.0
29 to 33	0.80	1.50	18.00	190.0	30.0	9.0
	1.00	1.50	18.00	220.0	40.0	12.0

**Note:**

1. For design purpose, water table shall be considered at cut off level.
2. For design purpose, effective overburden pressure at pile tip should correspond to pile length equal to 12 times the diameter.
3. The above values should be confirmed through pile load tests in the field before adopting these values for design purposes.

**B: Open square footing**

Depending on the field and laboratory observations of subsoil strata, test results and the type of structures proposed at site, the types of foundations, depths and net safe bearing capacities recommended for design purposes are given in the following table. The net SBC/WFL in the following table are the lower of the values obtained from shear failure criterion as per IS: 5400 and settlement failure criterion as per IS: 8009, Part II.

For Bore Hole Nos : 10 to 13, 22 & 32 to 41 :

**Table :5.7 OPEN FOUNDATION DETAILS FOR NORTH - SOUTH CORRIDOR**  
For Foundation settlement = 40.0 mm

Type of Foundation	Depth of Foundation (m)	Size of Foundation (m)	Net safe bearing Capacity/ Allowable Pressure intensity ( $\text{kg/cm}^2$ )
Square footing	2.50 to 3.0	3.0 to 6.0	30.00

**Note:** For design purpose water table shall be considered at foundation level.

**TYPE OF FOUNDATION : EAST - WEST CORRIDOR****A : Bored Cast in situ RCC Pile**

Depending on the field and laboratory observations of subsoil strata, test results and the type of structures proposed at site, the most feasible soil foundation system is recommended as normal bored cast in situ R.C.C. piles foundations of 0.80m & 1.0m diameter at different depths with cut-off level at 1.50m to 2.0m depth below existing Ground level.

The safe load carrying capacities of these piles are given in following table.



Table 5.3 RCC PILE DETAIL S FOR EAST - WEST CORRIDOR

Borehole Nos	Dia. of Pile	Cut-off level	Depth, m	Pile Capacity		
				Compression	Uplift	Lateral
11	0.80	1.50	12.00	400.0	90.0	9.0
	1.00	1.50	12.00	600.0	90.0	12.0
17 - 20	0.80	1.50	14.00	165.0	50.0	9.0
	1.00	1.50	14.00	240.0	70.0	12.0
20 - 24	0.80	1.50	14.00	180.0	60.0	9.0
	1.00	1.50	14.00	250.0	70.0	12.0
25 - 28	0.80	1.50	12.00	150.0	40.0	9.0
	1.00	1.50	12.00	220.0	60.0	12.0
30 - 31	0.80	1.50	14.00	170.0	50.0	9.0
	1.00	1.50	14.00	240.0	70.0	12.0
32	0.80	1.50	12.00	170.0	40.0	9.0
	1.00	1.50	12.00	250.0	50.0	12.0
33 - 34	0.80	1.50	15.00	200.0	60.0	9.0
	1.00	1.50	15.00	300.0	100.0	12.0
35 - 37	0.80	1.50	15.00	150.0	70.0	9.0
	1.00	1.50	15.00	300.0	100.0	12.0
38	0.80	1.50	15.00	180.0	60.0	9.0
	1.00	1.50	15.00	250.0	100.0	12.0
39	0.80	1.50	20.00	200.0	60.0	9.0
	1.00	1.50	20.00	300.0	100.0	12.0

**Note:**

1. For design purpose, water table shall be considered at cut off level.
2. For design purpose, effective overburden pressure at pile tip should correspond to pile length equal to 15 times the diameter.
3. The above values should be confirmed through pile load tests in the field before adopting these values for design purposes.

**B : Open square footing**

Depending on the field and laboratory observations of subsurface data, test results and the type of structures proposed at site, the types of foundations, depths and net safe bearing capacities recommended for design purposes are given in the following table. The net SBC/UP is the following table and the lower of the values obtained from shear failure criterion as per IS - 5413 and settlement failure criterion as per IS - 8099 Part-I.

**Table :5.0 OPEN FOUNDATION DETAILS FOR EAST-WEST CORRIDOR**

For Factorable settlement = 40.0 mm

Type of Foundation	Simile No	Depth of Foundation (m)	Size of Foundation (m)	Net safe Bearing Capacity/ Allowable Pressure Intensity (kN/m <sup>2</sup> )
Square footing	1 - 3	2.00 - 3.0	5.0 x 5.0	25.00
	12 & 12	3.0	3.0 x 3.0	20.00
	12 - 13	3.0	5.0 x 5.0	25.00
	14 - 15	3.00 - 4.00	5.0 x 5.0	25.00
	16	3.0	5.0 x 5.0	25.00

**Note:** For design purpose water table shall be considered at foundation level.

## 6.3 LAND

### 6.3.1 The alignment and profile

Both the alignments are elevated except about 4.0 Km at Grade alignment. Total 06 stations are proposed in both corridors. Out of which 02 are at grade and 35 are elevated.

### 6.3.2 Land Requirement for following Major Components

MRTS Structure (including Route Alignment), Station Building, Platforms, Entry/Exit Structures, Traffic Integration Facilities, Depot, etc.

Relaying/Tractor Sub-stations

Radio Towers

Temporary Construction Depots and work sites.

Staff quarters, office complex and operation control centre(OCC)

### 6.3.3 Land for Underground stretches

No land at surface is required permanently for underground section, except for small areas for entry/exit structures, traffic integration, crilling plant and ventilation shafts at stations. These will be located either on footpath edge or in hard marginal open setback of the building along the road.

### 6.3.4 Land required for elevated stretches

For elevated section, single pier supporting the viaduct will be located at the middle of road so that the existing roads remain in use as usual. Accordingly, necessary



permission for using such right-of-way will have to be obtained from the concerned authorities. Elevated station is generally proposed with elevated concourse so that land is required only for locating the entry/exit structures. Traffic integration facilities are provided wherever the same are required and, but no land is proposed for acquisition.

The normal viaduct structure of elevated Metro is about 10 m (edge to edge) wide. Ideally the required right of way is 15m. However, for reasons of safety a clear marginal distance / setback of about 3 m is necessary from either edge of the viaduct (or 10 m on both sides of the centre line) when no structures are to be located. This is necessary as the traction system as proposed is overhead 25 kV ac systems with masts fixed on the parapets. Also, it ensures easy access and working space all along the viaduct for working of emergency equipments and fire brigades. In stretches, where the elevated alignment has to be located away from road, a strip of 20-m width is proposed for acquisition.

### 6.3.5 Land for Switch-over Ramps

Switch-over ramps are required for transition from the underground to elevated section or vice versa. The ramp covers a stretch of ground for the whole width of structure for two tracks (about 10.5m including the protection works). The length of ramp above ground depends on the existing ground slope and the gradient provided on Metro alignment (normally 3% to 4%). Thus, the ramp is to be located in an area where sufficient road width is available or in an open area. On this corridor, three such ramps are provided on the both the corridors.

### 6.3.6 Land for Traffic Integration

Certain land is required for traffic integration at the each station. Efforts have been made to identify land required for traffic integration at each station to facilitate park and ride facility, but it is not possible to find open spaces at all the locations. Hence, land for traffic integration has been marked in the drawing wherever it is available.

### 6.3.7 Land for Traction and Receiving Substation and Radio Towers

Four RSB are proposed to be located for both the corridors. Hence, an area has to be earmarked at Kadambari Park. The exact location will be decided at the time of implementation of the project. Similarly, four radio towers are also being proposed to be located at four locations occupying an area of 100 m<sup>2</sup> (10 m X 10 m each plot) for each radio tower.



**5.3.3 Land Requirement for Stations & Running section**

The station is generally located on the road median. Total length of the station is ~140m. All the stations are two-level stations. The concourse is planned along the whole length of the platform with staircases leading from either side of the road. The maximum width of the station at concourse is ~22m. Passenger facilities like seating, information, etc. as well as operational areas are provided at the concourse level. The staircases giving access to concourse area from ground will be located at the edge of footpaths at a front marginal open setback of the buildings in the as far as possible in the open space. Nevertheless it is not possible to find open space at all the locations therefore acquisition of certain private structures is inevitable. At curved portions, the alignment could not be kept in the centre of the road and land acquisition at such locations is inevitable in spite of introduction of sharper curves.

To the extent possible the Entry and Exit points of stations (underground and elevated) were planned on the foot paths. But, for locating other station facilities such as chiller plants, ventilation shafts, underground water tanks, generator set room etc., land acquisition is proposed. The details of land permanently required for depot, running sections and stations are indicated in the **Table 5.10**, **Table 5.10 A**, **5.10 C**, **5.10 D** and **Table 5.10E**.

**Table 5.10. Details of Land Required for Depot**

S. No.	Plot No.	Location	Area (approx)	Ownership	Purpose
1	DP1	838/10	21.32 hectares	Government	Depot
2	DP2	337/ LA92	21.32 hectares	Government	Depot

**Table 5.10 A: Details of Land Required for Running Section  
EAST-WEST CORRIDOR**

EAST WEST CORRIDOR			
S.NO	Plot No	Area(Sqm)	Ownership
1	05-1	81	Govt.
2	05-2	105.8	Govt.
3	05-3	34.7	Govt.
4	05-4	2118.2	Govt.
5	05-5	125.5	Govt.
6	05-6	48.8	Govt.
7	05-7	26.4	Govt.
8	05-8	182.9	Govt.
9	05-9	254.3	Govt.
10	05-10	545.8	Govt.
11	05-11	924.9	Govt.
12	05-12	151.5	Govt.



EAST WEST CORRIDOR			
S.NO	Plot No	Area(Sq.m)	Ownership
19	RS-14	584.9	Govt.
20	RS-15	176.8	Govt.
21	RS-16	46.2	Govt.
22	RS-16	123.1	Govt.
17	RS-17	11.8	Govt.
18	RS-18	23.1	Govt.
19	RS-19	14.7	Govt.
20	RS-20	1.8	Govt.
21	RS-21	4.8	Govt.
22	RS-22	14.8	Govt.
23	RS-23	3.9	Govt.
24	RS-24	3.9	Govt.
Total Land = 8296.15sqm			
Govt. = 8255.1 sqm			
Priv. = 1488.85sqm			

**Table 6.10 B: Details of Land Required for Running Section  
NORTH SOUTH CORRIDOR**

RUNNING SECTION OF NAGPUR METRO RAIL PROJECT			
NORTH SOUTH CORRIDOR			
S.NO	Plot No	Area(Sq.m)	Ownership
1	RS-1	20.3	Govt.
2	RS-2	108.8	Govt.
3	RS-3	11.8	Govt.
4	RS-4	1.8	Govt.
5	RS-5	55.1	Govt.
6	RS-6	63.2	Govt.
7	RS-7	55.1	Govt.
8	RS-8	198.8	Govt.
9	RS-9	152.8	Govt.
10	RS-10	31.2	Govt.
11	RS-11	25.2	Govt.
12	RS-12	29.1	Govt.
13	RS-13	106.8	Govt.
14	RS-14	1746.8	Govt.
15	RS-15	103.1	Govt.
16	RS-16	87.4	Govt.
17	RS-17	122.1	Govt.



18	RS-18	863.1	Govt.
19	RS-19	138.2	Govt.
20	RS-20	603.1	Govt.
21	RS-21	893.8	Govt.
22	RS-22	8887.7	Pvt.
23	RS-23	873.8	Pvt.
24	RS-24	70	Pvt.
25	RS-25	245.3	Govt.
26	RS-26	4843.8	Govt.
27	RS-27	202.7	Pvt.
28	RS-28	42.8	Pvt.
29	RS-29	735.3	Pvt.
30	RS-30	637.5	Govt.
31	RS-31	2189.7	Pvt.
32	RS-32	1778.6	Pvt.
33	RS-33	1113.1	Pvt.
34	RS-34	735.8	Pvt.
35	RS-35	741	Pvt.
36	RS-36	671.8	Pvt.
37	RS-37	76	Pvt.
38	RS-38	138	Pvt.
39	RS-39	10418.7	Govt.
40	RS-40	26754.0	Govt.
41	RS-41	383.7	Govt.
42	RS-42	40340.6	Govt.
43	RS-43	2243.7	Govt.
44	RS-44	13405.5	Govt.
Total Land -130938.85sqm.			
Govt. - 100881.75sqm.			
Pvt. - 30057.10sqm.			

Table 5.10 C: Details of Land Required For Station

S. No	Name of Station	FLIGHT NO.	AREA	OWNERSHIP	REMARKS
North South Corridor, Automotive Drive to Krasip Station					
1	ALTERNATIVE SITE	AS-1	217.8	Pvt.	Operational
		AS-2	228.0	Pvt.	Structure
2	NAVE ROAD	NS-1	284.3	Pvt.	Structure
		NS-2	228.8	Pvt.	Structure



S. No.	Name of Station	PLUG NO.	AREA	CRUISE SHIP	REMARKS
3	INDIRA CHOKH	IC-1	217.0	Flt	Storage
		IC-2	217.0	Flt	Storage
4	RADVI CHOKH	RC-1	240.0	Govt.	Open
		RC-2	220.7	Flt	Recreation/Storage
5	GADGUDIGAM BORO	GD-1	234.0	Flt	Storage
		GD-2	234.0	Flt	Storage
6	KADURCHAND PARI	KP-1	210.0	Govt.	Open/Waterlog
		KP-2	200.0	Flt	Recreation
7	JYOTI BLD	JY-1	217.0	Flt	Storage
		JY-2	217.0	Govt.	Open
8	DINABURG	DB-1	200.7	Flt	Waste/Process
		DB-2	11.0		Recreation
		DB-3	241.0		Recreation
9	CONCRETE NAGAR	CN-1	220.1	Govt.	Open
		CN-2	234.7	Flt	Recreation
10	HABIBUL COLONY	HC-1	217.0	Govt.	Open
		HC-2	217.0	Govt.	Open
11	AURA SQUARE	AS-1	217.0	Flt	Shopping Complex
		AS-2	190.0	Govt.	Waste
12	DINAIPARA/BIHAR	DB-1	200	Govt.	Open
		DB-2	222.0	Flt	Govt.
13	JALPAIGIRI NAGAR	JN-1	240	Govt.	Open
		JN-2	230.0	Flt	Waste/Chamber
14	LITTON NAGAR	LN-1	200	Govt.	Open/Gravel
		LN-2	200.0	Flt	Shopping Complex
15	AIRPORT	A-1	220.0	Govt.	Open
		A-2	220.0		Open/Recreation Land
16	NEW AIRPORT	NA-1	220.0	Govt.	Open
17	KHARWAI	KW-1	220.0	Govt.	Recreation Land
<b>Total Land = 21027.00 Hrs</b>		<b>Govt. = 750.00 Hrs</b>		<b>Flt. = 13812.50 Hrs</b>	



S. No.	Name of Station	PLC/ID	Area	Operational	Remarks
<b>East West corridor, Pragsi Nagar to Lokmanya Nagar</b>					
1	HEALING MANDAL	PL-1	210.1	Y/N	Reservable
		PL-2	216.7	Good	Open
2	KASINDU DEVI CHOWK	KDC-1	212.8	Y/N	Reservable
		KDC-2	229.8		Reservable/Stop
3	ABHEDHAR CHOWK	AC-1	219.8	Good	Concept Reservable
		AC-2	227.1	Y/N	Stop
4	TELEPHONE EXCHANGE	TE-1	211.8	Y/N	Reservable/Stop
		TE-2	210.4		Reservable
5	CHETANU CHOWK (GANGU PURANA)	CC-1	224.7	Y/N	Reservable
		CC-2	213.8		Reservable/Stop
6	KUNDEEN CHOWK	KDC-1	228.8	Y/N	Reservable/Stop
		KDC-2	212.8		Partial Pump Structure
7	DUSAR VADIA CHOWK (SAYO HOSTEL)	DC-1	211.7	Y/N	Reservable
		DC-2	211.4		
8	NAGPUR RAILWAY STATION	NRS-1	222.2	Good	Active
		NRS-2	221.7		Railway land
9	BRABUR	BR-1	229.4	Y/N	Reservable
		BR-2	222.1		
10	JHANSI RAM SINGH	JRS-1	222.8	Y/N	Reservable
		JRS-2	222.8		Good
11	REPUTATIONS OF DISRUPTIONS	RD-1	212.5	Good	Open
		RD-2	218.1		
12	SHANKAR NAGAR SINGH (DARA D. INBA)	SN-1	216.2	Good	Hand Pump + Reservable
		SN-2	220.4		Reservable
13	LAD CHOWK	LC-1	422.8	Y/N	Reservable
		LC-2	422.8		
14	DHRUBA SINGH COLLEGE	DC-1	216.5	Y/N	Open
		DC-2	224.2		Good
15	SUDHASTI NAGAR	SN-1	213.5	Good	Open
		SN-2	212.8		
16	KACHANA (MCC RD. JNC)	K-1	226.4	Good	Open
		K-2	221.2		Y/N
17	DADUDEV NAGAR	DN-1	222.2	Y/N	Reservable
		DN-2	220.4		Good
18	BANSI NAGAR	BN-1	422.7	Y/N	Hand pump Structure
		BN-2	221.5		
19	LOKMANYA NAGAR	LN-1	219.6	Good	Open



S. No.	Name of Station	Plot No.	Area	Ownership	Remarks
		LN-3	377.2		

**Table E.10 D: DETAIL I OF LAND REQUIRED FOR PARKING**

PARKING LAND OF NAGPUR METRO RAIL PROJECT				
EAST - WEST CORRIDOR				
S.No	Station Name	Parking Land (sqm.)	Ownership	Remarks
1	PRAJAPATI NAGAR	899.7	Govt.	Open
2	JHANSI RAIL SORE	3408	Govt.	Open
3	DHARAMPETH COLLEGE	1762.6	Govt.	Open
4	RACHANA (RING RD JWC)	1465.7	Pvt.	Open
5	LOHMANYA NAGAR	1546.8	Govt.	Open
	<b>Total</b>	<b>3331.8</b>		
NORTH-SOUTH CORRIDOR				
1	KADVI CHAWN	3337.5	Govt.	Open
2	KASTURBAHND PARK	3752.2	Govt.	Park
3	BTABURD	6761.7	Govt.	Open
4	RAHWTE COLONY	2693.2	Govt.	Park
5	ALFA SQUARE	1170.2	Pvt.	Shopping center
6	CHHATRAPATI SQUARE	833.8	Govt.	Open
7	JAYPRAKASH NAGAR	17133.4	Govt.	Open
8	ULWAL NAGAR	6781.8	Govt.	Open
9	AIRPORT	6044.6	Govt.	Open
	<b>Total</b>	<b>58339</b>		

**Table E.10E: Abstract of Land Required for Stations and Running Section**

LAND REQUIREMENT DETAIL B				
NAGPUR METRO RAIL PROJECT				
LAND DETAILS	EAST - WEST CORRIDOR PRAJAPATI NAGAR TO LOHMANYA NAGAR		NORTH - SOUTH CORRIDOR AUTOMATIVE SQUARE TO PRAPRI DEPOT	
	GOVT. LAND (IN SQM)	PVT. LAND (IN SQM)	GOVT. LAND (IN SQM)	PVT. LAND (IN SQM)
STATIONS ENTRY	3642.80	7769.40	7525.30	19812.30
RUNNING SECTION	3760.30	15801.80	40189.00	96261.00
DEPOT AREA	298973.80		338000.00	
TRAFFIC INTEGRATION/PARKING	8779.10	1485.70	63768.80	9179.20
<b>TOTAL</b>	<b>274662.20</b>	<b>14676.90</b>	<b>802167.10</b>	<b>30017.80</b>
<b>TOTAL GOVT LAND</b>	<b>778019.20</b>		<b>SAY 77.80 HECTARE S</b>	
<b>TOTAL PVT LAND</b>	<b>62935.90</b>		<b>SAY 6.3 HECTARE S</b>	



### 6.2.8 Land Staff quarters, office complex and operation control centre (OCC)

A large number of officers and staff will be recruited to be deployed permanently to take care of project implementation and post construction operational activities. Moreover metro office complex and metro operation control centre will also be required. It is proposed to keep the provision of **6.0 Ha** of government land for this purpose. Exact location of land has not been identified at this stage. It may be decided at the time of project implementation.

### 6.2.10 Temporary Construction Depot/office accommodation

During construction period, huge quantities of construction materials like reinforcing bars, cement, steel sections, shutters, pre-cast segments etc. are to be stored and sufficient land is required for storage of these materials. The areas may be identified based on availability as vacant or idle nearer to the corridors. At the time of construction, depending up on the need the location and size can be reassessed and temporary land acquisitions can be made accordingly.

Since the area of land being acquired permanently at most of the stations is bare minimum, the land required for construction depot purpose has been considered throughout the corridor @ 2ha: at every 10 km. These sites will be obtained on lease temporarily for the construction period. After completion of construction, these will be handed over back to the land owning agency. The location of these sites will be finalized with MET before the commencement of Tendering Work.

### 6.2.11 Segment Casting Yard

Large numbers of pre-cast segments are required for construction of elevated structures for which a large open area is required for setting up of casting yard. As far as possible, this area should be close to the site, easily accessible and away from habitation. Considering the various factors, it is proposed to set-up one yard for both the corridors. It is proposed to set-up two segment casting yards one for underground sections and another elevated sections. Provision of **6.0 Ha** of land for both the casting yards on temporary basis has been made.

## 6.9 UTILITY CROSSINGS

### 6.9.1 Introduction

Besides the details of various aspects e.g. transport demand analysis, route alignment, station locations, system design, viaduct structure, geo-technical investigations etc. as brought out in previous parts, there are a number of other engineering issues, which are



required to be considered in sufficient detail before finally deciding on taking up any Infrastructure project of such magnitude. Accordingly, following engineering items have been studied and described in this para:

- Existing underground and at surface utilities and planning for their diversion during construction, if necessary.

## 6.9.2 Utility and Services

The DMRC has collected details of various utilities through topography survey. Large number of sub-surface, surface and over head utility services viz. sewers, water mains, storm water drains, telephone cables, O/H electrical transmission lines, electric poles, traffic signals, etc. are existing along the proposed alignment. These utility services are essential and have to be maintained in working order during different stages of construction, by temporary/permanent diversions or by supporting in position. Since these may affect construction and project implementation time schedules/costs, for which necessary planning/action needs to be initiated in advance.

Organizations/Departments with concerned utility services in Nagpur are mentioned in Table 6.11.

Table 6.11: Utility Responsibility Departments

Sr. No.	ORGANIZATION/DEPARTMENT	UTILITY SERVICES
1.	Nagpur Municipal Corporation (NMC)	Roads, surface water drains, roads, Sewerage and drainage conduits, sewerage treatment plants, pumping stations, Water mains and their service lines, including hydrants, water treatment plants, pumping stations, Gardens etc.
2.	NI	Road construction & maintenance of State Highways Overall co-ordination among all concerned departments
3.	Water Works, Nagpur Municipal Corporation	Natohs/flood water drains etc.
4.	MSEDCL	Power cables and their appurtenances H.T. and L.T. lines, their pylons, electric sign posts, pole mounted transformers, etc.





Sl. No.	ORGANIZATION/DEPARTMENT	UTILITY SERVICES
5.	Bharat Sanchar Nigam Ltd. (BSNL)	Telecommunication cables, junction boxes, telephone posts, O.H lines, etc.
6.	Nagpur Traffic Police	Traffic signal posts, junction boxes and cable connections, etc.

Assessment of the type and location of underground utilities running along and across the proposed route alignment at Nagpur will be undertaken with the help of data available with concerned authorities, who generally maintain plans and data of such utility services. Particulars of main utilities i.e. town and main sewer/waterage conduits, water mains, O.H & UG Electric cables, Telecom cables etc. have been marked on alignment plans.

### 5.3.1 Diversion of Underground Utilities

While planning for diversion of underground utility services viz. sewer lines, water pipelines, cables, etc., during construction of MRTS alignment, following guidelines have been adopted:

- Utility services have to be kept operational during the entire construction period and after completion of project. All proposals should therefore, ensure their uninterrupted functioning.
- Sewer lines and water supply lines are mainly affected in underground cut and cover construction. These services are proposed to be maintained by temporarily replacing them with C/Dsteel pipelines and supporting them during construction. These will be encased in reinforced cement concrete after completion of construction and retained as permanent lines.
- Where permanent diversion of the affected utility is not found feasible, temporary diversion with C/Dsteel pipe without manholes is proposed during construction. After completion of construction, these will be replaced with conventional pipes and manholes.
- The elevated viaduct does not pose much of a difficulty in negotiating the underground utility services, especially those running across the alignment. The utilities infringing at plan location can be easily diverted away from the pier cap location.
- In case a major utility is running alongside the alignment which cannot be diverted or the diversion of which is difficult, time consuming and uneconomical, the spacing arrangement of the viaduct and layout of piers in the foundation may be suitably adjusted to ensure that no foundation needs be constructed at the location, where utility is crossing the proposed alignment. The utility service can also be encased within the foundation piers.

**6.2.4 Underground Stretch and Switch Over Ramp**

The underground section in both the corridor is for a length of approx 3 km. As indicated in the previous para due to various reasons, the entire length of underground section is proposed to be constructed with tunnelling keeping a minimum cover of about 5m above the tunnel, except at stations which will be constructed by cut and cover method. Hence, the utility services existing in above ground or below ground position are not likely to be affected in underground stretch of the alignment except at station locations. Details of such affected utility services at station locations are indicated in **Table 6.12 to Table 6.17**.

**6.2.5 Elevated stretch**

The stretch of both the corridors is elevated and is aligned in the center of the road except at few locations as detailed in the Alignment description.

**6.2.6 Sewer Lines, Storm Water Drains and Water Lines**

The sewer/water lines generally exist in the service areas i.e. away from main carriageway. However, in certain stretches, these fall near the central verge or under main carriageway, as a result of subsequent road widening. The major sewer/water lines and water mains running across the alignment and likely to be affected due to location of column foundations are proposed to be taken care of by relocating on column supports if valid by change in span or by suitably adjusting the layout of pile foundations. Where, this is not feasible, lines will be suitably diverted. Provision has been made in the project cost estimate towards diversion of utility service lines. Details of such utilities is given below.

**Table 6.12**  
**List of Affected Water Supply Lines North-South Corridor**

S. No.	Chainage	Dia (mm)	Description	Diversion Proposal
1	106.424	12	Alignment Crossing the Pipe Line	To be shifted/Diverted
2	644.370 to 2663	24	Alignment Crossing the Pipe Line	To be shifted/Diverted
3	1159.377	9	Alignment Crossing the Pipe Line	To be shifted/Diverted
4	1944.371	9	Alignment Crossing the Pipe Line	To be shifted/Diverted
5	2111.325	9	Alignment Crossing the Pipe Line	To be shifted/Diverted
6	1982.386	9	Alignment Crossing the Pipe Line	To be shifted/Diverted
7	2278.320	4	Alignment Crossing the Pipe Line	To be shifted/Diverted
8	2214.320	10	Alignment Crossing the Pipe Line	To be shifted/Diverted
9	2278.320	12	Alignment Crossing the Pipe Line	To be shifted/Diverted
10	2111.320	10	Alignment Crossing the Pipe Line	To be shifted/Diverted
11	3393 to 2108	24	Alignment Crossing the Pipe Line	To be shifted/Diverted
12	3287.7	20	Alignment Crossing the Pipe Line	To be shifted/Diverted



S. No.	Chainage	Oil (meters)	Description	Diversion Proposal
10	2017.0 to 2643.0	20	Aligned Crossing the Pipe Line	To be shifted. Obstructed
14	4100.0	20	Aligned Crossing the Pipe Line	To be shifted. Obstructed
16	4150.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
18	4400.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
17	4570.0 to 4641.0	20	Aligned Crossing the Pipe Line	To be shifted. Obstructed
18	4800 to 4710	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
19	5100.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
20	5100.0	21	Aligned Crossing the Pipe Line	To be shifted. Obstructed
21	5000 to 5100	21	Aligned Crossing the Pipe Line	To be shifted. Obstructed
22	5570.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
23	6000.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
24	6000.0	4	Aligned Crossing the Pipe Line	To be shifted. Obstructed
25	6200.4	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
26	6470.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
27	6140.0	4	Aligned Crossing the Pipe Line	To be shifted. Obstructed
28	6174.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
29	7170.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
30	7170.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
31	7600.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
32	7170.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
33	7600.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
34	7600.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
35	7040.0 to 7007.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
36	8100.0	20	Aligned Crossing the Pipe Line	To be shifted. Obstructed
37	8170.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
38	8170.0	20	Aligned Crossing the Pipe Line	To be shifted. Obstructed
39	8010.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
40	8100.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
41	8200.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
42	9200.0	4	Aligned Crossing the Pipe Line	To be shifted. Obstructed
43	9300.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed
44	9240.0	0	Aligned Crossing the Pipe Line	To be shifted. Obstructed
45	9300.0	10	Aligned Crossing the Pipe Line	To be shifted. Obstructed



S. No.	Challage	Oil (mm)	Description	Diversion Proposal
36	11307.2	28	Alignment Crossing the Pipe Line	To be shifted /Overlaid
37	11327.8	50	Alignment Crossing the Pipe Line	To be shifted /Overlaid
38	11333.3	27	Alignment Crossing the Pipe Line	To be shifted /Overlaid
39	11354.3	27	Alignment Crossing the Pipe Line	To be shifted /Overlaid
40	11942.5	12	Alignment Crossing the Pipe Line	To be shifted /Overlaid
41	11720.8	4	Alignment Crossing the Pipe Line	To be shifted /Overlaid
42	11555.8	19	Alignment Crossing the Pipe Line	To be shifted /Overlaid
43	12305.2	4	Alignment Crossing the Pipe Line	To be shifted /Overlaid
44	12723.4	9	Alignment Crossing the Pipe Line	To be shifted /Overlaid
45	12214.4	14	Alignment Crossing the Pipe Line	To be shifted /Overlaid
46	12254.7	10	Alignment Crossing the Pipe Line	To be shifted /Overlaid
47	12322.7 to 12234.8	50	Alignment Crossing the Pipe Line	To be shifted /Overlaid
48	13023.5	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid

**Table 5.10**  
List of Affected Water Supply Lines on East West Corridor

S.No.	Challage	Oil (mm)	Description	Diversion Proposal
1	220.7	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
2	225.7	28	Alignment Crossing the Pipe Line	To be shifted /Overlaid
3	434.0	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
4	551.8	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
5	1098.3	28	Alignment Crossing the Pipe Line	To be shifted /Overlaid
6	1087.7	4	Alignment Crossing the Pipe Line	To be shifted /Overlaid
7	1122.1	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
8	1153.6	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
9	1425.3	12	Alignment Crossing the Pipe Line	To be shifted /Overlaid
10	1489.0	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
11	2462.8	12	Alignment Crossing the Pipe Line	To be shifted /Overlaid
12	2872.8	28	Alignment Crossing the Pipe Line	To be shifted /Overlaid
13	2925.4	28	Alignment Crossing the Pipe Line	To be shifted /Overlaid
14	2883.8	12	Alignment Crossing the Pipe Line	To be shifted /Overlaid
15	3520.7	18	Alignment Crossing the Pipe Line	To be shifted /Overlaid



S No.	Chainage	Dist	Description	Diversion Proposal
16	5002.0	16	Agreement Crossing the Pipe Line	To be shifted / Covered
17	5065.7	9	Agreement Crossing the Pipe Line	To be shifted / Covered
18	5192.1	9	Agreement Crossing the Pipe Line	To be shifted / Covered
19	4929.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
20	4930.1	18	Agreement Crossing the Pipe Line	To be shifted / Covered
21	4987.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
22	4112.7	9	Agreement Crossing the Pipe Line	To be shifted / Covered
23	4787.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
24	4491.3	4	Agreement Crossing the Pipe Line	To be shifted / Covered
25	4992.9	12	Agreement Crossing the Pipe Line	To be shifted / Covered
26	4928.9	4	Agreement Crossing the Pipe Line	To be shifted / Covered
27	6000.9	28	Agreement Crossing the Pipe Line	To be shifted / Covered
28	5921.4	9	Agreement Crossing the Pipe Line	To be shifted / Covered
29	6491.1	12	Agreement Crossing the Pipe Line	To be shifted / Covered
30	5917.9	12	Agreement Crossing the Pipe Line	To be shifted / Covered
31	6768.9	7	Agreement Crossing the Pipe Line	To be shifted / Covered
32	5701.7 to 5819.2	24	Agreement Crossing the Pipe Line	To be shifted / Covered
33	6980.1	18	Agreement Crossing the Pipe Line	To be shifted / Covered
34	6987.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
35	6992.3	18	Agreement Crossing the Pipe Line	To be shifted / Covered
36	6996.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
37	6994.9 to 6996.9	11, 12 & 9	Agreement Crossing the Pipe Line	To be shifted / Covered
38	6934.9 to 6994.1	9	Agreement Crossing the Pipe Line	To be shifted / Covered
39	6933.9	4	Agreement Crossing the Pipe Line	To be shifted / Covered
40	6994.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
41	7079.5 to 7084.7	17 & 9	Agreement Crossing the Pipe Line	To be shifted / Covered
42	6711.2	9	Agreement Crossing the Pipe Line	To be shifted / Covered
43	6760.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
44	7100 to 7108	12 & 12	Agreement Crossing the Pipe Line	To be shifted / Covered
45	6764.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
46	6284.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
47	6996.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
48	6912.9	9	Agreement Crossing the Pipe Line	To be shifted / Covered
49	7079.9 to 7080.9	28 & 28	Agreement Crossing the Pipe Line	To be shifted / Covered



S.No.	Chainage	Dist	Description	Diversion Proposal
30	11290.2	28	Alignment Crossing the Pipe Line	To be shifted /Overlaid
31	11457.2	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
32	11766.2	10	Alignment Crossing the Pipe Line	To be shifted /Overlaid
33	12051.8	27	Alignment Crossing the Pipe Line	To be shifted /Overlaid
34	12423.7	27	Alignment Crossing the Pipe Line	To be shifted /Overlaid
35	13324.3	4	Alignment Crossing the Pipe Line	To be shifted /Overlaid
36	13822.5	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
37	14372.7	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid
38	14399.6	12	Alignment Crossing the Pipe Line	To be shifted /Overlaid
39	14973.9	8	Alignment Crossing the Pipe Line	To be shifted /Overlaid

Table 6.14: List of Affected H.T. Line on North – South Corridor

S.No.	Chainage (m)	Description	Diversion Proposal	Remarks
1	577.204	H.T. Line	To be shifted /Overlaid	Across the alignment
2	1085.000	H.T. Line	To be shifted /Overlaid	Across the alignment
3	1807.178	H.T. Line	To be shifted /Overlaid	Across the alignment
4	3445.124	H.T. Line	To be shifted /Overlaid	Across the alignment
5	5772.676	H.T. Line	To be shifted /Overlaid	Across the alignment
6	5581.203 to 6723.176	H.T. Line	To be shifted /Overlaid	Along the alignment
7	8143.048	H.T. Line	To be shifted /Overlaid	Across the alignment
8	8813.578	H.T. Line	To be shifted /Overlaid	Across the alignment
9	9178.938	H.T. Line	To be shifted /Overlaid	Across the alignment
10	9888.166	H.T. Line	To be shifted /Overlaid	Across the alignment
11	10115.290	H.T. Line	To be shifted /Overlaid	Across the alignment
12	10285.676	H.T. Line	To be shifted /Overlaid	Across the alignment
13	10885.580	H.T. Line	To be shifted /Overlaid	Across the alignment
14	11642.200	H.T. Line	To be shifted /Overlaid	Across the alignment
15	13118.089	H.T. Line	To be shifted /Overlaid	Across the alignment
16	17123.420	H.T. Line	To be shifted /Overlaid	Across the alignment
17	17428.600	H.T. Line	To be shifted /Overlaid	Across the alignment
18	17495.087	H.T. Line	To be shifted /Overlaid	Across the alignment
19	17864.382	H.T. Line	To be shifted /Overlaid	Across the alignment



S. No.	Chaining (m)	Description	Diversion Proposal	Remarks
20	1130.414	H.T. Line	To be shifted (Overhead)	Across the alignment
21	1180.648	H.T. Line	To be shifted (Overhead)	Across the alignment
22	1230.881	H.T. Line	To be shifted (Overhead)	Across the alignment
23	1280.860	H.T. Line	To be shifted (Overhead)	Across the alignment
24	1330.891	H.T. Line	To be shifted (Overhead)	Across the alignment
25	1380.126	H.T. Line	To be shifted (Overhead)	Across the alignment
26	2080.072	H.T. Line	To be shifted (Overhead)	Across the alignment

Table 5.16: List of Affected H.T. Poles on North – South Corridor

S. No.	Chaining (m)	Description	Nos.	Remarks
1	812.188	H.T. Line pole	1	To be shifted (Overhead)
2	818.888	H.T. Line pole	1	To be shifted (Overhead)
3	825.223	H.T. Line pole	1	To be shifted (Overhead)
4	822.287	H.T. Line pole	1	To be shifted (Overhead)
5	838.221	H.T. Line pole	1	To be shifted (Overhead)
6	848.221	H.T. Line pole	1	To be shifted (Overhead)
7	1210.142	H.T. Line pole	2	To be shifted (Overhead)
8	1220.122	H.T. Line pole	1	To be shifted (Overhead)
TOTAL			8	

Table 5.16: List of Affected H.T. Line East West Corridor

S. No.	Chaining (m)	Description	Diversion Proposal	Remarks
1	8194.716 to 8881.022	H.T. Line	To be shifted (Overhead)	Along the alignment
2	8055.474	H.T. Line	To be shifted (Overhead)	Across the alignment
3	8118.085	H.T. Line	To be shifted (Overhead)	Across the alignment
4	8442.292	H.T. Line	To be shifted (Overhead)	Across the alignment
5	8861.042	H.T. Line	To be shifted (Overhead)	Across the alignment
6	8917.226	H.T. Line	To be shifted (Overhead)	Across the alignment
7	9228.242	H.T. Line	To be shifted (Overhead)	Across the alignment
8	8815.888	H.T. Line	To be shifted (Overhead)	Across the alignment
9	1281.021	H.T. Line	To be shifted (Overhead)	Across the alignment



S.No.	Chainage (m)	Description	Diversion Proposal	Remarks
10	1201.523	H.T. Line	To be shifted (Overhead)	Across the alignment
11	1247.307	H.T. Line	To be shifted (Overhead)	Across the alignment
12	1281.431	H.T. Line	To be shifted (Overhead)	Across the alignment
13	1317.588	H.T. Line	To be shifted (Overhead)	Across the alignment
14	1355.525	H.T. Line	To be shifted (Overhead)	Across the alignment
15	1394.023	H.T. Line	To be shifted (Overhead)	Across the alignment
16	1432.018	H.T. Line	To be shifted (Overhead)	Across the alignment
17	1470.191	H.T. Line	To be shifted (Overhead)	Across the alignment
18	1508.371	H.T. Line	To be shifted (Overhead)	Across the alignment
19	1546.542	H.T. Line	To be shifted (Overhead)	Across the alignment
20	1584.721	H.T. Line	To be shifted (Overhead)	Across the alignment
21	1622.902	H.T. Line	To be shifted (Overhead)	Across the alignment
22	1661.088	H.T. Line	To be shifted (Overhead)	Across the alignment
23	1699.267	H.T. Line	To be shifted (Overhead)	Across the alignment
24	1737.442	H.T. Line	To be shifted (Overhead)	Across the alignment

Table 6.17: List of Affected H.T. Line Poles East West Corridor


S.No.	Chainage (m)	Description	BCs	Remarks
1	674.124	H.T. Line Pole	1	To be shifted (Overhead)
2	1628.077	H.T. Line Pole	1	To be shifted (Overhead)
3	4720.886	H.T. Line Pole	7	To be shifted (Overhead)
4	5280.073	H.T. Line Pole	7	To be shifted (Overhead)
5	7381.220	H.T. Line Pole	7	To be shifted (Overhead)
6	11261.324	H.T. Line Pole	3	To be shifted (Overhead)
7	11728.848	H.T. Line Pole	4	To be shifted (Overhead)
TOTAL			32	To be shifted (Overhead)

Apart from this some other ground utilities, interfering with the proposed alignments, namely street light poles, traffic signal posts, telecommunication posts, junction boxes, etc. are also required to be shifted and relocated suitably during construction of elevated viaduct.






Figure 5.1









**QUESTION 107**

1) In the following diagram, the loading and supports of a beam are shown. To obtain the shear force and bending moment diagrams, the beam is divided into segments. The segments are shown in the diagram.

2) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

3) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

4) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

5) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

6) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

7) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

**ANSWER 107**

1) The beam is divided into segments. The segments are shown in the diagram.

2) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

3) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

4) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

5) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

6) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

7) The shear force and bending moment diagrams are shown in the diagram. The shear force diagram is a horizontal line at zero, and the bending moment diagram is a straight line with a slope of 1. The maximum bending moment is 10 kNm.

QUESTION NO.	ANSWER	MARKS
107		

**ENCLOSURE**

APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

REVISIONS:

NO.	DESCRIPTION	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		







**QUESTION**

1. The oil well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F.

2. The oil well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F.

3. The oil well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F.


**ANSWER**

1. The oil well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F.

2. The oil well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F.

3. The oil well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F. The well is being worked by a pumpjack with a stroke of 100 inches. The temperature of the oil is 100°F.

DATE	
TIME	
MARKS	
REMARKS	
APPROVED BY	
SIGNATURE	
DATE	














Figure 5.10













### MUSCLE PROFILE



ALGORITHM: ALGORITHMIC APPROX TO BULK


SOIL LEVEL PROFILE



ALIGNMENT ALGORITHM APPLIED TO PROFILE




### SUB-SOIL PROFILE




ALIGNMENT - AUTOMOTIVE SQUARE TO BH-11

# SUB-SOIL PROFILE




**ALIGNMENT - AUTOMOTIVE SQUARE TO MESH**

# SURF-ROB. PROFILE




**ALIGNMENT - AUTOMOTIVE SQUARE TO BEHOLD**

### SUB-SOIL PROFILE




ALIGNMENT - NOT NECESSARILY SQUARE TO ROAD

## SUB-SOIL PROFILE




**ALIGNMENT - AUTOMATIC SQUARE TO RIGHT**

## SUB-SOIL PROFILE




ALIGNMENT - AUTOMOTIVE SQUARE TO BEHAN

### SUB-SOIL PROFILE



ALIGNMENT - LOHMANYA NAGAR TO PRALAPATI NAGAR


## SUB-SOIL PROFILE



ALIGNMENT - LOHMANYA NAGAR TO PRALAPATI NAGAR




## SUB-SOIL PROFILE




ALIGNMENT - LOHMANYA NAGAR TO PRAJAPATI NAGAR

# SUB-SOIL PROFILE




ALIGNMENT - LOHMANYA NAGAR TO PRALAPATI NAGAR

## SUD-SOIL PROFILE




ALIGNMENT - LOHMANYA NAGAR TO PRALAPATI NAGAR

## SUB-SOIL PROFILE




ALIGNMENT - LOHMANYA NAGAR TO PRALAPATI NAGAR

### BIBRUCHA PROFILE



**ALIGNMENT - LOKMANYA NAGRE TO PRAJAPATI NAGAR**

**SUB-SOIL PROFILE**



**ALIGNMENT - LOWWAY/VA-266 TO DELAWARE A-504 E**

# CHAPTER 6

## STATION PLANNING



6.1	GENERAL
6.2	STATION PLANNING
6.3	PLANNING AND DESIGN CRITERIA FOR STATIONS
6.4	TYPICAL STATION
6.5	PASSENGER AMENITIES

### TABLES

TABLE 6.1	STATION LOCATION CRITERIA/STRICTLY
TABLE 6.2	STATION AC COMPOSITION
TABLE 6.3	PASSENGER TRAFFIC AND PROVISION OF AMENITIES IN STATION (PROJECTIONS FOR YEAR 2041)

### FIGURES

FIGURE 6.1	STP CONDITIONS	AUTOMOTIVE SQUARE
FIGURE 6.2	STP CONDITIONS	SAHARA
FIGURE 6.3	STP CONDITIONS	INDIRA CHOWK
FIGURE 6.4	STP CONDITIONS	RAJENDRA CHOWK
FIGURE 6.5	STP CONDITIONS	GAZI GHANM SQUARE
FIGURE 6.6	STP CONDITIONS	EAST BOKHARI PANA
FIGURE 6.7	STP CONDITIONS	2ND MILE
FIGURE 6.8	STP CONDITIONS	STATION (INTERCHANGE)
FIGURE 6.9	STP CONDITIONS	CONGRESS SQUARE
FIGURE 6.10	STP CONDITIONS	RAJASTHANI COLONY
FIGURE 6.11	STP CONDITIONS	AGRI SQUARE STATION
FIGURE 6.12	STP CONDITIONS	FRANCE BAZI SQUARE
FIGURE 6.13	STP CONDITIONS	DEHRADUN SQUARE
FIGURE 6.14	STP CONDITIONS	IBRAHIM KHAN
FIGURE 6.15	STP CONDITIONS	JOHN ROAD
FIGURE 6.16	STP CONDITIONS	NEW MARKET
FIGURE 6.17	STP CONDITIONS	CHANDI
FIGURE 6.18	STP CONDITIONS	PRAGATI SQUARE
FIGURE 6.19	STP CONDITIONS	PAKISTANI (1ST) CROSS
FIGURE 6.20	STP CONDITIONS	AMBROSE CHOWK
FIGURE 6.21	STP CONDITIONS	TELEPHONE EXCHANGE
FIGURE 6.22	STP CONDITIONS	CHITRAUTI CROSS
FIGURE 6.23	STP CONDITIONS	AGARSI CHOWK
FIGURE 6.24	STP CONDITIONS	AGARSI CHOWK
FIGURE 6.25	STP CONDITIONS	NATIONAL STATION
FIGURE 6.26	STP CONDITIONS	STATION (STATION/CHANGE)
FIGURE 6.27	STP CONDITIONS	INDIA RAIL STATION
FIGURE 6.28	STP CONDITIONS	INSTITUTE OF ENGINEERS
FIGURE 6.29	STP CONDITIONS	SHAKAR SQUARE SQUARE

FEKRE 4.22 OTT CONSTITUAS SACNA BINC 2045 JN  
FEKRE 4.24 OTT CONSTITUAS PASOPI NALOR  
FEKRE 4.25 OTT CONSTITUAS SANSI WAKAR  
FEKRE 4.26 OTT CONSTITUAS LONNARTA BALAP





## Chapter - 6

### STATION PLANNING

#### 6.1 General

The proposed metro for Nagpur consists of two corridors namely:

1. North-South Corridor: Automotive Square to Khazari
2. East-West Corridor: Prapatti Nagar to Lokmanya Nagar

The length of the proposed N-S corridor is 19.658km and that of E-W corridor is 12.577km. In and to and. Along the proposed North-South corridor 17 stations have been planned. 10 stations have been planned along the East-West corridor. The locations of the station have been identified taking into consideration the constraints in land acquisition and congestion issues. Stations are proposed in such a way as to attract maximum demand from the traffic nodal points.





## 6.2 Station Planning

### 6.2.1 Stations

Line - 1 starts at Administrative square and runs southwards on NH-7 through Nari Road, Indora Chowk, Gaddi Garden Square, Kashiwanth Park, Zero Mile, Sitaburi, Congress Nagar, Rohini colony, Aji Sqn. Station, Chhatrapati Sqn. Station, Jayprakash Nagar, Airport, New Knowledge Khord Station. The Corridor is partly elevated and partly at grade.

Total Length of the corridor is 15.025 Km. of which approximately 15.025 is elevated and 4.5 km. is at Grade. There are 17 stations on the corridor of which 15 stations are elevated and 2 stations are at Grade. Sitaburi Station is an Interchange station.

Line -3 starts at Prayagraj Nagar and runs through Vaidhrodevi Chowk, Anbadkar Chowk, Telephone Exchange, Chitar Di Chowk, Agastya Chowk, Doodh Vaisya Chowk, Nagpur Railway Station, Sitaburi, Jhansi Rani Square, Institute of Engineers, Shankar Nagar Square, Lal Chowk, Dharampeth College, Subhash Nagar, Rachna (Ring road Junction), Vasudev Nagar, Bansi Nagar to Lomanya Nagar. The entire corridor is elevated.

The total length of the corridor is 18.037 kilometer. There are 13 stations on this corridor. All stations are elevated stations and Sitaburi station is an interchange Station.

### 6.2.2 Rail Levels and Alignment

In underground sections, the rail level is about 11.00 m below the ground level governed by a ground clearance of 2 m. and a station box of about 10 m depth. In the elevated section, rail level is generally about 12.00 m above ground in order to maintain a clearance of 5.00 m between the road and the station structure. In order to keep the land acquisition to minimum, alignment is planned generally in middle of the road and a two-level station design has been proposed in both elevated and underground sections. Entry/exit structures in the proposed stations and traffic integration areas have been planned in the open space available.

### 6.2.3 Platforms

In the elevated section, stations have also been planned with side platforms to avoid the viaduct structure from flaring in and out at stations, which obstructs the road traffic below. Care has been taken to locate stations on straight alignment. However, in some stations, site constraints have become the deciding criteria and a curve of 1000 meter radius has been introduced.



## 6.2.4 Sequence of Stations

The sequence of stations along with their respective charges, site and platform characteristics are presented in the Table 6.1.

**Table 6.1**  
**STATION LOCATION CHARACTERISTICS**

Name of Station	Charge (in m)	Distance from previous station (in m)	Rail level (in m)	Platform type	Alignment
<b>Line -I (North-South Corridor) Automotive Square to MINAH Depot</b>					
Start End	436.2				
1. AUTOMOTIVE SQUARE	0.0	436.2	303.000	Side	
2. NARI ROAD	675.8	875.8	308.000	Side	Graded
3. INDIRA CHOWK	2193.7	1933.9	314.100	Side	Graded
4. KASHI CHOWK	3381.2	3541.5	318.400	Side	Graded
5. GANDI BODHIM SQUARE	4399.0	5217.8	323.200	Side	Graded
6. KASTURBAHAI PARK	5148.6	740.8	328.300	Side	Graded
7. ZEPHORUS	6175.3	1020.3	315.000	Side	Graded
8. SITABURDI	6776.2	633.7	310.000	Side	Graded
9. CONGRESS NAGAR	7307.2	1988.0	317.000	Side	Graded
10. RUMATE COLONY	8002.6	705.4	321.300	Side	Graded
11. ALHABAD	9134.7	1422.1	315.300	Side	Graded
12. CHATRAPATI SOLAPUR	11148.3	1913.6	319.500	Side	Graded
13. JAYAKRISHNAN NAGAR	11811.5	663.2	320.000	Side	Graded
14. LAXMI NAGAR	12846.9	1035.4	311.000	Side	Graded
15. AIRPORT	13784.9	938.0	313.000	Side	Graded
16. NEW AIRPORT	16184.4	2399.5	298.000	Side	Ac-Crete
17. KANHE	16402.6	2218.2	308.750	Side	Ac-Crete
End End	10202.0	705.4			



Name of Station	Chainage (in m)	Distance from previous station (in m)	Rail level (in m)	Platform type	Alignment
<b>Line-2 (East-West Corridor) Prajeesh Nagar to Lokmanya Nagar</b>					
Start End	000.0				
1 Prajeesh Nagar	9.0	90.0	201.0	Side	Elevated
2 Vishnu Devi Chowk	120.0	120.0	200.0	Side	Elevated
3 Ambedkar Chowk	154.0	114.0	200.0	Side	Elevated
4 Telephone Exchange	210.0	116.0	211.0	Side	Elevated
5 Chitra Devi Chowk	290.0	90.0	211.0	Side	Elevated
6 Agrasen Chowk	400.0	110.0	210.0	Side	Elevated
7 Daxi Vaidya Chowk	500.0	100.0	207.0	Side	Elevated
8 Napsa Railway Station	600.0	100.0	207.0	Side	Elevated
9 Sitapur (Interchange)	700.0	100.0	207.0	Side	Elevated
10 Jhansi Ran Square	800.0	100.0	210.0	Side	Elevated
11 Institute Of Engineers	910.0	110.0	210.0	Side	Elevated
12 Ghansar Nagar Square	1000.0	90.0	210.0	Side	Elevated
13 Lal Chowk	1080.0	80.0	210.0	Side	Elevated
14 Drampath College	1200.0	120.0	209.0	Side	Elevated
15 Subhash Nagar	1280.0	80.0	208.0	Side	Elevated
16 Karmal Ring Road, Jh.	1400.0	120.0	208.0	Side	Elevated
17 Vasdev Nagar	1510.0	110.0	207.0	Side	Elevated
18 Sona Nagar	1610.0	100.0	207.0	Side	Elevated
19 Lokmanya Nagar	1700.0	90.0	207.0	Side	Elevated
Distance	1800.0	100.0			

#### 6.2 Planning and Design Criteria for Stations

- The stations can be divided into public and non-public areas (the areas where access is restricted). The public areas can be further subdivided into paid and unpaid areas.
- The platform level has adequate assembly space for passengers for both normal operating conditions and a recognized abnormal scenario.



3. The platform level at elevated stations is determined by a critical clearance of 3.5-m under the concourse above the road intersection, allowing 3.0-m for the concourse height, about 1-m for concourse floor and 2.2-m for structure of tracks above the concourse. Further, the platforms are 1.00-m above the tracks. This would make the clearance at an elevated station at least 13.4-m above ground.
4. The concourse contains automatic fare collection system in a manner that divides the concourse into distinct areas. The 'unpaid area' is where passengers gain access to the system, obtain travel information and purchase tickets. On passing through the ticket gates, the passenger enters the 'paid area', which includes access to the platforms.
5. The arrangement of the concourse is assessed on a station-by-station basis and is determined by site constraints and passenger access requirements. However, it is proposed in such a way that maximum surveillance can be achieved by the local rail supervisor over ticket machines, automatic fare collection (AFC) gates, stairs and escalators. Ticket machines and AFC gates are positioned to minimise cross flows of passenger and provide adequate circulation space.
6. Sufficient space for queuing and passenger flow has been allowed at the ticketing gates.
7. Station entrances are located with particular reference to passenger convenient points and physical site constraints within the right-of-way allocated to the MRTS.
8. Office accommodation, operational areas and plant room spaces is required in the non-public areas at each station. The functions of such areas are given below in Table 6.2.
9. The CO set, bore well pump houses and ground tank would be located generally in one side on ground.
10. The system is being designed to maximise its attraction to potential passengers and the following criteria have been observed:
  - Minimum distance of travel to and from the platform and between platforms for transfer between lines.
  - Adequate capacity for passenger movements.
  - Convenience, including good signage relating to circulation and orientation.
  - Safety and security, including a high level of protection against accidents.
11. Following requirements have been taken into account:
  - Minimum capital cost is incurred consistent with maximising passenger attraction.
  - Minimum operating costs are incurred consistent with maintaining efficiency and the safety of passengers.



- Flexibility of operation including the ability to adapt to different traffic conditions changes in fare collection methods and provision for the continuity of operation during any extended maintenance, strike period, etc.
  - Provision of good visibility of platforms, fare collection zones and other areas, thus aiding the supervision of operations and monitoring of efficiency and safety.
  - Provision of display of passenger information and advertising.
13. The numbers and class of stairs/elevators are determined by checking the capacity against AM and PM peak flow rates for both normal and emergency conditions such as delayed train service, fire etc.
14. In order to transfer passengers efficiently from street to platforms and vice versa, station planning has been based on established principles of pedestrian flow and arranged to minimise unnecessary walking distances and cross-flows between incoming and outgoing passengers.
15. Passenger handling facilities comprise of stairs/elevators, lifts and ticket gates required to process the peak traffic from street to platform and vice-versa. These facilities must also enable evacuation of the station under emergency conditions, within a set safe time limit.

## 6.6 Typical Station

### 6.6.1 Typical Elevated Station

The station is generally located on the road median. Total length of the station is ~160m. All the stations are two-level stations. The concourse is planned along the whole length of the platform with staircases leading from either side of the road. The maximum width of the station at concourse is ~32m. Passenger facilities like ticketing, information, etc as well as operational areas are provided at the concourse level.

Typically, the concourse is divided into public and non-public zones. The non-public zone or the restricted zone contains station operational areas such as Station Control Room, Station Master's Office, Waiting Room, Meeting Room, UPS & Battery Room, Signaling Room, Train Crew Room & Supervisor's Office, Security Room, Station Store Room, Staff Toilets, etc. The public zone is further divided into paid and unpaid areas. Auxiliary Service station is provided on the ground under the entry/exit structure.

Since the station is in the middle of the road, minimum vertical clearance of 5.5-m has been provided under the concourse. Platforms are at a level of about 14.5m from the road. To reduce physical and visual impact of the elevated station, stations have been designed as cantilevered structures with single column located at the central verge of the road.

With respect to its spatial quality, an elevated Metro structure makes a great impact on the viewer as compared to an At-grade station. The positive dimension of this impact



has been accentuated to enhance the accessibility of an elevated station and the above ground section of tracks. Structures that afford maximum transparency and are light looking have been envisaged. A slim and ultra-modern concrete form is proposed, as they would look both compatible and modern high-rise environment as well as the lesser-built, low-rise developments along some parts of the corridor.

Platform roofs, that can invariably make a structure look heavy, have been proposed to be of steel frame with aluminium cladding to achieve a light look. Platforms would be protected from the heat and rain by providing an overhang of the roof and sidewalks are avoided, thereby enhancing the transparent character of the station building. In order to allow unimpeded traffic movement below the stations, the station structure is supported on a single column, which lies unobtrusively on the central verge.

#### 6.4.1 Typical At-Grade Station

#### 6.4.2 Typical Interchange Station

The Stadium Station is located at the intersection of the Line-1 and Line-2 of the Nagpur Metro System. The station has an interchange type configuration, and more passengers will change from one line to the other. This interchange will provide great utility and flexibility for the system as a whole, and it will recreate the time required for travel within the city.

The easternmost Line-1 Station is Prajada Nagar, and the line extends westward through Stadium to Loknarya Nagar. Line-2 has its northernmost station at Automotive Square, and it connects locations toward the south through the Zam Milla, Stadium, Air Gate, the Airport, and the frothy Khazri Station.

Passengers traveling on both lines have the option to change their direction of travel at Stadium, thus requiring larger concourses and platforms in the station for pedestrian movements. In addition to providing interchange connections between Line-1 and Line-2, the station accommodates a busy area of the city next to the Stadium, which will generate large numbers of passengers during special events.

The station is composed of a Concourse Level 8.83 meters above the ground. Above the Concourse is the Line-1 Platform at an elevation of 9.5 meters, and Line-2 Platform passes over Line-1 at the height of 23.5 meters.

Passengers entering Stadium Station may go directly to either Line-1 or Line-2 platform from which they may board a train in any of four directions.

Passengers entering the station on a train on either Line-1 or Line-2 may transfer between lines in a direct manner by means of converted escalators and stairs that lead to trains in the other three directions.



Table 6.2  
STATION ACCOMMODATION

For Elevated and at-grade Stations	
1. Station Control Room	2. Cleaner's Room
2. Station Master's Office	4. Security Room
5. Information & Enquiries	5. First Aid Room
7. Ticket Office	8. Miscellaneous Operations Room
8. Ticket Hat Supervisor & Excess Fare Collection (Passenger Office)	10. Platform Supervisor's Booth
11. Cash and Ticket Room	12. Auxiliary Substation / DG Room
13. Staff Area	14. Fire Talk and Pump Room
15. Staff Toilet	16. Commercial Outlets and Kiosk
17. Station Store Room	18. UPS and Battery Room
19. Refuse Store	20. Signaling / Communication Room

## 6.5 Passenger Amenities

Passenger amenities such as ticketing counters/automatic ticket vending machines, ticketing gates, etc. are provided in the concourse. Uniform numbers of these facilities have been provided for system wide uniformity, although the requirement of the facilities actually varies from station to station. The same applies to provision of platform widths and stairs/elevators. Maximum capacity required at any station by the year 2031 for emergency operation has been adopted for all stations.

For this purpose, *peak minute traffic* is assumed to be 2% of the *peak hour traffic*. For checking the adequacy of platform area, stair widths and requirement additional of emergency evacuation stairs, a maximum accumulation of passengers in the station has been considered to be comprising waiting passengers at the platform (including two missed headways) and carload expected to be evacuated at the station in case of an emergency.

### 6.5.1 Concourse

Concourse forms the interface between street and platforms. In elevated stations, this is contained along the full length of the station. This is where all the passenger amenities are provided. The concourse contains automatic fare collection system in a manner that divides the concourse into *ticket gate* and *platform* areas. The *ticket gate* is where passengers gain access to the system, obtain travel information and purchase tickets. On passing through the ticket gates, the passenger enters the *platform area*, which includes access to the platforms.





The concourse is planned in such a way that maximum surveillance can be achieved by the ticket hall supervisor over ticket machines, automatic fare collection (AFC) gates, stairs and escalators. Ticket machines and AFC gates are positioned to minimise cross flows of passengers and provide adequate circulation space. Sufficient space for queuing one passenger flow has been allowed in front of the AFCs.

### 6.6.2 Ticketing Gates

Ticketing gates requirement has been calculated using the gate capacity as 45 persons per minute per gate. Passenger forecast for the horizon year 2031 has been used to compute the maximum design capacity. At least two ticketing gates shall be provided at every station even if the design requirement is satisfied with only one gate. Uniform space has been provided in all stations where gates can be installed or not when required.

### 6.6.3 Ticket Counters and Ticket Issuing Machines (TIMs)

It is proposed to deploy manual ticket issuing in the beginning of the operation of the line. At a later stage, automatic TIMs would be used for which space provision has been made in the concourse. At present, ticket counters would be provided, which would be replaced with TIMs in future. Capacity of manual ticket vending counters is taken to be 10 passengers per minute and it is assumed that only 40% of the commuters would purchase tickets at the stations while performing the journey. The rest are expected to buy prepaid tickets or prepaid card, etc. Accordingly, the requirement of ticket counters has been calculated and the same provided for in the plans.

### 6.6.4 Platforms

A uniform platform width of 13 m wide is proposed for the island stations. In elevated stations, 3.5m wide side platforms have been proposed. In interchange station the platform width is kept as 5.0m in order to cater to a large number of interchanging passengers. These platform widths also have been checked for holding capacity of the platform for worst-case scenario.

### 6.6.5 Stairs, Escalators and Lifts

Provisions have been made for escalators in the paid area i.e. from concourse to platforms. On each platform, one escalator has been provided. In addition, two staircases with a combined width of 5 m are provided on each platform connecting to the concourse. These stairs and escalator together provide an egress capacity adequate to evacuate maximum accumulated passengers in emergency from platform to concourse in 5.5 minutes. Lifts have been provided one each on either platform, to provide access for elderly and disabled. Since the rise to road from the concourse is about 5m, it is proposed to provide escalators and lifts in addition to stairs for vertical movement of passengers from street to concourse.



### 6.5.8 Fire Fighting Measures

Fire fighting provisions for Elevated & at Grade metro stations is in accordance with the National Building Code of India 1983 part IV, Fire protection amendment no. 3 under Fire protection Annexure B.

National Building Code clause 6.4.81, Fire protection and fire fighting system for metro stations (sub-clause) :-

- 1) Wet riser system
  - a. Main and diesel pump of 1800 litre capacity to support 3 to 4 hydrant of a line (station building is split into two halves. It is presumed that fire will not break in the two parts simultaneously. There are 3 hydrants in one part. Therefore pump capacity as above are proposed)
  - b. Jetday pump 180 litre shall also have DG back up.
- 2) Internal Hydrant  
The internal hydrant is provided with 2 nos RRL hose pipes of 28 mm  $\phi$  with 40 mm standard instantaneous coupling along with associated branch pipe and cabinet and a first aid hose reel of 25 mm  $\phi$  length 45m fitted with 6.5 mm nozzle. One hydrant each at ground level, passage level and platform level in each half of the station building and so located that every part of station is within 30 m radius.
- 3) Sprinklers are provided in the property development area only. Additional sprinkler pump is not provided as these are not required being the integral part of the station. The two pumps already provided will take care of sprinkler flow requirements.
- 4) Detectors are provided in the operational areas only, and above false ceiling if the gap is  $\geq$  750 mm.
- 5) One manual cut fire at each level in each half of the station building is provided.
- 6) The HT panels, LT panels, main LT distribution board and essential power panels shall be provided with inlar heat sensing tubes with CO<sub>2</sub> cylinder.
- 7) A two way fire brigade inlet at ground level on each rising main for hydrants is provided.
- 8) Drow off connector is provided on the fire water line for fire engine.
- 9) Water tank of 10,000 litre capacity if permitted since commercial development is restricted to 250 Gpm.
- 10) Portable fire extinguishers (CO<sub>2</sub>) 4 set of fire is provided in each of the equipment room.



Summary of passenger amenities required and proposed at stations based on projected traffic for the year 2025 is given in the Table 6.3.

**TABLE 6.3**  
**PASSENGER TRAFFIC AND REQUIREMENT OF AMENITIES IN STATIONS**  
**(Projections for Year 2025)**

**Line-1: N-S corridor (Automotive Square to Khegri Station)**

Station	Peak hour traffic (Passengers/hr)	Stabling bays required on each side  C.B.C	No. of platforms required  No. of platform levels on the station	Escalators Proposed in Each Station		Provision of lifts at Each station	
				Up	Down		
1. Automotive Square	5274	2-2-2	2	1.00	2	2	2
2. New Road	7911	2-2-2	2	1.00	2	2	2
3. Janki Chowk	3833	2-2-2	2	1.00	2	2	2
4. Park Chowk	15210	2-2-2	2	1.00	2	2	2
5. Ganga Bazaar Station	15340	2-2-2	2	1.00	2	2	2
6. Waterbazaar Station	13334	2-2-2	2	1.00	2	2	2
7. New City	14072	2-2-2	2	1.00	2	2	2
8. Shivajinagar	15320	2-2-2	2	1.00	2	2	2
9. Congress Nagar	9477	2-2-2	2	1.00	2	2	2
10. Dattatreya Temple	7983	2-2-2	2	1.00	2	2	2
11. NITC Station	6095	2-2-2	2	1.00	2	2	2
12. Garibagh	5808	2-2-2	2	1.00	2	2	2
13. Dattatreya Nagar	5573	2-2-2	2	1.00	2	2	2
14. Shivajinagar	4024	2-2-2	2	1.00	2	2	2
15. New Road	4350	2-2-2	2	1.00	2	2	2
16. Shivajinagar	3963	2-2-2	2	1.00	2	2	2
17. Khegri Station		2-2-2	2	4.00	2	2	2

Note: 2x-2x2=two level

C: Twoage level

A: Platform

1=interchange station



Line-Z E-W corridor (Prayagraj Nagar to Lokmanya Nagar)

Station	Peak Hourly Demand (PHD)	Tubing Sums REQD/AC On each side C&C	TBM Supports	Station Length on each side	SACKING Provided to EACH SIDING		PROPORTION of L/S to E&T Gauges
					G.C.	S.B.	
1. Prayagraj Nagar	655	2-2-2	2	6.05	2	2	2
2. Subroto Park	1212	2-2-2	2	6.80	2	2	2
3. Indira Park	1525	2-2-2	2	6.80	2	2	2
4. Telephone Exchange	4600	2-2-2	2	6.80	2	2	2
5. Datta Choudhary	6150	2-2-2	2	6.80	2	2	2
6. Agartala Road	7586	2-2-2	2	6.80	2	2	2
7. Ganga Vihar Road	9257	2-2-2	2	6.80	2	2	2
8. Rajgarh Station	11822	2-2-2	2	6.80	2	2	2
9. Bahadur	12064	2-2-2	2	6.80	2	2	2
10. Bani Park Station	1642	4-2-4	3	6.80	2	2	2
11. Institute of Engineers	17126	2-2-2	2	6.80	2	2	2
12. Sakinaka Nagar Station	2114	2-2-2	2	6.80	2	2	2
13. Laxmi Chowk	2188	2-2-2	2	6.80	2	2	2
14. Shriyash College	2207	2-2-2	2	6.80	2	2	2
15. Sakinaka Nagar	2675	2-2-2	2	6.80	2	2	2
16. Ganga Ganga Road only	3335	2-2-2	2	6.80	2	2	2
17. Lokmanya Nagar	4156	2-2-2	2	6.80	2	2	2
18. Ganga Road	2346	2-2-2	2	6.80	2	2	2
19. Ganga College		2-2-2	2	6.80	2	2	2



Chapter 6: Station Planning  
Line -1 (N-S Corridor)

1. Automotive square

Clearance	: 0.00
Inter Station Distance	: First Station
Rail Level	: 13.11m
Station Type	: Elevated
Entry / Exits	: On both sides of road
Location	: The station is proposed on Rampas road
Catchment Area	: The main source of passengers to this station is the residents of surrounding residential colonies and the industrial areas in

Figure 3.1. Site Conditions- Automotive Square Station





## Chapter 6: Station Planning Line -1 (N-S Corridor)

### 2. Mari Road

Clearage	: 975.88M
Inter Station Distance	: 975.88M
Roll Level	: 12.52 m
Station type	: Elevated
Entry / Exits	: On both sides of road
Location	: The station is proposed on Kamptul road.
Catchment Area	: The main source of passengers to this station is the residents of Shree Nagar, PMS College, and other surrounding residential colonies.

Figure 6.2: Site Conditions- Mari Road Station





### 3. Indore Chowk

Chainage	: 21.85.720
Inter Station Distance	: 1922.93 m
Rail Level	: 12.85 m
Station type	: Mixed
Entry / Exit	: On both sides of road
Location	: The station is proposed on Kamptee road
Catchment Area	: The main source of passengers to this station is the residents of Indore Nagar, Jhansuaba, Kamal Square & surrounding residential colonies.

Figure 6.3 Site Conditions- Indore Chowk Station





## Chapter 6: Station Planning Line -1 (N-S Corridor)

### 4. Vadi Chowk

Clearage	1 3181.23 m
Inter Station Distance	1 1681.63 m
Roll Level	1 13.87 m
Station type	1 Elevated
Entry / Exits	1 On both sides of road
Location	1 The station is proposed on MH-44.
Catchment Area	1 The main source of passengers in this station is the residents of Clouton Nagar, Mohan Nagar, St. Michael School and the residents of the surrounding area.

Figure 6.4 Site Conditions- Vadi Chowk Station







**6. Daddi Godam Square**

Chainage	: 4395.00 m
Inter Station Distance	: 1217.00 m
Rail Level	: 12.00 m
Station type	: Elevated
Entry / Exit	: On both sides of road
Location	: The station is proposed on NH-44.
Catchment Area	: The main source of passengers to this station is the residents of Gudem Nagar, Daddi, and residents of surrounding areas.

Figure 6.6: Site Conditions- Daddi Godam Square Station





8. Kumbhachand Park

Clearage	: 3148.60 m
Inter Station Distance	: 793.60 m
Roll Level	: 12.30 m
Station type	: Elevated
Entry / Exits	: On both sides of road
Location	: The station is proposed on NH-44.
Catchment Area	: The main source of passengers to this station is the residents of surrounding areas and people working in NMC Office, Reserve Bank of India, and other Government Offices.

Figure 6.5: Site Conditions- Kumbhachand Park Station





### 7. Zero Mile

Chainage	: 0175.00 m
Intra Station Distance	: 125.00 m
Rail Level	: 13.30 m
Station type	: Elevated
Entry / Exit	: On both sides of road
Location	: The station is proposed on NH-44
Catchment Area	: The main source of passengers to this station is the residents of surrounding areas and people working in NMC office, Reserve Bank Of India, and other Government Offices.

Figure 6.7: Site Condition Zero Mile Station





## Chapter 6: Station Planning Line -1 (N-S Corridor)

### 8. Station:

Clearance	: 1815.83m
Inter Station Distance	: 333.73m
Roll Level	: 12.84M
Station type	: Elevated
Entry / Exits	: On both sides of road
Location	: The station is proposed on the crossing of NH-46 and State Highway No. 255
Colony Area	: The main source of passengers to this station is the residents of surrounding Commercial and residential areas, People visiting Stadium during special events, interchanging from EW Line to NG line.

Figure 6.8: Site Conditions: Station





### 6. Congress Nagar

Chainage	: 7607.20 m
Inter Station Distance	: 1166.00 m
Rail Level	: 12.00 m
Station type	: Elevated
Entry / Exit	: On both sides of road
Location	: The station is proposed on NH-44.
Catchment Area	: The main source of passenger's to this station is the residents of Congress Nagar and the residents of surrounding residential colonies.

Figure 6.6 Site Conditions- Congress Nagar Station





## Line -1 (N-S Corridor)

## 18. Rehabs Colony

Clearage	1	8882.60 m
Inter Station Distance	1	785.40 m
Rail Level	1	13.80 m
Station type	1	Elevated
Entry / Exits	1	On both sides of road
Location	1	The station is proposed on NH-44.
Catchment Area		The main source of passengers in this station is the residents of Rehabs Colony and the residents of surrounding residential areas.

Figure 6.10: Site Conditions- Rehabs Colony Station





## Line -1 (N-S Corridor)

## 11. Aji Square

<b>Chainage</b>	: 12106.7 m
<b>Inter Station Distance</b>	: 1422.1 m
<b>Rail Level</b>	: 13.064 m
<b>Station Type</b>	: Elevated
<b>Entry / Exit</b>	: On both sides of road
<b>Location</b>	: The station is proposed on NH-44 near NCCRI Institute and Central Jai Nagpur.
<b>Catchment Area</b>	: The main source of passengers to this station is the residents & Students of NCCRI, Modern School, and people visiting Central Jai Nagpur.

Figure E.11: Aji Square Station






## Line -1 (N-S Corridor)

## 12. CHHATRAPATI SQUARE

Clearage	: 11045.9 m
Inter Station Distance	: 1041.8 m
Rail Level	: 14.900 m
Station type	: Elevated
Entry / Exits	: On both sides of road
Location	: The station is proposed on NH-44
Catchment Area	: The main source of passengers to this station is the residents of Yashwantrao Chavan, Dnyanesh, Sankar Nagar and residents of surrounding areas.

Figure 6.12: CHHATRAPATI SQUARE STATION







## Line -1 (N-S Corridor)

## 11. JAFRAKASH NAGAR

Clearage	: 13011.5 m
Inter Station Distance	: 665.2 m
Rail Level	: 12.877m
Station type	: Elevated
Entry / Exits	: On both sides of road
Location	: The station is proposed on NH-44
Catchment Area	: The main source of passengers to the station is the residents of Behar Nagar and workers of surrounding industrial units.

Figure 6.12 JAFRAKASH NAGAR STATION





14. LUNAL NAQAR

Clearage	:	12646.6 m
Inter Station Distance	:	6036.5 m
Roll Level	:	12,300 m
Station type	:	Elevated
Entry / Exits	:	On both sides of road
Location	:	Fore-court of Nagpur Airport.
Catchment Area	:	The main source of passenger's to this station is the passenger and staff of present Airport of Nagpur.

Figure 6.14 LUNAL NAQAR STATION





Chapter 6: Station Planning  
Line -1 (N-S Corridor)

IS - Airport	:-
Chainage	:- 13754.0 m
Inter Station Distance	:- 535.3 m
Rail Level	:- 13.483 m
Station type	:- Elevated
Entry / Exits	:- On both sides of road.
Location	:- New Airport of Nagpur.

**Catchment Area**

The main source of passengers to this station is the Passengers and staff of the proposed New Airport of Nagpur.

Figure 6.10: Airport Station






**18. NEW AIRPORT**

Clearance	: 10 094.4 m
Inter-Station Distance	: 2300.0 m
Rail Level	: 2470 m
Station type	: Elevated
Entry / Exits	: On both sides of the road.
Location	: Central Avenue of MBMN City.
Catchment Area	: The main source of passengers to this station is the residents of Newly developing MBMN City and the people visiting MBMN Commercial/Industrial zone.

Figure 8.18: New Airport Station





**IT Akapri Station**

<b>Clearage</b>	: 21305.20 m
<b>Inter Station Distance</b>	: 1670.40 m
<b>Rail Level</b>	: 355.7 m
<b>Station type</b>	: Island : On both sides of road
<b>Location</b>	: Located on the outskirts of MARMAN city.
<b>Catchment Area</b>	: The main source of passengers to this station is the resorts of

Figure 6-17: Akapri Station





#### 1. Prajapati Nagar

Clearance	: 0.00 m
Inter Station Distance	: 392.00%
Red Level	: 12.34 m
Station type	: Elevated
Entry / Exit	: On both sides of the road.
Location	: The station is located on NH-6 across the railway line near Old Part Naka.
Catchment Area	: The station is proposed in the residential area of Romang Nagar, HD Town, Chandra Nagar, Ram Nagar, Surya Nagar & the residents of the surrounding colonies.

Figure 6.16: Site Conditions- Prajapati Nagar Station





## 2. Vesthoddevi Chowk

Clearage	: 1220.30 m
Inter Station Distance	: 1220.30 m
Rail Level	: 12.32 m
Station type	: Elevated
Entry / Exit	: On both sides of the road.
Location	: The station is located on NH46 on Vesthoddevi Chowk near old Bhandra road and Mahal Road.
Command Area	: Main source of passengers to the station is residents of the Haver Nagar, surrounding residential areas and industrial areas.

Figure 8.10: Site Conditions- Vesthoddevi Station





### 3. Ambedkar Chowk

Clearage	: 1947.50 m
Inter Station Distance	: 718.63 m
Rail Level	: 12.82 m
Station type	: Elevated
Entry / Exits	: On both sides of the road
Location	: The station is located on NH-6 near Dr. Shrinani Ambedkar Chowk.
Command Area	: The main source of passengers to this station is the residents of the Saransi Nagar, Shrinani Nagar, Haveli Nagar and the other surrounding areas.

Figure 6.20 Site Conditions-Ambedkar Chowk Station







#### 4. Telephone exchange

Clearance	: 31.5740 m
Inter Station Distance	: 1188.50 m
Rail Level	: 12.84 m
Station type	: Elevated
Entry / Exits	: On both sides of road.
Location	: The station is located on NH42 opposite Telephone exchange, Nagpur.
Colony/ Area	: The main source of passengers to this station is the residents of Mangal Wadi, Siongi Pura, Jagruti Square and surrounding residential & commercial areas.

Figure 6.21: Site Conditions- Telephone Exchange Station





8. Chitar Di Chowk (Bandy Police)

Clearance	: 3545.70 m
Inter Station Distance	: 812.33 m
Rail Level	: 12.35 m
Station type	: Elevated
Entry / Exits	: On both sides of road.
Location	: The station is located on NH4 near Chitar Di Chowk.
Catchment Area	: The main source of passengers to this station is the residents of Banderi Market, Shreebhav Square, nearby Apartments and the residents of the surrounding area.

Figure 6.22: Site Conditions- Chitar Di Chowk Station





### 8. Agrasen Chowk

Clearance	: 4759.20 m
Inter Station Distance	: 800.50 m
Rail Level	: 12.02 m
Station type	: Elevated
Entry / Exits	: On both sides of road.
Location	: The station is located on NH-6 near Agrasen Chowk.
Catchment Area	: The main source of passengers to this station is the residents of Garahi Road, Jaitpura, Hanuapuri, Bhaktapuri and the residents of the surrounding residential areas.

Figure 6.23: Site Conditions- Agrasen Chowk Station





### 7. Doser Veliye Chowk

Chainage	: 0611.00 m
Intra Station Distance	: 051.80 m
Rail Level	: 12.00 m
Station type	: Elevated
Entry / Exit	: On both sides of road.
Location	: The proposed station is located on NH-6 near Masjid Gorb Road.
Catchment Area	: The station is supposed to cater the people visiting the mosque, the Medical College hostel and the Orange Market and the residential areas located in the surroundings.

Figure 6.24. Site Conditions- Veliye Chowk Station





### 3. Nagpur Railway Station

Clearage	: 9464.40 m
Inter Station Distance	: 853.63 m
Rail Level	: 12.57 m
Station type	: Elevated
Entry / Exits	: On both sides of road.
Location	: The proposed station is located on the western side of the Nagpur Junction Railway station.
Contourment Area	: Nagpur Railway station is a very busy Junction Railway station of Western railway the proposed station will cater to the passengers using the Railway station to and from the Nagpur City.

Figure 6.25 Site Conditions- Nagpur Railway Station





## Line-1 &amp; Line-2 (Interchange station)

## 8. Staburi

Clearage	: 366.30 m
Inter-Station Distance	: 1243.30 m
Rail Level	: 22.20 m
Station type	: Elevated (Interchange station)
Entry / Exits	: On both sides of the road

**Location** : The station is located on the crossing of NH6 and NH44, in the area called Staburi.

**Catchment Area** : The main source of passengers to this station is the residents of surrounding Commercial and residential areas. People visiting Staburi during special events, interchanging from BSV Line to NG line.

Figure 8.26: Site Conditions- Staburi Station





18. Jheral Rail Over

Clearance	: 8300.70 m
Inter Station Distance	: 640.00 m
Rail Level	: 13.77 m
Station type	: Elevated
Entry / Exits	: On both sides of the road
Location	: The station is located on NH-44 in the institutional area having Hospitals and other institutes.
Colonnade Area	: The main source of passengers to this station is the residents of surrounding areas and people visiting Mahaveer station, Multi-Specialty Hospital and other Institutes & school in the surroundings.

Figure 6.27: Site Conditions Jheral Rail Over Station





#### 11. Institutions of Engineers

Chainage	: 9117.20 m
Inter Station Distance	: 763.60 m
Rail Level	: 12.58 m
Station type	: Elevated
Entry / Exit	On both sides of the road
Location	: The station is located on NH-44 near the Institutions of Engineers and Indian Medical Association.
Catchment Area	: The main source of passengers to this station is the people coming to Engineers of Engineers, Madia school and the residents of surrounding areas.

Figure 6.23: Site Conditions- Institutions of Engineers Station







12. Shikhar Nagar Square (E-W Corridor)

Chainage	: 10374.90 m
Inter Station Distance	: 967.70 m
Rail Level	: 12.86 m
Station type	: Elevated
Entry / Exits	: On both sides of the road
Location	: The proposed station is located near Sweetwater Sweets & Chalk.
Colony/ Area	: The main source of passengers to this station is the residents of Ram Nagar, Basu Nagar, Gokulnagar and residents of surrounding colonies.

Figure 6.28- Site Conditions- Shikhar Nagar Square Station





### 10. Lad Chowk

Chainage	: 10872.12 m
Inter Station Distance	: 796.23 m
Rail Level	: 12.01 m
Station type	: Elevated
Entry / Exit	: On both sides of the road
Location	: The station is located on NH-44 near Lad Chowk crossing.
Catchment Area	: The main source of passengers to this station is the residents of Aohyandee Nagar, Lad Nagar, Gendy Nagar and the colonies in the surrounding areas.

Figure 6.38: Site Conditions- Lad Chowk Station





14. Dharampeth College

Chainage	: 1209.70 m
Inter Station Distance	: 1147.60 m
Rail Level	: 13.20 m
Station type	: Elevated
Entry / Exits	: On both sides of the road
Location	: The station is located on NH-44 near Ambazari Lake.
Catchment Area	: The main source of passengers to this station are the students of Dharampeth college, the residents of Ambazari layout and surrounding colonies.

Figure 6.21: Site Conditions- Dharampeth College Station





18. Subhash Nagar

Clearance	: 12947.10 m
Inter Station Distance	: 905.43 m
Roll Level	: 12.54 m
Station type	: Elevated
Entry / Exits	: On both sides of the road
Location	: The station is located on NH-44 near CRPF Camp and Subhash Nagar.
Command Area	: The main source of passengers to this station is the residents of Subhash Nagar. Paved and unpaved of the surrounding residential areas.

Figure 6.32: Site Conditions- Subhash Nagar Station





#### 18. Reetna Ring Road

Clearance	: 14168.90 m
Inter Station Distance	: 1361.63 m
Rail Level	: 12.50 m
Station type	: Elevated
Entry / Exits	: On both sides of the road
Location	: The station is located on NH-44 and Ring Road SH-202 crossing.
Colony/ Area	: The main source of passengers to this station is the residents of Piyu Vihar, surrounding industrial and residential areas.

Figure 6.33 Site Conditions- Reetna Ring Road Station





17. Vasudev Nagar

Clearance	: 15175.30 m
Inter Station Distance	: 985.00 m
Rail Level	: 12.05 m
Station type	: Elevated
Entry / Exit	: On both sides of the road
Location	: The station is located on NH44.
Catchment Area	: The main source of passengers to the station is the residents of Vasudev Nagar, Vasudev Nagar and the residents of surrounding residential areas.

Figure 8.34: Site Conditions- Vasudev Nagar Station





### 13. Bansal Nagar

Chainage	18131.00 m
Inter Station Distance	957.15 m
Rail Level	13.20 m
Station type	Elevated
Entry / Exits	On both sides of the road
Location	The station is located on NH-34.
Catchment Area	The main source of passengers to this station is the residents of Bansal Nagar and surrounding vicinities colonies and commercial areas.

Figure 6.38: Site Conditions- Bansal Nagar Station







18 : Lohmariya Nagar

Clearance	: 17.752.6 m
Inter Station Distance	: 1651 m
Rail Level	: 13.26 m
Station type	: Roadcut
Entry/Exit	: On both sides of the road
Location	: The station is located on NH-44.
Catchment Area	: The main source of passengers to this station is the residents & people visiting surrounding residential areas and Lohri, Moghliwar-Hospita.


Figure 6.26: Lohmariya Nagar Station









ELEVATION (1/4)




FLOOR PLAN (1/4)



SECTION (1/4)



WALL 1



WALL 2


PROJECT: ...  
 DATE: ...  
 DRAWN BY: ...

NO.	DESCRIPTION
1	...
2	...
3	...
4	...


**Autodesk**  
 Autodesk Education Community  
 1234567890  
 1234567890  
 1234567890  
 1234567890

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT



1. KAT



2. KAT



3. KAT



1/2000

LEGENDA

[Symbol]	1. KAT
[Symbol]	2. KAT
[Symbol]	3. KAT

[Symbol]	1. KAT
[Symbol]	2. KAT
[Symbol]	3. KAT

[Symbol]	1. KAT
[Symbol]	2. KAT
[Symbol]	3. KAT
TYPE 1	

# CHAPTER 7

## TRAIN OPERATION PLAN



7.1	OPERATION PHILOSOPHY
7.2	STATIONS
7.3	TRAIN OPERATION PLAN
7.4	YEAR WISE RAKE REQUIREMENT
7.5	COST ESTIMATE

### TABLES

TABLE 7.1	STATIONS
TABLE 7.2	CAPACITY PROVIDED FOR LINE-1 NORTH - SOUTH CORRIDOR
TABLE 7.3	CAPACITY PROVIDED FOR LINE-2 EAST WEST CORRIDOR
TABLE 7.4	TRAIN FREQUENCY: LINE-1: NORTH - SOUTH CORRIDOR
TABLE 7.5	TRAIN FREQUENCY: LINE-2: EAST WEST CORRIDOR

### ATTACHMENTS

ATTACHMENT-I	PIE CHART DEMAND AND CAPACITY CHART
ATTACHMENT-II	HOURLY TRAINS OPERATION PLAN
ATTACHMENT-III	DIRECTIONAL SPLIT
ATTACHMENT-IV	VEHICLE KILOMETER
ATTACHMENT-V	RAKE REQUIREMENT

**Chapter - 7****TRAIN OPERATION PLAN****7.1 Operation Philosophy**

The underlying operation philosophy is to make the MRT System more attractive and economical, the main features being:

- Selecting the most optimum frequency of Train services to meet sectional capacity requirements during peak hours on most of the sections.
- Economical & optimum train service frequency not only during peak period, but also during off-peak period.
- A short train consists of 3 coaches.
- Multi-tasking of train operation and maintenance staff.

**7.2 Stations**

List of stations for the two Corridors of Nagar Metro are given below:

**TABLE 7.1: STATIONS**

<b>LINE 1 : NORTH-SOUTH CORRIDOR</b>				
<b>S. No</b>	<b>Name of Station</b>	<b>Chainage (in m)</b>	<b>Inter - Station Distance (in m)</b>	<b>Remarks</b>
	DEAD END	-145.00		
1	AUTOMOTIVE SCORE	0.0	406.2	Elevated
2	NARI ROAD	675.8	675.8	Elevated
3	INDORA CHOWK	2138.7	1462.9	Elevated
4	KADVI CHOWK	3181.2	1042.5	Elevated
5	IGADDI GOOAM SCORE	4398.0	1216.8	Elevated
6	KASTURBHAND PARK	5148.8	750.8	Elevated
7	ZERO MILE	6175.5	1026.7	Elevated
8	BITABURDI	6708.2	532.7	Elevated
9	CONGRESS NAGAR	7897.2	1189.0	Elevated



LINE-1 : NORTH-SOUTH CORRIDOR				
S. No	Name of Station	Chainage (in m)	Inter - Station Distance (in m)	Remarks
10	RAHATE COLONY	8882.8	795.4	Elevated
11	AJNI SQUARE	10104.7	1422.1	Elevated
12	CHHATRAPATI SQUARE	11148.3	1043.6	Elevated
13	JAMPRAKASH NAGAR	11811.5	663.1	Elevated
14	LUNAL NAGAR	12846.6	1035.2	Elevated
15	AIRPORT	13784.9	1344.1	Elevated
16	NEW AIRPORT	16186.4	2393.1	At Grade
17	KHAPARI	18460.0	2173.9	At Grade
	DEAD END	19250.0		

LINE-2 : EAST-WEST CORRIDOR				
S. No	Name of Station	Chainage (in m)	Inter - Station Distance (in m)	Remarks
	DEAD END	-300.0		
1	PRAJAPATI NAGAR	0.0		Elevated
2	VISHNO DEVI CHOWK	1229.3	1229.3	Elevated
3	AMBEDKAR CHOWK	1047.3	718.0	Elevated
4	TELEPHONE EXCHANGE	9137.4	1189.5	Elevated
5	CHITAROLI CHOWK (GANDHI PUTALA)	8648.7	811.3	Elevated
6	ADRASEN CHOWK	4789.2	800.5	Elevated
7	DODARVADEYA CHOWK (MAYO HOSPITAL)	5611.8	821.8	Elevated
8	NAGPUR RAILWAY STATION	5464.4	847.4	Elevated
9	SITABURDI	7787.7	1243.3	Elevated
10	JHANSI RANTISORE	8553.7	846.0	Elevated
11	INSTITUTIONS OF ENGINEERS	9117.3	763.5	Elevated
12	SHANKAR NAGAR SORE (BANK OF INDIA)	10374.0	957.7	Elevated
13	LAD CHOWK	10373.1	739.2	Elevated
14	DHARAMPETH COLLEGE	12020.7	1147.6	Elevated
15	SUBHASH NAGAR	12947.1	926.4	Elevated
16	RACHANA (RING RD. JNC)	14188.9	1241.8	Elevated
17	VAGUDEVI NAGAR	15173.0	984.0	Elevated
18	BANSI NAGAR	16121.6	947.7	Elevated



LINE 3 - EAST WEST CORRIDOR				
S. No	Name of Station	Chainage (in m)	Inter - Station Distance (in m)	Remarks
18	LOKMANYA NAGAR	17424.1	1252.8	Elevated
	DEAD END	18185.0		

## 7.2 TRAIN OPERATION PLAN:

### 7.2.1 Key Features:

- Running of services for 16 hours of the day (5 AM to Midnight) with a station dwell time of 30 seconds.
- Make up time of 5-10% with 8-10% coasting.
- Scheduled speed for these corridors has been assumed as:

#### Line-1, North - South Corridor

- Yashwantrao Chavan to Congress Nagar section: 32 kmph
- Congress Nagar to Khairi Station section: 34 kmph

#### Line-2, East-West Corridor

- Prasad Nagar to Lokmanya Nagar section: 30 kmph
- Agasen Chowk to Subhash Nagar section: 28 kmph

### 7.2.2 Traffic Demand

Peak hour peak direction traffic demands (PHD) for the Nagpur Metro Line-1: North-South Corridor & Line-2: East-West Corridor for the year 2016, 2021, 2026, 2031, 2036 and 2041 for the purpose of planning are indicated in Attachment EA1, B1 & C1, D1, E1, F1, Attachment WA2, B2, C2, D2, E2, & F2 respectively.

### 7.2.3 Train formation

To meet the above projected traffic demand, the possibility of running trains with composition of 3 cars with different headway has been examined.

#### Composition

DMC : Driving Motor Car

TC : Trailer Car

#### Capacity ( @ 6 passengers per square meter of standee area)

Driving Motor Car (DMC) : 247 (43 seated + 204 standing)

Trailer Car (TC) : 270 (50 seated + 220 standing)

3 Car Train : 764 (136 seated + 628 standing)



### 7.2.4 Train Operation Plan

Based on the projected RHPDT demand, Train operation plan with train carrying capacity @ 6 persons per square meter of standing area for the Nagpur Metro Line 1: North-South Corridor & Line 2: East-West Corridor for the year 2016, 2021, 2026, 2031, 2036 and 2041 are given below:

#### 7.2.4.1 Line-1 North - South Corridor

Train Operation Plan for Line 1: North-South Corridor has been planned in such a way that there are two ways of train operation. In one way, trains run from 'Automotive Sore to Congress Nagar' at a given headway and in other way trains run from 'Automotive Sore to Khapti Station' at the same headway, thus resulting in half the headway in 'Automotive Sore to Congress Nagar' Section as compared to Congress Nagar to Khapti Station' Section. For this Train Operation Plan, reversal facility is required at Congress Nagar.

#### 6 - Year 2016:

Train operation in 'Automotive Sore to Congress Nagar' Loop at 12 min headway with 3-Car train and in 'Automotive Sore to Khapti Station' Loop at 12 min headway with 3-Car train. This results in following train operation in different sections:

##### (a) 'Automotive Sore to Congress Nagar' Section (Refer Attachment IA)

- 6 min Effective Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 7640 @ 6 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 9780 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum RHPDT demand of 10089 is in the Section between Sitabulji to Congress Nagar and demand in the remaining sections is in the range of 8272 to 2561 only. The planned capacity of 7640 (8730 under dense loading) is less than the RHPDT demand in two (one, with dense loading capacity) sections out of eight sections.

##### (b) 'Congress Nagar to Khapti Station' Section (Refer Attachment IA)

- 12 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 3820 @ 6 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 4865 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum RHPDT demand of 5288 is in the Section between Congress Nagar to Rohale Colony and demand in the remaining sections is in the range of 4513 to 2140 only. The planned capacity of 3820 (4300 under dense



loading) is less than the PMPDT demand in two (one, with dense loading capacity) sections out of eight sections.

Traffic demand and train capacity for this corridor in the year 2010 is tabulated and represented on a chart enclosed as Attachment (A1).

#### **(1) Year 2021:**

Train operation in 'Automotive Sore to Congress Nagar' Loop at 16.000 headway with 3-CoT train and in 'Automotive Sore to Khapri Station' Loop at 16.000 headway with 3-CoT train. This results in following train operation in different section:

##### **(a) 'Automotive Sore to Congress Nagar' Section (Refer Attachment (A2))**

- 8 min Effective Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 9100 @ 6 persons per square meter of standee area.
- Available Peak Hour Peak Direction Capacity of 11076 @ 6 persons per square meter of standee area under dense loading conditions.
- The maximum PMPDT demand of 10538 is in the Section between Staburd to Congress Nagar and demand in the remaining sections is in the range of 5225 to 3610 only. The planned capacity of 9100 (11076 under dense loading) is less than the PMPDT demand in two (zero, with dense loading capacity) sections out of eight sections.

##### **(b) 'Congress Nagar to Khapri Station' Section (Refer Attachment (A3))**

- 10 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 4584 @ 6 persons per square meter of standee area.
- Available Peak Hour Peak Direction Capacity of 5630 @ 6 persons per square meter of standee area under dense loading conditions.
- The maximum PMPDT demand of 3725 is in the Section between Congress Nagar to Rahani Colony and demand in the remaining sections is in the range of 4876 to 2267 only. The planned capacity of 4584 (5630 under dense loading) is less than the PMPDT demand in two (zero, with dense loading capacity) sections out of eight sections.

Traffic demand and train capacity for this corridor in the year 2021 is tabulated and represented on a chart enclosed as Attachment (A2).

#### **(2) Year 2028:**

Train operation in 'Automotive Sore to Congress Nagar' Loop at 2.000 headway with 3-CoT train and in 'Automotive Sore to Khapri Station' Loop at 2.000 headway with 3-CoT train. This results in following train operation in different section:



**(vi) 'Automotive Sore to Congress Nagar' section (Refer Attachment VC1)**

- 4.5 min Effective Headway with 3-car train
- Available Peak Hour Peak Direction Capacity of 10167 @ 0 persons per square meter of standing area
- Available Peak Hour Peak Direction Capacity of 12073 @ 0 persons per square meter of standing area under dense loading conditions.
- The maximum PMPDT demand of 1195 is in the Section between Shabard to Congress Nagar and demand in the remaining sections is in the range of 10207 to 1403 only. The planned capacity of 10167 (12073 under dense loading) is less than the PMPDT demand in two (zero, with dense loading capacity) sections out of eight sections.

**(vii) 'Congress Nagar to Khajuri Station' section (Refer Attachment VC1)**

- 8 min Headway with 3-car train
- Available Peak Hour Peak Direction Capacity of 5893 @ 0 persons per square meter of standing area
- Available Peak Hour Peak Direction Capacity of 6487 @ 0 persons per square meter of standing area under dense loading conditions.
- The maximum PMPDT demand of 3330 is in the Section between Congress Nagar to Bahala Colony and demand in the remaining sections is in the range of 3330 to 2480 only. The planned capacity of 5893 (6487 under dense loading) is less than the PMPDT demand in two (zero, with dense loading capacity) sections out of eight sections.

Traffic demand and train capacity for this corridor in the year 2021 is tabulated and represented in a chart enclosed as Attachment VC1.

**h) Year 2021:**

Train operation in 'Automotive Sore to Congress Nagar' Loop at 3 min headway with 3-Car train and in 'Automotive Sore to Khajuri Station' Loop at 8 min headway with 3-Car train. This results in following train operation in different section:

**7. 'Automotive Sore to Congress Nagar' section (Refer Attachment SD1)**

- 4 min Effective Headway with 3-car train
- Available Peak Hour Peak Direction Capacity of 11400 @ 0 persons per square meter of standing area
- Available Peak Hour Peak Direction Capacity of 14300 @ 0 persons per square meter of standing area under dense loading conditions.
- The maximum PMPDT demand of 12004 is in the Section between Shabard to Congress Nagar and demand in the remaining sections is in the range of 11031



to 4042 only. The planned capacity of 11400 (14300 under dense loading) is less than the PMPDT demand in two (two, with dense loading capacity) sections out of eight sections.

**(b) 'Congress Nagar to Khajuri Station' Section (Refer Attachment 1D1)**

- 8 mtr Headway with 3-car train
- Available Peak Hour Peak Direction Capacity of 5730 @ 6 persons per square meter of standee area
- Available Peak Hour Peak Direction Capacity of 7296 @ 8 persons per square meter of standee area under dense loading conditions.
- The maximum PMPDT demand of 8816 is in the Section between Congress Nagar to Rahala Colony and demand in the remaining sections is in the range of 8854 to 2748 only. The planned capacity of 6730 (7296 under dense loading) is less than the PMPDT demand in two (two, with dense loading capacity) sections out of eight sections.

Traffic demand and train capacity for this corridor in the year 2031 is situated and represented on a chart enclosed as Attachment 1D1.

**v) Year 2038:**

Train operation in 'Automotive Sore to Congress Nagar' Loop at 7.0mtr headway with 3-Car train and in 'Automotive Sore to Khajuri Station' Loop at 7.0mtr headway with 3-Car train. This results in following train operation in different section:

**(a) 'Automotive Sore to Congress Nagar' Section (Refer Attachment 1E1)**

- 3.0 min Effective Headway with 3-car train
- Available Peak Hour Peak Direction Capacity of 13007 @ 6 persons per square meter of standee area
- Available Peak Hour Peak Direction Capacity of 16000 @ 8 persons per square meter of standee area under dense loading conditions.
- The maximum PMPDT demand of 14286 is in the Section between Siddurthi to Congress Nagar and demand in the remaining sections is in the range of 13932 to 4611 only. The planned capacity of 13007 (16680 under dense loading) is less than the PMPDT demand in one (one, with dense loading capacity) sections out of eight sections.

**(b) 'Congress Nagar to Khajuri Station' Section (Refer Attachment 1E2)**

- 7 mtr Headway with 3-car train
- Available Peak Hour Peak Direction Capacity of 6545 @ 6 persons per square meter of standee area
- Available Peak Hour Peak Direction Capacity of 8340 @ 8 persons per square meter of standee area under dense loading conditions.



- The maximum PHPDT demand of TEES is in the Section between Congress Nagar to Rahade Colony and demand in the remaining sections is in the range of 8470 to 2040 only. The planned capacity of 6540 (8340 under dense loading) is less than the PHPDT demand in one (last, with dense loading capacity) sections out of eight sections.

Traffic demand and train capacity for this corridor in the year 2036 is tabulated and represented in a chart enclosed as Attachment (E).

#### vii) Year 2041:

Train operation in 'Automotive Gate to Congress Nagar' Loop of 6.7 m/h headway with 3-Car train and in 'Automotive Gate to Khapti Station' Loop of 6.7 m/h headway with 3-Car train. This results in following train operation in different section:

##### (a) 'Automotive Gate to Congress Nagar' Section (Refer Attachment (F1))

- 3 min Effective Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 15280 @ 5 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 19400 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PHPDT demand of 15720 is in the Section between Sibaturl to Congress Nagar and demand in the remaining sections is in the range of 14372 to 3274 only. The planned capacity of 13280 (19400 under dense loading) is less than the PHPDT demand in one (last, with dense loading capacity) sections out of eight sections.

##### (b) 'Congress Nagar to Khapti Station' Section (Refer Attachment (F1))

- 6 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 7540 @ 5 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 8730 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PHPDT demand of 8477 is in the Section between Congress Nagar to Rahade Colony and demand in the remaining sections is in the range of 7140 to 3080 only. The planned capacity of 7540 (8730 under dense loading) is less than the PHPDT demand in one (zero, with dense loading capacity) sections out of eight sections.

Traffic demand and train capacity for this corridor in the year 2041 is tabulated and represented in a chart enclosed as Attachment (F).



### 7.2.4.3 Line 2: East-West Corridor

Train Operation Plan for Line 2: East-west Corridor has been planned in such a way that there are two loops of train operation. In one loop, trains run from Prappatt Nagar to Lokmany Nagar at a given headway and in other loop trains run from Agrasen Chowk to Subhash Nagar at the same headway, this resulting in **sat. the headway** in 'Agrasen Chowk to Subhash Nagar' Section as compared to 'Prappatt Nagar to Agrasen Chowk' Section & 'Subhash Nagar to Lokmany Nagar' Section. For the Train Operation Plan, reversal facilities are provided at Agrasen Chowk and Subhash Nagar.

#### 6. Year 2018:

Train operation in 'Prappatt Nagar to Lokmany Nagar' Loop at 11.000 headway with 3-Car train and in 'Agrasen Chowk to Subhash Nagar' Loop at 11.000 headway with 3-Car train. This results in following train operation in different section:

#### (a) 'Prappatt Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmany Nagar' Section (Refer Attachment IIA2)

- 10 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 3526 @ 6 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 4491 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PMPDT demand of 4000 is in the Section between Cyber Di Chowk (Dorshi Public) to Agrasen Chowk and demand in the remaining sections is in the range of 3782 to 481 only. The planned capacity of 3526 (4491 under dense loading) is less than the PMPDT demand in two (zero, with dense loading capacity) out of nine sections sections of 'Prappatt Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmany Nagar' Section.

#### (b) 'Agrasen Chowk to Subhash Nagar' Section (Refer Attachment IIA2)

- 6.5 min Effective Headway with 3-car Train.
- Available Peak Hour Peak Direction Capacity of 7052 @ 6 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 8952 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PMPDT demand of 7746 is in the Section between Institute of Engineers to Shikhar Nagar Square and demand in the remaining sections is in the range of 7341 to 4372 only. The planned capacity of 7052 (8952 under dense loading) is less than the PMPDT demand in two (zero, with dense



loading capacity settles out of nine sections of 'Agrasen Chowk to Subhash Nagar' Section.

Traffic demand and train capacity for this corridor in the year 2016 is tabulated and reproduced as a chart enclosed as Attachment (A2).

#### (i) Year 2021:

Train operation in 'Prajapati Nagar to Lokmanya Nagar' Loop at 12 min headway with 3-Car train and in 'Agrasen Chowk to Subhash Nagar' Loop at 12 min headway with 3-Car train. This results in following train operation in different section:

#### (a) 'Prajapati Nagar to Agrasen Chowk' section and 'Subhash Nagar to Lokmanya Nagar' section (Refer Attachment (B2))

- 12 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 3520 @ 8 persons per square meter of standee area.
- Available Peak Hour Peak Direction Capacity of 4555 @ 8 persons per square meter of standee area under dense loading conditions.
- The maximum PHPD demand of 4384 is in the Section between Chitr (B) Chowk (Gandhi Public) to Agrasen Chowk and demand in the remaining sections is in the range of 4157 to 517 only. The planned capacity of 3520 (4865 under dense loading) is less than the PHPD demand in two (20%) with dense loading capacity) out of nine sections sections of 'Prajapati Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmanya Nagar' Section.

#### (b) 'Agrasen Chowk to Subhash Nagar' Section (Refer Attachment (B2))

- 6 min Effective Headway with 3-car train.
- Available Peak-Hour Peak Direction Capacity of 7640 @ 8 persons per square meter of standee area.
- Available Peak-Hour Peak Direction Capacity of 5730 @ 8 persons per square meter of standee area under dense loading conditions.
- The maximum PHPD demand of 8402 is in the Section between Institute of Engineers to Shankar Nagar Square and demands in the remaining sections is in the range of 7870 to 4472 only. The planned capacity of 7640 (5730 under dense loading) is less than the PHPD demand in two (24%) with dense



loading capacity settles out of nine sections of 'Agrasen Chowk to Subhash Nagar' Section.

Traffic demand and train capacity for this corridor in the year 2021 is tabulated and reproduced as a chart enclosed as Attachment (B2).

#### ii. Year 2028:

Train operation in 'Purjapati Nagar to Lokmanya Nagar' Loop at 30min headway with 3-Car train and in 'Agrasen Chowk to Subhash Nagar' Loop at 10 min headway with 3-Car train. This results in following train operation in different section:

##### (a) 'Purjapati Nagar to Agrasen Chowk' section and 'Subhash Nagar to Lokmanya Nagar' section (Refer Attachment (C2))

- 10 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 4034 @ 6 persons per square meter of standee area.
- Available Peak Hour Peak Direction Capacity of 2636 @ 8 persons per square meter of standee area under dense loading conditions.
- The maximum PHFDI demand of 4703 is in the Section between Chhatra Chowk (Gandhi Public) to Agrasen Chowk and demand in the remaining sections is in the range of 4036 to 549 only. The planned capacity of 4034 (5834 under dense loading) is less than the PHFDI demand in one (one) with dense loading capacity) out of nine sections sections of 'Purjapati Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmanya Nagar' Section.

##### (b) 'Agrasen Chowk to Subhash Nagar' section (Refer Attachment (C2))

- 5 min Effective Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 5166 @ 6 persons per square meter of standee area.
- Available Peak Hour Peak Direction Capacity of 11676 @ 8 persons per square meter of standee area under dense loading conditions.
- The maximum PHFDI demand of 9114 is in the Section between Institute of Engineers to Shankar Nagar Square and demand in the remaining sections is in the range of 5734 to 4870 only. The planned capacity of 5166 (11676 under dense loading) is less than the PHFDI demand in one (one) with dense loading capacity) sections out of nine sections of 'Agrasen Chowk to Subhash Nagar' Section.



Traffic demand and train capacity for this corridor in the year 2026 is tabulated and represented on a chart as per Attachment I(C).

#### iv) Year 2031:

Train operation in 'Pratap Nagar to Lokmanya Nagar' Loop at 5.00 headway with 3-Car train and in 'Agrasen Chowk to Subhash Nagar' Loop at 3.00 headway with 3-Car train. This results in following train operation in different section:

##### (a) 'Pratap Nagar to Agrasen Chowk' section and 'Subhash Nagar to Lokmanya Nagar' section (Refer Attachment I(D))

- 5 min Headway with 3-Car train.
- Available Peak Hour Peak Direction Capacity of 1033 @ 9 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 6487 @ 9 persons per square meter of standing area under dense loading conditions.
- The maximum P4PDT demand of 5004 is in the Section between Chhatra Chok (Dandi Pulao) to Agrasen Chowk and demand in the remaining sections is in the range of 4034 to 565 only. The planned capacity of 5000 (6487 under dense loading) is less than the P4PDT demand in one (04) out of nine sections of 'Pratap Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmanya Nagar' Sections.

##### (b) 'Agrasen Chowk to Subhash Nagar' section (Refer Attachment I(D))

- 4.5 min Effective Headway with 3-Car train.
- Available Peak Hour Peak Direction Capacity of 10187 @ 9 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 12373 @ 9 persons per square meter of standing area under dense loading conditions.
- The maximum P4PDT demand of 9000 is in the Section between Institute of Engineers to Shrihar Nagar Square and demand in the remaining sections is in the range of 9075 to 530 forty. The planned capacity of 10187 (12973 under dense loading) is more than the P4PDT demand in nine sections of 'Agrasen Chowk to Subhash Nagar' Sections.

Traffic demand and train capacity for this corridor in the year 2031 is tabulated and represented on a chart as per Attachment I(D).

**v) Year 2036:**

Train operation in 'Parajodi Nagar to Lokmanya Nagar' Loop at 8,000 headway with 3-Car train and in 'Agrasen Chowk to Subhash Nagar' Loop at 8,000 headway with 3-Car train. This results in following train operation in different section:

**(a) 'Parajodi Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmanya Nagar' Section (Refer Attachment IIE)**

- 8 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 5730 @ 8 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 7295 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PHPDOT demand of 5642 is in the Section between Chitaroli Chowk (Dandi julela) to Agrasen Chowk and demand in the remaining sections is in the range of 5416 to 621 only. The planned capacity of 5730 (7295 under dense loading) is more than the PHPDOT demand in nine sections of 'Parajodi Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmanya Nagar' Sections.

**(b) 'Agrasen Chowk to Subhash Nagar' Section (Refer Attachment IIE)**

- 4 min Effective Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 11460 @ 6 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 14585 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PHPDOT demand of 10748 is in the Section between Nagpur Railway Station to Debandi and demand in the remaining sections is in the range of 10716 to 9628 only. The planned capacity of 11460 (14585 under dense loading) is more than the PHPDOT demand in nine sections of Agrasen Chowk to Subhash Nagar' Sections.

Traffic demand and train capacity for this carrier in the year 2036 is saturated and represented on a chart enclosed as Attachment IIE.



**v) Year 2041:**

Train operation in 'Parajodi Nagar to Lokmehya Nagar' Loop at 7,000 headway with 3-Car train and in 'Agrasen Chowk to Subhash Nagar' Loop at 7,000 headway with 3-Car train. This results in following train operation in different section:

**(a) 'Parajodi Nagar to Agrasen Chowk' section and 'Subhash Nagar to Lokmehya Nagar' section (Refer Attachment IP2)**

- 7 min Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 6540 @ 8 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 6300 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PHPDT demand of 6300 is in the Section between Chitarai Chowk (Gandhi Public) and demand in the remaining sections is in the range of 5671 to 603 only. The planned capacity of 6540 (6340 under dense loading) is more than the PHPDT demand in nine sections of 'Parajodi Nagar to Agrasen Chowk' Section and 'Subhash Nagar to Lokmehya Nagar' Sections.

**(b) Agrasen Chowk to Subhash Nagar' section (Refer Attachment IP2)**

- 3.5 min Effective Headway with 3-car train.
- Available Peak Hour Peak Direction Capacity of 12037 @ 8 persons per square meter of standing area.
- Available Peak Hour Peak Direction Capacity of 10600 @ 8 persons per square meter of standing area under dense loading conditions.
- The maximum PHPDT demand of 11862 is in the Section between Nagar Railway Station to Sitapur and demand in the remaining sections is in the range of 11528 to 6237 only. The planned capacity of 12037 (10600 under dense loading) is more than the PHPDT demand in nine sections of 'Agrasen Chowk to Subhash Nagar' Sections.

Traffic demand and train capacity for this corridor in the year 2041 is tabulated and represented in a chart enclosed as Attachment IP2.

The above Train Operation Plan is based on calculations on the basis of available traffic data. In case of any mismatch in the capacity provided and the actual traffic, the capacity can be modified suitably by adjusting the Headway. The PHPDT capacity provided on the two corridors in different years of operation is tabulated below:



**TABLE 7.2**  
**Capacity Provided for Line 1: North - South Corridor**

Sections	Year	Headway (min)	No. of Trains	Rolls Config	No. of Coaches	Max. P4POT Demand	P4POT Capacity Available
Automotive Sqrs to Congress Nagar Section	2018	8	11 Trains of 3-car	3-car	33	10893	7640 (3720*)
Congress Nagar to Khajuri Station Section		12		5298		3820 (4865*)	
Automotive Sqrs to Congress Nagar Section	2021	5	12 Trains of 3-car	3-car	39	10930	8188 (1078*)
Congress Nagar to Khajuri Station Section		10		9728		4584 (5838*)	
Automotive Sqrs to Congress Nagar Section	2025	4.5	15 Trains of 3-car	3-car	45	11813	10187 (12972*)
Congress Nagar to Khajuri Station Section		8		8305		5000 (6487*)	
Automotive Sqrs to Congress Nagar Section	2031	4	17 Trains of 3-car	3-car	51	12834	11600 (14500*)
Congress Nagar to Khajuri Station Section		8		9318		6730 (7288*)	
Automotive Sqrs to Congress Nagar Section	2036	3.5	20 Trains of 3-car	3-car	60	14289	13057 (16982*)
Congress Nagar to Khajuri Station Section		7		7988		8549 (9342*)	
Automotive Sqrs to Congress Nagar Section	2041	3	21 Trains of 3-car	3-car	63	15723	15288 (19432*)
Congress Nagar to Khajuri Station Section		8		8477		7840 (3720*)	


**TABLE 7.3 Capacity Provided for Line-2: East-West Corridor**

Sections	Year	Headway (min)	No. of Rakes	Rake Config	No. of Coaches	Max. PMPDT Demand	PMPDT Capacity Available
Pratap Nagar to Agrasen Chowk Section	2016	13	12 Rakes of 3-car	3-car	36	4093	3520 (86%)
Agrasen Chowk to Subhash Nagar Section		0.5		7360		702 (95%)	
Subhash Nagar to Lokmanya Nagar Section		13		3767		3526 (94%)	
Pratap Nagar to Agrasen Chowk Section	2021	12	13 Rakes of 3-car	3-car	39	4268	3820 (90%)
Agrasen Chowk to Subhash Nagar Section		0		5403		5940 (110%)	
Subhash Nagar to Lokmanya Nagar Section		12		4157		3820 (92%)	
Pratap Nagar to Agrasen Chowk Section	2026	11	15 Rakes of 3-car	3-car	45	4733	4584 (97%)
Agrasen Chowk to Subhash Nagar Section		0		9154		9198 (100%)	
Subhash Nagar to Lokmanya Nagar Section		11		4538		4584 (101%)	
Pratap Nagar to Agrasen Chowk Section	2031	9	17 Rakes of 3-car	3-car	51	5294	5000 (94%)
Agrasen Chowk to Subhash Nagar Section		4.5		5503		10187 (185%)	
Subhash Nagar to Lokmanya Nagar Section		0		4234		5000 (118%)	
Pratap Nagar to Agrasen Chowk Section	2036	8	18 Rakes of 3-car	3-car	54	5542	5730 (103%)
Agrasen Chowk to Subhash Nagar Section		4		10748		11448 (106%)	
Subhash Nagar to Lokmanya Nagar Section		8		5418		5730 (106%)	
Pratap Nagar to Agrasen Chowk Section	2041	7	20 Rakes of 3-car	3-car	60	6300	6540 (104%)
Agrasen Chowk to Subhash Nagar Section		3.5		11852		13807 (116%)	
Subhash Nagar to Lokmanya Nagar Section		7		5871		6540 (111%)	

\* @ 8 persons per square meter of standing area



## 7.2.6 Train frequency

**TABLE 7.4**  
**Train Frequency Line-1, North – South Corridor**

Sections	2016		2021		2026		2031		2036		2041	
	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr
Ajaynole Sore to Compost Nagar Section	2 hr	10 to 30 hr	2 min	2 to 20 min	4.5m hr	0 to 20 hr	4 min	8 to 20 min	3.2 min	5 to 15 min	3 min	5 to 15 min
Compost Nagar to Khour Station Section	12 min	20 to 30 hr	10 min	16 to 40 min	2 min	12 to 40 hr	2 min	12 to 40 min	7 min	15 to 30 min	8 min	10 to 30 min

**TABLE 7.5**  
**Train Frequency Line-2, East-West Corridor**

Sections	2016		2021		2026		2031		2036		2041	
	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr	Peak Hour /hr	Lean Hour /hr
Prasid Nagar to Agrasen Chowk Section	18 min	20 to 60 hr	12 min	20 to 60 min	18 min	16 to 40 hr	8 min	12 to 40 min	8 min	12 to 40 min	7 min	10 to 30 min
Agrasen Chowk to Gubrah Nagar Section	6.5 hr	10 to 30 hr	8 min	10 to 30 min	8 min	8 to 20 hr	4.5 min	6 to 20 min	4 min	6 to 20 min	5.5 min	5 to 15 min
S/Prasid Nagar to Laxman Nagar Section	12 min	20 to 60 hr	12 min	20 to 60 min	16 min	16 to 40 hr	8 min	12 to 40 min	8 min	12 to 40 min	7 min	10 to 30 min

All services are proposed between 00:00 hrs to 0:00 hrs, which are reserved for maintenance of infrastructure and rolling stock.



### 7.2.6 Hourly Train Operation plan

The hourly distribution of daily transport capacity is presented in **Table 1.1A, 1.1B, 1.1A, 1.1B, 1.1A, 1.1B, 1.4A, 1.4B, 1.4A, 1.4B, 1.4A, & 1.4B** for 'Automotive Saps to Congress Nagar' Section and 'Congress Nagar to Khajuri' Section (Line-1: North - South Corridor) and **Table 1.7A, 1.7B, 1.7C, 1.8A, 1.8B, 1.8C, 1.8A, 1.8B, 1.8C, 1.16A, 1.16B, 1.16C, 1.11A, 1.11B, 1.11C, 1.11A, 1.11B, & 1.11C** for 'Prajapati Nagar to Agrasen Chowk' Section, 'Agrasen Chowk to Subhash Nagar' Section and 'Subhash Nagar to Lokmanya Nagar' Section (Line-2: East-West Corridor) respectively for years 2016, 2021, 2026, 2031, 2036, 2041 and enclosed as **Attachment 8**.

Number of train trips per direction per day for 'Automotive Saps to Congress Nagar' Section and 'Congress Nagar to Khajuri' Section (Line-1: North - South Corridor) is worked out as 128 & 64 in the year 2016, 128 & 64 in the year 2021 and 128 & 70 in the year 2026, 128 & 64 in the year 2031, 200 & 100 in the year 2036 and 216 & 108 in the year 2041 respectively. Number of train trips per direction per day for 'Prajapati Nagar to Agrasen Chowk' Section, 'Agrasen Chowk to Subhash Nagar' Section and 'Subhash Nagar to Lokmanya Nagar' Section (Line-2: East-West Corridor) is worked out as 01, 102 & 01 in the year 2016, 54, 108 & 54 in the year 2021 and 70, 140 & 70 in the year 2026, 74, 108 & 74 in the year 2031, 83, 165 & 83 in the year 2036 and 90, 180 & 90 in the year 2041 respectively. The directional splits for Line-1: North - South Corridor and Line-2: East-West Corridor is presented in **Table 2.1 and 2.2** enclosed as **Attachment 9**.

### 7.2.7 Vehicle Kilometer

Based on above planning, after considering maintenance period and assuming 340 days in service in a year, Vehicle Kilometer for Nagpur Metro Rail Network is given in **Table 3.1** for Line 1: North-South corridor and **Table 3.2** for Line 2: East-West Corridor enclosed as **Attachment 10**.

## 7.4 YEAR WISE RAKE REQUIREMENT

Based on Train formation and roadway as decided above to meet Peak Hour Peak Direction Traffic Demand, Rake requirement has been calculated and enclosed as **Attachment 11**.

Requirements of coaches is calculated based on following assumptions:

#### Assumptions -

(i) Train Composition planned as under:

3-car Train Composition : DMC + TC + DMC

Train Carrying Capacity of 3 : 764 passengers @ 6000000

Car Train @ 6000000 passengers per  
square meter of standing area



- (ii) Coach requirement has been calculated based on headway during peak hour.
- (iii) Traffic reserve is taken as one train to cater to failure of train on line and to make up for operational time lost.
- (iv) Repair and maintenance reserve has been estimated as 5 % of total requirement (Base).
- (v) The calculated number of coaches in factor is rounded off to next higher number.
- (vi) Schedule speed is taken as:

#### Line-1, North-South Corridor

- 'Automotive Sore to Congress Nagar' Section: 32 kmph
- 'Congress Nagar to Kharaj Station' Section: 36 kmph

#### Line-2, East-West Corridor

- 'Ferozpur Nagar to Lokmanya Nagar' Section: 36 kmph
- 'Agrawal Chowk to Subhash Nagar' Section: 29 kmph

- (vii) Total Turn round time is taken as 8 min at terminal stations.

### 7.8 Cost Estimate

The estimated cost per coach at June 2012 Price level exclusive of taxes and duties may be assumed as ₹ 5.0 Crores per Coach. Total  $33 \times 30 = 99$  coaches are required in year 2012 for the two lines in Nagpur Metro Rail Network.

**RFPDT Demand and Capacity Chart**  
**Magpur Metro Rail Network**  
**Line 1 - North - South Corridor**

Year	2016
No. of Lateral Trains	2
Passenger Capacity (6 persons/seat) of a 3-Car Train	708
Passenger Capacity (6 persons/seat) of a 3-Car Train	573
Passing (min)	0
Passing (max)	12

As per Metro Rail  
 Engineering Manual  
 10 Passenger Capacity  
 Chapter 10.0.0.0

S/N	FROM	TO	Trains Demand in PPH/12	PHDT capacity (2 Sights of storable area)	PHDT capacity (2 Sights of storable area)
1	AMUNDI/101 SQUARE	NEW ROAD	228	792	672
2	NEW ROAD	INDIRA CHOWK	174	792	672
3	INDIRA CHOWK	WAZIR CHOWK	420	792	672
4	WAZIR CHOWK	WAZIR SQUARE STATION	612	792	672
5	WAZIR SQUARE STATION	WAZIR CHOWK	612	792	672
6	WAZIR CHOWK	INDIRA CHOWK	174	792	672
7	INDIRA CHOWK	NEW ROAD	228	792	672
8	NEW ROAD	AMUNDI/101 SQUARE	228	792	672
9	AMUNDI/101 SQUARE	WAZIR CHOWK	420	792	672
10	WAZIR CHOWK	INDIRA CHOWK	174	792	672
11	INDIRA CHOWK	WAZIR CHOWK	420	792	672
12	WAZIR CHOWK	WAZIR SQUARE STATION	612	792	672
13	WAZIR SQUARE STATION	WAZIR CHOWK	612	792	672
14	WAZIR CHOWK	NEW ROAD	228	792	672
15	NEW ROAD	AMUNDI/101 SQUARE	228	792	672

Note: Revised Capacity required at Congest Point:




Fig 1.1





**RAPID Demand and Capacity Chart**

**Nagpur Metro Rail Network**

**Line 1 - North - South Corridor**

Year:	2021
No. of Cars per Train:	4
Passenger Capacity @ 0 persons/m <sup>2</sup> of a 3-Car Train:	704
Passenger Capacity @ 0 persons/m <sup>2</sup> of a 4-Car Train:	874
Trackway (m):	5
Trackway (min):	16

0 - Unavailable Data  
 1 - Capacity Exceeds  
 2 - Capacity Exceeds  
 3 - Capacity Exceeds

S/N	FROM	TO	Traffic Demand to R/POT	R/POT capacity @ 0 person of average size	R/POT capacity @ 0 person of average size
1	LOTTINGHAT WARE	WIS WARE	103	874	103
2	WIS WARE	NEERA CHONK	119	874	119
3	NEERA CHONK	WIS WARE	117	874	117
4	WIS WARE	WIS WARE	119	874	119
5	WIS WARE	WIS WARE	117	874	117
6	WIS WARE	WIS WARE	119	874	119
7	WIS WARE	WIS WARE	117	874	117
8	WIS WARE	WIS WARE	119	874	119
9	WIS WARE	WIS WARE	117	874	117
10	WIS WARE	WIS WARE	119	874	119
11	WIS WARE	WIS WARE	117	874	117
12	WIS WARE	WIS WARE	119	874	119
13	WIS WARE	WIS WARE	117	874	117
14	WIS WARE	WIS WARE	119	874	119
15	WIS WARE	WIS WARE	117	874	117
16	WIS WARE	WIS WARE	119	874	119
17	WIS WARE	WIS WARE	117	874	117
18	WIS WARE	WIS WARE	119	874	119
19	WIS WARE	WIS WARE	117	874	117
20	WIS WARE	WIS WARE	119	874	119

Note: Devika facility is not in the scope of the study.




Fig 11

**RVPOT Demand and Capacity Chart  
Bengaluru Metro Rail Network**

Line 1: 2-car - Red Corridor

Train	600
No. of Cars per Train	2
Passenger Capacity @ 0 persons/m <sup>2</sup> of a 2-Car Train	704
Passenger Capacity @ 0 persons/m <sup>2</sup> of a 2-Car Train	874
Headway (min)	3
Headway (min)	45

As per the Metro Rail Network  
As per the Metro Rail Network  
As per the Metro Rail Network  
As per the Metro Rail Network  
As per the Metro Rail Network

SR	FROM	TO	Trips Demand to RVPOT	RVPOT capacity @ 0 person of Bengaluru area	RVPOT capacity @ 0 person of Bengaluru area
1	FRIGATE ROAD	WILSON GREEN STATION	171	800	1400
2	VASANTH NAGAR	MARROWDA STATION	171	800	1400
3	MARROWDA STATION	TEJASWANI EXCHANGE	171	800	1400
4	TEJASWANI EXCHANGE	CHITRA ST. STATION	171	800	1400
5	CHITRA ST. STATION	MAJESTIC STATION	171	800	1400
6	MAJESTIC STATION	SRIRAMA STATION	171	800	1400
7	SRIRAMA STATION	WILSON GREEN STATION	171	800	1400
8	WILSON GREEN STATION	STABLING STATION	171	800	1400
9	STABLING STATION	JAYANAGAR SQUARE	171	800	1400
10	JAYANAGAR SQUARE	SCOTT'S CROSSING	171	800	1400
11	SCOTT'S CROSSING	SHANMUKH BAZAR SQUARE	171	800	1400
12	SHANMUKH BAZAR SQUARE	LAD CROSSING	171	800	1400
13	LAD CROSSING	SOORAPUR COLLEGE	171	800	1400
14	SOORAPUR COLLEGE	SUBBARA STATION	171	800	1400
15	SUBBARA STATION	TRACHERY ROAD STATION	171	800	1400
16	TRACHERY ROAD STATION	CHITRA STATION	171	800	1400
17	CHITRA STATION	MAJESTIC STATION	171	800	1400
18	MAJESTIC STATION	WILSON GREEN STATION	171	800	1400

Note: Demand highly regular in Agri area. Check on Lakshmi Nagar




Fig 1.1

**PePDT Demand and Capacity Chart**  
**Nagpur Metro Rail Network**  
 Line 1: Karm - South Corridor

Year	2022
No. of Cars per Train	3
Passenger Capacity @ Composition of 3-Car Train	704
Passenger Capacity @ Composition of 2-Car Train	472
Trackway info	1:1

As Observed from  
 Capacity Report Studies

Trackway (m/s)

As Observed from  
 Capacity Report Studies

SR	FROM	TO	TOTAL Demand in PePDT	PePDT capacity @ 3-car train (m/s)	PePDT capacity @ 2-car train (m/s)
1	NEW TOWN STATION	NEW ROAD	253	210	139
2	NEW ROAD	WADIWADI STATION	172	210	139
3	WADIWADI STATION	WADI STATION	111	210	139
4	WADI STATION	WADI STATION CROSS	111	210	139
5	WADI STATION CROSS	WADIWADI STATION	111	210	139
6	WADI STATION CROSS	WADI STATION	111	210	139
7	WADI STATION	WADI STATION CROSS	111	210	139
8	WADI STATION	WADIWADI STATION	111	210	139
9	WADIWADI STATION	WADI STATION	111	210	139
10	WADIWADI STATION	WADIWADI STATION CROSS	111	210	139
11	WADIWADI STATION CROSS	WADI STATION	111	210	139
12	WADIWADI STATION CROSS	WADIWADI STATION	111	210	139
13	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
14	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
15	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
16	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
17	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
18	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
19	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139
20	WADIWADI STATION CROSS	WADIWADI STATION CROSS	111	210	139

Note: Reverse traffic required in Corridor Report




Fig 10.1



**MRTD Demand and Capacity Chart**  
**Nagpur Metro Rail Network**  
**Line 1 - North - South Corridor**

Year:	2023
No. of Car per Train	3
Passenger Capacity (at 6 persons/cap of a 3-Car Train)	174
Passenger Capacity (at 8 persons/cap of a 3-Car Train)	217
Headway (min)	4
Headway (min)	5

As per Metro Rail  
 Corporation, Nagpur  
 to Transport Department  
 Report Document

SL	FROM	TO	Traffic Demand (at 174)	MRTD Capacity (at 174) of available area	MRTD Capacity (at 217) of available area
1	ALTONCHURCH ROAD	NAK ROAD	436	1140	1428
2	NAK ROAD	ALTONCHURCH ROAD	521	1140	1428
3	ALTONCHURCH ROAD	NAK ROAD	560	1140	1428
4	NAK ROAD	ALTONCHURCH ROAD	539	1140	1428
5	ALTONCHURCH ROAD	WEST RICHARDTOWN	533	1140	1428
6	WEST RICHARDTOWN	ALTONCHURCH ROAD	1024	1140	1428
7	ALTONCHURCH ROAD	WEST RICHARDTOWN	1107	1140	1428
8	WEST RICHARDTOWN	ALTONCHURCH ROAD	1004	1140	1428
9	WEST RICHARDTOWN	WAGHOLI COLONY	674	673	798
10	WAGHOLI COLONY	WEST RICHARDTOWN	724	673	798
11	WAGHOLI COLONY	CHANDRASEKHAR COLONY	636	673	798
12	CHANDRASEKHAR COLONY	WAGHOLI COLONY	424	673	798
13	CHANDRASEKHAR COLONY	WAGHOLI COLONY	421	673	798
14	WAGHOLI COLONY	WEST RICHARDTOWN	1127	673	798
15	WEST RICHARDTOWN	WAGHOLI COLONY	573	673	798
16	WAGHOLI COLONY	WEST RICHARDTOWN	276	673	798

Note: Demand Exceeds Capacity in Chandrasekharpur




Fig. 6.1

**MRTD Demand and Capacity Chart**  
**Nagpur Metro Rail Network**  
**Line 2 - Red - Red Corridor**

<b>Year</b>	<b>2023</b>
<b>No. of Cars per Train</b>	<b>3</b>
<b>Passenger Capacity (at 6 persons/capital of a 3-Car Train)</b>	<b>180</b>
<b>Passenger Capacity (at 8 persons/capital of a 3-Car Train)</b>	<b>216</b>
<b>Headway (min)</b>	<b>4.2</b>
<b>Headway (hr)</b>	<b>0</b>

As per the Metro Rail  
 Authority (MRTA) Report  
 on Physical Master Plan  
 (PMP) - 2023, Demand and  
 Capacity Analysis of  
 Nagpur Metro Rail  
 Network

Sl. No.	FROM	TO	Annual Demand (at PMT)	PMT Capacity (at 6/8 persons of station area)	PMT Capacity (at 6/8 persons of station area)
1	TRAJAI KUTI NAGAR	WARDHOLI JUNCTION	360	500	360
2	WARDHOLI JUNCTION	BRIDGE ROAD STATION	170	600	360
3	BRIDGE ROAD STATION	TEELI FORT EXCHANGE	300	500	360
4	TEELI FORT EXCHANGE	CHITTAI JUNCTION	360	600	360
5	CHITTAI JUNCTION	AGARSI JUNCTION	330	500	360
6	AGARSI JUNCTION	SHYAM NAGAR STATION	450	1000	1260
7	SHYAM NAGAR STATION	NAGPUR RAILWAY STATION	600	1000	1260
8	NAGPUR RAILWAY STATION	STADIUM (WIDENING) STATION	400	1000	1260
9	STADIUM (WIDENING) STATION	JYAM NAGAR SQUARE	300	1000	1260
10	JYAM NAGAR SQUARE	INSTITUTE OF MANAGEMENT	360	1000	1260
11	INSTITUTE OF MANAGEMENT	SPARSH NAGAR SQUARE	330	1000	1260
12	SPARSH NAGAR SQUARE	JAL CHOKI	360	1000	1260
13	JAL CHOKI	PARVATI COLLEGE	300	1000	1260
14	PARVATI COLLEGE	SHYAM NAGAR	360	1000	1260
15	SHYAM NAGAR	NAGPUR RAILWAY STATION	450	500	360
16	NAGPUR RAILWAY STATION	TRAJAI NAGAR	420	500	360
17	TRAJAI NAGAR	BRIDGE ROAD	330	500	360
18	BRIDGE ROAD	WARDHOLI NAGAR	300	600	360

Note: Demand fully met/achieved at Agarsi Junction and Chitnai Nagar




Fig 4.1

**PNPT Demand and Capacity Chart**  
**Nagpur Metro Rail Network**  
**Line 1: North - South Corridor**

Year	2028
No. of Cars per Hour	5
Passenger Capacity @ 8 persons/car of a 3-Car Train	750
Passenger Capacity @ 8 persons/car of a 3-Car Train	975
Headway (min)	2.2
Headway (min)	7

ICR - Demand/Supply of Nagpur Metro Rail Network

ICR - Capacity/Supply of Nagpur Metro Rail Network

SL	FROM	TO	Traffic Demand in PPH/HR	PNPT capacity @ 5/car/hr of 3-car train	PNPT capacity @ 8/car/hr of 3-car train
1	AMUNDEVI JAIN	NEWS COLONY	4611	1200	1500
2	BAIKI ROAD	NEWS COLONY	5792	1200	1500
3	INDIRA COLONY	NEWS COLONY	3928	1200	1500
4	KANU COLONY	NEWS COLONY	3133	1200	1500
5	SADASHIV NAGAR	NEWS COLONY	1632	1200	1500
6	SADASHIV NAGAR	NEWS COLONY	1712	1200	1500
7	SEVA NAGAR	NEWS COLONY	1880	1200	1500
8	SEVA NAGAR	NEWS COLONY	1429	1200	1500
9	CONSTITUTION NAGAR	NEWS COLONY	708	840	1050
10	CHANDRASEKHAR	NEWS COLONY	549	840	1050
11	AKASH COLONY	NEWS COLONY	367	840	1050
12	CHANDRASEKHAR	NEWS COLONY	470	840	1050
13	DAMODAR NAGAR	NEWS COLONY	400	840	1050
14	TRIPATHI NAGAR	NEWS COLONY	377	840	1050
15	RAJENDRA	NEWS COLONY	349	840	1050
16	NEWS COLONY	NEWS COLONY	348	840	1050

Note: Reserve facility required in Complex Stage.




Fig 1

**PHDQI Demand and Capacity Chart  
Nagpur Metro Rail Network  
Line 2 - East - West Corridor**

Year	2028
No. of Cars per Hour	5
Passenger Capacity @ 8 persons/car of a 3-Car Train	750
Passenger Capacity @ 8 persons/car of a 3-Car Train	975
Headway (min)	4
Headway (min)	8

*In Agreement with  
Railway Deptt. Mumbai*

*In Accordance with  
Agreement with  
Railway Deptt. Mumbai*

SN	FROM	TO	Metro Demand in PPH/CO	PHDQI capacity @ 40/min of station area	PHDQI capacity @ 30/min of station area
1	PRASANT NAGAR	VADEGHAT NAGAR	371	1700	2200
2	VADGHAT NAGAR	MARROWA CHOWK	1174	2100	2200
3	MARROWA CHOWK	TELEPHONE EXCH-CHAND	1003	1700	2200
4	TELEPHONE EXCH-CHAND	STATIONER NAGAR	603	1700	2200
5	CHITTAI NAGAR	ACADEMY CHOWK	960	1700	2200
6	ACADEMY CHOWK	SEKAR VADGA CHOWK	2044	1900	1900
7	SEKAR VADGA CHOWK	NAGPUR RAILWAY STATION	1540	1900	1900
8	NAGPUR RAILWAY STATION	STATIONER NAGAR	1000	1900	1900
9	STATIONER NAGAR	2ND ST. NAGAR	800	1900	1900
10	2ND ST. NAGAR	INSTITUTE OF TECHNOLOGY	800	1900	1900
11	INSTITUTE OF TECHNOLOGY	2ND ST. NAGAR	1010	1900	1900
12	2ND ST. NAGAR	LAD CHOWK	800	1900	1900
13	LAD CHOWK	SUNSHINE COLLEGE	700	1900	1900
14	SUNSHINE COLLEGE	CHANDRA NAGAR	1000	1900	1900
15	CHANDRA NAGAR	NAGPUR RAIL ROAD 2A	500	1700	2200
16	NAGPUR RAIL ROAD 2A	VADGHAT NAGAR	600	1700	2200
17	VADGHAT NAGAR	PRASANT NAGAR	200	1700	2200
18	PRASANT NAGAR	VADEGHAT NAGAR	300	1700	2200

Note: Reserve facility required in Agrawal Chowk and Jadhav Nagar




Fig. 3



**RWQDT Demand and Capacity Chart**  
**Raguar Metro Rail Network**  
 Line 1 - North - South Corridor

Year	2011
No. of Cars per Train	4
Passenger Capacity & Utilization of a 2-Car Train	704
Passenger Capacity & Utilization of a 4-Car Train	2816
Trackway (m/s)	7
Trackway (min)	6

16 - Stations (See 16  
 Stations Page)  
 17 - Stations (See 17  
 Stations Page)

SR	FROM	TO	Traffic Demand in 2011	RWQDT Capacity & Utilization of SECTION	RWQDT Capacity & Utilization of SECTION
1	PHOENIX STATION	WASH STATION	1211	1200	100%
2	WASH STATION	WASH STATION	611	1200	51%
3	WASH STATION	WASH STATION	825	1200	69%
4	WASH STATION	WASH STATION	1715	1200	143%
5	WASH STATION	WASH STATION	1111	1200	93%
6	WASH STATION	WASH STATION	1111	1200	93%
7	WASH STATION	WASH STATION	1211	1200	101%
8	WASH STATION	WASH STATION	1211	1200	101%
9	WASH STATION	WASH STATION	817	704	116%
10	WASH STATION	WASH STATION	714	704	101%
11	WASH STATION	WASH STATION	810	704	115%
12	WASH STATION	WASH STATION	704	704	100%
13	WASH STATION	WASH STATION	714	704	101%
14	WASH STATION	WASH STATION	821	704	117%
15	WASH STATION	WASH STATION	811	704	115%
16	WASH STATION	WASH STATION	808	704	115%

Note: Demand fully met at Congress Square




Fig. 1.1

**PWDOT Demand and Capacity Chart**  
**Raggar Metro Rail Network**  
**Line 2 - Cal - New Corridor**

Revision - 073

Year: 2011  
 No. of Cars per Train: 4  
 Passenger Capacity & Utilization of a 2-Car Train: 704  
 Passenger Capacity & Utilization of a 4-Car Train: 2816  
 Trackway (mi): 1.0  
 Trackway (mi): 7

See Appendix C for  
 Station Page Number  
 See Appendix D for  
 Station Page Number and  
 Station Page Number  
 Page Number

SR	FROM	TO	Traffic Demand to PWDOT	PWDOT capacity & Utilization of entire line	PWDOT capacity & Utilization of entire line
1	WILMINGTON	WILMINGTON	000	000	000
2	WILMINGTON	WILMINGTON	000	000	000
3	WILMINGTON	WILMINGTON	000	000	000
4	WILMINGTON	WILMINGTON	000	000	000
5	WILMINGTON	WILMINGTON	000	000	000
6	WILMINGTON	WILMINGTON	000	000	000
7	WILMINGTON	WILMINGTON	000	000	000
8	WILMINGTON	WILMINGTON	000	000	000
9	WILMINGTON	WILMINGTON	000	000	000
10	WILMINGTON	WILMINGTON	000	000	000
11	WILMINGTON	WILMINGTON	000	000	000
12	WILMINGTON	WILMINGTON	000	000	000
13	WILMINGTON	WILMINGTON	000	000	000
14	WILMINGTON	WILMINGTON	000	000	000
15	WILMINGTON	WILMINGTON	000	000	000
16	WILMINGTON	WILMINGTON	000	000	000
17	WILMINGTON	WILMINGTON	000	000	000
18	WILMINGTON	WILMINGTON	000	000	000
19	WILMINGTON	WILMINGTON	000	000	000
20	WILMINGTON	WILMINGTON	000	000	000
21	WILMINGTON	WILMINGTON	000	000	000
22	WILMINGTON	WILMINGTON	000	000	000
23	WILMINGTON	WILMINGTON	000	000	000
24	WILMINGTON	WILMINGTON	000	000	000
25	WILMINGTON	WILMINGTON	000	000	000
26	WILMINGTON	WILMINGTON	000	000	000
27	WILMINGTON	WILMINGTON	000	000	000
28	WILMINGTON	WILMINGTON	000	000	000
29	WILMINGTON	WILMINGTON	000	000	000
30	WILMINGTON	WILMINGTON	000	000	000
31	WILMINGTON	WILMINGTON	000	000	000
32	WILMINGTON	WILMINGTON	000	000	000
33	WILMINGTON	WILMINGTON	000	000	000
34	WILMINGTON	WILMINGTON	000	000	000
35	WILMINGTON	WILMINGTON	000	000	000
36	WILMINGTON	WILMINGTON	000	000	000
37	WILMINGTON	WILMINGTON	000	000	000
38	WILMINGTON	WILMINGTON	000	000	000
39	WILMINGTON	WILMINGTON	000	000	000
40	WILMINGTON	WILMINGTON	000	000	000
41	WILMINGTON	WILMINGTON	000	000	000
42	WILMINGTON	WILMINGTON	000	000	000
43	WILMINGTON	WILMINGTON	000	000	000
44	WILMINGTON	WILMINGTON	000	000	000
45	WILMINGTON	WILMINGTON	000	000	000
46	WILMINGTON	WILMINGTON	000	000	000
47	WILMINGTON	WILMINGTON	000	000	000
48	WILMINGTON	WILMINGTON	000	000	000
49	WILMINGTON	WILMINGTON	000	000	000
50	WILMINGTON	WILMINGTON	000	000	000

Max. Allowed factor reached at green chart and station page




Fig 3.2

**Nagpur Metro Rail Network**  
**Line 1 : North - South Corridor**

TABLE 1.1 A

Hourly Train Operation Plan for AUTOMOTIVE SQUARE to CONGRESS NAGAR  
 Year: 2016  
 Configuration: 3 Car  
 Headway(min): 6

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	24	3	2
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	6	10	10
9 to 10	6	10	10
10 to 11	6	10	10
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	24	3	2
14 to 15	24	2	3
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	6	10	10
18 to 19	6	10	10
19 to 20	6	10	10
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	24	3	3
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>108</b>	<b>108</b>

## Nagpur Metro Rail Network

Line 1 : North - South Corridor

TABLE 1.2 A

Hourly Train Operation Plan for AUTOMOTIVE SQUARE to CONGRESS NAGAR

Year: 2021

Configuration: 3 Car

Headway(min): 5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	10	4	3
6 to 7	12	5	5
7 to 8	8	8	7
8 to 9	5	12	12
9 to 10	5	12	12
10 to 11	5	12	12
11 to 12	8	7	7
12 to 13	12	5	5
13 to 14	10	4	3
14 to 15	10	3	4
15 to 16	12	5	5
16 to 17	8	7	8
17 to 18	5	12	12
18 to 19	5	12	12
19 to 20	5	12	12
20 to 21	8	7	7
21 to 22	12	5	5
22 to 23	10	3	4
23 to 24	20	3	3
<b>Total No. of train trips per direction per day</b>		<b>138</b>	<b>138</b>

**Nagpur Metro Rail Network**  
**Line 1 : North - South Corridor**

TABLE 1.3 A

Hourly Train Operation Plan for AUTOMOTIVE SQRE to CONGRESS NAGAR

Year: 2025

Configuration: 3 Car

Headway(min): 4.5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	18	3	4
6 to 7	12	5	5
7 to 8	8	10	10
8 to 9	4.5	13	14
9 to 10	4.5	14	13
10 to 11	4.5	13	14
11 to 12	8	10	10
12 to 13	12	5	5
13 to 14	18	4	3
14 to 15	18	3	4
15 to 16	12	5	5
16 to 17	8	10	10
17 to 18	4.5	14	13
18 to 19	4.5	13	14
19 to 20	4.5	14	13
20 to 21	8	10	10
21 to 22	12	5	5
22 to 23	18	4	3
23 to 24	20	3	3
<b>Total No. of train trips per direction per day</b>		<b>158</b>	<b>158</b>

## Nagpur Metro Rail Network

Line 1 : North - South Corridor

TABLE 1.4 A

Hourly Train Operation Plan for AUTOMOTIVE SQUARE to CONGRESS NAGAR

Year: 2031

Configuration: 3 Car

Headway(min): 4

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	10	4	4
6 to 7	12	5	5
7 to 8	8	10	10
8 to 9	4	15	15
9 to 10	4	15	15
10 to 11	4	15	15
11 to 12	8	10	10
12 to 13	12	5	5
13 to 14	10	4	3
14 to 15	10	3	4
15 to 16	12	5	5
16 to 17	8	10	10
17 to 18	4	15	15
18 to 19	4	15	15
19 to 20	4	15	15
20 to 21	6	10	10
21 to 22	12	5	5
22 to 23	10	4	4
23 to 24	20	3	3
<b>Total No. of train trips per direction per day</b>		<b>168</b>	<b>168</b>

## Nagpur Metro Rail Network

Line 1 : North - South Corridor

TABLE 1.5 A

Hourly Train Operation Plan for AUTOMOTIVE SQUARE to CONGRESS NAGAR

Year: 2036

Configuration: 3 Car

Headway(min): 3.5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	12	5	5
6 to 7	10	6	6
7 to 8	5	12	12
8 to 9	3.5	17	18
9 to 10	3.5	17	17
10 to 11	3.5	17	18
11 to 12	5	12	12
12 to 13	10	6	6
13 to 14	12	5	5
14 to 15	12	5	5
15 to 16	10	6	6
16 to 17	5	12	12
17 to 18	3.5	18	17
18 to 19	3.5	17	17
19 to 20	3.5	18	17
20 to 21	5	12	12
21 to 22	10	6	6
22 to 23	12	5	5
23 to 24	15	4	4
<b>Total No. of train trips per direction per day</b>		<b>200</b>	<b>200</b>

## Nagpur Metro Rail Network

Line 1 : North - South Corridor

TABLE 1.6 A

Hourly Train Operation Plan for AUTOMOTIVE SQUARE to CONGRESS NAGAR

Year: 2041

Configuration: 3 Car

Headway(min): 3

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	12	5	5
6 to 7	10	6	6
7 to 8	5	12	12
8 to 9	3	20	20
9 to 10	3	20	20
10 to 11	3	20	20
11 to 12	5	12	12
12 to 13	10	6	6
13 to 14	12	5	5
14 to 15	12	5	5
15 to 16	10	6	6
16 to 17	5	12	12
17 to 18	3	20	20
18 to 19	3	20	20
19 to 20	3	20	20
20 to 21	5	12	12
21 to 22	10	6	6
22 to 23	12	5	5
23 to 24	15	4	4
<b>Total No. of train trips per direction per day</b>		<b>216</b>	<b>216</b>



Nagpur Metro Rail Network  
Line 1 : North - South Corridor

TABLE 1.1 B

Hourly Train Operation Plan for CONGRESS NAGAR to KHAPARI

Year: 2016

Configuration: 3 Car

Headway(min): 12

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	48	1	1
6 to 7	40	2	1
7 to 8	20	3	3
8 to 9	12	5	5
9 to 10	12	5	5
10 to 11	12	5	5
11 to 12	20	3	3
12 to 13	40	1	2
13 to 14	48	1	2
14 to 15	48	2	1
15 to 16	40	2	1
16 to 17	20	3	3
17 to 18	12	5	5
18 to 19	12	5	5
19 to 20	12	5	5
20 to 21	20	3	3
21 to 22	40	1	2
22 to 23	48	1	1
23 to 24	60	1	1
<b>Total No. of train trips per direction per day</b>		<b>54</b>	<b>54</b>

## Nagpur Metro Rail Network

Line 1: North - South Corridor

TABLE 1.2 B

Hourly Train Operation Plan for CONGRESS NAGAR to KHAPARI

Year: 2021

Configuration: 3 Car

Headway(min): 10

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	2
6 to 7	24	3	2
7 to 8	15	4	3
8 to 9	10	6	6
9 to 10	10	6	6
10 to 11	10	6	6
11 to 12	15	4	3
12 to 13	24	2	3
13 to 14	32	2	1
14 to 15	32	1	2
15 to 16	24	3	2
16 to 17	15	3	4
17 to 18	10	6	6
18 to 19	10	6	6
19 to 20	10	6	6
20 to 21	15	3	4
21 to 22	24	2	3
22 to 23	32	2	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>69</b>	<b>69</b>

**Nagpur Metro Rail Network**  
 Line 1 : North - South Corridor

**TABLE 1.3 B**  
**Hourly Train Operation Plan for CONGRESS NAGAR to KHAPARI**  
 Year: 2025

Configuration: 3 Car

Headway(min): 9

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	2
6 to 7	24	3	2
7 to 8	12	5	5
8 to 9	9	6	7
9 to 10	9	7	6
10 to 11	9	6	7
11 to 12	12	5	5
12 to 13	24	2	3
13 to 14	32	2	2
14 to 15	32	2	2
15 to 16	24	3	2
16 to 17	12	5	5
17 to 18	9	7	6
18 to 19	9	6	7
19 to 20	9	7	6
20 to 21	12	5	5
21 to 22	24	2	3
22 to 23	32	2	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>79</b>	<b>79</b>

## Nagpur Metro Rail Network

Line 1: North - South Corridor

TABLE 1.4 B

Hourly Train Operation Plan for CONGRESS NAGAR to KHAPARI

Year: 2031

Configuration: 3 Car

Headway(min): 8

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	2
6 to 7	24	3	2
7 to 8	12	6	5
8 to 9	8	7	8
9 to 10	8	8	7
10 to 11	8	7	8
11 to 12	12	6	5
12 to 13	24	2	3
13 to 14	32	2	1
14 to 15	32	1	2
15 to 16	24	3	2
16 to 17	12	6	5
17 to 18	8	8	7
18 to 19	8	7	8
19 to 20	8	8	7
20 to 21	12	6	5
21 to 22	24	2	3
22 to 23	32	2	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>84</b>	<b>84</b>

## Nagpur Metro Rail Network

Line 1: North - South Corridor

TABLE 1.5 B

## Hourly Train Operation Plan for CONGRESS NAGAR to KHAPARI

Year: 2036

Configuration: 3 Car

Headway(min): 7

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	24	3	2
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	7	8	9
9 to 10	7	9	9
10 to 11	7	8	9
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	24	2	3
14 to 15	24	3	2
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	7	9	8
18 to 19	7	9	9
19 to 20	7	9	8
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	24	2	3
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>100</b>	<b>100</b>

## Nagpur Metro Rail Network

Line 1: North - South Corridor

TABLE 1.5 B

Hourly Train Operation Plan for CONGRESS NAGAR to KHAPARI

Year: 2041

Configuration: 3 Car

Headway(min): 6

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	24	2	3
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	6	10	10
9 to 10	6	10	10
10 to 11	6	10	10
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	24	3	2
14 to 15	24	2	3
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	6	10	10
18 to 19	6	10	10
19 to 20	6	10	10
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	24	3	2
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>108</b>	<b>108</b>

**Nagpur Metro Rail Network**  
**Line 2 - East - West Corridor**

TABLE 1.7 A

Hourly Train Operation Plan for PRAJAPATI NAGAR to AGAR SEN CHOWK

Year: 2016

Configuration: 3 Car

Headway(Min): 15

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	48	1	1
6 to 7	40	2	1
7 to 8	20	3	3
8 to 9	15	4	5
9 to 10	15	5	4
10 to 11	15	4	5
11 to 12	20	3	3
12 to 13	40	1	2
13 to 14	48	1	2
14 to 15	48	2	1
15 to 16	40	2	1
16 to 17	20	3	3
17 to 18	15	5	4
18 to 19	15	4	5
19 to 20	15	5	4
20 to 21	20	3	3
21 to 22	40	1	2
22 to 23	48	1	1
23 to 24	60	1	1
<b>Total No. of train trips per direction per day</b>		<b>51</b>	<b>51</b>

TABLE 1.5 A

Hourly Train Operation Plan for PRAJAPATI NAGAR to AGAR SEN CHOWK

Year: 2021

Configuration: 3 Car

Headway (min): 12

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	48	1	1
6 to 7	40	2	1
7 to 8	20	3	3
8 to 9	12	5	5
9 to 10	12	5	5
10 to 11	12	5	5
11 to 12	20	3	3
12 to 13	40	1	2
13 to 14	48	2	1
14 to 15	48	1	2
15 to 16	40	2	1
16 to 17	20	3	3
17 to 18	12	5	5
18 to 19	12	5	5
19 to 20	12	5	5
20 to 21	20	3	3
21 to 22	40	1	2
22 to 23	48	1	1
23 to 24	60	1	1
<b>Total No. of train trips per direction per day</b>		<b>54</b>	<b>54</b>



TABLE 1.9 A

Hourly Train Operation Plan for PRAJAPATI NAGAR to AGAR SEN CHOWK

Year: 2026

Configuration: 3 Car

Headway(min): 10

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	2
6 to 7	24	3	2
7 to 8	18	4	3
8 to 9	10	6	6
9 to 10	10	6	6
10 to 11	10	6	6
11 to 12	18	4	3
12 to 13	24	3	3
13 to 14	32	2	2
14 to 15	32	2	2
15 to 16	24	3	2
16 to 17	18	3	4
17 to 18	10	6	6
18 to 19	10	6	6
19 to 20	10	6	6
20 to 21	18	3	4
21 to 22	24	3	3
22 to 23	32	2	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>70</b>	<b>70</b>

TABLE 1.10 A

Hourly Train Operation Plan for PRAJAPATI NAGAR to AGAR SEN CHOWK

Year: 2031

Configuration: 3 Car

Headway(min): 6

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	1	2
6 to 7	24	3	2
7 to 8	12	5	5
8 to 9	6	6	6
9 to 10	6	6	6
10 to 11	6	6	6
11 to 12	12	5	5
12 to 13	24	2	3
13 to 14	32	2	1
14 to 15	32	1	2
15 to 16	24	3	2
16 to 17	12	5	5
17 to 18	6	6	6
18 to 19	6	6	6
19 to 20	6	6	6
20 to 21	12	5	5
21 to 22	24	2	3
22 to 23	32	2	1
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>74</b>	<b>74</b>

TABLE 1.11 A

Hourly Train Operation Plan for PRAJAPATI NAGAR to AGAR SEN CHOWK

Year: 2036

Configuration: 3 Car

Headway (min): 8

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	1
6 to 7	24	3	2
7 to 8	12	5	5
8 to 9	8	7	8
9 to 10	8	8	7
10 to 11	8	7	8
11 to 12	12	5	5
12 to 13	24	3	3
13 to 14	32	1	2
14 to 15	32	2	1
15 to 16	24	3	2
16 to 17	12	5	5
17 to 18	8	8	7
18 to 19	8	7	8
19 to 20	8	8	7
20 to 21	12	5	5
21 to 22	24	3	3
22 to 23	32	1	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>83</b>	<b>83</b>

TABLE 1.12 A

Hourly Train Operation Plan for PRAJAPATI NAGAR to AGAR SEN CHOWK

Year: 2041

Configuration: 3 Car

Headway (min): 7

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	24	2	3
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	7	8	8
9 to 10	7	8	8
10 to 11	7	8	8
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	24	3	2
14 to 15	24	2	3
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	7	8	8
18 to 19	7	8	8
19 to 20	7	8	8
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	24	3	2
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>96</b>	<b>96</b>

**Nagpur Metro Rail Network**  
**Line 2 - East - West Corridor**

TABLE 1.7 B

Hourly Train Operation Plan for AGAR SEN CHOWK to SUBHASH NAGAR

Year: 2016

Configuration: 3 Car

Headway (min): 6.5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	20	3	2
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	6.5	8	8
9 to 10	6.5	8	8
10 to 11	6.5	8	8
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	20	3	2
14 to 15	20	2	3
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	6.5	8	8
18 to 19	6.5	8	8
19 to 20	6.5	8	8
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	20	2	3
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>162</b>	<b>162</b>

TABLE 1.5 B

Hourly Train Operation Plan for AGAR SEN CHOWK to SUDHASH NAGAR

Year: 2021

Configuration: 3 Car

Headway (min): 6

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	34	3	2
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	6	10	10
9 to 10	6	10	10
10 to 11	6	10	10
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	24	3	2
14 to 15	24	2	3
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	6	10	10
18 to 19	6	10	10
19 to 20	6	10	10
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	24	2	3
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>108</b>	<b>108</b>

TABLE 1.3 B

Hourly Train Operation Plan for AGAR SEN CHOWK to SUBHASH NAGAR  
 Year: 2026  
 Configuration: 3 Car  
 Headway(min): 5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	15	4	4
6 to 7	12	5	5
7 to 8	8	6	7
8 to 9	5	12	12
9 to 10	5	12	12
10 to 11	5	12	12
11 to 12	8	6	7
12 to 13	12	5	5
13 to 14	15	4	3
14 to 15	15	3	4
15 to 16	12	5	5
16 to 17	8	7	6
17 to 18	5	12	12
18 to 19	5	12	12
19 to 20	5	12	12
20 to 21	8	7	6
21 to 22	12	5	5
22 to 23	15	4	4
23 to 24	20	3	3
<b>Total No. of train trips per direction per day</b>		<b>140</b>	<b>140</b>

TABLE 1.10 D

Hourly Train Operation Plan for AGAR SEN CHOWK to SUBHASH NAGAR

Year: 2031

Configuration: 3 Car

Headway(min): 4.5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	16	3	4
6 to 7	12	5	5
7 to 8	6	10	10
8 to 9	4.5	14	13
9 to 10	4.5	13	14
10 to 11	4.5	14	13
11 to 12	6	10	10
12 to 13	12	5	5
13 to 14	16	4	3
14 to 15	16	3	4
15 to 16	12	5	5
16 to 17	6	10	10
17 to 18	4.5	13	14
18 to 19	4.5	14	13
19 to 20	4.5	13	14
20 to 21	6	10	10
21 to 22	12	5	5
22 to 23	16	4	3
23 to 24	20	3	3
<b>Total No. of train trips per direction per day</b>		<b>168</b>	<b>168</b>



TABLE 1.11 B

Hourly Train Operation Plan for AGAR SEN CHOWK to SUDHASH NAGAR

Year: 2036

Configuration: 3 Car

Headway/Min: 4

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	16	3	3
6 to 7	12	5	5
7 to 8	6	10	10
8 to 9	4	15	15
9 to 10	4	15	15
10 to 11	4	15	15
11 to 12	6	10	10
12 to 13	12	5	5
13 to 14	16	4	3
14 to 15	16	3	4
15 to 16	12	5	5
16 to 17	6	10	10
17 to 18	4	15	15
18 to 19	4	15	15
19 to 20	4	15	15
20 to 21	6	10	10
21 to 22	12	5	5
22 to 23	16	3	3
23 to 24	20	3	3
<b>Total No. of train trips per direction per day</b>		<b>166</b>	<b>166</b>

TABLE 1.12 B

Hourly Train Operation Plan for AGAR SEN CHOWK to SUDHASH NAGAR

Year: 2041

Configuration: 3 Car

Headway/Min: 3.5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	12	5	5
6 to 7	10	6	6
7 to 8	5	12	12
8 to 9	3.5	17	17
9 to 10	3.5	17	17
10 to 11	3.5	17	17
11 to 12	5	12	12
12 to 13	10	6	6
13 to 14	12	5	5
14 to 15	12	5	5
15 to 16	10	6	6
16 to 17	5	12	12
17 to 18	3.5	17	17
18 to 19	3.5	17	17
19 to 20	3.5	17	17
20 to 21	5	12	12
21 to 22	10	6	6
22 to 23	12	5	5
23 to 24	15	4	4
<b>Total No. of train trips per direction per day</b>		<b>158</b>	<b>158</b>

**Nagpur Metro Rail Network**  
**Line 2 - East - West Corridor**

TABLE 1.7 C

Hourly Train Operation Plan for **SUBHASH NAGAR to LOKMANYA NAGAR**

Year: 2016

Configuration: 3 Car

Headway(Min): 15

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	48	1	1
6 to 7	40	2	1
7 to 8	20	3	3
8 to 9	15	4	5
9 to 10	15	5	4
10 to 11	15	4	5
11 to 12	20	3	3
12 to 13	40	1	2
13 to 14	48	1	2
14 to 15	48	2	1
15 to 16	40	2	1
16 to 17	20	3	3
17 to 18	15	5	4
18 to 19	15	4	5
19 to 20	15	5	4
20 to 21	20	3	3
21 to 22	40	1	2
22 to 23	48	1	1
23 to 24	60	1	1
<b>Total No. of train trips per direction per day</b>		<b>51</b>	<b>51</b>

TABLE 1.B.C

Hourly Train Operation Plan for SUDHASH NAGAR to LOKMANYA NAGAR

Year: 2021

Configuration: 3 Car

Headway(min): 12

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	48	1	1
6 to 7	40	2	1
7 to 8	20	3	3
8 to 9	12	5	5
9 to 10	12	5	5
10 to 11	12	5	5
11 to 12	20	3	3
12 to 13	40	1	2
13 to 14	48	2	1
14 to 15	48	1	2
15 to 16	40	2	1
16 to 17	20	3	3
17 to 18	12	5	5
18 to 19	12	5	5
19 to 20	12	5	5
20 to 21	20	3	3
21 to 22	40	1	2
22 to 23	48	1	1
23 to 24	60	1	1
<b>Total No. of train trips per direction per day</b>		<b>54</b>	<b>54</b>

TABLE 1.3 C

Hourly Train Operation Plan for SURESH NAGAR to LOKMANYA NAGAR  
 Year: 2026  
 Configuration: 3 Car  
 Headway(min): 10

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	2
6 to 7	24	3	2
7 to 8	18	4	3
8 to 9	10	6	6
9 to 10	10	6	6
10 to 11	10	6	6
11 to 12	18	4	3
12 to 13	24	3	3
13 to 14	32	2	2
14 to 15	32	2	2
15 to 16	24	3	2
16 to 17	18	3	4
17 to 18	10	6	6
18 to 19	10	6	6
19 to 20	10	6	6
20 to 21	18	3	4
21 to 22	24	3	3
22 to 23	32	2	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>70</b>	<b>70</b>

TABLE 1.10 C

Hourly Train Operation Plan for SUSHASH NAGAR to LOKMANYA NAGAR  
 Year: 2031  
 Configuration: 3 Car  
 Headway(min): 5

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	1	2
6 to 7	24	3	2
7 to 8	12	5	5
8 to 9	5	6	6
9 to 10	5	6	6
10 to 11	5	6	6
11 to 12	12	5	5
12 to 13	24	3	3
13 to 14	32	2	1
14 to 15	32	1	2
15 to 16	24	3	2
16 to 17	12	5	5
17 to 18	5	6	6
18 to 19	5	6	6
19 to 20	5	6	6
20 to 21	12	5	5
21 to 22	24	3	3
22 to 23	32	2	1
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>74</b>	<b>74</b>

TABLE 1.11 C

Hourly Train Operation Plan for SUDHASH NAGAR to LOKMANYA NAGAR

Year: 2036

Configuration: 3 Car

Headway (min): 8

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	32	2	1
6 to 7	24	3	2
7 to 8	12	5	5
8 to 9	8	7	8
9 to 10	8	8	7
10 to 11	8	7	8
11 to 12	12	5	5
12 to 13	24	3	3
13 to 14	32	1	2
14 to 15	32	2	1
15 to 16	24	3	2
16 to 17	12	5	5
17 to 18	8	8	7
18 to 19	8	7	8
19 to 20	8	8	7
20 to 21	12	5	5
21 to 22	24	3	3
22 to 23	32	1	2
23 to 24	40	2	2
<b>Total No. of train trips per direction per day</b>		<b>83</b>	<b>83</b>

TABLE 1.12 C

Hourly Train Operation Plan for SUDHASH NAGAR to LOKMANYA NAGAR

Year: 2041

Configuration: 3 Car

Headway(min): 7

Time of Day	Headway in Minutes	No. of Trains per day	
		UP	DN
5 to 6	24	2	3
6 to 7	20	3	3
7 to 8	10	6	6
8 to 9	7	8	8
9 to 10	7	8	8
10 to 11	7	8	8
11 to 12	10	6	6
12 to 13	20	3	3
13 to 14	24	3	2
14 to 15	24	2	3
15 to 16	20	3	3
16 to 17	10	6	6
17 to 18	7	8	8
18 to 19	7	8	8
19 to 20	7	8	8
20 to 21	10	6	6
21 to 22	20	3	3
22 to 23	24	3	2
23 to 24	30	2	2
<b>Total No. of train trips per direction per day</b>		<b>96</b>	<b>96</b>



**TABLE 2.1**  
**Line 1 : North - South Corridor**  
**(PKM) for the Year 2018**

S.No	From Station	To Station	Maximum (PKM)	Unidirectional Split to KSRM	Unidirectional Split to A/C/DM/IN ± 20%
1	RAJGOMATI VILLAGE	RAJGOMATI	1381	30%	30%
2	SAHIBGAD	RAJGOMATI	1714	30%	30%
3	INDIRA CRUISE	RAJGOMATI	1880	30%	30%
4	RAJGOMATI	RAJGOMATI CROSSING	2038	30%	30%
5	SAHIBGAD	RAJGOMATI CROSSING	2202	30%	30%
6	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2158	30%	30%
7	VEDI HILL	RAJGOMATI	2212	30%	30%
8	NETAJI	RAJGOMATI CROSSING	2308	30%	30%
9	LONGIRI CROSSING	RAJGOMATI CROSSING	2438	30%	30%
10	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2512	30%	30%
11	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2600	30%	30%
12	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2687	30%	30%
13	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2778	30%	30%
14	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2868	30%	30%
15	RAJGOMATI CROSSING	RAJGOMATI CROSSING	2958	30%	30%
16	RAJGOMATI CROSSING	RAJGOMATI CROSSING	3048	30%	30%

**TABLE 2.2**  
**Line 2 : East - West Corridor**  
**(PKM) for the Year 2018**

S.No	From Station	To Station	Maximum (PKM)	Unidirectional Split to LUPRAMPA NAGAR	Unidirectional Split to PRAJAPATI NAGAR
1	PRAJAPATI NAGAR	PRAJAPATI CROSSING	401	30%	30%
2	PRAJAPATI CROSSING	PRAJAPATI CROSSING	503	30%	30%
3	PRAJAPATI CROSSING	TELEPHONE EXCHANGE	1103	30%	30%
4	TELEPHONE EXCHANGE	TELEPHONE CROSSING	2013	30%	30%
5	TELEPHONE CROSSING	RAJGOMATI CROSSING	2923	30%	30%
6	RAJGOMATI CROSSING	RAJGOMATI CROSSING	3833	30%	30%
7	RAJGOMATI CROSSING	RAJGOMATI CROSSING	4743	30%	30%
8	RAJGOMATI CROSSING	RAJGOMATI CROSSING	5653	30%	30%
9	RAJGOMATI CROSSING	RAJGOMATI CROSSING	6563	30%	30%
10	RAJGOMATI CROSSING	RAJGOMATI CROSSING	7473	30%	30%
11	RAJGOMATI CROSSING	RAJGOMATI CROSSING	8383	30%	30%
12	RAJGOMATI CROSSING	RAJGOMATI CROSSING	9293	30%	30%
13	RAJGOMATI CROSSING	RAJGOMATI CROSSING	10203	30%	30%
14	RAJGOMATI CROSSING	RAJGOMATI CROSSING	11113	30%	30%
15	RAJGOMATI CROSSING	RAJGOMATI CROSSING	12023	30%	30%
16	RAJGOMATI CROSSING	RAJGOMATI CROSSING	12933	30%	30%
17	RAJGOMATI CROSSING	RAJGOMATI CROSSING	13843	30%	30%
18	RAJGOMATI CROSSING	RAJGOMATI CROSSING	14753	30%	30%



**Table 1**  
**Summary of the**  
**Study**

Page 1

Study	Year	Country	Sample Size	Age Range	Gender	Education	Occupation	Income	Health Status	Life Satisfaction	Well-being
1	2010	USA	1000	18-65	M/F	High	Professional	High	Good	High	High
2	2011	UK	1200	25-75	M/F	Medium	Service	Medium	Fair	Medium	Medium
3	2012	Canada	800	30-80	M/F	Low	Unemployed	Low	Poor	Low	Low
4	2013	Australia	900	20-90	M/F	High	Professional	High	Good	High	High
5	2014	Germany	1100	15-85	M/F	Medium	Service	Medium	Fair	Medium	Medium
6	2015	France	1300	20-95	M/F	High	Professional	High	Good	High	High
7	2016	Italy	1000	25-75	M/F	Medium	Service	Medium	Fair	Medium	Medium
8	2017	Spain	900	30-80	M/F	Low	Unemployed	Low	Poor	Low	Low
9	2018	Japan	1100	15-85	M/F	High	Professional	High	Good	High	High
10	2019	China	1500	20-90	M/F	Medium	Service	Medium	Fair	Medium	Medium
11	2020	India	1200	25-75	M/F	Low	Unemployed	Low	Poor	Low	Low
12	2021	Brazil	1000	30-80	M/F	Medium	Service	Medium	Fair	Medium	Medium
13	2022	South Africa	800	20-90	M/F	Low	Unemployed	Low	Poor	Low	Low
14	2023	South Korea	1100	15-85	M/F	High	Professional	High	Good	High	High
15	2024	USA	1000	18-65	M/F	High	Professional	High	Good	High	High

### Rate Requirement

Nagpur Metro Rail Network

#### Line 1, North - South Corridor, Year: 2018

Section	Distance (km)	Schedule Speed in kmph	Frequency (per hr)	Rolling Requirement					
				Cars	Trains (Cars)	R&D	Total No. of Rakes	No. of Cars per rake	No. of Cars
Assumative Cars to be used	10.40	34.00	11	9	1	1	9	2	18
Assumative Cars to be used in Complete Stage	1.00	33.00	11	9	0	0	9	2	18
				9	1	1	11		36

Note: Revised Rolling Stock required in Complete Stage:

Rolling Stock required in Complete Stage:

Section	Effective Frequency	No. of Trains	No. of Cars
Assumative Cars to be used in Complete Stage	1	11 Rakes of 2 cars	22
Complete Stage to be used	10		

Total Rolling Stock Required: 2

#### Line 1, North - South Corridor, Year: 2019

Section	Distance (km)	Schedule Speed in kmph	Frequency (per hr)	Rolling Requirement					
				Cars	Trains (Cars)	R&D	Total No. of Rakes	No. of Cars per rake	No. of Cars
Assumative Cars to be used	10.40	34.00	11	9	1	1	9	2	18
Assumative Cars to be used in Complete Stage	1.00	33.00	11	9	0	0	9	2	18
				9	1	1	11		36

Note: Revised Rolling Stock required in Complete Stage:

Rolling Stock required in Complete Stage:

Section	Effective Frequency	No. of Trains	No. of Cars
Assumative Cars to be used in Complete Stage	1	11 Rakes of 2 cars	22
Complete Stage to be used	10		

Total Rolling Stock Required: 2

#### Line 1, North - South Corridor, Year: 2020

Section	Distance (km)	Schedule Speed in kmph	Frequency (per hr)	Rolling Requirement					
				Cars	Trains (Cars)	R&D	Total No. of Rakes	No. of Cars per rake	No. of Cars
Assumative Cars to be used	10.40	34.00	9	9	1	1	11	2	22
Assumative Cars to be used in Complete Stage	1.00	33.00	9	9	0	0	9	2	18
				9	1	1	11		22

Note: Revised Rolling Stock required in Complete Stage:

Rolling Stock required in Complete Stage:

Section	Effective Frequency	No. of Trains	No. of Cars
Assumative Cars to be used in Complete Stage	9	11 Rakes of 2 cars	22
Complete Stage to be used	9		

Total Rolling Stock Required: 2

### Route Requirement

Nagpur Metro Rail Network

#### Line 1 : North - South Corridor, Year : 2021

Section	Distance (km)	Schedule Speed in kmph	Frequency (min)	Route Requirements					
				Cars	Traffic Density	EMU	Total No. of Buses	No. of Cars per min.	No. of Cars
Assumative Cars to be used	10.40	24.00	5	5	1	1	10	2	10
Assumative Cars to Complete Route	7.00	22.00	5	5	0	1	5	2	10
				10	1	2	15		20

Note: Revised facility required in Complete Stage.

Above main Expansion resulting in:

Section	Effective frequency	No. of Trains	No. of Car
Assumative Cars to Complete Stage	1	27 Times of 2 cars	54
Complete Stage to be used	5		

Total Train/Bus/Tram: 1

#### Line 1 : North - South Corridor, Year : 2022

Section	Distance (km)	Schedule Speed in kmph	Frequency (min)	Route Requirements					
				Cars	Traffic Density	EMU	Total No. of Buses	No. of Cars per min.	No. of Cars
Assumative Cars to be used	10.40	24.00	7	11	1	1	13	2	13
Assumative Cars to Complete Stage	7.00	22.00	7	7	0	1	7	2	14
				18	1	2	20		27

Note: Revised facility required in Complete Stage.

Above main Expansion resulting in:

Section	Effective frequency	No. of Trains	No. of Car
Assumative Cars to Complete Stage	2.0	30 Times of 2 cars	60
Complete Stage to be used	7		

Total Train/Bus/Tram: 1

#### Line 1 : North - South Corridor, Year : 2023

Section	Distance (km)	Schedule Speed in kmph	Frequency (min)	Route Requirements					
				Cars	Traffic Density	EMU	Total No. of Buses	No. of Cars per min.	No. of Cars
Assumative Cars to be used	10.40	24.00	8	12	1	1	14	2	14
Assumative Cars to Complete Stage	7.00	22.00	8	8	0	1	7	2	16
				20	1	2	16		20

Note: Revised facility required in Complete Stage.

Above main Expansion resulting in:

Section	Effective frequency	No. of Trains	No. of Car
Assumative Cars to Complete Stage	2	27 Times of 2 cars	54
Complete Stage to be used	8		

Total Train/Bus/Tram: 1

### Ramp Requirements Bhopal Metro Rail Network

**Line 2: East - West Corridor, Year - 2012**

Section	Distance (km)	Schedule Speed (km/hr)	Frequency (hrly)	Ramp Requirements					
				Link	Traffic Density	ADD Tonnage of Trucks per side	No. of Cars per side	No. of Cars	
Proposed Vagda to Lal Bahadur Shastri	17.42	30.00	10	8	1	1	8	1	24
Agarwal Chowk to Subhash Nagar	8.18	30.00	10	4	0	0	4	2	12
				12	1	1	12		36

Note: Barakha facility required at Agarwal Chowk and Subhash Nagar

## Above with Expanded Resulting In:

Section	Effective Frequency	No. of Buses	No. of Car
Agarwal Chowk to Subhash Nagar	0.2	12 Buses of 2 MT	36
Proposed Vagda to Agarwal Chowk and Subhash Nagar to Lal Bahadur Shastri	0.2		
Total Turn Round Time (min)		6	

**Line 2: East - West Corridor, Year - 2011**

Section	Distance (km)	Schedule Speed (km/hr)	Frequency (hrly)	Ramp Requirements					
				Link	Traffic Density	ADD Tonnage of Trucks per side	No. of Cars per side	No. of Cars	
Proposed Vagda to Lal Bahadur Shastri	17.42	30.00	10	8	1	1	8	1	27
Agarwal Chowk to Subhash Nagar	8.18	30.00	10	4	0	0	4	2	12
				12	1	1	12		39

Note: Barakha facility required at Agarwal Chowk and Subhash Nagar

## Above with Expanded Resulting In:

Section	Effective Frequency	No. of Buses	No. of Car
Agarwal Chowk to Subhash Nagar	0.2	12 Buses of 2 MT	36
Proposed Vagda to Agarwal Chowk and Subhash Nagar to Lal Bahadur Shastri	0.2		
Total Turn Round Time (min)		6	

**Line 1: East - West Corridor, Year - 2016**

Section	Distance (km)	Schedule Speed (km/hr)	Frequency (hrly)	Ramp Requirements					
				Link	Traffic Density	ADD Tonnage of Trucks per side	No. of Cars per side	No. of Cars	
Proposed Vagda to Lal Bahadur Shastri	17.42	30.00	10	8	1	1	8	1	22
Agarwal Chowk to Subhash Nagar	8.18	30.00	10	4	0	0	4	2	11
				12	1	1	12		33

Note: Barakha facility required at Agarwal Chowk and Subhash Nagar

## Above with Expanded Resulting In:

Section	Effective Frequency	No. of Buses	No. of Car
Agarwal Chowk to Subhash Nagar	0.2	12 Buses of 2 MT	36
Proposed Vagda to Agarwal Chowk and Subhash Nagar to Lal Bahadur Shastri	0.2		
Total Turn Round Time (min)		6	

### Rake Requirement

#### Boggar Metro Rail Network

#### Line 1: East - West Corridor, Year - 2021

Station	Distance (km)	Schedule Speed (km/h)	Inventory (km)	Rake Requirement					
				Line	Traffic Density	RAM	Turn No. of Rakes	No. of Cars per rake	No. of Cars
Proposed Stage in Lumbiniya Stage	17.42	30.00	0	0	1	1	11	1	11
Agreed Check in Suburban Stage	3.18	30.00	0	0	0	1	2	2	11
				10	1	2	13		22

Note: Revised Rake(s) required in Agreed Check and Suburban Stage

Break into 2 quarter meeting in:

Station	Effective Inventory	No. of Rakes	No. of Car
Agreed Check in Suburban Stage	3.18	17 Rakes of 2 cars	34
Proposed Stage in Agreed Check and Suburban Stage in Lumbiniya Stage	0		
Total Turn Round Time(s)	4		

#### Line 2: East - West Corridor, Year - 2022

Station	Distance (km)	Schedule Speed (km/h)	Inventory (km)	Rake Requirement					
				Line	Traffic Density	RAM	Turn No. of Rakes	No. of Cars per rake	No. of Cars
Proposed Stage in Lumbiniya Stage	17.42	30.00	0	10	1	1	12	2	22
Agreed Check in Suburban Stage	3.18	30.00	0	0	0	1	2	2	11
				10	1	2	14		33

Note: Revised Rake(s) required in Agreed Check and Suburban Stage

Break into 2 quarter meeting in:

Station	Effective Inventory	No. of Rakes	No. of Car
Agreed Check in Suburban Stage	3	16 Rakes of 2 cars	32
Proposed Stage in Agreed Check and Suburban Stage in Lumbiniya Stage	0		
Total Turn Round Time(s)	4		

#### Line 3: East - West Corridor, Year - 2023

Station	Distance (km)	Schedule Speed (km/h)	Inventory (km)	Rake Requirement					
				Line	Traffic Density	RAM	Turn No. of Rakes	No. of Cars per rake	No. of Cars
Proposed Stage in Lumbiniya Stage	17.42	30.00	0	11	1	1	13	2	23
Agreed Check in Suburban Stage	3.18	30.00	0	0	0	1	2	2	11
				11	1	2	15		34

Note: Revised Rake(s) required in Agreed Check and Suburban Stage

Break into 2 quarter meeting in:

Station	Effective Inventory	No. of Rakes	No. of Car
Agreed Check in Suburban Stage	3.18	16 Rakes of 2 cars	32
Proposed Stage in Agreed Check and Suburban Stage in Lumbiniya Stage	0		
Total Turn Round Time(s)	6		

# CHAPTER 8

## ROLLING STOCK



- 8.1 INTRODUCTION
- 8.2 OPTIMIZATION OF COACH SIZE
- 8.3 PASSENGER CARRYING CAPACITY
- 8.4 WEIGHT
- 8.5 PERFORMANCE PARAMETERS
- 8.6 COACH DESIGN AND BASIC PARAMETERS
- 8.7 SELECTION OF TECHNOLOGY

### TABLES

- TABLE 8.1 SIZE OF COACH
- TABLE 8.2 CARRYING CAPACITY OF MODERN RAIL VEHICLE
- TABLE 8.3 WEIGHT OF LIGHT RAIL VEHICLES (TRAINS)

### FIGURES

- FIG. 8.1 PERFORMANCE PARAMETERS
- FIG. 8.2 INTERIOR VIEW OF THE COACH
- FIG. 8.3 VIEW OF THE PASSENGER DOOR
- FIG. 8.4 VIEW OF THE DRIVING CAB
- FIG. 8.5 VIEW OF THE GARAGE

### ATTACHMENT

- ATTACHMENT 1 SALIENT FEATURES OF THE PROPOSED ROLLING STOCK





## ROLLING STOCK

### 6.1 INTRODUCTION

The required transport demand forecast is the governing factor for the choice of the Rolling Stock. The forecasted Peak Hour Peak Direction Traffic calls for a Medium Rail Transit System (MRTS).

### 6.2 OPTIMIZATION OF COACH SIZE

The following optimum size of the coach has been chosen for this corridor as mentioned in Table 6.1.

Table 6.1  
Size of the coach

	Length*	Width	Height
Driving Motor Car (DMC)	21.84 m	2.9 m	3.9 m
Trailer car (TC)/Motor Car (MC)	21.24 m	2.9 m	3.9 m

\*Maximum length of coach over couplers/buffers = 23.6 m

### 6.3 PASSENGER CARRYING CAPACITY

In order to maximize the passenger carrying capacity, longitudinal seating arrangement shall be adopted. The whole train shall be vestibuled to distribute the passenger evenly in all the coaches. Criteria for the calculation of standing passengers are 3 persons per square meter of standing floor area in normal state and 6 persons in crush state of peak hour.

Therefore, for the Medium Rail Vehicles (MRV) with 2.9 m maximum width and longitudinal seat arrangement, conceptually the crush capacity of 43 seated, 304 standing thus a total of 247 passengers for a Driving motor car, and 60 seated, 320 standing thus a total of 270 for a trailer/motor car is envisaged.



Following train composition is recommended:

3-car Train: DMC+TC+DMC

Table 6.2 shows the carrying capacity of Medium Rail Vehicles:

**Table 6.2**  
Carrying Capacity of Medium Rail Vehicles

Particulars	Driving Motor car		Trailer car / Motor car		3 Car Train	
	Normal	Crush	Normal	Crush	Normal	Crush
Seated	43	42	50	58	130	138
Standing	102	284	110	220	314	628
<b>Total</b>	<b>145</b>	<b>247</b>	<b>160</b>	<b>278</b>	<b>430</b>	<b>764</b>

NORMAL – 3 Persons/m<sup>2</sup> of standing area

CRUSH – 8 Persons/m<sup>2</sup> of standing area

#### 6.4 WEIGHT

The weights of motorcar and trailer cars have been estimated as in Table 6.3, referring to the experiences in Delhi Metro. The average passenger weight has been taken as 65 kg.

**Table 6.3: Weight of Light Rail Vehicles (Tonnes)**

	DMC	TC	3 Car Train
<b>TARE (maximum)</b>	40	40	120
<b>Passenger</b>			
(Normal)	3.425	12.4	25.20
(Crush @50%)	16.050	17.55	45.60
(Crush @50%)	20.475	22.200	63.245
<b>Gross</b>			
(Normal)	43.425	52.4	148.25
(Crush @50%)	56.050	67.55	189.60
(Crush @50%)	66.475	82.255	189.23
Axle Load @3 persons/m <sup>2</sup>	14.014	14.388	
Axle Load @8 persons/m <sup>2</sup>	15.119	15.577	



The axle load (i) Comparison of standing area works out in the range of 14.014T to 14.385T. Heavy rush of passenger, having 8 standees per sq. meter can be experienced occasionally. It will be advisable to design the coach with sufficient strength so that even with this overload, the design will not result in oval stresses in the coach. Coach and bogie should, therefore, be designed for **16 T axle load**.

### 2.5 PERFORMANCE PARAMETERS

The recommended performance parameters are:

- Maximum Design Speed: 90 kmph
- Maximum Operating Speed: 85 kmph
- Max. Acceleration:  $1.5 \text{ ms}^{-2}$
- Max. Deceleration:  $1.1 \text{ ms}^{-2}$  (Normal brake)
- More than  $1.3 \text{ ms}^{-2}$  (Emergency brake)




Fig. 2.1 : PERFORMANCE PARAMETERS

### 2.6 COACH DESIGN AND BASIC PARAMETERS

The important criteria for selection of rolling stock are as under:

- (i) Proven equipment with high reliability
- (ii) Passenger safety feature
- (iii) Energy efficiency
- (iv) Light weight equipment and coach body
- (v) Optimised scheduled speed
- (vi) Aesthetically pleasing Interior and Exterior
- (vii) Low Life cycle cost
- (viii) Flexibility to meet increase in traffic demand
- (ix) Anti-theft/copy



The controlling criteria are reliability, low energy consumption, lightweight and high efficiency leading to lower annualized cost of service. The coach should have high use of accelerates and decelerates.

## 6.7 SELECTION OF TECHNOLOGY

### 6.7.1 Low life cycle cost

Low life cycle cost is achieved by the way of reduced scheduled and unscheduled maintenance and high reliability of the sub-systems. It is possible to achieve these objectives by adopting suitable proven technologies. Selection of following technologies has been recommended to ensure low life cycle cost.

### 6.7.2 Car body

In the past carbon high tensile steel was invariably used for car bodies. In fact almost all the coaches built by Indian Railways are of this type. These steel bodied coaches need frequent painting and corrosion repairs, which may have to be carried out up to 4-5 times during the service life of these coaches. It is now a standard practice to adopt stainless steel or aluminum for carbody.

The car bodies with aluminum require long and complex extruded sections which are still not manufactured in India. Therefore aluminum car body has not been considered for use. Stainless steel sections are available in India and therefore stainless steel car bodies have been specified. No corrosion repair is necessary on stainless steel cars during their service life.

Stainless steel car body leads to energy saving due to its lightweight. It also results in cost saving due to easy maintenance and reduction of repair cost from excellent anti corrosive properties as well as on improvement of riding comfort and safety in case of a crash or fire.

### 6.7.3 Bogies

Roller type lightweight fabricated bogies with rubber springs are now universally adopted in metro cars. These bogies require less maintenance and overhaul interval is also of the order of 4,20,000km. Use of air spring at secondary stage is considered with a view to keep the floor level of the cars constant irrespective of passenger loading unlike those with coil spring. Perturbations from the track are also damped inside the car body on account of the secondary air spring along with suitable vertical Hydraulic Damper. The primary suspension system improves the curve running performance by



reducing lateral forces through application of conical rubber spring. A smooth tuning performance with better ride index is being ensured by provision of above type of bogies.

### 3.7.4 Braking System

The brake system shall consist of –

- (i) An electro-pneumatic (EP) service friction brake
- (ii) A fail safe, pneumatic friction emergency brake
- (iii) A spring applied air-release parking brake
- (iv) An electric regenerative service brake
- (v) Provision of smooth and continuous blending of EP and regenerative braking

The regenerative braking will be the main brake power of the train and will recover the maximum possible energy and pump it back to the system and thus fully utilize the advantage of 3 phase technology. The regenerative braking should have air supplement control to bear the load of trailer car. In addition, speed sensors mounted on each axle, control the braking time of the axle with air slit valves, promoting re-adhesion in case of a skid. The brake actuator shall operate either a tread brake or a wheel disc brake, preferably a wheel disc brake.

### 3.7.5 Propulsion System Technology

In the field of Electric Rolling Stock, DC series traction motors have been widely used due to its ideal characteristics and good controllability for traction applications. But these required intensive maintenance because of commutators and electro-mechanical contactors, resistors etc.

The brushless 3 phase induction motor has now replaced the D.C. series motor in traction applications. The induction motor, for the same power output, is smaller and lighter in weight and ideally suited for rail based Mass Rapid Transit applications. The motor torque effort and speed is regulated by Variable Voltage and Variable frequency control and can be programmed to suit the track profile and operating requirements.

Another advantage of 3 phase a.c. drive and

VVVF control is that regenerative braking can be introduced by inverting the frequency and the voltage to reverse the power flow and to allow braking to very low speed.

For this corridor, three phase a.c. traction drive that are self-ventilated, highly reliable, robust construction and back up by digital control have been recommended for adoption.

The AC catenary voltage is stepped down through a transformer and converted to DC voltage through converter and supply voltage to DC link, which feeds inverter operated with Pulse Width Modulation (PWM) control technology and using insulated Gate Bipolar

Transistors (IGBT). This three-phase variable voltage variable frequency subset drives the traction motors for propulsion.

Recently advanced IGBT has been developed for inverter units. The advanced IGBT contains an Insulation Gate Bipolar Transistor (IGBT) and gate drive circuit and protection. The advanced IGBT incorporates its own over current protection, short circuit protection, over temperature protection and low power supply detection. The IGBT has inherent protection from over current, short circuit, over temperature and low control voltage.

The inverter unit uses optical fiber cable to connect the control unit to the gate interface. This optical fiber cable transmits the gate signals to drive the advanced IGBT via the gate interface. This optical fiber cable provides electrical isolation between the advanced IGBT and the control unit and is impervious to electrical interference. These are recommended for adoption in TGVs of MRTS.

### 3.7.3 Interior and Gangways

Passenger capacity of a car is maximised in a Metro System by providing longitudinal seats for sitting and utilising the remaining space for standing passenger. Therefore all the equipments are mounted on the under frame for maximum space utilisation. The gangways are designed to give a wider comfortable standing space during peak hours along with easy and faster passenger movement especially in case of emergency.

Fig. 3.2 Interior View of the Car



### 3.7.7 Passenger Doors

For swift evacuation of the passenger in short dwell period, four doors of adequate width, on each side of the coach have been considered. These doors shall be of such dimensions and location that all the passenger inside the train are able to evacuate within least possible time without conflicting movement. As the alignment passes through elevated section above ground, automatic door closing mechanism is envisaged for consideration of passenger safety. Passenger doors are controlled electrically by a switch in Driver cab. Electrically controlled door opening mechanism has been



preferred over pneumatically operated door to avoid cases of air leakage and sluggish operation of doors.

The door shall be of **B-parting Sliding Type** as in the existing coaches of DMRC.

**Fig 3.3 : View of the Passenger Doors**



### 3.7.2 Air-conditioning

With heavy passenger loading of 8 persons/m<sup>2</sup> for standing area and doors being closed for consideration of safety and with windows being sealed type to avoid transmission of noise, air conditioning of coaches has been considered essential. Each coach shall be provided with two air conditioning units capable of cooling, heating and dehumidifying and thus automatically controlling interior temperature throughout the passenger area at 25°C with 65% RH at the times under varying ambient conditions up to full load. For emergency situations such as power failure or both AC failures etc, ventilation provision supplied from battery will be made. Provision shall be made to shut off the fresh air intake and re-circulate the internal air of the coach, during an emergency condition, such as fire, to inhibit the fresh air causing excessive heat and smoke to be drawn in to the coach.



### 6.7.8 Cab Layout and Emergency Detrainment Door

The modern stylish driver panel shall be FRP moulded which gives maximum comfort and easy accessibility of different monitoring equipments to the driver along with clear visibility. The driver seat has been provided at the left side of the cabin.

Fig.6.4 : View of the Driving Cab



An emergency door for easy detrainment of the passenger on the track has been provided at the center of the front side of the coach cabin which has a easy operation with one handle type master controller.

### 6.7.9 Communication

The driving cab of the coach are provided with continuous communication with base Operational Control Center and station control for easy monitoring of the individual train in all sections at all the time .

Public Address and Passenger Information Display System is provided in the coach so that passengers are continuously advised of the next stoppage station, final destination station, interchange station, emergency situations if any, and other messages. The rolling stock is provided with Talk Back Units inside the coach, which permit conversation between passengers and the drivers in case of any emergency.

### 6.7.11 Noise and Vibration

The trains will pass through heavily populated urban areas. The noise and vibration for a metro railway becomes an important criteria from public acceptance view point. The source of noise are (i) rail-wheel interaction (ii) noise generated from equipment like Blower, Compressor, air conditioner, door, Inverter etc. (iii) traction motor in running train. For elimination and reduction of noise following feature are incorporated: -

- Provision of anti clunking floor and noise absorption material.
- Low speed compressor, blower and air conditioner.
- Mounting of under frame equipments on anti vibration pad
- Smooth and gradual control of door.





- Provision of DRP bells on the via-duct for elimination of noise transmission.
- Provision of sound absorbing material in the supply duct and return grill of air conditioner.
- Sealing design to reduce the aspiration of noise through the gap in the sliding doors and joining holes.

The lower vibration level has been achieved by provision of better loss type bogies having secondary air spring.

### 6.7.10 Passenger Safety Features

#### (i) ATP

The rolling stock is provided with Continuous Automatic Train Protection to ensure absolute safety in the train operation. It is an accepted fact that 63-70% of the accidents take place on account of human error. Adoption of this system reduces the possibility of human error.

#### (ii) Fire

The rolling stock is provided with the relining materials having low fire and low heat release rate, low smoke and toxicity inside the cars. The electric cables used are also normally low smoke and halogen type which ensures passenger safety in case of fire.

#### (iii) Emergency door

The rolling stock is provided with emergency doors at both ends of the coach to ensure well directed evacuation of passengers in case of any emergency including fire in the coach.

#### (iv) Crash worthiness features

The rolling stock is provided with inter-car couplers having crashworthiness feature which reduces the severity of injury to the passengers in case of accidents.

#### (v) Gangways

Broad gangways are provided in between the cars to ensure free passenger movement between cars in case of any emergency.



Fig.2.5 : View of the Gangway

The select features of the proposed Rolling Stock are enclosed as Attachment-I

**Salient Features of Rolling Stock for MRTS**

S.No	Parameter	Details
1	Gauge (Nominal)	1435mm
2	Traction system	
2.1	Voltage	25 KV AC
2.2	Method of current collection	Overhead Current Collection System
3	Train composition	
3.1	3 car trainset	DMC+TC+DMC
4	Coach Body	Stainless Steel
5	Coach Dimensions	
5.1	Height	3.9 m
5.2	Width	2.9 m
5.3	Length over body (approx)	
	- Driving Motor Car (DMC)	21.64 m
	- Trailer Car (TC)	21.34 m
	(Maximum length of coach over coupler buffer)	22 to 22.6 m (depending upon Kinematic @ vehicle)
5.4	Locked down Point height (if applicable)	400 mm
5.5	Floor height	1100mm
6	Designed - Passenger Loading	
6.1	Design of Propulsion equipment	3 Passenger/ m <sup>2</sup>
6.2	Design of Mechanical systems	10 Passenger/ m <sup>2</sup>
7	Carrying capacity - @ 6 stances/seat	
7.1	Coach carrying capacity	DMC: 247 (sitting - 43 ; standing - 204) TC: 270 (sitting - 50 ; standing - 220)
7.2	Train Carrying capacity	3 car train: 704 (sitting - 135 ; standing - 620)
8	Weight (Tonnes)	
8.1	Total weight (maximum)	DMC: 40 TC: 40
8.2	Passenger Weight in tons @ 6 stances/seat	@ 0.065 T per passenger
		DMC: 15.055 TC: 17.55
8.3	Gross weight in tons	DMC: 55.055 TC: 57.55
9	Axle load/Tr @ 3 persons per sqm of stances (max)	18 (System should be designed for 18T axleload)
10	Maximum Train Length - Approximate	
10.1	3 car trainset	<60



<b>11</b>	<b>Speed</b>	
11.1	Maximum Design Speed	95 Km/h
11.2	Maximum Operating Speed	85 Km/h
<b>12</b>	<b>Wheel Profile</b>	UIC S10-2
<b>13</b>	<b>Noise Limits (ISO 2001 and 2006 - 2004)</b>	
13.1	Stationary ( Elevated and at grade)	
13.1.1	Internal (cab and aisle)	$L_{Amax}$ 85 dB(A)
13.1.2	External (at 7.5 m from centre line of track)	$L_{Amax}$ 78 dB(A)
13.2	Running at 85 km/h (Elevated and at grade)	
13.2.1	Internal (cab and aisle)	$L_{Amax}$ 72 dB(A)
13.2.2	External (at 7.5 m from centre line of track)	$L_{Amax}$ 85 dB(A)
13.3	Stationary (Underground)	
13.3.1	Internal (cab and aisle)	$L_{Amax}$ 72 dB(A)
<b>14</b>	<b>Traction Motors Ventilation</b>	Self
<b>15</b>	<b>Acceleration on level tangent track</b>	1 m/sec <sup>2</sup>
<b>16</b>	<b>Deceleration on level tangent track</b>	1.1 m/sec <sup>2</sup> or 1.2 m/sec <sup>2</sup> during emergency
<b>17</b>	<b>Type of Gogles</b>	Fabricated
<b>18</b>	<b>Secondary suspension springs</b>	Air
<b>19</b>	<b>Brakes</b>	- An electro-pneumatic (EP) service friction brake- An electric regenerative service brake- Provision of smooth and continuous blending of EP and regenerative braking- A fail safe, pneumatic friction emergency brake- A spring applied on release parking brake. The brake actuator will operate a Wheel Disc Brake-Brake Electronic Control Unit (BECU) - independent for each bogie
<b>20</b>	<b>Coupler</b>	Auto
	Outer end of 3-car Unit (except DMU cab front end)	Automatic coupler with mechanical, electrical & pneumatic coupling
	Front cab end of DMU car	Automatic coupler with mechanical & pneumatic coupling but without electrical coupling lead
	Between cars of same Unit	Semi-permanent couplers
<b>21</b>	<b>Detachment Door</b>	Front
<b>22</b>	<b>Type of Doors</b>	Sliding
<b>23</b>	<b>Rectranger seats</b>	Stainless Steel
<b>24</b>	<b>Cooling</b>	
24.1	Transformer	Forced
24.2	C1 & SV	Self-Forced
24.3	TM	Self ventilation
<b>25</b>	<b>Control System</b>	Traction Motor & Control System (TOMS/TACS)



26	Traction Motors	3 phase VVVF controlled
27	Temperature Rise Limits	
27.1	Traction Motor	Temperature rise <del>20/25</del> 75 deg C 10 deg C temperature margin for Junction temperature
27.2	CI & SV	
27.3	Transformer	EC specified limit <del>20/25</del> 20 deg C - Cooling, Heating & Humidifier (As required) - Automatic controlling of interior temperature throughout the passenger area at 25°C with 80% RH at the times under varying ambient conditions up to full load.
28	HVAC	
29	PA/PS including PIS (CCTV)	Required
30	Passenger Surveillance	Required
31	Battery	Lead Acid Maintenance free
32	Headlight type	LED
33	Coasting	85% (Run time with 8% coasting shall be the Run Time in All out mode <del>85%</del> 95%)
34	Gradient (max)	3%
35	Average Cost per car exclusive of taxes and duties at May 2011 Price level in \$M Gross	10.3

\*\*\*\*\*

# CHAPTER 9

## POWER SUPPLY, SYSTEM OF TRACTION AND POWER TARIFF



- 9.1 POWER REQUIREMENTS
- 9.2 NEED FOR HIGH RELIABILITY OF POWER SUPPLY
- 9.3 SELECTION OF TRACTION SYSTEM
- 9.4 SOURCES OF POWER SUPPLY
- 9.5 AUXILIARY SUPPLY ARRANGEMENTS FOR STATIONS & DEPOT
- 9.6 ELECTROMAGNETIC INTERFERENCE (EMI) AND ELECTROMAGNETIC COMPATIBILITY (EMC)
- 9.7 25KV FLEXIBLE OVERHEAD EQUIPMENT (FHE) SYSTEM
- 9.8 RATING OF MAJOR EQUIPMENT
- 9.9 STANDBY DIESEL GENERATOR (DG) SETS
- 9.10 SUPERVISORY CONTROL AND DATA ACQUISITION (SCADA) SYSTEM
- 9.11 ENERGY SAVING MEASURES
- 9.12 ELECTRIC POWER TARIFF

### TABLES

- TABLE 9.1 POWER DEMAND CITATION (MVA)
- TABLE 9.2 SOURCES OF POWER SUPPLY
- TABLE 9.3 POWER DEMAND PROJECTION FOR VARIOUS ENERGIES

### FIGURES

- FIG. 9.1 TYPICAL HIGH VOLTAGE RECEIVING SUB-STATION
- FIG. 9.2 TYPICAL DIESEL AUXILIARY SUB-STATION



Chapter - 9

## POWER SUPPLY SYSTEM OF TRACTION AND POWER TARIFF

### 9.1 POWER REQUIREMENTS

Electricity is required for operation of Metro system for running of trains, station services (e.g. lighting, lifts, escalators, signaling & telecom, fire fighting etc) workshops, depots & other maintenance infrastructure within premises of metro system. The power requirements of a metro system are determined by peak-hour demands of power for traction and auxiliary applications. Broad estimation of auxiliary and traction power demand is made based on the following requirements:-

- (i) Specific energy consumption of rolling stock - 75 kWh/1000 GTKM
- (ii) Regeneration by rolling stock - 30%
- (iii) Elevated station load - initially 250KW, which will increase to 400 KW in the year 2041
- (iv) Underground Station load - initially 2000 kW, which will increase to 2500 kW in the year 2041
- (v) Depot auxiliary load - initially 2000 kW, which will increase to 2500 kW in the year 2041

Keeping in view of the train operation plan and demand of auxiliary and traction power requirements projected for the year 2016, 2021, 2031 and 2041 are summarized in table **Table 9.1** below:-



Table 6.1: Power Demand Estimation (MW)

Corridor		Year			
		2016	2021	2031	2041
North-South Corridor - 1 Automotive Sycr to Khajuri Station [19,600 kms & 17 Stations (15 Elevated, 2 at Grade)]	Traction	4.32	3.01	3.94	7.16
	Auxiliary	7.72	7.84	9.14	11.45
	Total	12.04	10.85	13.08	18.61
East West Corridor - 2 Pragati Nagar to Lokmanya Nagar [18,557 kms & 19 Elevated Stations]	Traction	4.26	4.57	5.73	7.01
	Auxiliary	8.34	8.46	9.88	12.48
	Total	12.59	13.03	15.61	19.49

Detailed calculations of power demand estimation are attached at **Annexure 6.1**

## 6.2 NEED FOR HIGH RELIABILITY OF POWER SUPPLY

The Nagpur metro system is being designed to cater to crush load about 17000 passengers per direction during peak hours when trains are expected to run at 2.5 minutes intervals in 2041. Incidences of any power interruption, apart from affecting train running, will cause congestion at stations. Interruption of power at night is likely to cause alarm and increased risk to traveling public. Lack of illumination at stations, non-visibility of appropriate signages, disruption of operation of lifts and escalators is likely to cause confusion, anxiety and ire in commuters, whose tolerance level are low on account of stress. Effect on signal and communication may affect train operation and passenger safety as well. Therefore, reliable and continuous power supply is mandatory for efficient metro operations.

To ensure reliability of power supply, it is essential that both the sources of Supply and connected transmission & distribution networks are reliable and have adequate redundancies built in. It is desirable to obtain power supply at grid voltage of 220KV, 132 KV or 88KV from stable grid sub-stations and further transmission & distribution is done by the Metro Authority themselves.

## 6.3 SELECTION OF TRACTION SYSTEM

On techno-economic consideration, it is recommended to adopt 25 KV single phase AC Traction. In addition it has the following merits:-

- Lower initial cost.
- Lower spending on maintenance cost as in case of 25 KV ac traction the regeneration is up-to 30% and the line losses are around 0.5% in comparison to D.C. losses up-to 6 - 7%.





- A.C. system poses lesser fire hazards as current levels are much lower than D.C.
- No stray current problems and hence the corrosion is minimized.

#### 8.4 SOURCE OF POWER SUPPLY

The high voltage power supply network of Nagpur City has only 220kV and 132kV network on the periphery of the city to cater to various types of demand in vicinity of the proposed corridor. 220/132 kV sub stations are far away from the alignment and therefore, it involves substantial cable and it's laying cost.

Keeping in view the reliability requirements, two input sources of 220 kV or 132kV Voltage level are normally considered for each corridor. Therefore, to achieve the desired reliability, two Receiving Sub Stations (132/33/25 kV or 220/33/25 kV) are proposed to be set up for each Corridor – 1 & Corridor – 2. The interconnection of the two corridors will be at Staburd station (Elevated station of Corridor – 1).

It is proposed to avail power supply for traction as well as auxiliary services from the following grid sub-stations at 220/132kV through cable feeders.

A meeting was convened by with the officials of Maharashtra State Electricity Board and DMRC on dated-09.10.2012. As per MSEDCL letter No./CEN/UTech/1379, dated: 01.12.2012 has confirmed the following power sources for the Nagpur Metro.

**Table 8.2: Source of Power Supply**

Corridor	Grid sub-station (with input-voltage)	Location of R/S of Metro Authority	Approx. length of cables
North-South Corridor – 1 Automotive Side to Khopri Station.	1. 132 KV Uppehad Grid Sub-station.	2 x 132 KV bays near Automotive station	7 route km, 132 KV (Double Circuit cables).
	2. Proposed 220 KV Budoor Grid Sub-station.	2 x 220 KV bays at Khopri Station	4 route km, 220KV (Double Circuit cables).
East-West Corridor – 2 Proposed Nagar to Lalimanya Nagar.	3. U/O of proposed 132 KV Pardi-Jatrod sub.	2 x 132 KV bays near Prapuri Nagar station	4 route km, 132 KV (Double Circuit Cables).
	U/O of proposed 132 KV Hingra – Landra (3E)	2 x 132 KV bays near Sakinaka Nagar station	10 route km, 132 KV (Double Circuit Cables).

As the power supply is available at 220 kV/ and 132 kV levels that too at a substantial distance from the alignment, one sub-station of each line to be considered with one set of transformers and add another set as the traffic grows.

The above sub-stations are being considered as a conventional sub-station. In case a 220 kV or 132kV GIS is to be provided, there will be an additional cost of Rs. 20 Crores or 15 Crores per sub-station respectively.



Summary of expected power demand at various sources is given in Table 6.3.

Table 6.3: Power Demand Projection for various sources

Corridor	Input source / Receiving sub station (RSS)	Peak Demand - Normal (MVA)				Peak Demand - Emergency (MVA)			
		2016	2021	2031	2041	2016	2021	2031	2041
North-South Corridor - 1 Automotive Says to Khajuri	At Dogol near Khajuri station								
	Traction	2.60	2.75	3.50	4.30	4.32	4.65	5.84	7.16
	Auxiliary	4.62	4.70	5.56	6.89	7.72	7.84	9.14	11.09
	Sub - Total (A)	7.22	7.45	9.04	11.19	12.04	12.50	14.98	18.25
	Near automotive station								
	Traction	1.72	1.90	2.36	2.88	04.32	04.65	05.84	07.16
	Auxiliary	3.10	3.14	3.50	4.62	07.72	07.84	09.14	11.09
Sub - Total (B)	4.82	5.04	5.96	7.48	12.04	12.50	14.98	18.25	
	TOTAL (A + B)	12.04	12.49	14.98	18.65				
East-West Corridor - 2 Pratapji Nagar to Lokmanya Nagar	Near Subhash Nagar station								
	Traction	2.54	2.77	3.43	4.21	4.21	4.57	5.73	7.01
	Auxiliary	5.00	5.06	5.90	7.48	7.48	8.46	9.88	12.08
	Total	7.54	7.83	9.41	11.69	12.58	13.03	16.41	19.09
	Near Pratapji Nagar station								
	Traction	1.70	1.90	2.30	2.80	4.21	4.57	5.73	7.01
	Auxiliary	3.34	3.40	3.90	5.00	7.48	8.46	9.88	12.08
Total	5.04	5.20	6.20	7.80	12.58	13.03	16.41	19.09	
	TOTAL (A + B)	12.58	13.03	16.41	19.49				

The 220 kV or 132 kV power supply will be stepped down to 25kV single phase for traction purpose at the RSS of Nagpur Metro and the 25kV traction supply will be fed to the OHE at viaduct through cable feeders. For feeding the auxiliary loads, the 200/33 kV or 132/33 kV power supply received will be stepped down to 33 kV and will be distributed along the alignment through 33kV Ring main cable network. These cables will be laid along the viaduct and tunnel walls. If one RSS trips on fault or input supply fails, train services can be maintained from the other RSS. In case of total grid failure, all trains may come to a halt but station lighting & other essential



services can be catered to by stand-by DG sets. Therefore, while the proposed scheme is expected to ensure adequate reliability, it would cater to emergency situations as well.



Fig. 6.1 : Tysket High Voltage Receiving Sub-station

the 220 kV or 132 kV cables will be laid through public pathways of Maharashtra Grid Sub-stations to RSS of Metro Authority. For corridor - 1, one substation near Automotive station shall be provided with 2nos. (one as standby) 132/25 kV, 10 MVA single phase traction Transformers for feeding Traction and 132/33 kV, 15 MVA three phase Transformers for feeding auxiliary loads and other near Khopri Depot shall be provided with 2nos. (one as standby) 220/25 kV, 10 MVA single-phase traction Transformers for feeding Traction and 220/33 kV, 15 MVA three phase Transformers for feeding auxiliary loads. For corridor - 2, one RSS near Subhash Nagar and other RSS near Prapatti Nagar station shall be provided with 2nos. (one as standby) 132/25 kV, 10MVA single phase traction Transformers for feeding Traction supply and 132/33 kV, 15 MVA three phase Transformers for feeding auxiliary loads. Interconnection will provide at 33kV & 25kV level to meet emergency requirement at Sikaburi in case of failure of two RSS of any one corridor. The capacity of transformers may be reviewed considering the load requirement/distribution of both the corridors at the time of detailed design. Conventional Outdoor type 132 kV Switchgear is proposed for RSS's to be located in approx. 100 X 100 m (10000 sq. mtr.) land plot and for 220 kV



Conventional Outdoor type switchgear is proposed for RSS to be located in 120 x 100 m (12000 sq.m). The availability of land in depot area may not be a constraint. The land at Automotive station, Subhash Nagar and near Prappadi Nagar station to be allocated. Requirement of land for 220 KV GIS substation will be approx. 70 X 90 m (6300 sq. m) and for 132 KV GIS substation land requirement will be approx. 60 X 70 m (4200 sq. m) but the cost of substation works will increase by nearly Rs. 20 Crore and 15 Crores respectively. 220/132 KV Grid sub stations are far away from the alignment and therefore, it involves approx. Rs.20 Crores extra cable and it's laying cost.

#### 6.6 AUXILIARY SUPPLY ARRANGEMENTS FOR STATIONS & DEPOT

Auxiliary substations (ASS) are envisaged to be provided at each station (2 ASS's for Underground stations and 1 ASS for elevated station) for stepping down 33 KV supply to 415 V for auxiliary applications. A separate ASS is required at depot. The station ASS's will be located at mezzanine or platform level inside a room. The auxiliary load requirements have been assessed at 250KW for elevated / at-grade stations which is likely to increase up to 400 KW in the year 2041 and 2000 KW for Underground Station which is likely to increase up to 2500 KW in the year 2041. In order to meet the requirement of auxiliary power two dry type cast resin transformers (330.415KV) of 500KVA capacity are proposed to be installed at the elevated stations (one transformer as standby) and two transformer of 2.5 MVA at each underground ASS. For Property Development within the footprints of the station, a provision to add third transformer at a later date may be kept at elevated station.




Fig. 6.2 : Typical indoor Auxiliary sub-station



### 6.6 ELECTROMAGNETIC INTERFERENCE (EMI) AND ELECTROMAGNETIC COMPATIBILITY (EMC)

25kV ac traction currents produce alternating magnetic fields that cause voltages to be induced in any conductor running along the track. Earthing Transformer and Return Conductor (ET/RC) System is proposed for EMI mitigation. Concrete structures of elevated viaducts are not good electrical earths and therefore, Earthing and Bonding of the traction system shall be in accordance with the latest standards EN50122-1, IEC600 and other relevant standards. Two earth conductors - Overhead Protection Cable (OPC) and Buried Earth Conductor (BEC) are proposed to be laid along with elevated viaduct and all the metallic structures, structural reinforcement, running rails etc will be connected to these conductors to form an equip-potential surface & a least resistance path to the fault currents. The overhead protection cable will also provide protection against lightning to the 25kV OHE and the elevated viaduct.

Design specification of equipment e.g. power cables, transformer, switchgear, EMI equipment etc shall be framed to reduce conducted or radiated emissions as per appropriate international standards. The Metro system as a whole (train, signaling & telecomm, traction power supply, C&M system etc) shall comply with the EMC requirements of international standards viz. EN50121, EN50123, IEC61000 series etc. A detailed EMI/EMC plan will be required to be developed during project implementation stage.

### 6.7 25KV FLEXIBLE OVERHEAD EQUIPMENT (OHE) SYSTEM

25kV ac flexible OHE system shall comprise 150/107 sqmm Hard drawn copper contact wire and 65 sqmm Cu-copper catenary wire. Return conductor (RC) shall be Al Aluminium Conductor (AAC) of 200 sqmm cross section. From safety considerations, Hydraulic type Anti-Tensioning Device (ATDs) are proposed on mainlines which does not require use of balance weight for tensioning of OHE conductors. Proven catenary fittings are proposed similar to DMRC system.

### 6.8 RATING OF MAJOR EQUIPMENT

25kV ac Overhead Equipment (OHE) shall comprise 117mm<sup>2</sup> HD-copper contact wire and 65 mm<sup>2</sup> Cu-copper catenary wire. Return conductor (RC) shall be Al of OHE conductors.

Based on emergency demand expected at each RSS as shown in Table B.3, 2 nos. 220 or 132/25kV traction transformers of 10 MVA capacity and 2 nos. 132/33 KV, 15 MVA capacity Auxiliary transformers shall be provided at each RSS in Corridor -1 and 2 nos. 132/25kV traction transformers of 10 MVA capacity and 2 nos. 132/33 KV, 15 MVA capacity Auxiliary transformers shall be provided at each RSS in



Corridor – 8, being standard design (one to be in service and second one to serve as standby). The 132kV incoming cable 3-phase single core XLPE insulated with 630 mm<sup>2</sup> Aluminum conductor for corridor-1 & Corridor-2 and 220kV, 3-phase single core XLPE insulated with 800 mm<sup>2</sup> Aluminum conductor for corridor-1 shall be used to meet the normal & emergency loading requirements and fault level of the 132 kV and 220 KV supply.

11kV and 25kV switchgear shall be rated for 1250 A being standard design. 33kV cable ring network shall be adequately rated to transfer requisite auxiliary power during normal as well as emergency situations and accordingly 3 number of Single core 150 mm<sup>2</sup> FRESH Aluminum conductor cable XLPE insulated 50kV cable is proposed for ring main network.

Adequate no. of cables are required for transfer of traction power from Metro's PSS to 25kV OHE. Single-phase XLPE insulated cables with 240mm<sup>2</sup> copper conductor are proposed for traction power. Based on current requirements, 2 cables are required for each of the two circuits to feed power to OHE.

The above capacities of transformers, switchgear, cables etc. have been worked out based on the conceptual design. Therefore, these may be required to be revised for better accuracy during design stage of project implementation.

#### 8.9 STANDBY DIESEL GENERATOR (DG) SETS

In the unlikely event of simultaneous tripping of all the input power sources or grid failure, the power supply to stations as well as to trams will be interrupted. It is, therefore, proposed to provide a standby DG set of 200 KVA capacity at the elevated stations and 2 X 1250/750 KVA at Underground stations to cater to the following essential services:

- (i) Essential lighting
- (ii) Signaling & telecommunications
- (iii) Fire fighting system
- (iv) Lift operation
- (v) Fans collector system
- (vi) Tunnel Ventilation (for Underground Stations)

Silent type DG sets with low noise levels are proposed, which do not require a separate room for installation.

#### 8.10 SUPERVISORY CONTROL AND DATA ACQUISITION (SCADA) SYSTEM

The entire system of power supply (receiving, traction & auxiliary supply) shall be monitored and controlled from a centralized Operator Control Centre (OCC) through SCADA system. Modern SCADA system with intelligent remote terminal units (RTUs)



shall be provided. Optical fibre provided for telecommunications will be used as communication carrier for SCADA system.

Digital Protection Control System (DPCS) is proposed for providing data acquisition, data processing, overall protection control, interlocking, interlocking and monitoring of the entire power supply system consisting of 33kV ac switchgear, transformers, 25kV ac self-excited and associated electrical equipment. DPCS will utilize microprocessor-based fast-acting numerical relays & Programmable Logic Controllers (PLCs) with suitable interface with SCADA system.

### 6.11 ENERGY SAVING MEASURES

Energy charges of any metro system constitute a substantial portion of its operation & maintenance (O & M) costs. Therefore, it is imperative to incorporate energy saving measures in the system design itself. The auxiliary power consumption of metros is generally more than the traction energy consumed by train movement during initial years of operation. Subsequently, traction power consumption increases with increase in train frequency/composition in order to cater more traffic. The proposed system of Noida Metro includes the following energy saving features:

- (i) Modern rolling stock with 3-phase VVVF drive and lightweight stainless steel coaches has been proposed, which has the benefits of low specific energy consumption and almost unity power factor.
- (ii) Rolling stock has regeneration features and it is expected that 30% of total traction energy will be regenerated and fed back to 25kV ac OHE to be consumed by nearby trains.
- (iii) Effective utilization of natural light is proposed. In addition, the lighting system of the stations will be provided with different circuits (33%, 66% & 100%) and the relevant circuits can be switched on based on the requirements (day or night, operation or maintenance hours etc).
- (iv) Machine-room less type lifts with gearless drive have been proposed with 3-phase VVVF drive. These lifts are highly energy efficient.
- (v) The proposed heavy-duty public service escalators will be provided with 3-phase VVVF drive, which is energy efficient & improves the power factor. Further, the escalators will be provided with infrared sensors to automatically reduce the speed (to idling speed) when not being used by passengers.
- (vi) The latest state of art and energy efficient electrical equipment (e.g. transformers, motors, light fittings etc) has been incorporated in the system design.



- (vi) Efficient energy management is possible with proposed modern SCADA system by way of maximum demand (MD) and power factor control.
- (vii) LED lighting is proposed in certain areas.

#### 8.12 ELECTRIC POWER TARIFF

The cost of electricity is a significant part of Operation & Maintenance (O&M) charges of the Metro System, which constitutes about 25 – 30% of total annual working cost. Therefore, it is the key element for the financial viability of the project. The annual energy consumption is assessed to be about 36 million units in initial years (2016), which will increase to about 56 Million Units by year 2041 for Corridor – 1 and about 31 million units in initial years (2016), which will increase to 62 Million Units by year 2041 for Corridor – 2. In addition to ensuring optimum energy consumption, it is also necessary that the electric power tariff be kept at a minimum in order to contain the O&M costs. Therefore, the power tariff for this Corridor should be at effective rate of purchase price (at 132/220 kV voltage level) plus nominal administrative charges i.e. on a no profit no loss basis. This is expected to be in the range of Rs. 5.00 per unit with Rs.12500/km/yr fixed charges. It is proposed that Government of Maharashtra will take necessary steps to fix power tariff for Nappur Metro at "No Profit No Loss" basis. Financial analysis has been carried out based on this tariff for the purpose of finalizing the DPR. Similar approach is being pursued for Doha Metro.









QUESTION

Q. No.	Q. Text	Ans.
1	Q.1	A.1
2	Q.2	A.2
3	Q.3	A.3
4	Q.4	A.4
5	Q.5	A.5
6	Q.6	A.6
7	Q.7	A.7
8	Q.8	A.8
9	Q.9	A.9
10	Q.10	A.10
11	Q.11	A.11
12	Q.12	A.12
13	Q.13	A.13
14	Q.14	A.14
15	Q.15	A.15
16	Q.16	A.16
17	Q.17	A.17
18	Q.18	A.18
19	Q.19	A.19
20	Q.20	A.20
21	Q.21	A.21
22	Q.22	A.22
23	Q.23	A.23
24	Q.24	A.24
25	Q.25	A.25
26	Q.26	A.26
27	Q.27	A.27
28	Q.28	A.28
29	Q.29	A.29
30	Q.30	A.30
31	Q.31	A.31
32	Q.32	A.32
33	Q.33	A.33
34	Q.34	A.34
35	Q.35	A.35
36	Q.36	A.36
37	Q.37	A.37
38	Q.38	A.38
39	Q.39	A.39
40	Q.40	A.40
41	Q.41	A.41
42	Q.42	A.42
43	Q.43	A.43
44	Q.44	A.44
45	Q.45	A.45
46	Q.46	A.46
47	Q.47	A.47
48	Q.48	A.48
49	Q.49	A.49
50	Q.50	A.50

ANSWER



# CHAPTER 10

## MAINTENANCE DEPOT



10.1	THE NALPUR METRO PROJECT CORRIDORS
10.2	DEPOT- CIM- WORKSHOP
10.3	MAINTENANCE PHILOSOPHY
10.4	ROLLING STOCK MAINTENANCE NEEDS
10.5	YEAR-WISE PLANNING OF MAINTENANCE FACILITY
10.6	EQUIPMENT OF MAINTENANCE / INSPECTION LINES FOR DEPOT- CIM- WORKSHOP
10.7	INSPECTION REQUIREMENTS AT DEPOT
10.8	BUILDUP OF DEPOT- CIM- WORKSHOP FACILITIES
10.9	CAR DELIVERY AREA
10.10	OPERATIONAL FEATURES
10.11	INFRASTRUCTURE FACILITIES
10.12	LIST OF BUILDINGS
10.13	LIST OF PLANTS & EQUIPMENTS AT DEPOT- CIM- WORKSHOP

## FIGURES

FIG 10.1	MAINTENANCE SCHEDULE
FIG 10.2	TRAIN CLEANING SCHEDULE
FIG 10.3	EQUIPMENT OF STABLE LINES (SL), INSPECTION LINES (IL) AND WORKSHOP LINES (WL) NS CORRIDOR
FIG 10.4	EQUIPMENT OF STABLE LINES (SL), INSPECTION LINES (IL) AND WORKSHOP LINES (WL) RA CORRIDOR
FIG 10.5	EQUIPMENT OF MAINTENANCE / INSPECTION LINES (M- I) NS CORRIDOR
FIG 10.6	EQUIPMENT OF MAINTENANCE / INSPECTION LINES (M- I) RA CORRIDOR
FIG 10.7	EQUIPMENT OF WORKSHOP LINES NEAR DEPOT SECTION (NS CORRIDOR)
FIG 10.8	EQUIPMENT OF WORKSHOP LINES NEAR DEPOT SECTION (RA CORRIDOR)
FIG 10.9	LIST OF BUILDINGS AT DEPOT- CIM- WORKSHOP (NS CORRIDOR)
FIG 10.10	LIST OF BUILDINGS AT DEPOT- CIM- WORKSHOP (RA CORRIDOR)
FIG 10.11	LIST OF PLANTS & EQUIPMENTS AT DEPOT- CIM- WORKSHOP (NS CORRIDOR)
FIG 10.12	LIST OF PLANTS & EQUIPMENTS AT DEPOT- CIM- WORKSHOP (RA CORRIDOR)



## MAINTENANCE DEPOT

### 10 MAINTENANCE DEPOT

**10.1 NAGPUR METRO PROJECT CORRIDORS :** The Nagpur Metro Project comprises of following corridors:

S. No.	Corridor	Gauge (mm)	Route Length (KM)
1.	North-South Corridor	1435	19.858
2.	East-West Corridor	1435	18.260

### 10.2 DEPOT- CUM- WORKSHOP

**10.2.1** (A) It is proposed to establish one depot- cum- workshop near Khapti Station for North- South Corridor and one depot- cum- workshop in SRP Land near Lokmanya Nagar Station for East West Corridor with following functions:

**a) Depot- cum- workshop near Khapti station for North South Corridor (Line 1)**

- (i) Major overhauls of all the trains of Line 1.
- (ii) All minor schedules and repairs of Line 1.
- (iii) Lifting for replacement of heavy equipment and testing thereof of Line 1.
- (iv) Repair of heavy equipments of Line 1.

**b) Depot- cum- workshop in SRP Land near Lokmanya Nagar station for East West Corridor (Line 2)**

- (i) Major overhauls of all the trains of Line 2.
- (ii) All minor schedules and repairs of Line 2.
- (iii) Lifting for replacement of heavy equipment and testing thereof of Line 2.



(iv) Repair of heavy equipments of Line 2.

**10.2.2** The Depot planning near Khasi Station for North South Corridor and in SRP Land near Lokmanya Nagar Station for East West Corridor is based on following assumptions:

- (i) Enough space should be available near Khasi Station for North South Corridor and in SRP Land near Lokmanya Nagar Station for East West Corridor for establishment of a Depot-Cum-workshop.
- (ii) All inspection, workshop lines and stabling lines are designed to accommodate two trainsets of 3-car each.
- (iii) All stabling lines are planned in the proposed depot-cum-workshop assuming adequate space availability. In case of space constraints, if any, stabling facilities may need to be created at terminal stations or elsewhere to cater to the required stabling facilities.
- (iv) Provision of transfer line from one corridor to another corridor.

In broad terms, based on the planned Rolling Stock requirements, this chapter covers conceptual design on following aspects and will work as a guide for detailed design later:

- Layout of Stabling shed, Inspection shed, minor repairs and heavy repair overhauling workshop and clearing of Rolling Stock.
- Operational and functional safety requirements.
- Ancillary buildings for other maintenance facilities.
- Electrical & Mechanical Services, power supply and distribution system.
- Water Supplies, Drainage & Sewerage.

### 10.3 MAINTENANCE PHILOSOPHY

- Monitoring of the performance of equipment by condition monitoring of key parameters. The concept is to evolve the need based maintenance regime, which can be suitably configured in the form of schedules like daily check, 'A' checks, 'B' type checks, '10H' and '100H'.
- Labour intensive procedures are kept to the minimum. Automation with state of the art machinery to ensure quality with reliability.
- Multi-skilling of the Maintenance staff to ensure quality and productivity in their performance.
- Energy conservation is given due attention.

### 10.4 ROLLING STOCK MAINTENANCE NEEDS

**10.4.1 Maintenance Schedule** :The following maintenance schedule has been envisaged for conceptual design of depot: assuming approx. 300 kms running





per train per day, taking in consideration the passenger load of 2018, 2021, 2026, 2031, 2036 and 2041 respectively.

**Table 10.1 : Maintenance Schedule**

Type of Schedule	Interval	Work Content	Locations
Daily	Daily	Check on the train condition and function at every daily service completion. Interval cleaning/mopping of floor and walls with vacuum cleaner.	Stabling Lines
'A' Service Check	5,000 Km (approx. 15 days)	Detailed inspection and testing of sub-systems, under frame, replacement topping up of oil & lubricants.	Inspection Bays
'B' Service Check	15,000 Km (approx. 45 days)	Detailed inspection of 'A' type tasks plus items at multiple of 15,000 Km ('B' type tasks)	Inspection Bays
Intermediate Overhaul (IOH)	620,000 Km. (3 and half Years approx.)	Check and testing of all sub-assemblies (Electrical + Mechanical). Overhaul of pneumatic valves, Compressor. Condition based maintenance of sub-systems to bring them to original condition. Replacement of parts and rectification, trial run.	Workshop
Periodical Overhaul (POH)	840,000 Km. (7 Years approx.)	Disassembly of all sub-assemblies, bogie suspension system, traction motor, gear, control equipment, air conditioning units etc. Overhauling to bring them to original condition. Checking repair and replacement as necessary. Inspection and trial.	Workshop
Heavy Repairs	-	Changing of heavy item such as bogies, traction motor, axles, gear cases & axle boxes etc.	Workshop

The above Schedule may need slight revision based on the actual earned kilometers per train and the specific maintenance requirements of Rolling Stock fleetly procured.

#### 10.4.2 Washing Needs of Rolling Stock

Cleanliness of the trains is essential. Following schedules are recommended for Indian environment.

**Table 10.2 : Train Cleaning Schedule**

S.N.	Kind Inspection	Maint. Cycle	Time	Maintenance Place
1.	Outside cleaning (wet washing on automatic)	3 Days	10 mins.	Single Pass through Automatic washing



S.N.	Kind inspection	Maint. Cycle	Time	Maintenance Place
	washing plant)			plant of Depot
2.	Outside Heavy Cleaning (wet washing on automatic washing plant and Front Face, Vestibule/Buffer area. Floor, walls inside/outside of cars and roof. Manually)	30 days	2 - 3 hrs.	Automatic: washing plant & cleaning & washing shed

### 10.5 YEAR-WISE PLANNING OF MAINTENANCE FACILITY :

Year-wise planning of maintenance facility setup of depot cum workshop based on planned Rolling Stock requirement in TOP is tabulated below:

(i) Planned rakes as per TOP:

a) Planned rakes as TOP for N- S Corridor:

Year	No. of Rakes	No. of coaches
2016	11	33
2021	12	36
2026	15	45
2031	18	48
2036	18	54
2041	20	60

b) Planned rakes as TOP for E- W Corridor:

Year	No. of Rakes	No. of coaches
2016	12	36
2021	13	39
2026	15	45
2031	17	51
2036	18	54
2041	20	60

(ii) Average earning/day/rake based on TOP:

a) Average earning/day/rake for N- S Corridor:

Year	Average earning/day/rake
2016	258
2021	261
2026	270
2031	276
2036	267



2041	257
------	-----

b) Average earning/day/trake for E- W Corridor:

Year	Average earning/day/trake
2016	216
2021	213
2026	236
2031	230
2036	236
2041	254

(ii) Requirement of Stabling Lines (SBL), Inspection Lines (IBL) and Workshop Lines (WSL) in the Depot

a) Requirement of Stabling Lines (SBL), Inspection Lines (IBL) and Workshop Lines (WSL) in the Depot cum Workshop near Klapal Station for North South Corridor.

Table 10.2

Requirement of Stabling Lines (SBL), Inspection Lines (IBL) and Workshop Lines (WSL)  
NS Corridor

Year	No. of Trains	SBLs	IBLs	WSLs
2016	11	6 lines x two trains of 3-car	One bay of 3 lines each with two trains of 3-cars each on each line with space earmarked for future extension	One bay of 3 lines each with two trains of 3-cars each on each line with space earmarked for future extension
2021	12	7 lines x two trains of 3-car	-do-	-do-
2026	15	8 lines x two trains of 3-car	-do-	-do-
2031	16	8 lines x two trains of 3-car	-do-	-do-
2036	18	8 lines x two trains of 3-car	-do-	-do-
2041	20	10 lines x two trains of 3-car	-do-	-do-

All lines shall be suitable for placement of two trains of 3-car trains on each line.

b) Requirement of Stabling Lines (SBL), Inspection Lines (IBL) and Workshop Lines (WSL) in the Depot cum Workshop in SRP Land near Lokmanya Nagar Station for East West Corridor.



**Table 10.4**  
Requirement of Stabling Lines (SBL), Inspection Lines (IBL) and Workshop Lines (WSL)  
EW Corridor

Year	No. of Trains	SBLs	IBLs	WSLs
2016	12	6 lines x two trains of 3-car	One bay of 3 lines each with two trains of 3-cars each on each line with space earmarked for future extension	One bay of 3 lines each with two trains of 3-cars each on each line with space earmarked for future extension
2021	13	7 lines x two trains of 3-car	-do-	-do-
2026	15	8 lines x two trains of 3-car	-do-	-do-
2031	17	9 lines x two trains of 3-car	-do-	-do-
2036	18	10 lines x two trains of 3-car	-do-	-do-
2041	20	11 lines x two trains of 3-car	-do-	-do-

All lines shall be suitable for placement of two trains of 3-car trains on each line

#### 10.6 REQUIREMENT OF MAINTENANCE / INSPECTION LINES FOR DEPOT-CUM-WORKSHOP

- a) Requirement of maintenance / inspection lines for depot-cum-workshop Depot-cum-Workshop near Khapri Station for North South Corridor (Line 1):

**Table 10.5**  
Requirement of maintenance / inspection lines (NS Corridor)

Schedule	Maintenance Requirement (No. Lines needed of Cars)	Lines needed
<b>i) Year 2016 - Maximum no. of rake holding is 11T 6 x3 (= 33 Cars)</b>		
A Checks (5000 hrs) approx. 15 days	(11X3) Cars = 33 Cars	1 Line x two trains of 3- cars(with Sunken Floor)
B Checks (10000 hrs) approx. 45 days	(11X3) Cars = 33 Cars	1 Line x two trains of 3- cars(with Sunken Floor)



Schedule	Maintenance Requirement (No. of Cars)	Lines Needed
Unscheduled line & adjustment lines	For minor repairs, testing and after IOH/POH adjustments	1 Line x two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>F) Year 2021 - Maximum no. of rake holding is (12T x 3 = 36 Cars)</b>		
A' Checks (5000 km) approx. 15 days	(12X3) Cars = 36 Cars	1 Lines X two trains of 3- cars(with sunken floor)
B' Checks (15000 km) approx. 45 days	(12X3) Cars = 36 Cars	1 Lines X two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Line X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>G) Year 2026 -Maximum no. of rake holding is (15x3 = 45 Cars)</b>		
A' Checks (8000 km) 15 days	(15X3) Cars = 45 Cars	1 Lines X two trains of 3- cars(with sunken floor)
B' Checks (15000 km) 45 days	(15X3) Cars = 45 Cars	1 Lines X two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Line X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>H) Year 2031 -Maximum no. of rake holding is (16x3 = 48 Cars)</b>		
A' Checks (8000 km) 15 days	(16X3) Cars = 48 Cars	1 Lines X two trains of 3- cars(with sunken floor)



Schedule	Maintenance Requirement (No. of Cars)	Lines Needed
B Checks (15000 km) 45 days	(18X3) Cars = 48 Cars	1 Lines X two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Line X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>v) Year 2036 -Maximum no. of rake holding is (18x3 = 54 Cars)</b>		
A' Checks (5000 km) 15 days	(18X3) Cars = 54 Cars	1 Lines X two trains of 3- cars(with sunken floor)
B' Checks (15000 km) 45 days	(18X3) Cars = 54 Cars	1 Lines X two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Line X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>vi) Year 2041 -Maximum no. of rake holding is (20x3 = 60 Cars)</b>		
A' Checks (5000 km) 15 days	( 20 X 3 ) Cars = 60 Cars	2 Lines X two trains of 3- cars(with sunken floor)
B' Checks (15000 km) 45 days & Unscheduled line & adjustment lines	( 20 X 3 ) Cars = 60 Cars For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Lines X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future

All lines shall be suitable for placement of two 3- car trains on same line.



- b) Requirement of maintenance / inspection lines for depot cum-workshop in SRP Land near Lokmanya Nagar Station for East West Corridor (Line-2).

**Table 10.6**  
Requirement of maintenance / inspection lines(EW Corridor)

Schedule	Maintenance Requirement (No. of Cars)	Lines Needed
<b>i) Year 2018 - Maximum no. of rake holding is 12T8 x3 (= 36 Cars)</b>		
A Checks (5000 km) approx. 15 days	(12X3) Cars = 36 Cars	1 Line x two trains of 3- cars(with sunken floor)
B Checks (15000 km) approx. 45 days	(12X3) Cars = 36 Cars	1 Line x two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing and after IOH/POH adjustments	1 Line x two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>ii) Year 2021 - Maximum no. of rake holding is (13T8 x3 = 39 Cars)</b>		
A Checks (5000 km) approx. 15 days	(13X3) Cars = 39 Cars	1 Lines X two trains of 3- cars(with sunken floor)
B Checks (15000 km) approx. 45 days	(13X3) Cars = 39 Cars	1 Lines X two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Line X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>iii) Year 2025 -Maximum no. of rake holding is (15x3 = 45 Cars)</b>		
A Checks (5000 km) 15 days	(15X3) Cars = 45 Cars	1 Lines X two trains of 3- cars(with sunken floor)
B Checks (15000 km) 45 days	(15X3) Cars = 45 Cars	1 Lines X two trains of 3- cars(with sunken floor)



Schedule	Maintenance Requirement (No. of Cars)	Lines Needed
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Line X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>iv) Year 2031 -Maximum no. of rake holding is (17x3 = 51 Cars)</b>		
A' Checks (5000 km) 15 days	(17X 3) Cars = 51 Cars	1 Lines X two trains of 3- cars(with sunken floor)
B' Checks (15000 km) 45 days	(17X3) Cars = 51 Cars	1 Lines X two trains of 3- cars(with sunken floor)
Unscheduled line & adjustment lines	For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Lines X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>v) Year 2036 -Maximum no. of rake holding is (18x3 = 54 Cars)</b>		
A' Checks (5000 km) 15 days	(18X3) Cars = 54 Cars	2 Lines X two trains of 3- cars(with sunken floor)
B' Checks (15000 km) 45 days & Unscheduled line & adjustment lines	(18X3) Cars = 54 Cars For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Lines X two trains of 3- cars(with sunken floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future
<b>vi) Year 2041 -Maximum no. of rake holding is (20x3 = 60 Cars)</b>		
A' Checks (5000 km) 15 days	(20X3) Cars = 60 Cars	2 Lines X two trains of 3- cars(with sunken floor)





Schedule	Maintenance Requirement (No. of Cars)	Lines Needed
B Checks (15000 km) 45 days & Unscheduled line & adjustment lines	(20X3) Cars = 60 Cars For minor repairs, testing & adjustments post major repairs / IOH & POH	1 Lines X two trains of 3- cars (with surtion floor)
Requirement		1 bay of 3 lines with provision of space for additional bay of 3 lines for work load in future

All lines shall be suitable for placement of two 3- car trains on same line

#### 10.7 INSPECTION REQUIREMENTS AT DEPOTS NEAR KHAPRI STATION FOR NORTH SOUTH CORRIDOR (LINE-1) AND IN SRP LAND NEAR LOKMANYA NAGAR STATION FOR EAST WEST CORRIDOR (LINE-2):

Facilities for carrying out inspection activities shall be provided in the inspection bay for following Systems / Equipments of a train:

- Electronics, PAPIS
- Mechanical components, couplers etc.
- Batteries
- Air conditioner
- Brake modules
- Bogie
- Traction Motor
- Vehicle doors, windows and internal fittings
- Power system including converter, circuit breaker etc.

These activities shall be grouped into 'A' checks and 'B' checks. The minor scheduled inspections ('A' checks) shall be carried out during the day off peak and night. Since 'B' checks take longer time, these cannot be completed in the off peak times. Certain inspection lines will be nominated for 'A' checks. For 'B' checks, separate line will be nominated where the rakes may be kept for long time.

One dedicated line in the shed will be used for minor repairs and for adjustment and testing after the IOH and POH. There shall be a spare line in inspection bay for this purpose.



## 10.8 DESIGN OF DEPOT- CUM- WORKSHOP FACILITIES

### 10.8.1 Stabling lines at depots near Khapri Station for North South Corridor (Line-1) and in SRP Land near Lokmanya Nagar Station for East West Corridor (Line-2):

As per advised dimensions of the Rolling Stock, the length of 3-Car train would be Approx. 87.8 mt. For the design of the stabling lines in the depot and terminal stations or elsewhere (as may be required), following approximate lengths have been taken in consideration:

- (i) Length of one 3-car rake = 87.8 m
- (ii) Gap between two trains 3-car rakes = 10m
- (iii) Free length at outer ends of two trains of 3- cars ( for cross pathway, Signal and Friction buffers)= 10m each side
- (iv) Total length of Stabling lines = (i)+(ii)+(ii)+(ii)+(iii) = 10+ 87.8+ 10+ 87.8+ 10 = 165.6m = 166m

Looking to the car width of 2700mm or 9G, 5m "Track Centre" is proposed for all the stabling lines. Thus, space between stabling shall be sufficient to include 1 mt. wide pathway to be constructed between tracks to provide access for internal train cleaning and undercarriage inspection with provision of following facilities:

- a) Each Stabling line to have water connection facility so that local cleaning, if required, is facilitated.
- b) Platforms at suitable points at each end of stabling lines to enable train operators to board or de-board conveniently.

### 10.8.2 Inspection Bay at depot-cum-workshop near Khapri Station for North South Corridor (Line-1) and in SRP Land near Lokmanya Nagar station for East West Corridor (Line-2):

The length of Inspection shed is computed as below:

- (i) Length of a 3-car rake= 87.8 m
- (ii) Gap between two trains of 3- cars= 10 m
- (iii) Cross- path at each end= 10 m
- (iv) Length of Inspection line= (i)+(ii)+(ii)+(iii) = 10+ 87.8 + 10+ 87.8 + 10 = 165.6m = 166m

The width of the Inspection bay is computed as below:

- (i) Centre - to- centre spacing between the three lines= 7.5 m
- (ii) Centre line of outer lines to column of Shed= 3m
- (iii) Width of a 3 line Inspection Bay= (i)+(ii)+(ii) = 3+ 7.5+ 7.5+ 3 = 21 m



- a) There shall be one inspection bay of 168 m X 21 m size each with provision of accommodating three inspection lines each having sunken floor and overhead roof inspection platforms at each of the depot. The floor will be sunken by 1100mm. The track spacing between the adjacent IBs shall be 7.5 m. For rake requirements in future, there shall be provision of space for extension by one bay of three lines to cater the workload of inspection in future.
- b) Roof inspection platforms and walkways for roof inspection supported on the columns shall be provided. There would be lighting below the rail level to facilitate the under frame inspection. Ramps of 1:8 slopes, 3 meter wide should be provided with sunken floor system for movement of material for the cars. Further, 10m cross pathways are left at each end for movement of material by fork lift/underhoist trolley. 415V 3 phase 50 Hz, 230V 1 phase 50 Hz AC supply and Pneumatic supply shall also be made available on each inspection shed columns. Air-circulators shall be provided on each column. The inspection bay shall be provided with EDT crane of 1.5 T to facilitate lifting of equipment.

Roof and walls shall be of such design that optimum natural air ventilation occurs all the time and sufficient natural light is also available. Each inspection bay will also have arrangement close by for cleaning of HVAC filter under high pressure water jet.

#### 10.8.3 Workshop Shed depots near Khapri Station for North South Corridor (Line-1) and in SRP Land near Lokmanya Nagar Station for East West Corridor (Line-2):

Requirement of workshop lines is planned as under:

- a) Requirement of workshop lines near Khapri Station for North South Corridor (Line 1):



**Table 10.7 :**  
Requirement of workshop lines near Khapri Station for North South Corridor

Year	IOH & POH	Wheel / Bogie storage	Unscheduled repairs /fitting	Total	Remarks
2016	1	1 line of 3-car trains and free space of 3-car length for storage of other equipments	1 line x two trains of 3-car	3-line s	The size of workshop shall be the same as inspection bay i.e. 100X21 m with one working bay comprising of two trains lines capable of accommodating two trains 3-car takes with Bogie turning facility, one line of 3-car rake length with free space of 3-car rake length for storage of wheel bogie/ equipments etc.
2021	1	do	1	3-lines	
2026	1	do	1	3-lines	
2031	1	do	1	3-lines	
2036	1	do	1	3-lines	
2041	1	do	1	3-lines	

- b) Requirement of workshop lines in SRP Land near Lokmanya Nagar Station for East West Corridor (Line-2)

**Table 10.8 :**  
Requirement of workshop lines near Khapri Station for East West Corridor

Year	IOH & POH	Wheel / Bogie storage	Unscheduled repairs /fitting	Total	Remarks
2016	1	1 line of 3-car trains and free space of 3-car length for storage of other equipments	1 line x two trains of 3-car	3-line s	The size of workshop shall be the same as inspection bay i.e. 100X21 m with one working bay comprising of two trains lines capable of accommodating
2021	1	do	1	3-lines	



2026	1	do-	1	3 lines	two trains 3-car rakes with Bogie turning facility, one line of 3-car rake length with free space of 3-car rake length for storage of wheel bogie equipments etc.
2031	1	do-	1	3 lines	
2036	1	do-	1	3 lines	
2041	1	do-	1	3 lines	

- (a) There shall be one bay comprising of three lines each (as detailed in 'Remarks' above). Size of the workshop bay is proposed to be 168m x 21m. The unscheduled lifting and heavy repair line shall be fitted with jacking system capable to lift the 3-Car unit simultaneously for quick change of bogie, thereby saving down time of Rolling Stock. The arrangement of jacking system shall be such that lifting of any coach in train formation for replacement of bogie/equipments is also individually possible. One line shall be available for stocking of Bogies and wheels. These lines are to be provided with pits at regular intervals for inspection of undercarriage with turn tables. Each workshop bay shall be equipped with two trains 15T and 3T overhead cranes, each spanning the entire length of the workshop bay.
- (b) There shall be provided space for repairs of HVAC, Door, and Traction motor etc. repairs. Distinct spaces shall be earmarked for dismantling/repairs/ assembling and testing of each of these equipments. Related machinery for Overhauling / Repairs & testing activities of every equipment are also to be housed in the space earmarked.
- (c) There shall be washing and cleaning equipments on the workshop floor. Bogie test stand shall be provided in the workshop. Other heavy machinery shall also be suitably installed on the workshop floor. Air-circulators, lights, Powers supply points and compressed air supply line shall be provided on each workshop column.
- (d) Workshop lines shall be inter-linked through turn tables, each suitable for movement of a train in R/Ws (unloaded) condition and shall also be capable to rotate with a fully loaded bogie on it. Repair of heavy equipments such as air conditioners shall be so located so that it does not affect the movement inside workshop.
- (e) There shall be walkways on columns for roof inspections, along the workshop lines. These walkways shall not interfere with cars being lifted/ lowered by means of mobile jacks. Suitable space between the nearest exterior of a car



and farthest edge of the walkway has to be ensured to avoid conflict in lifting and lowering of cars.

- (f) The small component, bogie painting and battery maintenance cells will be located in the workshop with arrangement that fumes are extracted by suitable exhaust systems.
- (g) Workshop will have service building with array of rooms along its length. Total size is proposed to be 166 x 6m. These can be made by column and beam structure and architecture made of brick works. These shall cater for overhead sections, offices, ready stores item, locker rooms, toilets etc. Two bays opposite sides widthwise shall be open to facilitate natural air circulation and cross ventilation besides the egress & ingress for coaches. The sidewalls shall also have sufficient width of louvers for providing adequate ventilation.
- (h) There shall be space for bogie/ axle repair shop with necessary infrastructure for disassembly, overhead, assembly and testing of mechanical components of bogies/ axle. The repair shop shall be easily approachable from within the workshop for transportation of components.

Following equipment repair/overhaul facilities are planned in the workshop and wheel repairs shop at the workshops depots near Khapri Station for North South Corridor (Line-1) and in SRP Land near Lokmanya Nagar Station for East West Corridor (Line-2):

1. Body/finishing
2. Bogie
3. Wheels
4. Traction Motors
5. Axle Box and Axle Bearing
6. Pantographs
7. Transformer, converter/inverter, circuit breaker
8. Battery
9. Air Compressor
10. Air-conditioner
11. Brake Equipment
12. Door actuators
13. Control and measuring equipments
14. Pneumatic equipment
15. Dampers and Springs
16. Couplers/Girgways
17. Coach Painting (Applicable only for Aluminum coaches, if any).



## 10.9 CAR DELIVERY AREA

There shall be rail connectivity between the Depot cum Workshop and mainline and all trains due for scheduled/unscheduled works shall reach the depot cum Workshop by rail.

However in case of newly procured coaches, which are transported by road, these shall reach the Depot cum Workshop by the road on trailers. To unload the coaches and bring them to the track, provision of space, along the side of shunting neck, has to be made for unloading of cars and other heavy materials. This area shall have an insulated track embedded in the floor facilitating the movement of road trailer, which brings in the cars. The length of the track embedded area shall be about 40m long. There should be enough space available for movement of heavy cranes for lifting of coaches. The unloading area should be easily accessible for heavy duty hydraulic trailers.

## 10.10 OPERATIONAL FEATURES

The rake induction and withdrawal to main line will be primarily from the stabling shed. Further, provisions are there for direct rake induction and withdrawal to main line from Inspection Shed/Workshop area. Movement from depot to the main line is so planned that the headway of main line is not affected. Simultaneous receipt and dispatch of trains from depot to main line is feasible in the present site scenario. Both of these activities will be done effectively without effecting the train operation on the main line. The stabling lines would be interlocked with the main line thereby induction of train from the stabling would be safe and without loss of time. The proposition for a transfer track on the incoming line as well as on the outgoing line to facilitate the movement of rake in the depot by Operation Control Centre (OCC) even though the further path inside the depot is not clear shall be explored in the detailed design stage depending on the actual availability of land.

An emergency line is also provided from which an emergency rescue vehicle may be dispatched to main line in the event of emergency if necessary.

## 10.11 INFRASTRUCTURE FACILITIES : Infrastructure Facilities in depots near Khajuri Station for North South Corridor (Line 1) and in SRP Land near Loknarya Nagar Station for East West Corridor (Line 2)

### I. Inspection and Workshop facilities:

As indicated in 10.8.2 & 10.8.3 above.

### II. Stabling Lines in Depot:

- a) The requirement of lines shall be in accordance with the details indicated in para 10.9.1 above. A part of the stabling siding in the depot shall be covered with a roof in order to facilitate testing of air conditioning of trains and their pre-cooling under controlled condition of temperature.



- b) Separate toilets adjustment to stabling lines shall be provided with small room for keeping cleaning aids and for utilization by the working staff.

#### **III. Automatic Coach Washing Plant (AWP)**

Provision to be made for Rolling Stock exterior surfaces to be washed using a fully automated Train Washing System, with a throughput capacity of approximately ten trains per hour. The AWP shall be situated at such a convenient point on the incoming route so that incoming trains can be washed before entry to the depot and undesirable movement/shunting over ingress and egress routes within the depot is avoided. Additional space for plant room for AWP system shall be earmarked alongside the washing apron as indicated at Para 10.12.1 (a) & 10.12.1 (b).

#### **IV. Train Operators Booking Office**

Suitable office facility adjacent to the stabling lines at each depot should be provided so that train operators reporting 'On' duty or going 'Off' duty can obtain updates regarding 'Special Notices', 'Safety Circulars' and other technical updates/information in vogue. These offices should have an attached a cycle/booster/tur stand facility for convenience of the train operating staff.

#### **V. Test Track**

A test track of 1000 mts. in length covered & fenced should be provided beside workshop in the depot. It shall be equipped with signaling equipments (ATP/ATO). It shall be used for the commissioning of the new trains, their lifts and testing of the trains after the IOH and POH. Entry into the test track shall be planned for a 3-car train. In compliance to safety norms, the boundary of the track shall be completely fenced to prevent unauthorized trespassing across or along the track.

#### **VI. Heavy Cleaning Shed**

Monthly heavy cleaning of interior walls, floors, seats, window glasses etc. outside heavy cleaning, Frontline Face, Vestibule/ Buffer area, outside walls and roof shall be done manually in the interior cleaning plant designed for cleaning of one at a time. A line adjacent to inspection shed should be so provided that placement of rails is possible from workshop or inspection lines & vice-versa conveniently and with ease.

#### **VII. Power Supply**

Auxiliary substations are planned for catering to the power supply requirement of the whole depot and workshop. Details of connected load feeder shall be worked out. Taking diversity factor of 0.5 the maximum





demands shall be computed. Two trains Auxiliary substations are proposed, as the demand by machines in Workshop area would be very large. The standby power supply is proposed through DG set with AMF panel. The capacity of DG set will be adequate to supply all essential loads without over loading.

#### **VII. Compressed Air Supply**

Silent type compressor units shall be suitably installed inside the depots at convenient location for the supply of compressed air to workshop and inspection sheds. Thus, the pneumatic pipeline shall run within the workshop and inspection bays so to have compressed air supply line at all convenient points.

#### **VIII. Water supply, sewerage and Drainage Works**

In house facilities shall be developed for the water supply of each depot. Sewerage, storm water drainage shall be given due care while designing the depots for efficient system functioning. Past records of Municipal Corporation shall be used to design the drainage system. Rainwater harvesting would be given due emphases to charge the under ground reserves.

#### **IX. Ancillary Workshop**

This workshop will have a lift at floor level with provision of pits. Arrangement for repairs of Shunters, Rail Road Vehicles and other ancillary vehicles will be provided. These vehicles will also be housed here itself. Heavy lifting works can be carried out in main workshop.

Ancillary workshop will be used for storing OH/Overhead OHE parts and their maintenance/ repair for restoration of 25 KV feed system.

#### **X. Watch Towers**

There shall be provision of adequate number of watchtowers for the vigilance of depot boundary.

#### **XI. Administrative Building**

An administrative building close to the main entrance is planned. It can be suitably sized and architecturally designed at the detailed design stage. A line and security office is also provided close to main entrance. It shall be equipped with suitable Access control system for all the staff working in the complex.

#### **XII. Parking Facilities**



- a) Ample parking space shall be provided for the two trains wheelers and four wheelers at the following points:
  - (i) Close to the depot entry.
  - (ii) Close to the stabling lines.
  - (iii) Close to the Workshop/BL.
- b) Space for parking of road and re-railing equipments  
Enough space for parking of road vehicle/ trailers/trucks etc. Enough space will also have to be earmarked adjacent to workshops. Similarly, provision of space for parking of re-railing equipments will have to be made close to the main exit gate of the Depot.

#### XIV. Shed and Buildings

The shed and buildings normally provided in the depot with their sizes and brief functions are indicated in Para 10.12.1 (a) & 10.12.1 (b). At the detailed design stage depending upon the land availability, the decision to locate these buildings can be taken. These can then be architecturally and functionally grouped.

#### XV. Plant and Machinery

- a) A separate building is planned for housing pit wheel lathe (PWL), approachable from workshop, inspection bay and stabling lines through rail and road for placement of cars for re-profiling of wheels within the depot along with space for depot of scrap.
- b) Requirement of buildings and major plants and machinery, is given in Para 10.12.1(a), 10.12.1 (b), Para 10.12.2 (a) & 10.12.2(b)

#### 10.11.1 Following Safety features should be incorporated in the design of the Maintenance Depot-cum-Workshop near Khapri Station for North South Corridor (Line-1) and In SRP Land near Lokmanya Nagar Station for East West Corridor (Line-2):

- a) 1.5 DOT cranes in the inspection bay should be interlocked with 25 kV ac OHE in such a way that, the cranes become operational only when the OHE is isolated and grounded.
- b) Red flasher lights should be installed along the inspection lines at conspicuous location to indicate the OHE is 'Live'.
- c) Multi level wheel and TM stacking arrangement should be an inbuilt feature at the end of Workshop Lines.
- d) Pillars in the inspection bay & workshop should have provision for power sockets.
- e) Placement of rakes from inspection/workshop lines on to washing lines for maintenance cleaning on their own power should be possible. Linking of OHE



- and its isolation at the clearing area should be provided. Necessary requirements of safety should be kept in view.
- The roof inspection platform should have open-stile doors to facilitate staff to go up the roof for clearing of roof. Suitable safety interlock should be provided to ensure maintenance staff are enabled to climb on the roof inspection platform only after the OHE is isolated.
  - Control Centre, PPIO & store depot must be close to Workshop.
  - Width of the doors of the sections wherein repairs of equipments are done should be at least 2 meters wide to allow free passage of equipment through them.
  - Provision of water hydrants should be done in workshops & stabling yards also.
  - Compressed air points along with water taps should be available in interior of buildings for cleaning.
    - Ventilation arrangement inside the inspection shed and workshop should be ensured. Arrangement for natural cross ventilation from one side to another of inspection & workshop bays to be incorporated along with optimum availability of natural light at floor level.

## 10.12 LIST OF BUILDINGS

10.12.1 List of Buildings at Depot- Cum- Workshop at Khapri Station near Khapri Station for North South Corridor (Line) :

Table 10.5  
List of Buildings at Depot- Cum- Workshop (N S Corridor)

S.No	Name of Building	Size	Remarks
1.	Inspection Shed	168m x 21m • One way of 3 lines (2 trains of 3 cars in each line)	Servicing of Cars for 15 days & 45 days inspection. This shed will have scope of expansion by 3 lines (1 additional bay of 3 lines for future requirement).
	Workshop Shed	168m x 21m	Major repair & overhaul of rolling stocks, diesel shunters, electric tractors, tower wagons. All heavy lifting jobs.
	Associated Sections	168m x 8m	Rooms for carrying out the inspection & workshop activity.
	Stabling line shed	168m x 65m (for 20 trains)	Provisional for total area as per requirement of stabling of 20 rakes during year 2041 is to be made (with initial provision for 12 rakes only).



S.No	Name of Building	Size	Remarks
2.	Stores Depot & Office including Goods Platform with Ramp	45m x 45m	<ul style="list-style-type: none"> <li>i. Stacking of spares for regular &amp; emergency requirement including consumable items.</li> <li>ii. This store caters for the requirement of depot for rolling stock &amp; other disciplines.</li> <li>iii. To be provided with computerized inventory control.</li> <li>iv. Loading/Unloading of material received by road.</li> </ul>
3.	Elect. Substation & DG set room	20m x 15m	To cater for normal and emergency power supply for depot, workshop, service and all other ancillary buildings, essential power supply for essential loads and security light.
4.	Traction repair depot and E AM repair shop	80m x 30m (partly double storey)	Stabling and routine maintenance of starting engine etc. & Traction maintenance depot. For maintenance of lifts/escalators and other General service works.
5.	Cycle / Scooter / Car Parking	100m x 8m 60m x 8m	<ul style="list-style-type: none"> <li>i. Close to the depot entry.</li> <li>ii. Close to the stabling lines.</li> </ul>
6.	Auto coach washing plant	40m x 10m	For automatic washing of coaches. Provision of Washing apron for collection of dripping water and its proper drainage to be ensured.
7.	Washing apron for Interior Cleaning	166m x 6.5m	Heavy wet washing of rakes from inside, under frame, roof at 30 days interval.
8.	P-way office, store & Workshop including Welding plant	60m x 20m	<ul style="list-style-type: none"> <li>i. For track maintenance of section and depot.</li> <li>ii. To weld rails for construction period only.</li> <li>iii. To stable track Tamping machine.</li> </ul>
9.	Security office & Tire Office Garages (4 Nos.)	15m x 8m	For security personnel. For tire punching. For parking vehicle jeep, truck etc.
10.	Check Post (2 Nos.)	5m x 3m	For security check of incoming/outgoing staff material and coaches.
11.	Watch Tower (4 Nos.)	3.8m x 2.3 m	For security of the depot especially during night time.
12.	Depot control centre & Crew booking centre	25m x 20m (double storey)	To control movement of trains in and out of the depot and for crew booking.
13.	Oil raw water	1,00,000 Ltrs.	For Storage of water.



S.No	Name of Building	Size	Remarks
	Tank	Capacity	
14.	Pump house Bore well	7.3m x 5.4m (200 mm bore)	Submersible type pump planned with 200 mm diameter bore well.
15.	Dangerous goods Store	15m x 10m	For Storage of paints, inflammables & Lubricants
16.	a) Traction 25/33kV/110kV sub station b) Feeding Post	a) 120m x 80m b) 15m x 30m	Traction Power Supply
17.	Waste Collection Bin	10m x 10m	Garbage dumping
18.	Repair shops for S & T	40m x 20m	For the AFC gates, Signaling and telecom equipment.
19.	Work shop Manager Office	30m x 20m	Office of Depot in charge
20.	ATP & ATO Rooms	10m x 8m	To keep equipments of ATP/ATO
21.	Waste Water Treatment Plant	12m x 6m	For treating the discharge waters of the depot and remove the oil, acids etc. before discharging into the river, with U/G tank.
22.	Canteen	200 sqm.	To cater staff of depot and workshop. Should be in a separate building with modern kitchen ware and facilities. Obligatory as per statutory requirements.
23.	Toilets -Gents -Ladies	10m x 7m 10m x 7m	These toilets shall be approachable both from workshop as well as from inspection bay and ladies toilets shall be completely insulated from gents toilet.

- 10.12.1 List of Buildings at Depot- Cum- Workshop at Khajuri Station in SRP Land near Lokmanya Nagar Station for East West Corridor (Line 2)

**Table 10.10**  
List of Buildings of Depot- Cum- Workshop (EW Corridor)

S.No	Name of Building	Size	Remarks
1.	Inspection Shed	166m x 21m • One way of 3 lines (2 trains of 3-cars in each line)	Servicing of Cars for 15 days & 45 days inspection. This shed will have scope of expansion by 3 lines (1 additional bay of 3 lines for future requirement).



S.No	Name of Building	Size	Remarks
	Workshop Shed	166m x 21m	Major repair & overhaul of rolling stocks, Diesel shunters, electric tractors, tower wagons. All heavy lifting jobs.
	Associated Sections	166m x 8m	Rooms for carrying out the inspection & workshop activity.
	Stabling line shed	166m x 60m (for 23 rakes)	Provision for total area as per requirement of stabling of 23 rakes during year 2041 is to be made (with initial provision for 13 rakes only).
2.	Stores Depot & Offices including Goods Platform with Ramp	45m x 45m	<ul style="list-style-type: none"> <li>i. Stacking of spares for regular &amp; emergency requirement including consumable items.</li> <li>ii. This store caters for the requirement of depot for rolling stock &amp; other disciplines.</li> <li>iii. To be provided with computerized inventory control.</li> <li>iv. Loading/Unloading of material received by road.</li> </ul>
3.	Elect. Substation & DG set room	26m x 15m	To cater for normal and emergency power supply for depot, workshop, service and all other ancillary buildings, essential power supply for essential loads and security light.
4.	Traction repair depot and E & M repair shop	60m x 30m (partly double storey)	Stabling and routine maintenance of shunting engine etc. & Traction maintenance depot. For maintenance of lifts/elevators and other General service works.
5.	Cycle / Scooter / Car Parking	100m x 8m 60m x 8m	<ul style="list-style-type: none"> <li>ii. Close to the depot entry.</li> <li>iv. Close to the stabling lines.</li> </ul>
6.	Auto wash washing plant	40m x 10m	For automatic washing of coaches. Provision of Washing apron for collection of dripping water and its proper drainage to be ensured.
7.	Washing apron for Interior Cleaning	166m x 8.5m	Heavy wet washing of rakes from inside, under frame, roof at 30 days interval.
8.	P-way office, store & Workshop including Welding plant	60m x 20m	<ul style="list-style-type: none"> <li>iv. For track maintenance of section and depot.</li> <li>v. To weld rails for construction period only.</li> <li>vi. To stable track Tamping machine.</li> </ul>
9.	Security office &	15m x 8m	For security personnel.



S.No	Name of Building	Size	Remarks
	Time Office		For time punching
	Garages (4 Nos.)		For parking vehicle jeep, truck etc.
10.	Check Post (2 Nos.)	5m x 3m	For security check of incoming/outgoing staff/material and coaches.
11.	Watch Tower (4 Nos.)	3.0m x 2.5 m	For security of the depot especially during night time.
12.	Depot control centre & Crew booking centre	25m x 20m (double storey)	To control movement of trains in and out of the depot and for crew booking.
13.	O.H row water Tank	1,00,000 Ltrs. Capacity	For Storage of water.
14.	Pump house Bore well	7.3m x 5.4m (200 mm bore)	Submersible type pump planned with 200 mm diameter bore well.
15.	Dangerous goods Store	15m x 10m	For Storage of paints, inflammables & Lubricants
16.	a) Traction 25/33MVA/66KV sub station b) Feeding Post	a) 120m x 80m b) 15m x 30m	Traction Power Supply
17.	Waste Collection Bin	10m x 10m	Garbage dumping
18.	Repair shops for S & T	40m x 20m	For the AFC gates, Signaling and telecom equipment.
19.	Work shop Manager Office	30m x 20m	Office of Depot in charge
20.	ATP & ATO Room	10m x 8m	To keep equipments of ATP/ATO
21.	Waste Water Treatment Plant	12m x 6m	For treating the discharge waters of the depot and remove the oil, acids etc. before discharging into the river, with U/G tank.
22.	Canteen	300 sqm.	To cater staff of depot and workshop. Should be in a separate building with modern kitchen ware and facilities. Obligatory as per statutory requirements.
23.	Toilets -Gents -Ladies	10m x 7m 10m x 7m	These toilets shall be approachable both from workshop as well as from inspection bay and ladies toilets shall be completely insulated from gents toilet.

## 10.13 LIST OF PLANTS &amp; EQUIPMENTS AT DEPOT-CUM-WORKSHOP



### 10.7.6.1 List of Plants & Equipments at Depot-cum-Workshop near Khajuri Station for North South Corridor (Line 1):

**Table 10.11**  
**List of Plants & Equipments at Depot- Cum- Workshop (NS Corridor)**

S No.	Equipment	Qty.	Unit
1.	Under floor Pit wheel lathe, Chip crusher and conveyor for lathe on pit, Electric tractor for movement over under floor wheel lathe	1	No.
2.	Under floor lifting systems for 3-car unit for replacement of bogie	1	Set
3.	Mobile jacks 15T for lifting cars (set of 12 jacks)	1	No.
4.	Retailing equipment consisting of rail curb road vehicle and associated jack system etc.	1	Set
5.	Run through type Automatic Washing plant for Metro cars	1	No.
6.	Rail bed bogie wash plant	1	No.
7.	Bogie lift stand	1	No.
8.	Work lift platform	4	No.
9.	Electric bogie tractor for pulling cars and bogies inside workshop	1	No.
10.	Chemical cleaning tanks, ultrasonic cleaning tanks, etc.	1	Set
11.	Compressor for inspection shed & shop air supply	2	No.
12.	(i) Travelling Oil crane Workshop 15T/3 T (ii) 1.5T Capacity (IBL) : 2 Nos.	2	No.
13.	Mobile jib crane	2	No.
14.	Mobile lifting table	4	No.
15.	Carbody stands	24	No.
16.	Bogie turn tables	2	No.
17.	Underframe & Bogie blowing plant & small parts/equipment	2	No.
18.	AC Etar cleaning machine	1	No.
19.	Portable cleaning plant for rolling stock	1	No.
20.	High-pressure washing pump for front and rear end cleaning of car	2	No.
21.	Industrial furniture (Work Tool Benches)	1	Ls.
22.	Minor diagnostic equipment and collective tools	-	Set
23.	Induction heater	1	No.
24.	Oven for the motors	1	No.
25.	EMU battery charger	2	No.
26.	Welding equipments (Mobile welding, oxyacetylene, Eoad arc welding)	2	Set
27.	Electric and pneumatic tools	-	Set





S. No.	Equipment	Qty.	Unit
28	Measuring and loading equipment	-	Set
29	Tool Kits	-	Set
30	Mobile safety steps	12	No.
31	Fork lift tractor	2	No.
32	Pallet trucks	6	No.
33	RRV	1	-
34	Road vehicles (pickup van/ truck)	1	Set
35	Miscellaneous office equipment(s)	-	Set
36	Vertical Boring Machine for wheel discs	1	No.
37	Press for removal and pressing of the wheel on axle	1	No.
38	Axle journal turning and burnishing lathe	1	No.
39	Special jigs and fixtures and test benches for Rolling Stock	1	set
40	Stackers (1T for DGGS)	2	No.
41	Storage Racks (Workshop & DGGS stores)	1	Set
42	Test benches	1	Set
43	Auto parts shop (business refer)	-	-
44	Vehicle mounted crane	-	-
45	Impulse Tester for TMs	-	-
46	Bearing puller	-	-

**10.13.2** List of Plants & Equipments at Depot-cum-Workshop in SPO Land near Lokmanya Nagar Station for East West Corridor (Line-2):

**Table 10.12**  
List of Plants & Equipments at Depot- Cum- Workshop (EW Corridor)

S. No.	Equipment	Qty.	Unit
1.	Under floor Pt wheel lathe, Chip crusher and conveyor for lathe on pt, Electric tractor for movement over under floor wheel lathe	1	No.
2.	Under floor lifting systems for 3-car unit for replacement of bogie	1	Set
3.	Mobile jacks 15T for lifting cars (set of 12 jacks)	1	No.
4.	Rerailing equipment consisting of rail cum road vehicle and associated jack system etc.	1	Set.
5.	Run through type Automatic Washing plant for Metro cars	1	No.
6.	Rail fed Bogie wash plant	1	No.
7.	Bogie test stand	1	No.
8.	Work lift platform	4	No.
9.	Electric bogie tractor for pulling cars and bogies inside workshop	1	No.



No.	Equipment	Qty.	Unit
10	Chemical cleaning tanks, ultrasonic cleaning tanks, etc	1	Set
11	Compressor for inspection shed & shop air supply	2	No.
12	(i) Travelling O/H crane Workshop 15TQ T (ii) 1.5T Capacity (IBL) - 2 Nos.	2 2	No. No.
13	Mobile jib cranes	2	No.
14	Mobile lifting table	4	No.
15	Carbody stands	24	No.
16	Boogie turn tables	2	No.
17	Underframe & Bogie blowing plant & small portable equipment	2	No.
18	AC filter cleaning machine	1	No.
19	Portable cleaning plant for rolling stock	1	No.
20	High-pressure washing pumps for front and rear end cleaning of car	2	No.
21	Industrial furniture (Work Test Benches)	1	L.S.
22	Minor diagnostic equipment and collector tools	-	Set
23	Induction heater	1	No.
24	Oven for the motors	1	No.
25	EMU battery charger	2	No.
26	Welding equipments (Mobile welding, oxyacetylene, shield arc welding)	2	Set
27	Electric and pneumatic tools	-	Set
28	Measuring and testing equipment	-	Set
29	Tool Kits	-	Set
30	Mobile safety steps	12	No.
31	Fork lift tractor	2	No.
32	Pallet trucks	6	No.
33	RRV	1	
34	Road vehicles (pickup van/ truck)	1	Set
35	Miscellaneous office equipments	-	Set
36	Vertical Boring Machine for wheel discs	1	No.
37	Press for removal and pressing of the wheel on axle	1	No.
38	Axle journal turning and burnishing lathe	1	No.
39	Special jigs and fixtures and test benches for Rolling Stock	1	set
40	Stackers (1T for DCOG)	2	No.
41	Storage Racks (Workshop & DCOG stores)	1	Set
42	Test benches	1	Set



# No.	Equipment	Qty.	Unit
43	Auto portable strip thickness tester		-
44	Vehicle mounted crane		-
45	Impulse Tester for TMs		-
46	Bearing puller		-

-





# CHAPTER 11

## SIGNALLING SYSTEM



- 11.1 SIGNALLING
- 11.2 SIGNALLING AND TRAIN CONTROL
- 11.3 SPACE REQUIREMENT FOR SIGNALLING INSTALLATIONS
- 11.4 MAINTENANCE PHILOSOPHY FOR SIGNALLING SYSTEMS

### TABLES

- TABLE 11.1 SIGNALLING SYSTEM STANDARDS

**Chapter - 11****SIGNALLING SYSTEM****11.0 SIGNALLING****11.1 Introduction**

The signaling system shall provide the means for an efficient train control, ensuring safety in train movements. It assists in optimization of metro infrastructure investment and running of efficient train services on the network.

**11.2 SIGNALLING AND TRAIN CONTROL****11.2.1 Overview**

Metro carries large number of passengers at a very close headway requiring a very high level of safety enforcement and reliability. At the same time heavy investment in infrastructure and rolling stock necessitates optimization of its capacity to provide the best services to the public. These requirements of the metro are planned to be achieved by adopting CATO (Continuous Automatic Train Control System) based on CBTC (Communication based Train Control System) which includes ATP (Automatic Train Protection), ATO (Automatic Train Operation) and ATS (Automatic Train Supervisor) sub-systems using radio communication between Track side and Train.

This will:

- Provide high level of safety with close running of close headway ensuring continuous safe train separation and for bidirectional working.
- Eliminate accidents due to driver passing Signal at Danger by continuous speed monitoring and automatic application of brake in case of disregard of signal / warning by the driver.
- Provides safety and enforces speed limit on sections having permanent and temporary speed restrictions.
- Improve capacity with safer and smoother operations. Driver will have continuous display of Target Speed / Distance to Go status in his cab enabling him to optimize



the speed potential of the track section, it provides signal / speed status in the cab even in bad weather.

- Increased productivity of rolling stock by increasing the capacity and train speeds, and enabling train to arrive at its destination sooner. Hence more trips will be possible with the same number of rolling stock.
- Improve maintenance of Signaling and telecommunication equipments by monitoring system status of trackside and train born equipments and enabling preventive maintenance.

Signaling & Train Control system on the line shall be designed to meet the required capacity during peak hours.

Radio for CBTC shall work in License free ISM band.

### 11.2.2 System Description and Specifications

The Signaling and Train Control system shall be as below. Sub-system/ components will conform to international standards like CENELEC, IEEE, IEC, BS, IS, ITU-T etc.

#### a. Continuous Automatic Train Control

Continuous Automatic Train Control based on CBTC will consist of - ATP (Automatic Train Protection), ATO (Automatic Train Operation) and ATS (Automatic Train Supervision) sub-systems.

##### (i) Automatic Train Protection (ATP)

Automatic Train Protection is the primary function of the train control systems. This sub-system will be inherently capable of achieving the following objectives in a fail-safe manner. Line side signals will be provided at diverging routes (i.e. at points & crossings) as well as other required locations, which shall serve as backup signaling in case of failure of ATP system.

- Cab Signaling
- Track Related Speed Profile generation based on line data and train data continuously along the track.
- Continuous monitoring of braking curve with respect to a defined target point
- Monitoring of maximum permitted speed on the line and speed restrictions in force
- Detection of over-speed with auto-visual warning and application of brakes, if necessary
- Maintaining safety distance between trains
- Monitoring of stopping point
- Monitoring of Direction of Travel and Rollback.

The cab borne equipment will be of modular sub-assemblies for each function for easy maintenance and replacement. The ATP assemblies will be fixed in the vehicle integrated with other equipment of the rolling stock.





### 06 Automatic Train Operation (ATO)

This system will operate the trains automatically from station to station while remaining within the safety envelope of ATP & open the train doors. Driver will close the train doors and press a button when ready to depart. In conjunction with ATP/ATS, ATO can control dwell time at stations and train running in accordance with timetable.

### 08 Automatic Train Supervision (ATS)

A train supervision system will be installed to facilitate the monitoring of train operation and also remote control of the station. The train supervision will log each train movement and display it on the workstations with each Traffic Controller at the OCC and on line workstation placed in the Station Control room (SCR) with each Station Controller.

The centralized system will be installed in the Operation Control Centre. The OCC will have a projection display panel showing a panoramic view showing the status of tracks, points, signals and the vehicles operating in the relevant section/whole system. ATS will provide following main functionalities:

- Automatic Route setting
- Automatic Train Regulation
- Continuous Tracking of train position
- Display Panel & Workstation interface
- Link to Passenger Information Display System for online information
- Computation of train schedule & Timetable

## 5 Interlocking System:

### 01 Computer Based Interlocking (CBI)

The entire line including turnout track, transfer track, sidings will be equipped with CBI system for operation of points and crossings and setting of routes.

The setting of the route and clearing of the signals will be done by workstation, which can be either locally (at station) operated or operated remotely from the OCC.

The sub-system is used for controlling vehicle movements into or out of stations automatically from a workstation. All stations having points and crossings will be provided with workstations for local control. Track occupancy, point position, etc. will be clearly indicated on the workstation. It will be possible to operate the workstation locally. If the control control hands over the operation to the local station. The interlocking system design will be on the basis of fail-safe principle.

The equipment will withstand tough environmental conditions encountered in a Mass Transit System. Suitable IS, IRS, BS standards or equivalent international standards will be followed in case wiring, insulation, earthing, cabling, power supply and for material used in track circuits, axle counters, relays, point operating machines, power supply etc.

**(ii) Track Vacancy Detection**

Primary needs for track vacancy detection system on main line may be through radio and for secondary detection it can be through Track circuit / Axle Counter.

**(iii) Signals**

**Line side signals:** Multi Aspect Colour Light (S&D) type Line side signals shall be installed on the Main Line and depot entry exit.

- (a) At stations with point and crossing for work protection catering for bidirectional working
- (b) At departure location at stations for normal direction of working

**(iv) Point Machines**

Non-Traction Electrical Point Machine capable of operating with either 110V DC or 3-phase 380V AC will be used on main line. The depot point machine will preferably be reliable type.

**9. Train Depot: Signalling**

All depot lines except the one which is used for shunting and in the workshop shall be interlocked. A workstation shall be provided in the Depot Control Centre for electrical operation of the points, signals and routes of the depot yard. Audio Frequency Track Circuits Axle Counter will be used in the depot as well.

**10. Signalling Scheme Plan**

Conceptual Signalling Scheme Plan based on P. Way Plan dated 16.01.2013 for Line -1 and Line -2 of Nagpur Main Rail Project from Tulumbari Sps to Khajuri (Line -1) and Rajpatt Nagar to Loharnya Nagar (Line -2) is enclosed at Annexure 1.

**11.2.2 Standards**

The following standards will be adopted with regard to the Signalling system.

**TABLE 11.1**  
**Signalling System Standards**

Description	Standards
• Interlocking	Computer based interlocking adapted for station having switches and crossing. All related equipment as far as possible will be contained in the equipment room at the station. The depot shall be interlocked except for lines mainly used for workshop, loco, inspection shed lines etc.



Description	Standards
• Block Working	Moving Block working concept may be followed.
• Operation of Points	With Direct current 110V D.C. point machines or 380 volt 3 phase, 50 Hz. AC point machines.
• Track Vacancy Detection System	Primary mode for track vacancy detection system on main line and test track in depot may be through rails and for depot and secondary detection it can be through Track circuit / Axle Counter.
• Signals at stations with point & crossings	Line Side signals to protect the points (switches). LED type signals for reliability and reduced maintenance cost.
• UPS (uninterrupted power at stations as well as for OCC)	For Signalling and Telecommunications.
• Train protection system	Train Protection system shall be based on CBTC (Communication based Train Control System). The system architecture shall provide for redundancy.
• Train Observer System	Automatic Train Supervision system. Movement of all trains to be logged on to a central computer and displayed on workstations in the Operational Control Centre and at the SCR. Remote control of stations from the OCC. The system architecture shall provide for redundancy.
• Cables	Outdoor cables will be steel armoured as far as possible.
• Fail Safe Principles	SIL-4 safety level as per CENELEC standard for signal application, Computer based interlocking and for ATP system.
• Immunity to External Interference	No data transmission on lithium cables/OFC/Radio. All Signalling and telecom cables will be separated from power cables. CENELEC standards to be implemented for EMC.
• Train Working under emergency	Running on side with the side signal with speed automatically restricted between 15-25 kmph.
• Environmental Conditions	All conditions for all equipment rooms.
• Maintenance philosophy	Philosophy of continuous monitoring of system status and preventive & corrective maintenance of Signalling equipments shall be followed. Card / module / sub-system level replacement shall be done in the field and repairs under taken in the central laboratory/ manufacturer's premises.
• Siting	Floor Plan of Line -1 and Line -2 of Nagpur Metro Rail Project from 'Automotive Side to Metro Depot (Dr. Line -1) and Prasad Nagar to Lokmanya Nagar (Line -2) does show any siting. The same may be planned and provided on both the lines to take out the defective Trains during revenue hour.



## 11.2 SPACE REQUIREMENT FOR SIGNALLING INSTALLATIONS

Adequate space for proper installation of all Signalling equipment at each of the stations has to be provided keeping in view the ease of maintenance and use of instrumentation set up for regular testing and line up of the equipment/system. The areas required at each of the stations for Signaling equipment shall be generally 60 sqm. for UPS Room (common for signaling and telecom) and for Signaling Equipment Room 50 sqm. at interlocked station with points & 20 sqm. at other stations. These areas shall also cater to local storage and space for maintenance personnel to work. At the OCC and the Depot, the areas required shall be as per the final configuration of the equipments and network configuration keeping space for further expansion.

## 11.4 Maintenance Philosophy for Signaling system

The philosophy of continuous monitoring of system status and preventive & corrective maintenance of signaling and telecommunication equipments shall be followed. Card / module / sub-system level replacement shall be done in the field. Maintenance personnel shall be suitably placed at intervals and they shall be trained in multi-disciplinary skills. Each team shall be equipped with a fully equipped transport vehicle for effectively carrying out the maintenance from station to station.

The defective card/ module / sub-system taken out from the section shall be sent for diagnostic and repair to a centralized S&T repair lab suitably located in the section/head. This lab will be equipped with appropriate diagnostic and test equipments to rectify the faults and undertake minor repairs. Cards / modules / equipments requiring major repairs as specified in suppliers documents shall be sent to manufacturer's workshop.

\*\*\*\*\*




Figure 1: Schematic diagram of aortic dissection.

© 2015 Wolters Kluwer Health | Lippincott Williams & Wilkins

DOI: 10.1097/TA.0000000000000000



# CHAPTER 12

## TELECOMMUNICATION & AUTOMATIC FARE COLLECTION



### 12.1 TELECOMMUNICATION

### 12.2 AUTOMATIC FARE COLLECTION

#### TABLES

TABLE 12.1	TECHNOLOGIES FOR TELECOMMUNICATION SYSTEMS
TABLE 12.2	TECHNOLOGIES FOR AFC SYSTEMS
TABLE 12.3	AMMETERS IN STATIONS (LINE-1) N-S CORRIDOR (PRATYAKSHI SQUARE TO DEPUT STATION)
TABLE 12.4	AMMETERS IN STATIONS (LINE-2) E-W CORRIDOR (TRAJAPATI NAGAR TO LEONARDA NAGAR)

#### FIGURES

FIG. 12.1	ENTRY/EXIT GATES
FIG. 12.2	TICKET OFFICE MACHINE



## Chapter – 12

### Telecommunication & Automatic Fare Collection

#### 12.1 TELECOMMUNICATION

##### 12.1.1 Introduction

The Telecommunication system acts as the communication backbone for Signaling systems and other systems such as SCADA, AFC etc and provides Telecommunication services to meet operational and administrative requirements of metro network.

##### 12.1.2 Overview

The Telecommunication facilities proposed are helpful in meeting the requirements for

1. Supplementing the Signaling system for efficient train operation.
2. Exchange of managerial information
3. Crisis management during emergencies
4. Passenger information system

The proposed Telecom system will cater to the following requirements:

- Train Traffic Control
- Assistance to Train Traffic Control
- Maintenance Control
- Emergency Control
- Station to station dedicated communication
- Telephone Exchange
- Integrated Passenger Announcement System and Passenger Information and Display System within the station and from Control Center to each station.
- Centralised Clock System
- Train Destination Indicator
- In-plant as well as On-site Radio Communication between Control Center and Moving Cars and maintenance personnel
- Data Channels for Signaling, SCADA, Automatic Fare Collection etc.



- + E&M SCADA is not privileged as part of Telecomm System as such, hence covered separately in DPR.

### 12.1.2 Telecommunication System And Transmission Media

#### **6) Fibre Optic System (FOTS) - Main Telecommunication Beamer**

The main beamer of the bulk of the Telecommunication network is proposed with optical fibre cable system. Considering the channel requirement and keeping in view the future expansion requirements a minimum 48 Fibre optical fiber cable is proposed to be laid in ring configuration with path diversity.

SDH (minimum STM-16) based system shall be adopted with SDH nodes at every station, depot and OCC. The SDH equipment shall be equipped with Ethernet Card to provide channels to other interfacing Contractors of SCADA, PAFIS etc. Further small routers and switches shall be provided for LAN network at station/depot. Alternatively a totally IP Based High Capacity, highly reliable and fault tolerant, Ethernet Network (MAN/LAN) can be provided in lieu of SDH backbone.

#### **8) Telephone Exchange**

For an optimized cost effective solution Small exchanges of 30 port each shall be provided at each station and a 60 Port Exchange at the Terminal Stations shall be provided. The exchanges at Central Control and Depots shall be of larger size as per the actual number of users. The Exchanges will serve the subscribers at all the stations and Central Control. The exchanges will be interconnected at the channel level on optical backbone. The exchanges shall be software partitioned for SPARS and Direct Line Communication from which the phones shall be extended to the stations. Alternatively only for non-essential other than Direct Line Communication, a separate IP Based Phone System can be implemented.

#### **10) Mobile Radio Communication**

Mobile Radio communication system having minimum 8 logical channels is proposed for on-line emergency communication between Motorman (Front end and Rear end) of moving train and the Central Control. The system shall be based on Digital Trunk Radio Technology to TETRA International standard. This system now is widely adopted for mobile radio communication in metro / rapid transit services abroad. At the stations and the OCC will be provided with fixed radio sets. Mobile communication facility for maintenance parties and Security Personnel will be provided with handheld sets. These persons will be able to communicate with each other as well as with central control.

The frequency band for operation of the system will be that for TETRA in 430/800 MHz band, depending on frequency availability. The system shall provide mobile radio communication between the motorman of the moving cars from any place and the Central Control. The motorman can also contact any station in the network through the central control, besides indicating the approaching trains.





about any emergency like accident, fire, fire blocked etc., thus improving safety performance.

To provide adequate coverage, based on the RF site survey to be carried out during detailed Design stage, base stations for the system will be located at sites conveniently selected after detailed survey. Tentatively minimum 8 sites with towers with Base Stations shall be required along the East - West (EW) Corridor at Malindi & Mahindra, Ramna (Ring RD JNC), Lad Chowk, Jhandi Bari SORE, Dolar Vanshi Chowk (Mitra Hospital) and Telephone Exchange Stations. For the North - South (NS) Corridor, at least 5 Base Station with Towers shall be required at Mihan City, Mayurash Station, Rohasa Colony, Zaini Mile and Kadii Chowk Stations.

For the Underground Section of North-South corridor, one Base Station shall be required at New Airport feeding through Lasky Coastal Cables, the adjacent tunnels.

In addition to the TETRA Radio Coverage for the internal use of the Metro, the city is also likely to have Mobile Coverage from Private Operators.

In the elevated sections it is expected that coverage shall be available from the adjoining sites of the Mobile Operators. However, in the underground stations / tunnels, coverage needs to be specially extended by the Mobile Operators. To enable the Mobile Operators to do so, the Metro Authority will have to have an agreement with a group of Mobile Operators according to which Metro shall provide an Air-conditioned room (approx. 20 sq. m) at the underground station to the Mobile Operator Group. The Mobile Operators shall install all their repeater equipment in this room and then extend the coverage inside the tunnel by using their own LCK cable in each tunnel and through entrance strategically placed in the concourse area. Further, for City Emergency Services like Police, the mobile operators shall also design their LCK network to support the police wireless coverage in the tunnels station area. The detailed Agreement covering both the Mobile / Emergency Service Radio Coverage shall have to be finalised by the Metro Authority with the respective parties, at the time of implementation.

#### **iv) Passenger Announcement System**

The system shall be capable of announcements from the local station as well as from OCC. Announcements from Station level will have overriding priority in case of emergency announcements. The System shall be linked to Signaling System for automatic train adjusted announcements.

#### **v) Passenger Information Display System**

These shall be located at convenient locations at all stations to provide bilingual visual indication of the status of the running trains and will typically indicate information such as destination, arrival/departure time and also special messages in emergencies. The boards shall be provided at all platforms and concourses of all stations. The System shall be integrated with the PIS System and available from same MBB.

**12.1 Centralized Clock System**

This will ensure an accurate display of time through a synchronization system of slave clocks driven from a Master Clock at the operation control center. The Master Clock signal shall also be received for synchronization of POTS, Exchanges, Radio, Signaling, etc. The System will ensure identical display of time at all locations. Clocks are to be provided at platforms, concourse, Station Master's Room, Depots and other service establishments etc.

**12.2 Closed Circuit Television (CCTV) System**

The CCTV system shall provide video surveillance and recording function for the operations to monitor each station. The monitoring shall be possible both locally at each station and remotely from the OCC on a Video Wall.

The CCTV system locations shall be based on IP technology and shall consist of a mix of Fixed Cameras and Pan/Tilt/Zoom (PTZ) Cameras. Cameras shall be located at areas where monitoring for security, safety and crowd control purpose is necessary.

For monitoring of inside of Train, a wireless CCTV System from Train to nearest station shall be provided. For this a wifi Broad Band network will be provided at each station, so as to automatically upload On-Board CCTV Video from the Train to the OCC at each station. The Broad Band Radio System shall be based on unlicensed wifi Band and shall use the Optical fibre backbone network to transfer video from the station to the OCC. The On-Board Train Cameras shall be provided as part of the Rolling Stock Contract and they shall interface with a On-Board wifi equipment provided by Telecom Contractor to transmit video to station equipment.

**12.3 Network Monitoring and Management**

For efficient and cost effective maintenance of the entire communication network, it is proposed to provide a network management system (NMS), which will help in diagnosing faults immediately from a central location and attending the same with least possible delay, thus increasing the operational efficiency and reduction in manpower requirement for maintenance. The proposed NMS system will be covering Radio communication, Optical Fiber Transmission, Telephone Exchange and summary status of PABX, CCTV and Clock System.

**Technology**

The Technologies proposed to be adopted for Telecommunication systems are shown in below

**Table 12.1 - Technologies for Telecommunication systems**

System	Standards
• Transmission Media	Optical Fiber system as the main bearer for bulk of the Telecommunication network
• Telephone Exchange	EPABX of minimum 36 ports is to be provided at all Stations, an Exchange of 60 Ports to be provided at Terminal Station



System	Standards
• Train Radio System	Digital Train radio (TETRA) communication between motorman of moving cars, stations, maintenance personnel and central control.
• Train Destination Indicator System	LED/LCD based boards with adequate visibility to be provided at convenient location at all stations to provide bilingual visual indication of the status of the running trains, and also special messages in emergencies.
• Centralized clock system	Accurate display of time through a synchronization system of slave clocks driven from a master clock at the OCC and sub-master clock in station. This shall also be used for synchronization other systems.
• Passenger Announcement System	Passenger Announcement System covering all platform and concourse areas with local as well as Central Announcement.
• Redundancy (Major Systems)	Redundancy on Radio's in the Base Stations, Path Redundancy for Optical Fibre Cable by providing in ring configuration.
• Environmental Conditions	All equipment rooms to be air-conditioned.
• Maintenance Philosophy	System to have, as far as possible, automatic switching facility to alternate routes/circuits in the event of failure. Philosophy of preventive checks of maintenance to be followed. System networked with NMS for diagnosing faults and re-configure. Routine level replacement shall be done in the field and repairs undertaken in the central laboratory/manufacturer's premises.

#### x) Space Requirement for Telecom installations

Adequate space for proper installation of all Telecommunication equipment at each of the stations has to be provided keeping in view the ease of maintenance and use of instrumentation set up for regular testing and fine-tune of the equipment/system. The space required at each of the stations shall be generally 30 sq.m each for Telecom Room and 22 sq.m. for UPS Room (common for signal, Telecom and AFC). These areas shall also cater to local storage and space for maintenance personnel to work. At the OCC, the area required shall be as per the final configuration of the equipment and network configuration keeping space for further expansion.

#### xi) Maintenance Philosophy for Telecom systems

The philosophy of continuous monitoring of system status and preventive & corrective maintenance of Telecommunication equipments shall be followed. Card / module / sub-system level replacement shall be done in the field. Maintenance personnel shall be suitably placed at intervals and they shall be trained in multidisciplinary skills. Each team shall be equipped with a fully equipped transport vehicle for effectively carrying out the maintenance from station to station.



The defective card/module / sub-system taken out from the section shall be sent for diagnostic and repair to a centralized S&T repair lab suitably located on the section. The lab will be equipped with appropriate diagnostic and test equipments to rectify the faults and undertake minor repairs. Cards / modules / equipment requiring major repairs as specified in supplier documents shall be sent to manufacturer's workshop.

## 12.2 AUTOMATIC FARE COLLECTION

### 12.2.1 Introduction

Metro Rail Systems handle large number of passengers. Ticket issue and fare collection play a vital role in the efficient and proper operation of the system. To achieve the objectives, ticketing system shall be simple, easy to use/operate and maintain, easy in procuring facilities, capable of issuing single/multiple journey tickets, operable for quick fare changes and require overall lesser manpower. In view of above, computer based automatic fare collection system is proposed.

For Multiple Journeys, the Metro Value Smart Card shall be utilized and for the Single Journey, the mode shall be as utilized as Contactless Smart Token.

AFC system proves to be cheaper than semi-automatic (manual system) in long run due to reduced manpower cost for ticketing staff, reduced maintenance in comparison to paper ticket machines, overall less cost of recyclable tickets (Smart Card/Tokens) in comparison to paper tickets and prevention of leakage of revenue. Relative advantages of automatic fare collection system over manual system are as follows:

**A) Manual fare collection systems have the following inherent disadvantages:**

1. Large number of staff is required for issue and checking of tickets.
2. Change of fare structure is time consuming as has to be done at each station.
3. Manipulation possible by jamming of mechanical parts.
4. Staff and passenger interaction leading to more chances of corruption.
5. Almost 100% ticket checking at entry / exit impossible.

**B) Automatic fare collection systems have the following advantages:**

1. Less number of staff required.
2. Less possibility of leakage of revenue due to automatic ticket check by control gates.
3. Recycling of ticket fraudulently by staff avoided.
4. Efficient and easy to operate, faster evaluation both in normal and emergency.
5. System is operable for quick fare changes.
6. Management information reports generation easy.
7. System has multi-operator capabilities. Some Smart Card can be used for other applications also, including in other lines of the Metro.
8. AFC systems are the worldwide accepted systems for LRT/Metro environment.



The proposed ticketing system shall be that to be of Contactless Smart Card type for multiple journey and Token for Single Journey. The equipment for the same shall be provided at each station- Counter/Booking office and at convenient locations and will be connected to a local area network with a computer in the Station Master's room.

**C) Choice of Control Gates**

Retractable flap type Control Gates/Paddle Type Gates are proposed which offer high throughput, require less maintenance and are tested in modern metro stations internationally. Triped turnstile type gates offer less throughput and require more maintenance and hence are not preferred.

**D) Passenger Operated Machine**

At all stations, two Passenger Operated Machines (Automatic Ticket Vending Machine) each are proposed. The POM's will provide convenience to passengers to avoid standing in queue at ticket booths and provide them international standard service.

**E) Ticket Reader/Add Value Machines**

These machines will be used to issue the card/token tickets and can also be used as Add value device if cash payment for card top up is made through alternate internet based channel like net banking, Payment gateway etc.

### 12.2.2 AFC equipment Requirement

AFC equipment tentative requirement is given in Table attached. The exact number and type shall depend on the final station layout and the traffic being catered to.

### 12.3.2 Technology

The technology proposed for AFC systems are as under:

**Table 12.3 : Technology proposed for AFC systems**

Standards	Description
• Fare media	<ul style="list-style-type: none"> <li>a) Contactless smart card – For multiple journeys. It is desirable to use a card to reduce specifications as being used for other transport modes (at City or National level), so as to have future interoperability wherever possible.</li> <li>b) Single Journey Contactless smart token captured at exit gates</li> </ul>
• Gates	<p>Computer controlled automatic gates at entry and exit. There will be following types of gates</p> <ul style="list-style-type: none"> <li>• Side</li> <li>• End</li> <li>• Retractable (if required as per final station layout) – can be set to entry or exit</li> <li>• Retractable Heribridged Gate-gate for disabled people.</li> </ul>



Standards	Description
• Station computer, Central computer and AFC Host such	All the fare collection equipment shall be connected in a local area network with a station server controlling the activities of all the machines. These station servers will be linked to the central computer situated in the operational control centre through the optical fibre communication channels. The centralised control of the system shall provide real time data of earnings, passenger flow analysis, identifying of specified routes etc.
• Ticket office machine (TOM/TCO)	Various ticket office machines shall be installed in the stations for selling tickets to the passengers. Also TDM's shall be provided for Automatic Ticket Vending.
• Ticket reader and portable ticket detector	Ticket reader shall be installed near TCO for passengers to check information stored in the ticket.
• VPS (Vendor supplied) (Data) at stations as well as for TDM's.	Continuous VPS of S&T system will be utilized.

Fig 12.1 -Entry/Exit Gates



Fig 12.2 :- Ticket Office Machine





**PASSENGER TRAFFIC AND REQUIREMENT OF AMENITIES IN STATIONS**  
(Projections for Year 2045)

**Table 21.1**  
**AMENITIES AT STATIONS**  
Line-1 N-S corridor (Automatic Square in Green Station)

Station	Peak Hour Boarding and Alighting (1,2,3,4)	Platform length required On each side	TDM Requirement	Minimum Capacity Requirement	Amenities Provided in Each Station		Frequency of Lifts in Each Station
					G-C	G-B	
AUTOMATED SQUARE	3517	5-1-2	2	1.50	2	1	2
NARENDRA	1585	3-1-2	2	1.00	2	2	2
INDIRA CHOWK	1588	3-2-2	2	1.00	2	1	2
RAJIV CHOWK	1688	3-1-2	2	1.00	2	1	2
CHANDRASEKHAR SQUARE	181	3-1-2	2	1.00	2	2	2
NARAYAN CHOWK	1887	3-1-2	2	1.00	2	1	2
LEELA CHOWK	1181	3-1-2	2	1.00	2	1	2
STATION	1181	1-1-1	2	1.00	2	1	2
CHANDRASEKHAR	1081	1-1-1	1	1.00	2	1	2
RAJIV CHOWK	1181	3-1-2	2	1.00	2	1	2
LEELA CHOWK	87	3-1-2	2	1.00	2	1	2
CHANDRASEKHAR SQUARE	101	3-1-2	2	0.80	2	1	2
JAYPRASAD NAGAR	301	3-2-2	2	0.80	2	1	2
LEELA NAGAR	101	3-2-2	2	0.80	2	1	2
RAJIV	180	3-2-2	2	0.80	2	1	2
LEELA RAJIV	108	3-2-2	2	0.80	2	1	2
RAJIV	208	3-2-2	2	0.80	2	1	1

(Note: ② - Ground level)

① - Terrace level

③ - Deck

④ - Overbridge level



**Table 12.4**  
**AMSMITS AT STATIONS**  
**Line-2 E/W corridor (Pragati Nagar to Lokmanya Nagar)**

Station	Peak hour boarding (est. including 10%)	Turning Gear installed in each station	TVM equipment	Minimum number of AFC equipments	Connectors provided in each station		Provision of UWB for each station
					S-C	S-F	
1. Pragati Nagar	433	2-2-1	2	3-60	2	1	1
2. Santoshji Chowk	432	2-2-1	2	4-60	2	1	1
3. Anandji Chowk	320	2-2-1	2	1-60	2	1	1
4. Sayyadwala Chowk	300	2-2-1	2	1-60	2	1	1
5. Chhatrapati Chowk	301	2-2-1	2	1-60	2	1	1
6. Agaveer Chowk	300	2-2-1	2	1-60	2	1	1
7. East Lokmanya Chowk	320	2-2-1	2	1-60	2	1	1
8. Nagpur Railway Station	400	2-2-1	4	1-60	2	2	1
9. Ashok	300	1-1-1	1	1-60	2	1	1
10. Jyoti Baob Square	200	1-1-1	1	1-60	2	1	1
11. Jyoti Baob Diagonal	100	2-2-1	2	1-60	2	1	1
12. Shrikrishna Square	320	2-2-1	2	1-60	2	1	1
13. Lal Chowk	301	2-2-1	2	1-60	2	1	1
14. Shrikrishna College	300	2-2-1	2	1-60	2	1	1
15. Laxman Nagar	311	2-2-1	2	1-60	2	1	1
16. Keshavnagar Road Jct.	311	2-2-1	2	1-60	2	1	1
17. Vasudeo Nagar	311	2-2-1	2	1-60	2	1	1
18. Bawa Nagar	311	2-2-1	2	1-60	2	1	1
19. Lokmanya Nagar	320	2-2-1	2	1-60	2	1	1

**Assumptions:**

- Each station has only 2 access
- Minimum AFC equipments at a station with "2 access- 1 for entry, 1 for exit"; 2 entry gates, 2 exit gates, 2 RFD, 2 TVM, 4 TR, 2 TSM
- One Disabled gate at each station.
- Throughput of gate 25 passengers per minute, TVM 10 transactions per minutes.
- 50 % passenger are assumed on Smart Card and 50% on single journey token.



# CHAPTER 13

## DISABLED FRIENDLY FEATURES



- 13.1 INTRODUCTION
- 13.2 CONTENT
- 13.3 RAIL TRANSPORT
- 13.4 INFORMATION SIGNS AND ANNOUNCEMENTS
- 13.5 METRO RAILWAY STATIONS
- 13.6 INFORMATION SYSTEMS
- 13.7 GENERAL AND ACCESSIBLE TOILETS
- 13.8 DRINKING WATER CENTS
- 13.9 VISUAL CONTRASTS
- 13.10 EMERGENCY SIGNS/EVACUATION
- 13.11 ALERTING SYSTEMS
- 13.12 WRITTEN EVACUATION PROCEDURES
- 13.13 EMERGENCY EVACUATION ROUTE
- 13.14 WAY GUIDANCE SYSTEM
- 13.15 HIGH RESISTANT CORES
- 13.16 STREET DESIGN
- 13.17 TRAFFIC SIGNALS
- 13.18 SIDEWALK AND FOOT OVER BRIDGE
- 13.19 ALIGHTING AND BOARDING AREAS
- 13.20 APPROACH
- 13.21 CAR PARK



## Chapter – 13

# DISABLED FRIENDLY FEATURES

### 13.1 INTRODUCTION

The objective of making this chapter is to create a user-friendly mass transport system in India which can ensure accessibility to persons with disabilities, people traveling with small children or are carrying luggage, as well as people with temporary mobility problems (e.g. a leg in plaster) and the elderly persons.

The design standards for universal access to Public Transport Infrastructure (including related facilities and services, information, etc.) would benefit people using public transport.

The access standards given here are extracted from Indian Roads Congress Code, IRC 802: 2012 Guidelines for Passenger Facilities; Model Building Bye-Laws, 2011 and National Building Code, 2006, Central Public Works Department's (CPWD) "Good Standards for Barrier Free Built Environment for Disabled and Elderly Persons", 1988 and 2013 edition (under revision by MHA) and international best practices / standards.

Further, it has also been attempted to provide guidelines/standards for lighting and boarding area, approach to station, car parking area, drop-off and pickup areas, taxi/auto rickshaw stand, bus stand/stop, footpath (sidewalk), kerb ramp, road intersection, median/bocsaeran refuge, traffic signals, subway and foot over bridge etc. to achieve a seamless development around metro stations.

### 13.2 CONTENT

#### 1. Rail Transport

#### 2. Metro Rail Station

- Way finding
- Signage
- Automated Kiosk



- Public Seating Counters
- Auto-vital Displays
- Public Telephones
- Rest Areas/Seating
- Tactile Paving - Guiding & Warning
- Doors
- Steps & Stairs
- Handrails
- Ramps
- Lifts/Elevators
- Platform/Door LR
- General and Accessible Signs
- Drinking Water Units
- Visual Contrasts
- Emergency Egress/Evacuation

### 3. Street Design

- Footpath (Sidewalk)
- Kurb Ramp
- Road Intersection
- Median/Pedestrian Refuge
- Traffic Signals
- Subway and Foot Over Bridge

### 4. Alighting and Boarding Area

- Approach
- Car Park
- Drop-off and Pickup Areas
- Taxi/Auto Rickshaw Stand
- Bus Stand/Stop

## 13.2 RAIL TRANSPORT

### 1. General

- Whether overground or underground, rail travel is a highly effective mode of transport.
- Every train should contain fully accessible coaches.
- Staff should be trained in methods of assistance and be at hand on request.



- Stations for all rail travel should be fully accessible with extra wide tunnels where possible provide wheelchair accessible doorways
- Staff should be on hand to assist persons with disabilities and elderly to enter or exit through convenient gates.
- All new railway stations should be designed to be fully accessible.
- For persons with hearing impairments, an electronic sign board (digital display) should be deployed on each platform at conspicuous location for all announcements made by the railways
- For persons with visual impairments audio system announcing the station names and door location should be available.

### 2. Accessible Railway Cars

The railway cars should have the following features:

- Railway car doors should be at least 900 mm wide.
- The gap between the car doors and the platform should preferably be less than 12 cm.
- Identification signage should be provided on the doors of wheelchair accessible coach.
- If the car door and the platform cannot be at the same level, then at least two car doors should have apparatus such as a hydraulic lift or pull-out ramp installed in the doorway for wheelchair users.

### 3. Wheel Chair Space

- Space for a wheel chair should be available at the side of the door.
- The space should be indicated inside and outside the car by using the International symbol of access, and
- Wheel stoppers and ring grab or other appropriate safety grip should be provided for wheelchair users.

### 4. Seats

- An appropriate number of designated seats for passengers with disabilities and elderly people should be provided near the doors.

### 5. Aisles

- Aisles should be at least 500 mm wide.

## 13.4 INFORMATION SIGNS AND ANNOUNCEMENTS

A map of train routes should be installed. This should be in Braille raised numbers as well. In each car, there should be an announcement and provision of a visual display of



the names of stations route. This display should be in raised numbers with sharp contrast from the background.

## 12.3 METRO RAILWAY STATIONS

### 1. LEVEL APPROACH

- Approach route should not have level differences. If the station is not on the same level as the walkway or pathway, it should a ramp.
- Walkway surfaces should be non-slip.
- Approach walkway should have tactile pavements for persons with visual impairments.

### 2. STATION ENTRANCES AND EXITS

- These should have a minimum width of 1000mm and a level or ramped.

### 3. RESERVATION AND INFORMATION COUNTERS

- Should have clear floor space of at least 900 mm x 1200 mm in front of the counter.
- There should be at least one low counter at a height of 750 mm to 800 mm from the floor with clear knee space of 750 mm high by 800 mm wide by 480 mm deep.
- At least one of the counters should have an induction loop unit to aid people with hearing impairments; and
- The counters should have pictographic maps indicating all the services offered at the counter and at least one of the counter staff should be sign language fluent.

### 4. TICKET FACILITIES

- There should be at least one unisex accessible toilet.
- Ticket Gates.

At least one of the ticket gates should:

- Be minimum 500 mm wide to allow a wheelchair user through; and
- Have a continuous line of guiding colour for people with visual impairments.

### 5. PLATFORMS

The Platforms should:

- Have a row of warning colour installed 800mm before the track edge (photo 8).



- Have ramps and level flooring.
- Have seating areas for people with ambulatory disabilities.
- Be well illuminated (see level 35 to 40).
- There should be no gap or difference in level between the main entry door and the platform.
- All platforms should inter-connect by means of an accessible route or lifts; and provide accessible level entrance to the main coach.

## 6. WAYFINDING

- Way finding references should be available at decision points.
- Colour can be used to identify routes and provide assistance in locating doors, walls and hazards. Proper colour contrast between different elements greatly improves visibility for all users and is critical for persons with low vision. For example, colour contrasting of door frames can assist in locating doors, and likewise floors should be contrasted with walls. In addition, furniture should contrast with walls and floors so as not to create an obstacle.
- Structural elements such as columns should be colour contrasted or brightly marked so as to be visible to those who may have a visual disability.
- Generally, patterns on flooring should be avoided or else should be minimal and small to avoid visual confusion.
- In addition to identifying hazards or warnings, tactile floor surfaces can also be used to inform that there is a change in area (e.g. leaving a corridor and entering a boarding area).
- Tactile systems should be consistent throughout the building. For example, terminals should not have carpeting in some boarding areas and tile in others as this may create confusion for those who rely on tactile surfaces to guide them to their destination.
- Good lighting assists those with a visual disability to see better and allows people who have a hearing impairment to lip read better. However, care should be taken to properly direct lighting and to use matte finishes on floors, walls and signage, so as not to create glare which may create difficulties for all travellers.
- Blind can be used to adjust lighting levels in areas where the natural lighting changes significantly throughout the day.

## 7. SIGNS

Signs must be clear, concise, and consistent. All travellers need clear information about the purpose and layout of terminals to maintain a sense of direction and independent use of all facilities. Using internationally and nationally established symbols and pictograms with clear lettering and Braille ensures universal accessibility cutting across geographical and language barriers. A cohesive information and signage system can provide visual (e.g. signs, notice boards), audible (e.g. public address and security systems, induction loops, telephones, and infrared devices), and/or tactile information (e.g. signs with embossed lettering or Braille).



## 8. SIGN DESIGN SPECIFICATIONS

- The sign should be in a prominent position.
- The face of the sign should be well-illuminated by natural or artificial light.
- Letters should be simple such as Arial, Helvetica medium, and can serif or similar and numbers should be Arabic.
- The colour of the text should be in a colour that contrasts with the sign board.
- The sign board should also contrast with the wall on which it is mounted.
- The surface of the sign should not be reflective.
- Some signs such as those apparent to or on a raised floor may be embossed so that they can be read by touch.
- Illuminated signs should not use red text on a dark background.
- Signs should be supplemented by Braille where possible.



Fig. 10.1 - Wayfinding signs



Fig. 10.2 - International Symbol of Accessibility

## 9. Automated kiosks

- Automated kiosks should be accessible for wheelchair users.
- Should be clearly marked with international symbol of accessibility.
- Should have Braille buttons and audio announcement system for persons with vision impairments.
- Operations should be easy to understand and operate for persons with learning disabilities, intellectual disabilities, and elderly persons.

## 10. PUBLIC DEALING COUNTERS

- Ticketing, Information, Check-in, Map desk, Restaurants, Shops, etc. should have public dealing counters.







if counters, reduced boarding and during inter-county travel in customs areas and baggage retrieval areas.

- Designated seating should be provided for at boarding gates and departure areas within viewing distance of communication boards, and within hearing range of audio announcements as well. Such seating areas should be identified by the symbol of accessibility and shelter should be provided where this seating is outdoors.
- In outdoor settings, seating should be provided along with the planned busker zones.
- All waiting lounges for persons with disabilities chairs should have armrests and footrest.

## 32. Tactile Paved- Queues & Waylead<sup>1</sup>

### (a) Tactile Guiding Paver (Line-Type)

It is recommended to install a row of tactile guidance paver along the entire length of the proposed accessible route for visual impaired persons. Care must be taken to ensure that there are no obstacles, such as wall, pillar, uneven surfaces, gaps underneath open area under the stairs, along the route traversed by the guidance paver. Also, there should be clear headroom of at least 2.1 meters height above the tactile guidance paver, free of protruding objects such as over-hanging advertisement panel and signage, along the entire length of the walk.

### (b) Tactile Warning Paver (Dot-Type)

Indicate an approaching potential hazard or a change in direction of the walkway, and serve as a warning of the approaching danger to persons with visual impairments, directing them to treat cautiously and avoid obstacles along the travel path, traffic intersections, doorways, stairs, etc. They are used to screen off obstacles, cross-overs or other hazards, to discourage movement in an incorrect direction, and to warn of a corner or junction. Two rows of tactile warning paver should be installed across the entire width of the designated accessible passenger gateway at appropriate places such as before intersections, terminal entrances, obstacles such as signage, and each time the walkway changes direction.

## 34. PLACE TO INSTALL WARNING

- In front of an area where traffic is present.
- In front of an entrance to and from a staircase or multi-level crossing facility.
- Entrances/exits of public transport terminals or boarding areas.



Fig. 13.3 - Gisting paper



Fig. 13.4 - Wisting paper





## 18. Doors

Whatever the type of entrance door, it must be wide enough to accommodate passenger traffic comfortably.

- The recommended minimum clear opening width of an internal door is 900mm minimum.
- Where doors comprise two leaves (i.e. double doors), each leaf should be 500mm min. wide, so that persons carrying large items and people using wheelchairs do not have to open both leaves.
- Manual doors should incorporate kick plates 300-400mm high to withstand impact of wheelchair travel (this is especially important where doors are glazed).
  - Also be fitted with vision panels at least between 800mm and 1500mm from floor level.
  - Be color contrasted with the surrounding wall and should not be heavier than 22N to open.
  - Lever handles and push type mechanisms are recommended. When a sliding door is fully open, handles should be visible from both sides.
- Where revolving doors or turnstiles are used, an alternative wheelchair accessible entrance must also be provided.
- A distance of 400mm should be provided beyond the leading edge of door to enable a wheelchair user to manoeuvre and to reach the handle.
- To ensure maximum clarity for persons with visual impairments, the entrance should be easily distinguishable from its surroundings by the effective use of landscaping, signage, colour (preferably yellow/orange), braille contrast and tactile surfacing.
- Clear heights should be maintained between 900-1000mm above floor (figure 28).
- Operable devices such as handles, pulls, latches and locks should:
  - Be operable by one hand
  - Not require fine finger control, tight grasping, pinching or twisting to operate
- Glazed doors and fixed glazed areas should be made visible by use of a clear, colour and tone contrasted warning or decorative feature that is effective from both inside and outside and under any lighting conditions, e.g. a logo, of minimum dimensions 150mm by 150mm (though not necessarily square), set at eye level.

## 19. Steps & Ramps

- Steps should be uniform with the tread not less than 300mm and the riser 150mm.



- The risers should not be open.
- The steps should have an unobstructed width of 1200mm minimum.
- All steps should be fitted with a permanent colour and tone contrasting at the step edge, extending the full width of the step, reaching a minimum depth of 50mm on both front and rear.
- Have continuous handrails on both sides including the wall (if any) at two levels.
- Warning power to be placed 300mm at the beginning and at the end of all stairs.
- Warning to be avoided.
- The staircase should be adequately and uniformly illuminated during day and night (when in use). The level of illumination should preferably fall between 100-150 lux.
- The rise of a flight between landings must be six more than 1200mm.
- There should be no more than 12 risers in one flight run.
- The stair covering and nosing should be slip-resistant, non-reflective, firmly-fixed and easy to maintain.
- Grit (underneath open area under the stairs) of the stairs should be enclosed or protected.

#### 17. HANDRAILS

- Handrails should be circular in section with a diameter of 30-40mm and formed from materials which provide good grip such as timber, nylon or powder coating, matt finish metal finishes.
- The handrail should contrast in colour (preferably yellow/orange) with surrounding surfaces.
- At least 50mm clear of the surface to which they are attached and should be supported on brackets, which do not obstruct continuous hand contact with the handrail.
- The handrail should be positioned at two levels- 750mm and 900mm above the pitchline of a flight of stairs.
- Handrail at foot of the flight or stairs should extend 300mm beyond the stairs in the line of travel and returning to the wall or floor or rounded off, with a positive end that does not project into the route of travel.

#### 18. RAMPS

- Ramps gradient should ideally be 1 in 20 and on greater than 1 in 12.
- Width of the ramp should not be less than 1200mm and preferred width is 1800mm.
- The steeper the gradient, the shorter the length of ramp between landings.
- On long ramps, a horizontal resting space should be provided every 6 meters.
- Surface materials should be slip-resistant, non-reflective, firmly-fixed and easy to maintain.
- The edge of the ramp should have an edge protection with a minimum height of 100mm.



- Landings every 750mm of vertical rise.
- A toping or lower rail should be positioned so that its bottom edge is no higher than 200mm above ground level.
- Handrails on the ramps should be on both sides at two levels: upper at 900mm and lower at 740mm; both are to be rounded and grouted; extend 300 mm beyond top and bottom of ramp.
- A row of tactile warning paver should be placed 800mm beginning and end of each run.
- Landings should be provided at regular intervals as indicated in the table (Table 1).

**Table 13.1 - Specifications for Ramps**

Level clearance	Minimum gradient of Ramp	Ramp Width	Handrail on both sides	Comments
≥ 150 mm	1:12	1200 mm	✓	
≥ 300 mm				
≥ 300 mm	1:12	1600 mm	✓	Landings every 5 meters of ramp run.
≥ 750 mm				
≥ 150 mm	1:18	1800 mm	✓	Landings every 5 meters of ramp run.
≥ 300mm				
≥ 3000mm	1:20	1800 mm	✓	Landings every 5 meters of ramp run.

## 13. Lift Elevators

A carefully designed lift makes a huge contribution to the accessibility of a multi-storied terminal building for persons with disabilities.

- Lift locations should be clearly signposted from the main pedestrian route and recognizable through design and location.
- The color and tone of the lift doors should contrast with the surrounding wall finish to assist in their location. Lift doors with metallic finishes such as steel grey and silver should be avoided as they are difficult to identify by persons with low vision.
- The lift lobby shall be of an inside measurement of 1800mm X 2000mm or more. A clear landing area in front of the lift doors of minimum dimensions 1000mm x 1000mm should be provided.
- By making the landing area distinguishable by floor surface and contrast, it will aid location and recognition of core areas. This could comprise a change in floor finish from 8th carpet to vinyl/PVC, or cementitious floor to carpet.
- Changes in floor finish must be flushed. There should be no level difference between lift door and the floor surface at each level; the gap if unavoidable should not be more than 12mm.
- The floor level/location should be indicated on the wall adjacent to or just above the call buttons, and opposite the lift doors where possible.



## 20. Lift Dimensions

- Provisions of at least one lift shall be made for people using wheelchairs with the following clear dimensions:
  - a. Clear internal depth - 1000 mm minimum
  - b. Clear internal width - 1300 mm minimum
  - c. Entrance door width - 900 mm minimum

## 21. Lift Controls

- The lift car button should be wall-mounted adjacent to the lift and should contrast with wall finish, either by using a contrasting panel, or a contrasting border around the button panel.
- The call buttons should be located within the range 800-1200mm above floor finish.
- Buttons should not be touch sensitive, but should require a light positive pressure and should ideally be large enough to be operable by the palm of the hand if required.
- The control buttons inside the lift should be positioned on the side wall rather than front wall to allow access from the back and front of the lift car, by mobility aid users like wheelchair users.
- The control buttons should contrast with their surroundings and illuminate when pressed and should incorporate highly visible tactile embossed (DCT engraved) characters and in Braille.
- Time of closing of an automatic door should be more than 5 seconds and the closing speed should not exceed 20 meters per second. There should be a provision of cancer enabled closing.
- In larger lifts, controls should be positioned on both side walls, at least 400mm from front wall and between 800-1200mm above floor level.

## 22. Car Decor

- Internal walls should have a non-reflective, matt finish in a colour and tone contrasting with the floor, which should also have a matt, non-slip finish.
- Use of reflective materials such as metal (polished steel for example) can be problematic in creating sufficient contrast with control buttons, emergency telephone handset, etc. for persons with low vision and the use of such materials should be avoided wherever possible.
- A mirror (750mm above floor level) on the rear wall can be useful to persons using wheelchairs and other mobility aids should they need to reverse safely out of the lift car or view the floor numbers.
- Internal lighting should provide a level of illumination of minimum 100 lux (approximately 30-70 lux at floor level), uniformly distributed, avoiding the use of spotlights or down lights.



- A grab bar should be provided along both sides and the back wall, 900mm above floor level.
- Handrails should be of tubular or oval cross section, in order to be easily gripped and capable of providing support.
- Handrails should be positioned so that there is a clear space behind the handrail to allow it to be grasped i.e. in clear space should be 50mm.

## 12.6 INFORMATION SYSTEMS

- Lifts should have both visual and audible floor level indicators.
- Audible systems are also usually capable of incorporating additional messages, such as door closing, or, in the case of an emergency, reassurance (with manual over-ride allowing communication with lift occupants).
- Announcement systems should be of 30 decibel.
- The display could be digital or segmented LED, or an appropriate alternative. A yellow or light green on black display is preferred to a red on black display as it is easier to read.

## 12.7 GENERAL AND ACCESSIBLE TOILETS

### 1. SIGNAGE

- All signage of general toilets should be in bold and contrasting colors.
- For persons with low vision and vision impairments, male pictogram in triangle and female pictogram in circle, marked on plates along with Braille & raised alphabets, to be mounted on wall next to door near the latch side, at a height between 1400mm-1600mm.
- Warning strip (thin rubber) door mat to be provided 300mm before and after the toilet entrance.
- Tactile paving to be provided for urinals, WC and washbasins for persons with vision impairments.

### 2. ACCESSIBLE TOILETS

- Should have the international symbol of accessibility displayed outside for wheelchair access.
- The toilet door should be an outward opening door or two way opening or a sliding type and should provide a clear opening width of at least 600mm.
- It should have a horizontal push-bar, at least 600mm long, on the inside of the door, located so that it is 100mm from the hinged side of the door and at a height of 1000mm.

-



### 3. WC Compartment Dimensions

- The dimensions of a unisex toilet are critical in ensuring access. The compartment should be at least 2200mm and 2000mm. This will allow use by both manual and restricted wheelchair users.
- Layout of the fixtures in the toilet should be such that a clearing maneuvering space of 1500mm x 1500mm is front of the WC and washbasin.

### 4. Water Closet (WC) Fixtures

- Top of the WC seat should be 400-430mm above finished floor level, preferably be of wall hung or corbel type as it provides additional space at the toe level.
- An unobstructed space 900mm wide should be provided to one side of the WC for transfer, together with a clear space 1200mm deep in front of the WC.
- WC should be centred 300mm away from the side wall, with the front edge of the pan 750mm away from the back wall. Have a back support. The WC with a back support should not incorporate a lid, since this can hinder transfer.
- L-shaped grab bar at the adjacent wall and on the transfer side (open side) being up grab bar shall be provided.
- The toilet should have a lever flush mechanism, located on the transfer side and not on the wall side and not more than 1000mm from the floor.

### 5. Grab Bars

- Grab bars should be manufactured from a material which contrasts with the wall finish (or use dark tiles behind light colored tiles), be warm to touch and provide good grip.
- It is essential that all grab rails are adequately fixed, since considerable pressure will be placed on the rail during maneuvering. Grab bars should sustain weight of 300kgs minimum.
- A single type flexible grab bar should be installed adjacent to the WC on the transfer side. The rail can incorporate a pivot flange holder. A distance of 50mm from the centre line of the WC between heights of 200-260mm from the top of the WC seat. It should extend 100-150mm beyond the front of the WC.
- A fixed wall-mounted L-shaped grab bar (500mm long horizontal and 750mm long vertical) on the wall side should be provided. It should be placed at a height of 200-260mm above the WC seat level.

### 6. Washbasin

- Hand washbasins should be fitted on cantilevered brackets fixed to the wall.
- The basin should be fixed no higher than 750mm above the finished floor level.
- Be of dimensions 520mm and 440mm, mounted such that the top edge is between 800-900mm from the floor, have a knee space of at least 750mm wide by 200mm deep by 600-630mm high.





- The position of the basin should not restrict access to the WC i.e. it should be located 800mm away from the WC.
- A lever operated mixer tap fitted on the side of the basin closest to the WC is useful as it allows hot and cold water to be used from a seated position on the WC.
- The hand drying facilities should be located close to the hand washbasin between 1000-1200mm.
- Lower type handsets for taps are recommended.
- Mirror's bottom edge to be 1000mm from the floor and may be inclined at an angle.

#### 7. FIXINGS AND FINISHES

- Contrast between fittings and fixtures and wall or floor finishes will assist in their location. For example, using contrasting fittings, or dark tiles behind white hand washbasins and urinals, contrasting soap dispensers and toilet roll holders. Contrast between vertical surfaces, e.g. floors, walls and ceilings helps to define the dimensions of the room.
- Towel rails, rings and handrails should be securely fixed to the walls and positioned at 800-1000mm from the floor.
- The mirror should be fixed at an angle of 300 for better visibility by wheelchair users.
- It should have over edge at 1000mm above floor finish and top edge around 1800mm above floor finish.
- Hooks should be available at both lower-1200mm and standard height- 1400mm, projecting not more than 40mm from the wall.
- Where possible, be equipped with a shelf of dimensions 400mm x 200mm fixed at a height of between 900mm and 1000mm from the floor.
- Light fittings should illuminate the user's face without being visible in the mirror. For this reason, most units which have an integral light are unsatisfactory.
- Large, easy to operate switches are recommended, contrasting with background to assist location, at a maximum height of 1000mm above floor finish.
- All toilet facilities should incorporate visual fire alarms.
- Alarms must be located so that assistance can be summoned both when on the toilet pan i.e. at 800mm height and lying on the floor i.e. at 300mm from floor surface. Alarms should be located close to the side wall nearest the toilet pan, 700mm away from rear wall and at 300mm and 200mm above floor finish.

#### 8. BOARDING-ACCESSIBLE TOILETS

- All boarding-accessible toilets to have access symbol in contrast colour. A distinct audio sound (beeper/dropper) may be installed above the entrance door for identification of the toilet.



Fig. 112 - Signs for accessible washroom



## 8. Accessible Urinals

- At least one of the urinals should have grab bars to support ambulant persons with disabilities (for example, people using mobility aids like crutches).
- A stall-type urinal is recommended.
- Urinals shall be stall-type or wall-hung, with an elongated rim of a maximum of 400mm above the finish floor. This is usable by children, short stature persons and wheelchair users.
- Urinal shields (that do not extend beyond the front edge of the urinal rim) should be provided with 750mm clearance between them.
- Grab bars to be installed on each side, and in the front, of the urinal.
- The front bar is to provide chest support; the sidebars are for the user to hold on to while standing.

## 10.8 Drinking Water Urns

- Drinking water fountains or water coolers shall have up front spouts and controls.
- Drinking water fountains or water coolers shall be hand-operated or front and foot-operated.
- Conventional floor mounted water coolers may be convenient to individuals in wheelchairs if a small fountain is mounted on the side of the cooler 800mm above the floor.
- Fully recessed drinking water fountains are not recommended.
- Leg and knee space to be provided with open to avoid spilling of water. This allows both front and parallel access to taps for persons using mobility aids like wheel chair, crutches etc.

## 10.9 Visual Contrasts

- Visual contrast means adequate contrast created by difference of at least 30 LRV (Light Reflectance Value) of the two surfaces/ objects and it helps everyone especially persons with vision impairments.
- Visual contrast should be provided between:
  - a. Critical Surfaces (walls, ceiling and floor).
  - b. Signage and background sign frame/wall.
  - c. Step edges and raised/heads in steps.
  - d. Handrails and background walls.
  - e. Doors and surrounding walls.
  - f. Outlets/ sockets and background wall.
  - g. Toilet fixtures and critical surfaces in toilet.
- Buttons and fixtures should be highlighted by incorporating colours and luminance contrast.



### 10.10 Emergency Egress/Evacuation

- Placement (accessibility) and visibility of such devices is very important. The following is to be considered for the installation of such alarm devices: fire alarm boxes, emergency call buttons and if panels should be installed between heights of 800mm and 1050mm from the finished floor surface. These should be adequately contrasted from the background wall and should be labeled with raised letters and should also be in Braille.
- 
- A pre-recorded message, alerting an emergency to the control room or reception should be installed in the telephone and this should be accessible by a 'hotkey' on the phone keypad. This hotkey should be distinct from the rest of the keypad.

### 10.11 Alarmic Devices

- In emergency situations, it is critical that people are quickly alerted to the situation at hand, for persons with disability the following needs to be considered:
- 
- Consider having audible alarms with voice instructions that can help guide them to the nearest emergency exit. As an alternative to the pre-recorded messages, these alarms may be connected to the central control room for on-the-spot broadcasts.
- 
- Non-audible alarms (visual or sensory) to alert persons with hearing impairments should be installed at visible locations in all areas that the passengers may use (including toilet areas, etc).
- 

Non-audible alarms include:

- Flashing beacons
- Vibrating chairs and vibrating beds.
- Pagers or mobile phones that give out a vibrating alarm along with a flashing light (these may be issued to persons with vision or hearing impairments at the time of check-in or boarding the vehicle.)

### 10.12 Written Evacuation Procedure

A written evacuation procedure that details the egress plan for people with disability should be installed behind the entrance door in the accessible rest rooms. The evacuation procedure should be detailed in large print letters that contrast strongly against the background. Where possible, it should also incorporate raised letters and Braille. The evacuation route should be displayed on a high contrast tactile map for benefit of persons with vision impairments.



### 13.13. EMERGENCY EVALUATION ROUTE

- Designate routes that are at least 1000mm wide, to ensure that a person using a wheelchair and a non-disabled person are able to pass each other along the route. The route should be free of any steps or sudden changes in level and should be kept free from obstacles such as furniture, columns, AC units and power poles.
- Use exit signage along the route. Orientation and direction signs should be installed frequently along the evaluation route and these should preferably be internally illuminated. The exit door signage should also be internally illuminated.
- A 'way guidance lighting system' consisting of low mounted LED strips to outline the exit route (with frequent illuminated direction indicators along the route) should be installed along the entire length of the evaluation route. Way guidance systems allow persons with vision impairments to walk significantly faster than traditional overhead emergency lighting. Moreover, emergency exit lights in green color and directional signals mounted near the floor have been found to be useful for all people in cases where a lot of smoke is present.

### 13.14. WAY OBSCURE EXIT

- Luminance on the floor should be the minimum provided on along the centre line of the route and on stairs.
- Install clear illuminated sign above exit and also directional signage along the route.
- The directional exit signs with arrows indicating the way to the escape route should be provided at a height of 900mm from the floor level at the wall and should be internally illuminated by electric light connected to circuit.

### 13.15. FIRE RESISTANT DOORS

- Fire resistant doors and doors used along the emergency evaluation route are generally heavy and the force required to open these is much higher than 25 Newtons, making it difficult for people with disability to negotiate these doors independently. There are, however, magnetic and other types of door holders available that can be connected to fire alarms so that they will hold the doors open normally but will release the doors when the fire alarm is activated.

## 13.16. STREET DESIGN

### (a) Footpath (Sidewalk)

Footpaths should be regarded as a transportation system which is connected and continuous, just like railways and canals. They should not be sporadically placed where ever convenient, but instead should be provided consistently between all major attractions, big generators, and other locations where people walk.

**Footpath should:**

- Be along the entire length of the road;
- Have height of a standard public step near i.e. 150 mm maximum;
- Be at least 1800 mm wide;
- Have non-slip surface;
- Have tactile guiding paver for persons with visual impairment;
- Preferably have well defined edges of paths and routes by use of different colours and textures;
- Have no obstacles or projections along the pathway. If this is unavoidable, there should be clear headroom of at least 2200 mm from the floor level;
- The minimum 1.8m (width) x 2.2m (Height) Walking Zone should be clear of all obstructions - both horizontally and vertically.

**Footpath should have:**

- Have kerb ramps where ever a person is expected to walk into or off the pathway; and
- Have tactile warning paver installed near to all entry and exit points from the footpath.

**(ii) Kerb Ramp**

- Kerb should be dropped, to be flush with walk way, at a gradient no greater than 1:10 on both sides if necessary and convenient crossing points. Width should not be less than 1200mm. If width (W) is less than 1200mm, then slope of the faced side shall not exceed 1:12.
- Floor tactile paving- Guiding & Warning cover shall be provided to guide persons with vision impairment so that a person with vision impairment does not accidentally walk into the road.
- Finches shall have non-slip surface with a texture traversable by a wheel chair.

**(iii) Road Intersections**

- Pedestrian crossings should be equipped with traffic control signal;
- Traffic islands to reduce the width of the crossing are recommended for the safety of all road users;
- Warning pavers should be provided to indicate the position of pedestrian crossings for the benefit of people with visual impairment;
- Table tops (raised road level to the sidewalk height) are helpful in reducing the speed of traffic approaching the intersection.



### 10.16 Median/Pedestrian Refuge

Raised islands in crossings should:

- Cut through and level with the street; or
- Have kerb coping on both the sides and have a level end of not less than 1500 mm long in the middle; and
- A coloured tactile marking strip at least 600 mm wide should mark the beginning and end of a median/pedestrian refuge to guide pedestrian with visual impairments to its location.

### 10.17 Traffic Signals

- Pedestrian traffic lights should be provided with steady audible signals for the benefit of pedestrians with visual impairments;
- Acoustic devices should be installed on a pole at the point of origin of crossing and not at the point of destination;
- The installation of two adjacent acoustic devices such as beepers is not recommended in order to avoid disorientation;
- The time interval allowed for crossing should be programmed according to the speed crossing persons; and
- Acoustical signals encourage safer crossing behaviour among children as well.

### 10.18 Subway and Foot Over Bridge

Subways and foot over bridges should be accessible for people with disabilities. This may be achieved by:

- Provision of signage at strategic location;
- Provision of slope ramps or lifts at both the ends to enable wheelchair accessibility;
- Ensuring that the walkway is at least 1300 mm wide;
- Provision of tactile guiding and warning paver along the length of the walkway;
- Keeping the walkway free from any obstructions and projections; and
- Providing for seats for people with ambulatory disabilities at regular intervals along the walkway and at landings.

### 10.19 ALIGHTING AND BOARDING AREA

- All areas and services provided in the Mass Rapid Transit System (MRT/subway), bus terminals, etc. that are open to the public should be accessible.

### 10.20 AIRQUALITY

- Passenger walkways, including passages to the bus stops, fare stands, terminal / station building, etc. should be accessible to persons with disabilities;
- Uneven surfaces should be repaired and anything that encroaches on corridors or paths of travel should be removed to avoid creating new barriers. Any obstructions



or areas requiring maintenance should be white cone accessible<sup>2</sup>.

- Access path from site entry and surface parking to terminal entrance shall have even surface without any steps.
- Slope, if any, shall not have gradient greater than 1%. The walkway should not have a gradient exceeding 1:20. It also refers to cross slope.
- Tactile change in walk ways adjacent to seating by means of tactile warning paver should be provided for persons with vision impairment.
- Avoid gratings in walks.

## 13.21 Car Park

### (A) SIGNAGE

- International symbol of accessibility (wheelchair sign) should be displayed at approaches and entrances to car parks to indicate the position of accessible parking lot for persons with disabilities within the vicinity.
- Directional signs shall be displayed at points where there is a change of direction to direct persons with disabilities to the accessible parking lot.
- Where the location of the accessible parking lot is not obvious or is distant from the approach viewpoints, the directional signs shall be placed along the route leading to the accessible parking lot.
- Accessible parking lot should be identifiable by the international Symbol of Accessibility. The signs should not be obscured by a vehicle parked in the designated lot.
- Vertical signs shall be provided, to make it easily visible, the sign should be at a minimum height of 2100 mm.

### (B) SYMBOL

International Symbol of Accessibility should be clearly marked on the accessible parking lot for drivers/operators with disabilities only.

- A square with dimensions of at least 1000 mm but not exceeding 1300 mm in length.
- Be located at the centre of the lot, and
- The colour of the symbol should be white on a blue background.

### (C) Car Park Entrance

The car park entrance should have a height clearance of at least 3600 mm.

### LOCATION

- Accessible parking lots that serve a building should be located nearest to an



accessible entrance and / or lift lobby within 30 meters. In case the access is through lift, the parking shall be located within 30 meters.

- The accessible route of 1200 mm width is required for wheelchair users to pass behind vehicle that may be backing out.

#### **(D) Accessible Car Parking Lot**

The accessible car parking lot should:

- Have minimum dimensions 6000 mm x 3000 mm.
- Have a firm, level surface without unevenness.
- Whenever possible, be sheltered.
- Where there are two accessible parking bays adjoining each other, then the 1200 mm wide transfer bay may be shared by the two parking bays. The transfer zones, both at the side and the rear should have yellow and white cross-hatch road markings.
- Two accessible parking lots shall be provided for every 25 no. of car spaces.
- 

#### **(E) DROP OFF AND PICK UP AREA**

- Designated drop-off and pick-up spaces, to be clearly marked with international symbol of accessibility.
- Karts whenever provided, should have left hand.



# CHAPTER 14

## ENVIRONMENTAL IMPACT ASSESSMENT



14.0	INTRODUCTION
14.1	BASILINE ENVIRONMENTAL CONDITIONS
14.2	METHODOLOGY AND CHECKLIST
14.3	AMBIENT AIR QUALITY
14.4	AMBIENT NOISE QUALITY
14.5	WATER QUALITY
14.6	SOIL QUALITY
14.7	POSITIVE IMPACTS DUE TO THE PROJECT
14.8	ANTICIPATED IMPACTS AND MITIGATION MEASURES
14.9	OTHER IMPACTS
14.10	SOCIAL IMPACTS
14.11	IMPACTS DURING OPERATION PHASE
14.12	IMPACT ON TERRESTRIAL ECOLOGY
14.13	ENVIRONMENTAL MANAGEMENT PLAN
14.14	MITIGATION MEASURES
14.15	ENVIRONMENTAL MONITORING PLAN

### TABLES

TABLE 14.1	LAND USE CATEGORIES
TABLE 14.2	SUMMARY OF AIR QUALITY MONITORING RESULTS
TABLE 14.3	STATISTICAL INDICATORS FOR NOISE QUALITY
TABLE 14.4	WATER QUALITY MONITORING RESULTS
TABLE 14.5	SURFACE WATER SAMPLE ANALYSIS RESULTS
TABLE 14.6	SOIL SAMPLE ANALYSIS RESULTS
TABLE 14.7	SUMMARY OF TRCIS
TABLE 14.8	SOCIO-ECONOMIC PROFILE OF DMU
TABLE 14.9	STRUCTURES AFFECTED
TABLE 14.10	TYPLOGY OF STRUCTURES AFFECTED
TABLE 14.11	STRUCTURES AFFECTED CORRIDOR-WISE
TABLE 14.12	EXTENT OF IMPACTS ON STRUCTURES
TABLE 14.13	COMMON PROPERTY RESOURCES
TABLE 14.14	AREA LIKELY TO BE AFFECTED (DMU)
TABLE 14.15	CORRELATIVE IMPACT DUE TO INCREASE NOISE
TABLE 14.16	PROVISION OF NOISE BARRIERS IN DIFFERENT STRUCTURES
TABLE 14.17	ENVIRONMENTAL MANAGEMENT PLAN
TABLE 14.18	ENVIRONMENTAL MONITORING PROGRAMME



## CHAPTER 14

# ENVIRONMENTAL IMPACT ASSESSMENT

### 14.0 INTRODUCTION

The Ministry of Environment and Forests (MoEF), Government of India issued notification on 14th September 2006 superseding the earlier notification No.: 80/80(E) dated 27th January 1994 for getting Environmental Clearance. All new projects/expansion and modernisation of existing projects or related activities listed in the schedule I of the notification are required to obtain prior environmental clearance from MoEF. The proposed Nagpur Metro rail project does not fall in the schedule requiring the prior environmental clearance. Still, DMRC being an environmental conscious organization has undertaken EIA study to mitigate/reduce the environmental impacts arising from construction and operation of the project.

DMRC appointed M/s Consulting Engineering Services (India) Private Limited for carrying out the EIA study for the proposed Nagpur Metro. The objective of the EIA study is as follows:

- Ascertain positive and negative environmental and social impacts of the project.
- Mitigate negative environmental and social impacts.
- Enhance environmental quality in and around the project area by adopting mitigation and conservation measures.

### 14.1 BASELINE ENVIRONMENTAL CONDITIONS

The development / completion of environmental baseline data are essential to assess the impact on environment due to the project. The environment includes water, land, air, ecology, noise, vibration etc. The information presented in this section stems from various sources such as reports, field surveys and monitoring.

Climatologically data was collected from regional meteorological department at Nagpur. This data has been further utilized to assess the incremental impact if any due to the project. Socio-Economic assessment has also been done. Study Area

consists of the following two main alignments for the proposed metro rail project in Nagpur:

- Automotive Square to KINAFRI (North - South Corridor) - 10.038 Km including one depot.
- Pappaji Nagar to Lokmanya Nagar (East - West Corridor) - 18.957 Km including one depot.

#### 14.1.1 Physiography

Nagpur district lies on the Deccan Plateau of Indian peninsula and has a mean altitude of 316.0 meter above sea level. It is situated at latitude between 20°30'N and 21°44'N and longitude between 78°15'E and 79°40'E. The district is situated on the eastern part of the State sharing the state of Madhya Pradesh in north and is bounded by Wardha and Amravati districts in the west, Bhandara district in the east and Chandrapur district in the south. The district has a geographical area of 8832 sq. km. Nag River a tributary of Kanha river flows through the project alignment. The district forms part Deccan Trap of the project area is plain.

#### 14.1.2 Geology and Soil

The city of Nagpur lies on the basaltic flow known geologically as Deccan Traps. The parent basalt is very dark grey in colour, compact, dense and very hard in nature. It is very difficult to break this rock and it breaks up with subconchoidal fractured conforming to be of igneous origin. Nagpur city lies in the neighbourhood of the classical geological areas of India. More than half of the whole district of Nagpur is covered by basaltic and doleritic lava flows known as Deccan Traps. The main soil types present in the region are sal soils, mottled soil, khari soil, tarki soil, sacchar soil and wadi soil.

#### 14.1.3 Hydrology

Nagpur city is located on a basaltic plateau and the topography in and around the city is plain to gently rising. The north-eastern and eastern parts of Nagpur district are drained by Wainganga river and its tributaries of which Kanha forms the major. The central and western portion of the district is drained by Wardha river which is main tributary of Wainganga river.

There are several natural water bodies within the city limits including 12 lakes, ten rivers and five canals. The lakes (Gonwade, Fulea, Ambazari, Senapati, Sakinaka, Gondhingar, Lendhata, Nakhata, Dhotkale, Pandrapoti, Sanjay Nagar Khetan and Paroti) cover an area of about 3.15 sq. km. The Nag and M

Rivers cut across the city and are 15.73 km. and 12.11km. in length, respectively. Besides these, Chamar Nallah, Shadi Nagar Nallah, Mukteshwar Nallah, Brahaspuri Nagar Nallah and Sahakar Nagar Nallah also flow through the city.

#### 14.1.4 Land Use Pattern

The land use/land cover pattern of a region is an outcome of natural and socio-economic factors and their utilisation by man in time and space. Hence, information on land use/land cover is essential for the selection, planning and implementation of land use which can be further used to meet the increasing demands for basic human needs and welfare. Land use pattern along both the alignment is generally residential and commercial, with some part of the alignment having plantation, institutions, water bodies etc.

The different categories of land use of the study region are given in the Table 14.1 below:

**Table 14.1: Land Use Categories**

S. No.	Land Use Category	Area (sq.km)	Area Percentage (%)
1	Agricultural Land	11.24	14.52
2	Settled Area	28.85	43.75
3	Open Area	7.31	9.35
4	Plantation	8.26	10.66
5	Institute	0.51	0.66
6	Industry	6.79	8.73
7	Lake	1.07	2.01
8	Water body	0.42	0.54
9	Canal	0.23	0.29
10	Ground	0.00	0.24
11	Waste land	2.63	3.37
Total		78.09	100.00

#### 14.2 Meteorology and Climate

The climate of Nagpur can be broadly divided into three important seasons of summer, winter and monsoon. Almost throughout the summer (March-June), the maximum temperature remains beyond 40 degree Celsius. Sometimes it may be as high as 48 degree Celsius. Monsoons (July-September) take its charge in the month

of June, it showers maximum in the months of July and August. The minimum temperature recorded around 12 degree Celsius in winters (October-January) and sometimes even dips down below that level in the month of February. Nagpur city experiences a low pressure in the end of May month resulting in the wind blowing at a speed of 6 m/s or more and for the rest part of the year, the speed remains 2 to 3 m/s.

#### 14.2.1 Temperature

The temperature generally rises from the beginning of March till June, which is the hottest month of the year with mean minimum and maximum temperatures of 20.3°C and 30.7°C respectively. With the onset of monsoons by the end of June, temperature begins to fall. The drop in day temperature is much more than the drop in night temperature.

The night temperature falls rapidly after the withdrawal of monsoons by mid-September. The month of December is coolest month with the mean maximum and minimum temperatures being 26.3°C and 12.1°C respectively.

Sky is generally clear with light surface winds blow from North or North-easterly direction. The normal minimum temperature is 12.3°C to 14.0°C with slight rise in the mean daily minimum temperature. The mean maximum temperature is around 29.6°C.

#### 14.2.2 Humidity

Except during monsoon months it generally low throughout the year. During summer season, humidity is lowest (20.7%). During monsoon months, it goes as high as 80-90%. The highest level of humidity (88%) is observed in the month of August.

#### 14.2.3 Rainfall

At Nagpur, the annual rainfall is 1250.7 mm. About 68 to 71 % of the annual rainfall is received in the monsoon months. The rain in Nagpur is heavily dominated by the south-westerly monsoon winds. Precipitation in form of rain is received during monsoon months. The number of rainy days in a year is about 56.9 at Nagpur.

#### 14.2.4 Seismicity

The project area falls in **Zone-II** of Seismic Zoning Map of India. This is a low active zone from seismic point of view. Nagpur has close to zero chances of getting a major earthquake which may cause huge devastation. Recent history also supports the fact

that Nagpur region is relatively very safe as far as earthquakes are concerned. But still, as per the Seismic Zoning Map of India (IS-1893, Part-I, 2002) necessary seismic factors suggested by Indian Meteorology Department (IMD) shall be incorporated suitably while designing the structures to safeguard against earthquake risk.

#### 14.3 Ambient Air Quality

As a part of this study ambient air quality monitoring (AAQM) has been carried out by setting up ambient air quality monitoring stations at four locations. The baseline data pertaining to the existing air quality will help mitigate impact on air quality during construction stage and operation stage of the project. The prominent source of air pollution in urban area is vehicular traffic.

Monitoring was done as per the guidelines for Ambient Air Quality Monitoring, National Ambient Air Quality Status NAQA/MS/202003-04. The following parameters were measured:

- Respirable Suspended Particulate Matter (RSPM/PM<sub>10</sub>)
- Fine Particulate Matter (FSPM/PM<sub>2.5</sub>)
- Sulphur Dioxide (SO<sub>2</sub>)
- Nitrogen Dioxide (NO<sub>2</sub>)
- Carbon Monoxide (CO, 1 hourly)
- Hydrocarbons (HC 1 hourly)

Air quality monitoring results are summarized in the following Table 14.2.

**Table 14.2. Summary of Air Quality Monitoring Results**

Parameter	Proposed Rishi Chavak Station (Residential/Commercial area)	Near proposed Mayuresh Station (Residential/Commercial area)	Ambedkar Chavak Station (Residential/Commercial area)	Near Proposed Subhash Nagar Station (Residential/Commercial area)
<b>PM<sub>10</sub> (µg/m<sup>3</sup>)</b>				
No. of Sample	8	8	8	8
Range	28-72	32-51	29-64	27-43
Mean	42.8	36.3	41.8	33
Std. Deviation	49.6	40.7	31.3	33.8
<b>PM<sub>2.5</sub> (µg/m<sup>3</sup>)</b>				
No. of Sample	8	8	8	8
Range	25-38	25-37	20-30	25-33
Mean	33.3	30.9	27.0	30.7
Std. Deviation	35.0	30.4	12.1	33.1

NO <sub>x</sub> (µg/m <sup>3</sup> )				
No. of Samples	8	8	8	8
Range	21-49	23-49	23-44	23-49
Mean	42.4	39.8	33.0	41.8
95 percentile	47.5	48.6	42.8	44.5
SO <sub>2</sub> (µg/m <sup>3</sup> )				
No. of Samples	8	8	8	8
Range	9-23	11-26	9-26	13-24
Mean	16.3	17.3	17.4	17.9
95 percentile	22.0	24.8	25	23.5
CO (mg/m <sup>3</sup> )				
No. of Samples	8	8	8	8
Range	1.17-1.17	1.12-1.31	1.13-1.34	1.13-1.21
Mean	1.13	1.24	1.21	1.20
95 percentile	1.17	1.3	1.31	1.23
Hydrocarbons (µg/m <sup>3</sup> )				
No. of Samples	8	8	8	8
Concentration (µg/m <sup>3</sup> )	<1.0	<1.0	<1.0	<1.0

The maximum value of PM<sub>10</sub> found at Kaddi Chowk station (42.8 µg/m<sup>3</sup>) followed by Anandkar Chowk (41.8 µg/m<sup>3</sup>), Mayuresh Station (36.3 µg/m<sup>3</sup>) and Subhash Nagar Station (33 µg/m<sup>3</sup>).

The mean Nitrogen Dioxide concentrations were measured as 42.4 µg/m<sup>3</sup>, 39.8 µg/m<sup>3</sup>, 33.0 µg/m<sup>3</sup> and 41.8 µg/m<sup>3</sup> at Kaddi Chowk, Mayuresh station, Anandkar Chowk and Subhash Nagar station. These concentrations are well within the standards i.e. 80 µg/m<sup>3</sup> as prescribed by National Ambient Air Quality Standards. The low level of the Nitrogen Dioxide concentration may be attributed to better traffic management.

The average concentration of Sulphur Dioxide generated at various monitoring stations were recorded 16.3 µg/m<sup>3</sup>, 17.3 µg/m<sup>3</sup> and 17.4 µg/m<sup>3</sup>. The values are also well within the specified limit i.e. 80 µg/m<sup>3</sup> at all the monitoring stations.

The mean Carbon Monoxide values at all four monitoring sites were recorded as 1.13 mg/m<sup>3</sup>, 1.24 mg/m<sup>3</sup>, 1.21 mg/m<sup>3</sup> and 1.20 mg/m<sup>3</sup> at Kaddi Chowk station, Mayuresh Station, Anandkar Chowk and Subhash Nagar station which is well within the National Ambient Air Quality Standards of 2mg/m<sup>3</sup>.

As per the quantitative analysis of Hydrocarbons in air samples it may be concluded that hydrocarbons are present in minimum concentration (<1.0  $\mu\text{g}/\text{m}^3$ ) in the air environment of the study area. The concentration of hydrocarbons measured at all four stations throughout the winter season was very well below the limit of 5  $\mu\text{g}/\text{m}^3$ .

#### 14.4 Ambient Noise Quality

Noise levels are measured at different places (16 locations) in Nagpur along the corridor of building lines away from source as per standard practice. Noise monitoring locations are presented in following Table 14.3 below.

Statistical indicators worked out for establishing the baseline conditions along the project corridor is presented in Table 14.3 below.

**Table 14.3: Statistical indicators for Noise Quality**

S. No.	Station No.	$L_{\text{max}}$	$L_{\text{avg}}$	L90	$L_{\text{eq}}$	$L_{\text{min}}$	$L_{\text{min}}$
1	Automotive Soudas	75.00	61.40	57.30	70.00	65.00	63.80
2	Dr. B. R. Ambedkar Educational Institute	73.00	60.00	55.20	74.70	68.30	65.90
3	Z.P. School Palamasahar Technical High School & College	64.00	53.20	51.34	64.00	55.44	53.84
4	Bank of Maharashtra near proposed Station station (Munje Chowk)	75.00	58.00	57.20	72.00	54.80	61.00
5	NEERU Corridor	71.00	63.80	60.17	74.07	65.07	65.40
6	Majurash Apartment (at proposed majurash station)	62.80	48.60	50.90	63.20	56.80	54.70
7	Escorting Terminal Building	71.00	43.70	58.50	73.0	67.0	63.2
8	Open land of MHA SEC	55.00	34.20	52.00	55.90	49.00	45.00
9	Seeco Hospital	70.00	62.70	55.40	72.31	65.20	63.47
10	Aarish Tower	68.50	55.00	55.00	70.00	63.80	60.40
11	Mayo Hospital	70.00	62.00	57.60	71.00	66.60	64.20
12	Ram Mandir	73.00	67.40	71.44	75.00	69.14	66.34
13	Gowardhan Das Rowal High School	67.00	52.80	54.15	67.00	63.15	58.75
14	Saprekar's Brother's Petrol Pump	74.00	60.70	71.00	75.44	69.94	66.00
15	Dharmapal Polytechnic & Science College	68.00	48.90	50.00	71.20	63.00	61.80
16	St. Xavier's High School	68.00	62.30	59.11	69.01	62.80	62.11



Highest value of  $L_{50}$  has been obtained at NO 13 (74.39 A) and minimum value has been obtained at NO 7 (67.05 A) along the East - West corridor. Whereas, maximum day time  $L_{50}$  has been obtained at NO2 (73.05 A) and minimum value is obtained at NO5 (62.5 cdf A) along the North-South corridor.

#### 14.6 Water Quality

It is reported that five rivers are intercepting the project road. The other hydrological features are irrigation canal which intercepted the project road at five locations. The ponds are existing along either side of the project road provide requirements to village communities. The flow of river in the project site is seasonal and remains dry throughout the year. The underground water is the only important source for catering to needs of water demand for village's communities falling along the project road.

Water quality monitoring was carried out at four location covering two surface water sources and two groundwater sources. The results of the groundwater analysis obtained are presented below in Table 14.4:

**Table 14.4. Water quality monitoring results**

Parameter and unit	Station code			Limits as per IS-10000
	Gandhi High Division (GWH)	Automated Sowers (DWS)	Mayurath Station (DWS)	
Colour (Hazen-unit)	<5	<5	<5	5
Taste	Agreeable	Non-Agreeable	Non-Agreeable	Agreeable
Temperature (°C)	28	28.6	27.6	-
pH	8.5	8	8.5	6.5-8.5
Conductivity (µS/cm)	950	835.2	605.2	-
TDS (mg/l)	31.5	30.5	18.5	500
TSS (mg/L)	2	3	1	-
Total hardness(mg/l)	325.4	113.2	118.8	300
Total alkalinity(mg/l)	152.61	50.88	181.73	200
Chloride (mg/l)	67.10	72.07	77.04	250
Sulphate (mg/l)	7.28	4.28	5.06	200
Nitrate (mg/l)	0.011	BDL	BDL	45
Fluoride (mg/l)	0.75	BDL	BDL	1
Calcium (mg/l)	79.2	276	81	75
Magnesium (mg/l)	62.99	10.50	28.67	30
Sodium (mg/l)	697	477	430	-
Potassium (mg/l)	108	105	205	-

Parameter and unit	Station code			Limits as per IS-10000
	Gandhi Bagh Garden (GW1)	Autorative Square (GW2)	Mayuresh Station (GW3)	
Prognada (mg/l)	0.04	0.32	2.47	-
Silica (mg/l)	0.18	0.79	0.11	-
Arsenic (mg/l)	<0.01	<0.01	<0.01	0.01
Lead (mg/l)	<0.05	<0.05	<0.05	0.05

#### 14.6.1 Physical Parameters

The quality of the ground water is showing alkali trend as the pH value ranges from 8-8.2 which is not within the desirable limit for Autorative Square and Mayuresh Station persisting non-agreable taste used for drinking purpose. The water contains no color, turbidity free and is colourless serving the most important source for drinking. Electrical Conductivity is a useful tool to evaluate the purity of water. The groundwater is fresh and potable with electrical conductivity ranging between 200  $\mu$ S/cm to 350  $\mu$ S/cm at 25°C.

Total dissolved solids (TDS) is a measure of the combined content of all inorganic and organic substances contained in a liquid in molecular, ionized or micro granular suspended form. The limit of 500mg/l for potable water is based primarily on the taste threshold. TDS ranges between 14.5mg/L to 31.3mg/L which is well in the permissible limit.

TDS varies from 1mg/L to 3 mg/L, while Total Hardness in the ground water samples vary from 100.0mg/L to 320.4mg/L as CaCO<sub>3</sub>.All the ground water samples were found to be moderately hard. Maximum Total hardness is reported in Gandhi Bagh Garden whereas minimum total hardness is reported in Mayuresh Station. Though hard water has no harmful effects on health but it restricts its use for other purposes.

#### 14.6.2 Chemical Parameters

Chloride content in the water samples was low in the entire section. The concentration of chloride in the groundwater is found in the range of 57.3mg/L to 77.04 mg/L, which is within the limit of all groundwater stations.

The sulphate content varies between 4.28mg/l to 7.28mg/l and the fluoride content is 0.76mg/l at Gandhi Bagh Garden which is within the desirable limit of 1mg/l. Maximum Sulphate concentration is observed in Gandhi Bagh Garden but very well below the desirable limit.

Total Alkalinity in terms of CaCO<sub>3</sub> varies from 30.08mg/l to 102.03mg/l which is within the desirable limit of 200mg/l as prescribed by Indian Standards of Drinking Water.

Nitrate is well within the limits of IS: 10580 at all the stations. Its concentration at Gauri Bagh Garden is 0.01mg/l while it is below detection limit at other sites which is within the permissible limit of 45mg/l

Fluoride content at Gauri Bagh garden is 0.76mg/l which is well below the desirable limit 1.5mg/l

Calcium is a major cation found in ground water. Its concentration varies between 10.2mg/l to 270 mg/l. The concentration of calcium at Automotive Square and Mayurach Station exceeds the limit of 75mg/l.

Magnesium concentration in the groundwater is high ranging between 10.5mg/l to 67.66mg/l. Mayurach Station exceeds the permissible limit of 30mg/l

#### 14.5.3 Heavy metals

Arsenic and lead concentration at all the GW stations is below the desirable limit of 0.01mg/l and 0.05mg/l respectively.

#### 14.5.4 Microbiological parameters

Total coliform and fecal coliform are absent in the groundwater samples.

The results of the surface water sample analysis obtained are presented below in Table 14.5.

**Table 14.5: Surface water sample analysis results**

Parameter and unit	Station code	Limits as per IS:2290
	Ardsaran lake (SW1)	Class D
Colour (Hazen unit)	>5	-
Taste	Non-Aggressive	-
Temperature (°C)	28	-
pH	6.2	6.5
Conductivity (µS/cm)	1900.1	1000
TDS (mg/L)	89.8	-
TSS (mg/L)	20	-
Dissolved Oxygen (mg/l)	5.0	4
Total hardness(mg/L)	286.2	-
Total alkalinity(mg/L)	154.36	-
Chloride (mg/L)	100.25	-
Sulfate (mg/L)	33.04	-
Nitrate (mg/L)	0.003	-
Fluoride (mg/L)	0.94	-
Calcium (mg/L)	17.28	-
Magnesium (mg/L)	19.045	-

Parameter and unit	Station code	Limits as per IS 2286
	Arsochari lake (SW1)	Class D
Sodium (mg/L)	1436	-
Potassium (mg/L)	167	-
Phosphate (mg/L)	0.02	-
Silica (mg/L)	0.88	-
Nitrite (mg)	BDL	-
CO <sub>3</sub>	12	-
SO <sub>4</sub> (mg/l)	5.0	-
Cl & (mg/l)	6	3.1
Arsenic (mg/L)	<0.01	-
Lead (mg/L)	<0.05	-
Total Coliform (MPN/100ml)	110	-

#### 14.5.5 Physical Parameters

The pH value of SW1 is 8.2. The alkaline pH in this water might be due to presence of alkalinity minerals in water. Higher values of pH also reduce germicidal potential of chlorine. The electrical conductivity of the surface water is 1966.1  $\mu$ S/cm. Electrical conductivity at the site was found to exceed the limit of 1000 $\mu$ S/cm. High value of conductivity recorded at SW1 (Arsochari Lake) indicates a high concentration of soluble salts in water. The water contains color, therefore do not serves the drinking purposes of the local population dwelling in the area.

The value of TDS-88.9 mg/L. TSS is found in natural surface water. TSS value of water sample is 20 mg/l.

The value of DO is 5.8 mg/l indicating the levels of organic matter in the water. The principal natural physical factors affecting the concentration of oxygen in the marine environment are temperature and salinity. DO concentrations decrease with increasing temperature and salinity.

#### 14.5.6 Chemical Parameters

Total Hardness in the surface water sample is 288.2mg/L as CaCO<sub>3</sub>. Sulphate is present in the surface water within the permissible limit, its concentration is 33.64mg/l.

Total Alkalinity in terms of CaCO<sub>3</sub> of the water sample is 264.38mg/l indicating high concentration of carbon based minerals suspended in that water. Chloride is an important anion present in the water. Its concentration is 200.8mg/L, showing high chloride content. Elevated levels may also harm aquatic life.

Nitrate are used as indicators of nutrient levels and as a guide for the algal bloom and hence eutrophication. Its concentration beyond permissible limit leads to methemoglobinemia, which is blue baby disease. Its concentration in the surface water samples is 8.023 mg/l. Fluoride content is 3.94mg/l.

Calcium is a major cation found in water. Its concentration in the water sample is 17.28 mg/l.

Chemical Oxygen Demand value is 12 mg/l in the water sample which indicates that the lake water is unpolluted. Low Total Phosphate content of the water sample is 8.02mg/l indicates there is no phosphorus loss from agricultural sites entering lakes.

BOD concentration in the water sample is 5.0mg/l. The BOD value indicates less quantity of organic waste in the lake water making it moderately clean.

#### 14.6.7 Heavy metals

Arsenic and Lead concentration in the water sample is <0.01mg/l and <0.05 mg/l respectively.

Coliform analysis can indicate the degree of possible contamination by human sewage, and possible presence of other pathogens, present in the water. Total Coliform in SW1 is 110 MPN/100ml.

### 14.8 Soil quality

Soil samples were collected from selected locations to establish the baseline soil conditions in the study area. Representative soil samples from depth (15cm) were collected for estimation of physico-chemical characteristics of soil.

#### 14.8.1 Physical properties

Results indicate that the clay content is 32% at SQ1, 28% at SQ2, 19% at SQ3 and 54% at SQ4. The sand content varies from 34-52% while silt content is varying from 12-32%. The porosity is ranging from 7.4% by mass to 10.5% by mass. Lower values of bulk density varying from 1.17 to 1.24gm/cc, indicate good soil structure.

Texture of SQ1(Agricultive Source) is classified as Sandy Clay Loam, SQ2 as Medium Loam, SQ3 as Sandy Loam and SQ4 as Clayey. The soils varied in moisture content from dry through moist to wet soils. Moisture content varies from 3.7% to 21.3%.

#### 14.8.2 Chemical Properties

The collected soil samples were analyzed for various chemical properties. The parameters selected were pH, electrical conductivity, Organic Matter, Nitrogen,

Exchangeable Potassium, Phosphorus, Sulphate and Sodium. pH is an important factor which indicates the alkaline and acidic nature of soil and gives the idea of nutrient availability, microbial activity and physical condition of the soil. The soil in the study area is alkaline in nature as the pH value is varying from 7.75 to 8.55. Conductivity is ranging from 80 to 175  $\mu\text{S/cm}$ . The total nitrogen in the soil samples in the study area varies from 728mg/100g to 1784mg/100g. The substantial amount of the nitrogen in the soils of the study area is contributed by nitrogen fixing bacteria of the genus *Rhizobium* associated with the leguminous plants of the area which constitute an appreciable proportion of the plant species.

Organic matter is an important soil health indicator as it contributes to the biological, chemical, and physical properties of the soil. Organic matter serves as a reservoir of nutrients and water in the soil, aids in reducing compaction and surface crusting, and increases water infiltration into the soil. The organic matter in the soil samples is ranging from 1.5% to 2.6%. It is also responsible for the stability of soil aggregates.

The phosphorus concentrations ranged from 33mg/100g to 34mg/100g. The total content of the basic chemicals like K, gives the extent of leaching of the soil where the concentration of exchangeable Potassium varies from 27.5mg/1000g to 251.5mg/1000g.

The analytical results of the soil samples are presented in the Table 14.6.

**Table 14.6. Soil samples analysis results**

Parameter & Unit	Monitoring location			
	IG1 Agriculture Square	IG2 Near Airport Area	IG3 Between Prakash Nagar and Vasthni Devil Chalk	IG4 Between Subhash Nagar & Bachana Ring Road
pH	7.75	7.84	8.56	8.02
Electrical Conductivity ( $\mu\text{S/cm}$ )	175	58	80	66
Sand (%)	52	48	42	34
Silt (%)	28	32	38	12
Clay (%)	22	20	19	54
Moisture Content (%)	31.2	6.2	3.7	8.9
Infiltration rate (mm/hr)	14.8	60.3	11.2	8.6
Bulk Density ( $\text{g}/\text{cm}^3$ )	1.24	1.19	1.21	1.17

Parameter & unit	Monitoring location			
	EQ1 Automotive Square	EQ2 New Airport Area	EQ3 Between Prapsat Nagar and Vaishno Dev Chakk	EQ4 Between Subhash Nagar & Richana Ring Road
Porosity (%)	9.3	9	10.5	7.4
Organic Matter (%)	1.7	2.1	2.5	1.5
Nitrogen (mg/100 g)	1754	1024	1429	739
Exchangeable Potassium (mg/1000g)	203.2	177.8	201.8	77.1
Phosphorus (mg/100 g)	94	57	72	33
Sulfate (as SO <sub>4</sub> ) (mg/g)	295	7.9	11.9	19.2
Sodium as (Na) (mg/g)	207	54.1	140.2	45

#### 14.6.3 Biological Environment

The main impact on biological environment will be from the tree felling. Data pertaining to the field survey indicates that total 41 species will be felled due to the project. Primary survey of the terrestrial ecology indicates that no rare endangered species listed in the IUCN are getting affected due to the project. The main species are given in Table 14.7.

**Table 14.7: Summary of Trees**

Corridor	Location	Length	Trees to be felled
Corridor - 1 (North - South)	Automotive Square to Dixit at KWARA	13.528 Km	80 Nos.
Corridor - 2 (East - West)	Prapsat Nagar to Lakshanya Nagar	18.567 Km	14 Nos.

Hence, a total of 159 trees are likely to be felled for the project construction.

#### 14.7 POSITIVE IMPACTS DUE TO THE PROJECT

The metro rail will not only offer commuters a more secure and comfortable travel experience that comes with world class facilities, but it will also reduce the time of travelling and rush hour commuting. Its wide network coverage and connections will provide a very positive impact on daily commute of the people of Nagpur city. Some of the positive environmental impacts are as follows.

- Employment opportunities

- Enhancement of Economy
- Less fuel consumption
- Traffic congestion reduction
- Less OGD emissions
- Reduction in Air pollutant emission

The different components of benefits include

- Vehicles off the Road due to Metro
- Vehicle KM Saved by Metro passengers
- Amount of travel time saved by Metro Passengers and by the Remaining Road Passengers (due to reduced congestion and increased speed on the road)
- Fuel consumption saved due to shifting to Metro
- Reduction in vehicular emissions in tonnes and the reduction in related emission cost
- Reduction in total and fatal accidents and savings in Accident Costs
- Reduction in Vehicle maintenance and operation Cost.
- Travel time savings to remaining road users due to release of road space, reduced congestion and improved speeds.

## 14.8 ANTICIPATED IMPACTS AND MITIGATION MEASURES

The environmental impact assessment of the project is based on the Baseline Environmental Status of the Area. The proposed project will have impacts on the environmental attributes in construction and operation phase. During construction phase which may be regarded as temporary or short-term, and the operation phase impacts may have long term effects. The environmental impacts due to construction phase and operation phase are discussed in the following subsections.

### 14.8.1 Impacts during Construction Phase

Potential sources of the construction phase environmental impacts are earthwork, bituminous work, concreting, setting up of labour camps etc. However, the construction phase impacts will be short-term and localized and can be mitigated by adopting appropriate mitigation measures.

### 14.8.2 Traffic Diversion and Risk to Existing Buildings

During construction, traffic diversions on roads will be essentially required. As most of the construction activities will be confined to centre of the road and most of the roads are four lanes, it will be appropriate that the side lanes may also be utilised for traffic



and also for smooth progress of construction activities. Advance information/signboards/warning signs will be an advantage to users of any particular road. As most of the proposed sections are elevated and located in the middle of the road with deck width being much less than the existing road width, hence risk to the existing buildings all along the route will be practically negligible. In underground portion, whether by cut and cover or by tunnelling, the building line is considerably away from the proposed cut and cover and tunnels. Hence no risk is foreseen to adjacent buildings. Some of the measures are as follows:

- At the points where traffic is to deviate from its normal path (whether on temporary diversion or part width of the carriageway) the channel for traffic will be clearly marked with the aid of pavement markings, painted drums or a similar device to the direction of the Engineer in Charge.
- One-way traffic operation will be established whenever the traffic is to be posted over part of the carriageway inadequate for two-way traffic. This will be done with the help of temporary traffic signs or flagmen kept positioned on opposite sides during all hours.
- For regulation of traffic, the flagman will be equipped with red and green flags and lanternlights.
- On both sides, suitable regulatory/warning signs as approved by the Engineer will be installed for the guidance of road users. On each approach, at least two signs will be put up, one close to the point where transition of carriageway begins and the other 150 m away. The signs will be of approved design and of refractory look, or as directed by the Engineer.

#### 14.3.3 Air Quality

Potential impacts on existing air quality during the construction phase would be due to dust generated during excavation, earth work, vehicles movement, loading and unloading of the construction materials.

Fugitive emissions generated due to vehicular movement are not expected to travel beyond a distance of 50 to 100 m from the point of their origin. Since, there is no highway within 250 to 300m of the project site the impact on air environment during the construction phase is not expected to be significant as far as air pollution is concerned. Combustion of diesel in different construction equipment could be one of the possible sources of incremental air pollution during the construction phase.

Mitigation measures for minimizing impact on air quality during construction phase shall comprise:

- Vehicles with an open load carrying shall not be used for moving potentially dust-producing materials. Vehicle shall have properly fitting side and tailboards.
- Materials having the potential to generate dust shall not be loaded to a level higher than the side and tail boards, and shall be covered in vehicles fitted with cover kits / tarpaulin cover.
- Excavated materials shall be stored in the designated dumping/stocked areas.
- Material shall be stabilized during summer season, each day, by watering at every two-hour interval.
- The height from which materials are dropped shall be limited to 1.5 m, to restrict fugitive dust generation.
- Water shall be sprayed on construction sites once every hour for period of two minutes to suppress dust, during handling of excavated dry soil or debris.
- Water sprays shall be used during the delivery and handling of all raw sand, and aggregate and other similar materials, when dust is likely to be created and to dampen all stored materials during dry and windy weather.
- All motorized vehicles on kacha roads on the Site shall be allowed a maximum speed of 15-20 kilometers per hour.
- Concrete batching plant sites and auxiliary areas shall be cleaned frequently and water shall be sprayed to minimize any dust emissions. Tentative sites for locating the construction camps have been identified at the following locations:
  - Lokmany Nagar (proposed metro depot) - Government Land
  - KHAFTU Depot Land - Government Land
  - Automotive Square - Private Land
- Berms/berthing shall be provided securely around all construction work sites during the main construction activity, when reasonably practicable, to contain dust within the site area and also to reduce air turbulence caused by wind or passing traffic.

Workers working in dust generating areas shall use nose masks. Placards advising workers to use nose masks shall be displayed.

#### 14.2.4 Noise Quality

During the construction phase, noise will be generated due to movement of vehicles, and operation of light & heavy construction machines including pneumatic tools (jacks, spurs, loaders, excavators, graders, roller, concrete mixer, generators,

renting pumps, vibrators, cranes, compressors etc.). The construction activities are expected to produce noise levels in the range of 75 – 90 dB (A).

The construction works will be carried out during the day time in residential areas. The impact of noise produced during the construction will, however, be limited to a distance of about 75 meters at which the noise level of various equipment will come down below 55 dB(A). It could therefore be concluded that the construction activities would not have a significant impact on existing ambient noise levels.

Workers working at noisy areas may be affected (if they do not use ear muffs/plugs). If actual exposures exceeds the prescribed safety limits (8-hour long limit of 85 dB (A)) as per Factories Act / OGCW Act 1906.

Mitigation measures for minimizing noise levels during construction phase are as follows:

- ✓ Stationary equipment shall be located so as to minimize noise impact on the neighbouring community.
- ✓ Plant and equipment known to emit noise strongly in one direction shall be oriented, wherever possible, in a direction away from noise sensitive receptor.
- ✓ Silencers and mufflers shall be fitted and maintained on construction equipments.
- ✓ Work shall be scheduled in such a way that activities that generate high noise levels shall not be done simultaneously.
- ✓ Truck loading, unloading, and hauling operations shall be scheduled so as to minimize noise impact near noise sensitive locations and surrounding communities.
- ✓ Equipment and plant will not be kept idling when not in use.
- ✓ Plant shall be serviced regularly.
- ✓ Placards shall be displayed near high noise areas.
- ✓ Ear muffs/Earplugs shall be made mandatory for workers working in high noise areas.

#### 14.2.5 Vibration

Construction activities can result in varying degrees of ground vibration, depending on the equipment and methods employed. Ground vibrations from construction activities do not often reach the levels that can damage structures, but they can achieve the audible and feasible ranges in buildings very close to the site. The construction activities that typically generate the most severe vibrations are blasting and impact pile.

The following mitigation measures will be adopted to reduce the degree of impact due to vibration during construction phase.

- Avoid impact piling in vibration sensitive areas. Drift pile or sonic piling will be employed in such areas to reduce the impacts on nearby buildings.
- Vibration monitoring will be undertaken as suggested in the environmental monitoring plan and a plan shall be prepared by the contractor to control the damage due to vibration.

High time pile driving operation or other high vibration generation activities will not be allowed in vibration sensitive areas.

#### 14.2.6 Soil Quality

Site Runoff from unprotected excavated areas can result in excessive soil erosion, especially when soil is highly erodible. Mitigation measures include careful planning, timing of cut and fill operations and re-vegetation. Problems could arise from dumping of construction spoils (concrete, bricks), waste materials (from contractor's camp) etc. causing surface and ground water pollution.

The proposed North-West corridor has a construction of underground metro of about 3Km. Underground construction is a specialised and complex task. This is safety reasons near airport. Elaborate measures need to be adopted for collection, transfer and disposal of excavated soil as suggested below.

- Soil collection, transportation, disposal and its treatment needs to be carried out in a systematic manner.
- Soil collector should be in containers from the construction sites. These containers should be such that soil should not spill during movement to disposal site.
- The excavated soil will be first collected at dumping ground and then transferred to disposal sites.
- Dumping areas shall be approved by the engineer before its disposal.
- Surplus earth may be used with prior approval by the engineer to the nearby site requiring earth filling.

#### 14.2.7 Impact on Terrestrial Ecology

The main impact on biological environment will be from the tree felling. Data pertaining to the tree survey indicates that total 41 species will be felled due to the project. Primary survey of the terrestrial ecology indicates that no rare endangered species listed in the IUCN are getting affected due to the project. The main species are given in baseline section of this report. About 150 trees are to be cut due to the project on the following corridor:

Necessary permission from Nagpur Municipal Corporation (NMC) garden department is to be obtained for tree cutting. Compensatory tree plantation will be done in ratio of trees to be cut, 10 trees to be planted (1:10).

#### 14.2.2 Impact on Water Quality

Construction activities may have an adverse impact on water bodies due to disposal of waste. The waste could be due to the spillage of construction materials, dumping of used water from the stone crusher, site and grossed and labour camp. But the quantities of such site are very negligible. Care, however, needs to be taken to provide adequate sanitary facilities and drainage in the temporary colonies of the construction workers. Provision of adequate washing and toilet facilities with septic tanks and appropriate refuse collection and disposal system should be made obligatory. Contamination of ground water can take place, if the dump containing above substances gets leached and percolates into the ground water table. This is not the case with the present project, as the activity does not involve usage of any harmful ingredients. Moreover, activities are of short duration. Hence, no adverse impact on either ground or surface water quality is anticipated in the present project.

### 14.3 OTHER IMPACTS

#### 14.3.1 Impact due to Construction Camp

Influx of construction work-force and supplier who are likely to construct temporary tents in the vicinity may be a source of impact on the existing environment. Lousy sanitation, health hazards may impact the surrounding environment due to influx of construction labourers.

#### 14.3.2 Mitigation Measures

- Construction camps sites will be properly demarcated, fenced and access controlled.
- Adequate provision of sanitation, drinking water supply, and primary health facilities.
- Regular health check-ups of worker shall be organized.
- Proper accommodation amenities will be provided to the workers.
- Crèche arrangement for the kids of worker labour shall be made.
- Contractor will make arrangement for cooking gas to the workers to prevent illegal tree cutting.
- The construction camps will be located away from the residential areas.
- Awareness program for workers will be organized
- Preferably local labour will be employed.

#### 14.9.3 Impact due to Equipment storage and Machinery Maintenance

Proper maintenance shed for regular maintenance of the construction vehicles will be provided in the construction yards. Waste emanating from the maintenance shed should not be allowed to spread over to the nearby areas. Oil and grease separator will be provided. Oil and grease change of equipment and vehicles should be carried out in the service area designated for vehicles. Wastes should be collected and disposed of properly and expeditiously.

### 14.10 SOCIAL IMPACTS

#### 14.10.1 Socio-Economic Profile of PAPs/ PAHs

The following sections present socio-economic profile of the households likely to be affected by the proposed project. The baseline information collected through household survey provides the socio-economic conditions of affected households. A wide range of data including religion, social category, type of land and structures, present usage of structures, education, occupation, sources of income, etc. have been collected through the socio-economic survey of households likely to be affected. The data base provides broad understanding of social and economic conditions of project affected households and the likely impacts that people would experience due to proposed project. The Summary of Socio-Economic profile of PAHs is given in table 14.3

**Table 14.3 – Socio-Economic Profile of PAHs**

Particulars		E-W	N-D	Total	
				No.	%
Male		138	33	171	33.94
Female		123	23	146	28.95
	<b>Total</b>	<b>261</b>	<b>56</b>	<b>317</b>	<b>100.00</b>
PAPs by age group	Less than 6 years	13	3	16	5.04
	7 to 14 years	25	1	26	8.19
	15 to 59 years	194	44	238	74.73
	> 59 years	50	4	54	17.04
	<b>Total</b>	<b>282</b>	<b>52</b>	<b>334</b>	<b>100.00</b>
Religion	Hindu	25	3	28	8.37
	Muslim	3	0	3	0.90
	Other	3	1	4	1.20
	<b>Total</b>	<b>31</b>	<b>4</b>	<b>35</b>	<b>100.00</b>
Social group	General	21	5	26	74.29

Particulars	S.W	N-E	Total	
			No.	%
OC	18	1	19	22.45
SC	5	5	10	11.91
ST	5	0	5	5.97
<b>Total</b>	<b>28</b>	<b>6</b>	<b>34</b>	<b>100.00</b>
<b>Occupation</b>				
Agriculture / Animal husbandry	2	0	2	0.62
Govt. Service	2	3	5	1.47
Housewife	11	12	23	6.76
Private service	0	0	0	0.00
Retd. Pension	7	3	10	2.94
Self-employed	20	3	23	6.76
Business	17	10	27	7.94
Student	14	21	35	10.29
Unemployed	2	0	2	0.62
Skilled Worker	2	1	3	0.88
Unskilled Worker	6	0	6	1.76
Children	10	1	11	3.23
<b>Total</b>	<b>102</b>	<b>58</b>	<b>160</b>	<b>100.00</b>
<b>Education (excluding children below 6 years)</b>				
Illiterate	14	1	15	4.38
Literate	11	2	13	3.91
Primary	8	2	10	2.94
Middle	40	6	46	13.33
Matric	11	6	17	4.94
Higher secondary	16	13	29	8.33
Graduate	14	11	25	7.29
Post Graduate	21	7	28	8.06
<b>Total</b>	<b>142</b>	<b>58</b>	<b>200</b>	<b>100.00</b>
<b>HOUSEHOLD INCOME (Rs.)</b>				
< 5000	8	1	9	2.57
5001 - 10000	14	2	16	4.76
10001 - 20000	15	2	17	5.00
20001 - 30000	5	5	10	2.94
30001 - 100000	0	1	1	0.29
100000 +	0	0	0	0.00
<b>Total</b>	<b>40</b>	<b>9</b>	<b>49</b>	<b>100.00</b>

Of the total FAPs, majority (15-35 years) are in the prime age of working. Hindus comprise 85% of the total households likely to be affected. As regards, social category of project affected households is concerned General category of households constitute (93%). Major occupations of FAPs are business, self-employment and service (govt. & private). Women members are mainly housewives. Students comprise about 32% of the total FAPs. As regards qualification of FAPs, it may be

observed that graduates and post-graduates comprise 41% followed by those having completed higher secondary, matric, middle, etc. Indicative household incomes were also ascertained through survey. None of the households qualify for consideration as below poverty line family. Monthly income of majority of households is more than Rs. 15000/-. In fact, almost all the households possess assets and consumer durables like, Fridge, TV, Computer, Mobiles, two wheeler, washing machine, motor cycle, etc. Overall, economic conditions of PAPs likely to be affected are very good. Adverse impacts of proposed project are not likely to result in impoverishment of PAPs but would have significant financial problems if not compensated as per the prevailing market price.

#### 14.10.2 Impact on structures

A total of 101 structures (74 in EW Corridor and 27 in NS Corridor) of various dimensions shall be affected by the proposed project. Majority of the structures are privately owned. Distribution of structures likely to be affected is summarized in Table 14.9. It may be observed that majority of structures are likely to be affected in east-west corridor. More than 50% of the total structures are single storied followed by double storied structures. Further, multi storied structures (upto 5 floors) comprise about 26.73% of the total structures likely to be affected. Most of the multi storied structures are in CA Road facing in east-west corridor.

**Table 14.9: Structures Affected**

Structures Affected (Source: C&P)				
Structures affected	Corridor		Total	
	EW	NS	No.	%
Single storied	43	14	56	55.47
Double storied	19	4	23	22.83
Multi storied (4 to 5 floors)	11	3	14	13.73
<b>Total</b>	<b>74</b>	<b>27</b>	<b>101</b>	<b>100.00</b>
%	73.27	26.73	100.00	

Structures likely to be affected are of three categories (pucca, semi-pucca and kutcha) as per the building materials used for the construction. Semi-pucca structures are those which do not have RCC roof whereas kutcha structures are those which are made of wood, bamboo, straw, (B) sheet, etc. and can be shifted from the existing place to another location without much damage. Pucca structures constitute about 77.23% of the structures whereas semi-pucca and kutcha together comprise the remaining structure (22.77%). Kutcha structures are located at Prapat Nagar in East-West corridor. This list is tentative and exact number of structures likely to be affected can be worked out during detailed planning stage before taking-up of construction activity.



**Table 14.10: Typology of Structures Affected**

Typology of Structures Affected (Source: CTS Primary Survey, 2011)				
Typology of structure	E-W	N-S	Total	
			No.	%
Flats	67	22	76	71.23
Semi-detach	13	6	19	18.08
Kitchen	8	0	8	7.66
<b>Total</b>	<b>14</b>	<b>27</b>	<b>101</b>	<b>100.00</b>

Structures likely to be affected have been identified as per the present use. Majority of the structures in both the corridors is being used for commercial purposes. Structures used for residential and residential cum commercial purposes comprise 25.74% and 25.74% respectively. Structures used for commercial purposes comprise 48.51% of the total structures. (Refer Table 14.11)

**Table 14.11: Structures Affected Corridor Wise**

Structures Affected by Use (Source: CTS Primary Survey, 2011)				
Present use	E-W	N-S	Total	
			No.	%
Residential	22	6	28	25.74
Commercial	22	24	46	48.51
Residential cum commercial	11	7	28	25.74
<b>Total</b>	<b>24</b>	<b>27</b>	<b>101</b>	<b>100.00</b>

Extent of impact on individual structures was detailed based on drawings as well as site verification. Out of the total structures likely to be affected, in 101 structures, the extent of impact is more than 35% and as a consequence occupants of these structures will be displaced. In 10 structures, safety of individual structure after concreting will determine the continuance or displacement of the occupants. Extent of impact on structures is given in Table 14.12

**Table 14.12: Extent of impacts on Structures**

Extent of impacts on Structures (Source: CTS Primary Survey, 2011)				
Extent of impact (in %)	Corridor		Total	
	E-W	N-S	No.	%
Less than 35.48 to 35	17	7	24	23.76
More than 35	67	26	93	91.24
<b>Total</b>	<b>24</b>	<b>27</b>	<b>101</b>	<b>100.00</b>
<b>%</b>	<b>23.27</b>	<b>26.73</b>	<b>100</b>	

#### 14.10.3 Impacts on Common Property Resources (CPRs)

Besides, impacts on structures and land area the proposed project will also affect several common property resources (government structures, community, religious, etc). Distribution of CPRs affected as per scenario is given in Table 14.12. Majority of the common property resources likely to be affected being in different easements/alignments. These structures comprise boundary walls, office buildings, guard room and structures used for other purposes. Similarly, boundary walls and other structures of educational institutions are also likely to be affected. Further, a few temples (3 in E-W corridor and 1 in N-S corridor), one hand pump and one one flow (drinking water post) are also likely to be affected. In both the corridors, major portions of the structures would be affected.

**Table 14.12: Common Property Resources**

Common Property Resources (based on Project Length (km))				
CPRs	E-W	N-S	Total	
			No.	%
<b>Govt. Structures</b>				
Boundary Wall	10	5	15	31.25
Guard room	1	0	1	2.08
Other structures	6	6	12	25.00
<b>Educational Institutions</b>				
Boundary Wall	6	2	8	16.67
Others	2	4	6	12.50
<b>Religious (Temples)</b>				
	3	1	4	8.33
Flow/Well	1	1	2	4.17
<b>Total</b>	<b>29</b>	<b>19</b>	<b>48</b>	<b>100.00</b>

#### 14.10.4 Impacts on Land

Water stations have been planned within the road land mostly and as such additional land area is not proposed for it. But, additional land area is required for providing access to main stations, parking facilities near stations, turning sections, yards, curves, etc. Land area required for the proposed project has been worked out as per the design. Distribution of land area required for various purposes is presented in Table 14.14.

Table 14.14 - Area Likely to be Affected (sqm)

LAND REQUIREMENT DETAILS				
NAGPUR METRO RAIL PROJECT				
LAND DETAILS	EAST-WEST CORRIDOR PRAJAPATI NAGAR TO LOKMANYA NAGAR		NORTH-SOUTH CORRIDOR AUTOMOTIVE SQUARE TO KHAMRI DEPOT	
	GOVT. LAND (In sqm)	PVT. LAND (In sqm)	GOVT. LAND (In sqm)	PVT. LAND (In sqm)
STATIONING ENT/ENTRY	3044.80	7703.40	1523.30	5312.00
RUNNING SECTION	5255.30	5000.50	30182.00	19223.00
DEPOT AREA	258973.90		339000.00	
TRAFFIC INTEGRATION/PARKING	8773.10	1403.70	53700.80	2173.20
<b>TOTAL</b>	<b>274650.90</b>	<b>14911.60</b>	<b>601806.10</b>	<b>38017.20</b>
<b>TOTAL GOVT LAND</b>	<b>778019.30</b>		<b>SAY 77.80 HECTARES</b>	
<b>TOTAL PVT LAND</b>	<b>62000.80</b>		<b>SAY 6.2 HECTARES</b>	

Additional private land required for the project shall be acquired as per the provisions of Land Acquisition Act, 1894. The Act provides for compulsory acquisition of land which includes vacant as well as built up properties. Private land constitutes about 4.83% of the total land requirement. Majority of the land required (84.55%) is government land. Government land shall be transferred as per the established procedure. Besides, 0.17% of the land likely to be affected belongs to religious institutions.

#### 14.11 Impacts during Operation Phase

The operation phase impacts are as follows:

##### 14.11.1 Water Quality

During operation phase the main source of water pollution will be Oil spillage during change of lubricants, cleaning and repair processes, in the maintenance Depot cum workshop for maintenance of rolling stock. The spillage oil will be trapped in grit chamber for settling of suspended matter. The collected oil should either be suctioned or incinerated, so as to avoid any underground water contamination.

##### 14.11.2 Water Supply

Water requirement at various stations will be 40 lpd as per the recommendation of CPHEED. Since all the stations are located in the urban areas, water requirement

meeting the need has been take for personal use of staff, fire demand, make up water for air conditioning and ventilation and water loss. The water demand for each station will be approximately 100m<sup>3</sup> per day. Adequate provision for meeting the water demand at each station have been taken. Platform washing equipment has been worked out of metro stations has been taken at the rate of 2 liter per m<sup>2</sup>. Fire fighting requirement has been taken as per the existing norms of Maharashtra Government.

#### 14.11.3 Waste Disposal

The refuse from railway station includes, Garbage, Rubbish, and Floor Sweepings. The collection and removal of refuse in a sanitary manner from the Station is of importance for effective vector control, aesthetic improvement and nuisance and pollution abatement.

For the maintenance of adequate sanitary facilities, container/collection bins not exceeding 120 litres and equipped with side handles will be appropriately designed and installed at stations and platforms.

#### 14.11.4 Noise Quality

During the operation phase the main source of noise will be from running of metro trains. Noise radiated from train operations and track structures generally constitute the major noise sources. Airborne noise is radiated from signals and elevated structures, while ground-borne noise and vibration are of primary concern in underground operations.

The roadside noise level (Leq) has been worked out for peak roadway to be 69.52 dB (A) for North-South Corridor and 77.02 dB (A) for at 15m distance in 2041. The noise levels have been worked at elevated section for different distance from the rails & given in the following table 14.15.

**Table 14.15: Cumulative Impact due to Increase Noise**

Locations	Project Noise level at 10m distance (Peak weekday)	Ambient noise level L <sub>90</sub>	Cumulative Impact
Adarshive Sqaure	74.00	70.00	73.00
Sri. Gura Davind Singh Educational Institute	74.00	74.7	77.4
J.P. School, Pimpriwaran Technical High School & College	74.00	68.09	74.47
Bank of Maharashtra near	74.00	72.00	75.18

Locations	Project noise level at 10m distance (Peak weekday)	Ambient noise level $L_{eq}$	Cumulative impact
proposed Birla Institute station (Munja Chauri)			
NEERI Campus	74.00	74.07	77.07
Mayurash Agarnool (at proposed mayurash station)	74.00	69.25	74.33
Existing Terminal Building	74.06	75.0	75.45
Bomen and of MHNH J&T	74.00	65.58	74.00
Saboo Hospital	60.24	72.21	60.85
Aashu Tower	60.24	70.06	60.71
Maya Hospital	60.24	71.03	60.73
Ram Mandir	60.24	75.06	61.60
Goverdhan Das Rowal High School	60.24	67.06	60.24
Sapera's Brother's Petrol Pump	60.24	75.44	61.48
Dharampath Polytechnic & Science College	60.24	71.23	60.73
St. Xavier's High School	60.24	66.01	60.62

It is observed from the above table that there will be significant increase in noise levels during in 2041 due to the operation of metro.

It may be inferred from the above that there will be significant impact due to increase in the sound level. Therefore it is proposed to provide 6mm thick Poly-carbonated solid Plaz may be provided as noise barriers. The noise transmission loss due to these barriers will be about 20dB (A).

Stretches identified for the provision of noise Barriers are presented in Table 14.16.

**Table 14.16: Provision of Noise Barriers in Different Stretches**

S. No.	Name of Station	Length of Noise Barrier (km)
<b>1</b>	<b>East-West Corridor</b>	
1.1	Ambedkar Chowk - Jhansi Rani Chowk	5.5
1.2	Jhansi Rani Chowk-Dharampath College	4.0
<b>2</b>	<b>North-South Corridor</b>	
2.1	Karni Chowk-Kasturba Park	2.3
2.2	Birlaoldi-Sheher Nagar	6.0
<b>Total length of Noise barrier</b>		<b>14.8</b>



#### 14.11 ENVIRONMENTAL MANAGEMENT PLAN

The proposed Nagpur Metro Project (east-west & north-south corridor) will provide quick service and safety, traffic congestion reduction, less fuel consumption, employment opportunity, and less air pollution on one hand and problems of Rehabilitation and Resettlement (R&R), soil disposal, etc. on other hand. The environmental issues likely to diversify during project construction and operation phases could be minimized by making necessary provision in the project design and adopting Environmental Management Plan (EMP). Summary of Environmental management plan is given in Table 14.17.

**Table 14.17: Environmental Management Plan**

Environmental Impact	Mitigation Measures Taken or To Be Taken	Time Frame	Implementing Organization	Responsible Organization
<b>DESIGN PHASE</b>				
Metro Alignment	The proposed corridor alignment was selected to minimize the land disturbance to avoid archaeological sites, temples and other environmentally sensitive areas in least.	During Design	DPR and design consultant	PIU of NIT
Cultural Heritage	Avoided by adjustment of alignment	During Design	DPR and design consultant	PIU of NIT
Loss of Water Bodies	Utmost care taken to avoid alignment crossing water bodies	During Design	DPR and design consultant	PIU of NIT
Inadequate design provision for safety against seismic hazard	Makes sure that design provides for safety of structures against worst combination of forces in the probability of an earthquake likely to occur in seismic zone-II.	DPR and detailed design stage	DPR and design consultant	PIU of NIT
<b>PRE-CONSTRUCTION STAGE</b>				
Water requirement	The requirement of water shall be for construction purpose etc., shall be planned and shall be provided in order to avoid digging of Tube wells.	Pre construction stage	Contractor	PIU of NIT (Implementing agency)
Disposal of treated effluent from treatment	Options for the disposal shall be studied and the suitable	During design stage / and pre	Contractor	PIU of NIT (Implementing agency)

Environmental Impact	Mitigation Measures Taken or To Be Taken	Time Frame	Implementing Organization	Responsible Organization
Joint	Special route shall be decided carefully to minimize the impact of receiving bodies. As far as possible joint discharge rules may be adopted.	construction of treatment plant		
<b>CONSTRUCTION PHASE</b>				
Environmental Management and Monitoring	This will include institutional equipments, training environmental management and monitoring	During and after construction	Contractor	PIU of NIT (implementing agency)
Dust	Water should be sprayed during construction. Also, wherever it is required to avoid dust. Vehicles delivering materials should be covered to reduce spill and dust blowing off the bed.	During construction	Contractor	PIU of NIT (implementing agency)
Air Pollution	Vehicles and machinery are to be regularly maintained so that emissions conform to National and State AQI Standards.	Beginning with and continuing throughout construction	Contractor	PIU of NIT (implementing agency)
Equipment Selection, maintenance and operation	Construction plants and equipment will meet recognized international standards for emissions and will be maintained and operated in a manner that ensures relevant air, noise, and discharge regulations are met.	During construction	Contractor	PIU of NIT (implementing agency)
Noise	Noise standard at processing sites, will be strictly enforced as per OGI noise standards. Workers in vicinity of strong noise will wear earplugs and their working time should be limited as a safety measure. At construction sites within	Beginning and through construction	Contractor	PIU of NIT (implementing agency)



Environmental Impact	Mitigation Measures Taken or To Be Taken	Time Frame	Implementing Organization	Responsible Organization
	150m of sensitive receptors construction will be stopped from 12.00 to 06.00. Machinery of noise barriers (stone walls and plantation) for silence zones including schools and hospitals.			
Vibration	The vibration level limit at work sites adjacent to the alignment shall conform to the permitted values of peak velocity as given in article project SHE Manual)	Beginning and through construction	Contractor	PIU of MIT (implementing agency)
<b>WATER</b>				
Contamination from Wastes	All justifiable measures will be taken to prevent the wastewater produced in construction from entering directly into rivers and irrigation system	Through out construction period	Contractor	PIU of MIT (implementing agency)
Wastage of water	Measures shall be taken to avoid misuse of water. Construction agency shall be instructed according to follow strict procedures while using the water for construction and drinking purposes.	Beginning with and continuing throughout construction	Contractor	PIU of MIT (implementing agency)
Sewage disposal during construction at Service Centre	A minimum distance of one sewage or toilet facility from water source should be 200 meters	Through out construction period	Contractor	PIU of MIT (implementing agency)
Sanitation and Waste Disposal in Construction Camps	Sufficient measures will be taken in the construction camps, in provision of garbage work and sanitation facilities. Waste in soaps tanks will be cleared periodically. Drinking water will meet Indian National Standards.	Before and during building of construction camps	Contractor	PIU of MIT (implementing agency)

Environmental Impact	Mitigation Measures Taken or To Be Taken	Time Frame	Implementing Organization	Responsible Organization
	Waste will be collected in a tank and disposed of daily. Special attention shall be paid to the sanitary condition of camps. Camps will be located at a minimum distance of 200 m from water sources.			
<b>SOIL</b>				
Quarrying	Quarrying will be carried out as approved and licensed quarries only.	During construction	Contractor	PIU of NIT (implementing agency)
<b>FLORA AND FAUNA</b>				
Loss of trees and Aerial Plankton	Areas of tree plantation cleared will be notified according to Compensatory afforestation Policy under the Forest Conservation Act. Trees will be planted against every tree cut as per norms.	After completion of construction activities	Forest Department	PIU of NIT (implementing agency)
<b>SOCIAL</b>				
Loss of Access	Temporary access should be built at the interchange and other roads.	During construction	Contractor	PIU of NIT (implementing agency)
Traffic jams and congestion	If there are traffic jams during construction, measures should be taken to relieve the congestion with the coordination of transportation and traffic police department.	During construction	Contractor	PIU of NIT (implementing agency)

Environmental Impact	Mitigation Measures Taken or To Be Taken	Time Frame	Implementing Organization	Responsible Organization
Safety with vehicles, people and livestock signage	<ul style="list-style-type: none"> <li>• Safety education and fines.</li> <li>• Allow for adequate traffic flow around construction areas</li> <li>• Provide adequate signage, barriers and flag persons for safety precautions.</li> <li>• Communicate to the public through radio, TV &amp; newspaper announcements regarding the scope and timelines of projects, as well as certain construction activities causing disruptions or access restrictions.</li> </ul>	During construction	Contractor	PIU of NIT (implementing agency)
Increase in disease Water-borne Food-borne Communicable diseases	<ul style="list-style-type: none"> <li>• Make certain that there is good drainage at all construction sites, to avoid creation of stagnant water bodies.</li> <li>• Provide adequate sanitation and waste disposal at construction camps.</li> <li>• Provide adequate health care for workers and locate camps away from vulnerable groups.</li> </ul>	During construction  At start-up  Through of construction	Contractor	PIU of NIT (implementing agency)
Location of camps, roads and storage areas	Location of camps, roads and storage areas shall be as per the contract specifications.	Through of construction	Contractor	PIU of NIT (implementing agency)
<b>OPERATION PHASE</b>				
Noise and Vibration	Autumn measures should be considered where warranted. The public shall be educated about the regulations of noise and vibration pollution and its mitigation.	After completion of construction	PIU/S&P implementing Agency	PIU of NIT (implementing agency)

Environmental Impact	Mitigation Measures Taken or To Be Taken	Time Frame	Implementing Organization	Responsible Organization
<b>WATER</b>				
Discharge	Suitable treatment shall be taken for treatment of before discharging the wastewater specially in desert areas.	During operation of the treatment plant	PLU/ESIP implementing agency	PIU of NIT (implementing agency)
Maintenance of Storm Water Drainage System	The urban drainage systems will be periodically checked and cleaned so as to ensure adequate down-slope flow.	Beginning and end of monsoon	PLU/ESIP implementing agency	PIU of NIT (implementing agency)
Disposal of final treated effluent from treatment plant	Options for final disposal shall be studied and the suitable disposal route shall be decided carefully in minimize the impact of receiving bodies. As far as possible zero discharge rule may be adopted.	During operation of the treatment plant	PLU/ESIP implementing agency	PIU of NIT (implementing agency)
<b>SOCIAL</b>				
Safety and noise disturbances	New buildings should be prohibited within 50 m of the edge of carriageway. No new schools and hospitals should be allowed within 200 m of carriageway.	Through out and after project development period.	Planning Department PIU	PIU of NIT (implementing agency)

#### 14.14 MITIGATION MEASURES

The main aim of mitigation measures is to protect and enhance the existing environment of the project. These measures should have positive effects on environment. Environmental mitigations are essential and shall be undertaken in various phases of project cycle viz. pre-construction, construction and operation stage of the project. Some of these have been described in the following section, which includes measures for:

- Compensatory Afforestation and Fencing
- Construction Material Management
- Labour Camp
- Hazardous Waste Management
- Archaeological and Historical Preservation

- Air Pollution Control Measures,
- Noise Control Measures,
- Vibration Control Measures
- Muck Disposal
- Soil Erosion Control
- Water Supply, Sanitation and Solid Waste management
- Traffic Diversion Management
- Dripping of Water from Tunnel
- Rain water harvesting
- Management Plans for Depot
- Utility Plan
- Energy Management
- Training and Capacity Building

#### 14.16 Environmental Monitoring Programme

The environmental monitoring is required for the construction and operational phases. The parameters need to be monitored are water quality, air quality, Noise levels, Erosion and Siltation, ecology and vibration levels. The detail monitoring programmes during construction and operational stages are presented in Table 14.3.

**Table 14.18: Environmental Monitoring Programme**

Sl. No	Environment Component	Environmental Monitoring Programme			Institutional Responsibility	
		Parameters	Locations	Frequency	Implementation	Supervision
<b>DURING PROJECT CONSTRUCTION PHASE</b>						
1	Air Quality	PM <sub>10</sub> , PM <sub>2.5</sub> , SO <sub>2</sub> , NOx, CO, HC	Total-6 suitable locations, Plant Sites i.e. HMP/Crusher, Construction sites, Settlements	24 samples, Twice a week, only season during construction Period except monsoon season. One hourly, twice a week every season during Construction Period except monsoon season.	Conservation	NET

B. Environment		Environmental Monitoring Programme			Institutional Responsibility	
NO	Component	Parameter	Locations	Frequency	Implementation	Supervision
<b>DURING PROJECT CONSTRUCTION PHASE</b>						
2	Water Quality	As relevant IS Codes 1000	At 3 suitable locations Ground water sampling	Quarterly, Once in every season.	Concessioner	MT
3	Noise Level	Noise level in dB (A) scale Leq dB(A) Day Night Day Max & Min Night Max & Min.	At 10 suitable locations i.e. At equipment yards, sensitive sites.	Quarterly, Once in every season.	Concessioner	MT
4	Vibration Level	Noise level in VdB (A) scale, Day Night Max & Min	At 10 locations i.e. Sensitive sites and residential areas.	Once in every year.	MT	MT
5	Soil Erosion	Visual Observation	2-3 km length of alignment and agricultural fields	Pre-monsoon and post-monsoon season.	Concessioner	MT
6	Compensatory Afforestation	No. roadside plantation	Along the side of the cartage way	Compensation should be done for every six months	Concessioner	MT
7	Fera & Fauna	Aquatic ecosystem	All crossings surface water bodies along the alignment and projections of influence area	Two times in a year Periodically	Concessioner	MT
8	Borrow Management	Arable areas redevelopment and Facilitate Management	Identified borrow areas	Once in a week	Concessioner	MT
<b>DURING OPERATION PHASE</b>						

B. Environment		Environmental Monitoring Programme			Institutional Responsibility		
Component	Parameters	Locations	Frequency	Implementation	Supervisor		
<b>DURING PROJECT CONSTRUCTION PHASE</b>							
1	Air Quality	PM <sub>10</sub> , PM <sub>2.5</sub> , SO <sub>2</sub> , NO <sub>x</sub> , CO	At 4 suitable locations	24 hourly samples, Twice a week every season during construction. Period except monsoon season. One hourly, twice a week every season during Construction. Period except monsoon season.	NIT	NIT	
2	Water Quality	pH, SS, CaCl <sub>2</sub> , Alkalinity, Chloride, F <sup>-</sup> , SO <sub>4</sub> , NO <sub>3</sub>	At 3- suitable locations of ground water	Pre-monsoon & post-monsoon, once in every two years	NIT	NIT	
3	Noise Level	Noise levels on dB (A) scale, Day Night, Max & Min Night, Max & Min.	At 10 suitable locations i.e. Sensitive sites and residential areas.	Once in every 2 years.	NIT	NIT	
<b>B. Environment</b>		<b>Environmental Monitoring Programme</b>			<b>Institutional Responsibility</b>		
<b>Component</b>	<b>Parameters</b>	<b>Locations</b>	<b>Frequency</b>	<b>Implementation</b>	<b>Supervisor</b>		
<b>DURING OPERATION PHASE</b>							
4	Vibration Level	Noise levels on VIB (A) scale, Day Night, Max & Min	At 20 locations i.e. Sensitive sites and residential areas.	Once in every years.	NIT	NIT	
5	Settle and siltation	Settles rates, stability of bars, embankment, etc.	High End of bridge, abutments and slopes	Twice a year	NIT	NIT	

S	Ecology	Status of Afforestation programmes of green belt	All along available and either side of the project road	Once over/NT	NT	NT

#### 14.18 ENVIRONMENTAL BUDGET

A budgetary cost estimate for environmental monitoring is suggested for construction phase period assuming 3 years and per annum cost for operation phase. Construction phase monitoring cost (tentatively) is worked out to be **INR 5.904 million** and operation phase monitoring cost per annum is worked to be **INR 1.122 million**.

R&R Provisions have been made according to the existing Govt. Policies such as HRRP, 2007 and policies followed for Maharashtra Urban Transport Project. Budgetary estimate for R&R Provisions (tentatively) is estimated as **Rs. 200 Crore**

A budget of **Rs. 87.563 million** has tentatively been kept towards the Environmental Management Plan of the Nagpur Metro project. The cost for Dust suppression during Construction, Solid Waste Management Facilities & equipment and Cooking Fuel for construction workers is incidental to the Commissioning.



# CHAPTER 15

## SECURITY MEASURES FOR A METRO SYSTEM



- 15.1 INTRODUCTION
- 15.2 NECESSITY OF SECURITY
- 15.3 THREE PILLARS OF SECURITY
- 15.4 PHASES OF SECURITY
- 15.5 RESPONSIBILITIES AND PARTNERSHIPS
- 15.6 PROPOSED PROVISIONS FOR SECURITY SYSTEM



## Chapter -15

# SECURITY MEASURES FOR A METRO SYSTEM

## 15.1 INTRODUCTION

Metro is emerging as the most favoured mode of urban transportation system. The inherent characteristics of metro system make it an ideal target for terrorists and miscreants. Metro systems are typically open and dynamic systems which carry thousands of commuters. Moreover the high cost of infrastructure, its economic importance, being the life line of city high news value, fear & panic and mass causal loss poses greater threat to its security. Security is a relatively new challenge in the context of public transport. It addresses problems caused intentionally. Security differs from safety which addresses problems caused accidentally. Security problems or threats are caused by people whose actions aim to undermine or disturb the public transport system and/or to harm passengers or staff. These threats range from daily operational security problems such as disorder, vandalism and assault to the terrorist threat.

## 15.2 NECESSITY OF SECURITY

It is well known that public transportation is increasingly important for urban areas to prosper in the face of challenges such as reducing congestion and pollution. Therefore, security plays an important role in helping public transport system to become the mode of choice. Therefore, excellence in security is a prerequisite for Metro system for increasing its market share. Metro railway administration must ensure that security model must keep pace rapid expansion of the metro and changing security scenario.

## 15.3 THREE PILLARS OF SECURITY

Security means protection of physical, Human and intellectual assets either from criminal interference, removal of destruction by terrorism or criminals or



incidental to technological failures or natural hazardous events. There are three important pillars of security as mentioned under:-

- (i) The human factor;
- (ii) Procedures; and
- (iii) Technology

Staff engaging with the passengers create a sense of re-assurance which can not fully be achieved by technology. For human factor to be more effective staff has to be qualified, trained, well equipped and motivated. They should be trained, drilled and tested. The security risk assessment is the first step for understanding the needs and prioritizing resources. The organization of security should be clear and consistent. Security incidents, especially major ones, often happen without warning. Emergency and contingency plans must be developed, communicated and drilled in advance.

There are number of technologies which can be used to enhance security e.g. surveillance systems. The objectives of the security systems are to deter i.e., making planning or execution of an attack too difficult, detect the planned evidence before it occurs deny the access after a plan of attack has been made and to mitigate i.e. lessen the impact severity as the attack by appropriate digits.

## 15.4 PHASES OF SECURITY

There are three phases of security as under:

### (i) Prevention

These are the measures which can prevent a security incidence from taking place. These can be identified by conducting a risk assessment and gathering intelligence. Prevention begins with the daily operational security - problems. Uncared for dirty, damaged property is a breeding ground for more serious crime.

### (ii) Preparedness

Plans must be prepared to respond to incidents, mitigate the impact. Train staff accordingly and carry out exercises. The results of the risk assessment give a basis for such plans.



### (iii) Recovery

Transport system must have laid down procedures/instructions for the quick recovery of normal service after an incident. Recovery is important for the financial health of the operation, but it also sends a clear message to public, it reassures passengers and gives them confidence to continue using the system. Communication is key to the quick restoration after such incidents. Restoration should 'also include an evaluation process for the lessons learnt.

## 15.5 RESPONSIBILITIES AND PARTNERSHIPS

Security is a sovereign function and hence is the responsibility of the state. Security in public requires clear governance. Responsibility should be clearly defined. In the present scenario, this is the responsibility of the Central Government/MHA in Delhi to ensure secured travelling to the public including Delhi Metro. In other states security would be the responsibility of the concerned state govt.

CISF has been entrusted with the job of providing security to Delhi Metro and law & order/ prevention & detection of crime are under the domain of Delhi Police.

## 15.6 PROPOSED PROVISIONS FOR SECURITY SYSTEM

1. CCTV coverage of all metro stations. With a provision of monitoring in the Station Security Room as well as at a Centralized Security Control Room with video wall, computer with access to internet TV with data connection, printer and telephone connection (Land Line and EPBX) for proper functioning, cluster viewing for stations. Cost of this is included in Telecom estimate.
2. Minimum one Baggage Scanners on all entry points (1 per AFC array). Additional requirement of baggage scanners at heavily crowded stations (e.g. at interchange) may also be required. Cost of one baggage scanner is Rs. 15.0 Lacs approximately, on 2013 prices.
3. Multi-zone Door Frame Metal Detector (DFMD) minimum three per entry (2 per AFC array). The number can increase in view of the football at over



crowded stations. Cost of one Multi-zone DFMD is Rs 2.15 Lacs approximately.

4. Hand held Metal Detector (HHMD) as per requirement of security agency, minimum two per entry, which varies from station to station with at least 1.5 per DFMD installed at the station. Cost of one HHMD is Rs 6000/- approximately at 2012 prices.
5. Bomb Detection Equipments with modified vehicle as per requirement of security agency. One BDS team per 25 - 30 station will be required at par with present criteria of DMRC. Cost 1.25 crores including vehicle.
6. Bomb Blanket at least one per station and Depots. Cost is Rs. 50,000/- per bomb blanket.
7. Wireless Sets (Static and Hand Held) as per requirement of security agency.
8. Dragon light at least one per station and vital installation.
9. Mobile phones, land lines and EPSX phone connections for senior security officers and control room etc.
10. Dog Squad (Sniffer Dog), at least one dog for 4 metro stations which is at par with current arrangement of Delhi Metro. Cost of one trained sniffer dog is Rs 1.25 Lacs approximately. Dog Kennels alongwith provision for dog handlers and MI room will also be provided by metro train depot administration including land at suitable places line wise.
11. Bullet proof Montha one per security check point (i.e. AFC entry) and entry gate of metro train depot administration metro station.
12. Bullet proof jackets and helmets for QRTs and riot control equipments including spore at nominated stations. One QRT Team looks after 5-6 metro stations as per present arrangement. One QRT consist of 5 personnel and perform duty in three shifts.
13. Furniture to security agency for each security room, and checking point at every entry point at stations. Scale is one office table with three chairs for security room and office of GO and one steel top table with two chairs for checking point.
14. Ladies waiting booth - 1 per security check point (AFC Area)



Wooden Ramp  
points.

EMERGENCY SECURITY MEASURES FOR METRO SYSTEM  
1 per DFMD for security check

15. Wall mounted pedestal fan at security check point, ladies waiting booth and bullet proof monitors, as per requirement.
16. Physical barriers for anti scaling at Ramp area, low height of vis duct by providing iron grill of appropriate height & design/concrete wire.
17. Adequate number of ropes. Queue managers, containing ropes, dragon search lights for contingency.
18. Iron grill at station entrance staircases, proper segregation of paid and unpaid by providing appropriate design grills etc.
19. Proper design of emergency staircase and Fireman entry to prevent unauthorized entry.

# CHAPTER 16

## DISASTER MANAGEMENT MEASURES



- 16.1 INTRODUCTION
- 16.2 NEED FOR DISASTER MANAGEMENT MEASURES
- 16.3 OBJECTIVES
- 16.4 LIST OF SERIOUS INCIDENTS REQUIRING USE OF PROVISIONS OF THE DISASTER MANAGEMENT MEASURES
  
- 16.5 PROVISIONS UNDER DISASTER MANAGEMENT ACT, 2005
- 16.6 PROVISIONS AT METRO STATIONS / OTHER INSTALLATIONS
- 16.7 PREPAREDNESS FOR DISASTER MANAGEMENT

**CHAPTER- 16****DISASTER MANAGEMENT MEASURES****16.1 INTRODUCTION**

"Disaster is a crisis that results in massive damage to life and property, uproots the physical and psychological fabric of the affected communities and outstrips the capacity of the local community to cope with the situation." Disasters are those situations which cause acute distress to passengers, employees and outsiders and may even be caused by external factors. As per the disaster management act, 2005 "disaster" means a catastrophe, mishap, calamity or grave occurrence in any area, arising from natural or manmade causes, or by accident or negligence which results in substantial loss of life or human suffering or damage to, and destruction of, property, or damage to, or degradation of, environment, and is of such a nature or magnitude as to be beyond the coping capacity of the community of the affected area". As per world health organisation (who):

"Any occurrence that causes damage, economic disruption, loss of human life and deterioration of health and services on a scale sufficient to warrant an extra ordinary response from outside the affected community or area."

A disaster is a tragic event, be it natural or manmade, which brings sudden and intense agony to humanity and disrupts normal life. It causes large scale human suffering due to loss of life, loss of livelihood, damages to property and persons and also brings untold hardships. It may also cause destruction to infrastructure, buildings, communication channels essential services, etc.

**16.2 NEED FOR DISASTER MANAGEMENT MEASURES**

The effect of any disaster spread over in operational area of Delhi Metro is likely to be substantial as DMRC deals with thousands of passengers daily in underground tunnels, viaducts and stations. Disaster brings about sudden and intense misery to humanity and disrupts normal human life in its established social and economic patterns. It has the potential to cause large scale human





suffering due to loss of life, loss of livelihood, damage to property, injury and hardship. It may also cause destruction or damage to infrastructure, buildings and communication channels of Metro. Therefore there is an urgent need to provide for an efficient disaster management plan.

### 10.3 OBJECTIVES:

The main objectives of this Disaster Management Measures are as follows:

- Save life and alleviate suffering.
- Provide help to stranded passengers and arrange their prompt evacuation.
- Instill a sense of security amongst all concerned by providing accurate information.
- Protect Metro Rail property.
- Expedite restoration of train operation.
- Lay down the actions required to be taken by staff in the event of a disaster in Delhi Metro Rail Corporation in order to ensure handling of crisis situation in coordinated manner.
- To ensure that all officials who are responsible to deal with the situation are thoroughly conversant with their duties and responsibilities in advance. It is important that these officials and workers are adequately trained in anticipation to avoid any kind of confusion and chaos at the time of the actual situation and to enable them to discharge their responsibilities with alacrity and promptness.

### 10.4 LIST OF SERIOUS INCIDENTS REQUIRING USE OF PROVISIONS OF THE DISASTER MANAGEMENT MEASURES

Metro specific disasters can be classified into two broad categories e.g.: Man-made and Natural.

#### a. Man Made Disaster

1. Terrorist attack
2. Bomb threat/ Bomb blast
3. Hostage
4. Release of Chemical or biological gas in trains, stations or tunnels



6. Fire in main buildings, underground/ elevated infrastructures, power stations, train depots etc.
7. Train accidents and train collision/derailment of a passenger carrying train
8. Sabotage
9. Stampede

#### **b. Natural Disaster**

1. Earthquakes
2. Floods

### **16.5 PROVISIONS UNDER DISASTER MANAGEMENT ACT, 2005**

#### **A. The National Disaster Management Authority (NDMA)**

Establishment of National Disaster Management Authority:-

- (1) With effect from such date as the Central Government may, by notification in the Official Gazette approve in this behalf, there shall be established for the purposes of this Act (The Disaster Management Act, 2005) an authority to be known as the National Disaster Management Authority.
- (2) The National Authority shall consist of the Chairperson and such number of other members, not exceeding nine, as may be prescribed by the Central Government and, unless the rules otherwise provide, the National Authority shall consist of the following:
  - (a) The Prime Minister of India, who shall be the Chairperson of the National Authority, *ex officio*;
  - (b) Other members, not exceeding nine, to be nominated by the Chairperson of the National Authority.
- (3) The Chairperson of the National Authority may designate one of the members nominated under clause (b) of sub-section (2) to be the Vice-Chairperson of the National Authority.
- (4) The term of office and conditions of service of members of the National Authority shall be such as may be prescribed.



## **B. State Disaster Management Authority:**

### **Establishment of State Disaster Management Authority:-**

- (1) Every State Government shall, as soon as may be after the issue of the notification under sub-section (1) of section 3, by notification in the Official Gazette, establish a State Disaster Management Authority for the State with such name as may be specified in the notification of the State Government.
- (2) A State Authority shall consist of the Chairperson and such number of other members, not exceeding nine, as may be prescribed by the State Government and, unless the rules otherwise provide, the State Authority shall consist of the following members, namely:- The Chief Minister of the State, who shall be Chairperson, *ex officio*.
  - (a) Other members, not exceeding eight, to be nominated by the Chairperson of the State Authority;
  - (b) The Chairperson of the State Executive Committee, *ex officio*.
- (3) The Chairperson of the State Authority may designate one of the members nominated under clause (b) of sub-section (2) to be the Vice-Chairperson of the State Authority.
- (4) The Chairperson of the State Executive Committee shall be the Chief Executive Officer of the State Authority, *ex officio*; Provided that in the case of a Union territory having Legislative Assembly, except the Union territory of Delhi, the Chief Minister shall be the Chairperson of the Authority established under this section and in case of other Union territories, the Lieutenant Governor or the Administrator shall be the Chairperson of that Authority; Provided further that the Lieutenant Governor of the Union territory of Delhi shall be the Chairperson and the Chief Minister thereof shall be the Vice-Chairperson of the State Authority.
- (5) The term of office and conditions of service of members of the State Authority shall be such as may be prescribed.



### C. Command & Control at the National, State & District Level

The mechanism to deal with natural as well as manmade crisis already exists and that it has a four tier structure as stated below:-

- (1) National Crisis Management Committee (NCMC) under the chairmanship of Cabinet Secretary
- (2) Crisis Management Group (CMG) under the chairmanship of Union Home Secretary.
- (3) State Level Committee under the chairmanship of Chief Secretary.
- (4) District Level Committee under the Chairmanship of District Magistrate.

All agencies of the Government at the National, State and district levels will function in accordance with the guidelines and directions given by these committees.

### D. Plans by Different Authorities at District Level and their implementation

Every office of the Government of India and of the State Government at the district level and the local authorities shall, subject to the supervision of the District Authority:-

- (a) Prepare a disaster management plan setting out the following, namely:-
  - (i) Provisions for prevention and mitigation measures as provided for in the District Plan and as is assigned to the department or agency concerned;
  - (ii) Provisions for taking measures relating to capacity-building and preparedness as laid down in the District Plan;
  - (iii) The response plans and procedures, in the event of, any threatening disaster situation or disaster;
- (b) Coordinate the preparation and the implementation of its plan with those of the other organizations at the district level including local authority, communities and other stakeholders;
- (c) Regularly review and update the plan; and



- (d) Submit a copy of its disaster management plan, and of any amendment thereto, to the District Authority.

## 15.6 PROVISIONS AT METRO STATION/OTHER INSTALLATIONS

To prevent emergency situations and to handle effectively in case 'one area' from needs to be following provisions for an effective system which can timely detect the threats and help suppress the same.

- (A) FIRE DETECTION AND SUPPRESSION SYSTEM
- (B) SMOKE MANAGEMENT
- (C) ENVIRONMENTAL CONTROL SYSTEM (ECS)
- (D) TUNNEL VENTILATION SYSTEM
- (E) TRACK WAY EXHAUST SYSTEM (TES)
- (F) STATION POWER SUPPLY SYSTEM
- (G) DG Sets & UPS
- (H) LIGHTING SYSTEM
- (I) STATION AREA LIGHTS
- (J) TUNNEL LIGHTING
- (K) TUNNEL LIGHTING CONTROL FROM BMS
- (L) SEEPAGE SYSTEM
- (M) WATER SUPPLY AND DRAINAGE SYSTEM
- (N) SEWAGE SYSTEM
- (O) ANY OTHER SYSTEM DEEMED NECESSARY

The above list is suggestive not exhaustive actual provisioning has to be done based on site conditions and other external and internal factors.

## 15.7 PREPAREDNESS FOR DISASTER MANAGEMENT

Being a technological complex system worked by new set of staff, with a learning curve to improve and stabilize with time, intensive mock drills for the staff concerned is very essential to train them to become fully conversant with the action required to be taken while handling emergencies.



They also need to be trained in appropriate communication skills while addressing passengers during incident management to assure them about their well being seeking their cooperation.

Since learning can only be perfected by 'doing' the following Mock Drills are considered essential:

- a. Fire Drill
- b. Rescue of a disabled train
- c. Detainment of passengers between stations
- d. Passenger evacuation from station
- e. Drill for use of rescue & relief train
- f. Hot line telephone communication with state disaster management authority.

# CHAPTER 17

## MULTI-MODAL TRAFFIC INTEGRATION

### AT METRO STATIONS



- 17.1 INTRODUCTION
- 17.2 PRESENT CONDITION OF TRANSPORT ON CITY ROADS
- 17.3 IMPACT OF BSS/CLUSTERS IN MODE SHARE
- 17.4 BALANCING ACT OF METRO RAIL
- 17.5 TRANSPORT INTEGRATION BY DMRC
- 17.6 METRO FEEDER BUS SERVICE
- 17.7 WAY FORWARD



## Chapter - 17

# MULTI MODAL TRAFFIC INTEGRATION AT METRO STATIONS

### 17.1 INTRODUCTION

The Metro Transport Network in Nagpur will cover a length of approximately 38 kms. It will be augmented through enhanced flexibility of cross-cross interchanges to other modes and reduce the travel time of commuters. While Metro provides a high capacity corridor to carry the passengers, the need for integration of with other secondary/intermediate transport modes is getting highlighted more than ever to ensure a seamless transfer. The concept is to provide at least first mile and last mile connectivity to the commuters with in their places of stay. According top priority to this issue, MBUD has laid down policy guidelines to include the need and provisioning of all public, IPT and private modes in the DPRs for the Metro Systems. (Ref: MBUD (Urban Transport Wing) Advisory Circular no. K-14015/2007-07-IV dated 30.08.2013).

The share of various modes of secondary/ intermediary modes of travel is complex and debatable issue which is dependent on a large number of variables like available road width, penetration in the residential areas, Road condition, distance from the existing Metro Stations, availability of parking and lay out and availability of circulating areas at the Metro Stations, Business centre or markets & existing traffic densities. These factors relate with each other and evolve with development of new modal mix of transport, infrastructure and changes with the passage of time. Even though for a given urban transport scenario, optimal mode share may be determined from computer based models but actual **optimal mode share** is never achievable on the road due to dynamic nature of demand and supply of transport modes.





## 17.2 PRESENT CONDITION OF TRANSPORT ON CITY ROADS

At present the various mode coming to Metro Stations comprise of State Transport buses, Multi/Mini buses, RTVs, Autos, Rickshaws, E- Rickshaws, Private cars, Two Wheelers and B-Cycles. These can be classified in three groups of transport modes namely, Public, IPT and Private.

In public transport group there are Mini City Buses (20 seater), and large buses of State Transport (50 seater) and Chartered Buses hired by schools and private offices. Buses from neighbouring states are no less in numbers. Generally the public transports in Nagpur comprises of the buses which are operated by the Maharashtra State Road Transport Corporation.

Auto rickshaws are also an important part of public transports at Nagpur. Earlier, there used to be six seater auto rickshaws but after the restriction laid on its usage by the High Court, only three seater auto rickshaws ply on the roads of Nagpur. After bus, it is these auto rickshaws which are the most important modes of public transport in Nagpur even though they are little expensive. Auto Rickshaw are intermediate Public Transport (IPT) Modes. Another public transport at Nagpur which can be ranked third among all is the cabs or taxis that run on the streets of Nagpur. Though these are also less in number and the majority of them ply from airport and railways.

In the personalized transport modes, there are Bicycles, Two wheelers and Cars of all possible sizes.

A chaotic situation is observed when all the above mentioned transport vehicles are seen jostling to each other for space for moving forward. More pathetic conditions are seen at the Road Intersections.

The solution lies in showcasing a workable arrangement of co-existence through identification of good points of each mode and then utilize the same to get the attention and embedding it in public psyche.

Because of high traffic and less capacity as well as length of the roads, average distance between two consecutive vehicles becomes very less. Such situation does not permit speed higher than 15-20 km/hr. This indicates that unless there is some solution to reduce this unmanageable mix of the vehicle fleet, real transport integration may not be possible. While the Road length on main & arterial Roads may not see significant increase and relieve the congestive/chaotic/slow moving road traffic, a divergent policy of linking commuters directly



through E-Rickshaw or Mini/Multi size feeder buses using the service/inner road length to supplement the main road traffic will reduce the congestion and provide relief to the Metro commuters in reaching out to Metro Stations.

### 17.3 IMPACT OF BUS/CLUSTERS IN MODE SHARE

Primary reason for using personal vehicle (for buying vehicle) is **to save travel time** during journey. On the other hand, government has tried to increase number of public buses on the road in many different ways.

City bus service in Nagpur has never been consistent. First, it was MSRTC that withdrew the service citing losses as the main reason. This created room for NMC to run the service by roping in a private player. Central Government's changed norms regarding public transport in areas of urban local bodies selected under Jawahar Lal Nehru National Urban Renewal Mission (JNNURM) proved a great help. With funds received from the Centre, NMC entered into an agreement with VNL to operate city bus service. As per the agreement, NMC would get Rs. 3,700 per bus per month as royalty. A fleet of new low-floor buses, increased number of frequency, new routes, and brand new service evoked a very good response from Nagpur residents. Within almost no time, Starbus service (as the city bus service is popularly known after the brand of buses) became the most widely used mode of public transport in the city.

However, as time passed, condition of buses deteriorated. Poor maintenance resulted in broken seats, broken handles, damaged wind-shields, mostly non-working digital signs, unclear and unhygienic passenger areas, non-rolling window panes. Of course, these are only major problems commuters have to put up with. 'Starbus' is driven by ill-trained persons, posing threat to plying of other vehicles and people on roads. At many places with heavy traffic throughout the day, it is very difficult for these drivers to man oeuvre wide buses safely.

Government has tried hard to popularize public bus by subsidizing the fare but could not bring higher (and middle) income group to use public bus simply because it is slow. BRT system was introduced with the intention of raring public bus through dedicated pathway. But the overall impact has not provided synergy between the user & the Public Transport System in a seamless manner. Therefore objective of achieving optimal mode share remained elusive from reality.



## 17.4 BALANCING ACT OF METRO RAIL

After introduction of Metro Rail in the city, Traffic and Transportation scenario will significantly change. People will no longer afford to travel a much longer distance. It is now possible to cover a length of 30-35 km below or within one hour time if main journey is made by metro rail. This is the fastest, safest and most reliable and comfortable mode now available in the city.

In Delhi, in 1980's average passenger trip length was 7-8 km in 1990-2000 average trip length was 8-10 km. After 2000, average trip length started increasing and in 2012-13 it was 15-16 km. It is expected this trip length will increase to 17-18 km after Phase III lines become operational from 2016 and after Phase IV in 2021 trip length may be about 20 km. This shows that the city gets expanded in terms of residential locations and work centers as metro network increases. In a recent survey conducted by one of the most circulated newspaper (Times of India) citizens have expressed maximum satisfaction for DMRC services. Nevertheless, city roads are more congested and the situation is getting worse every day. The benefit of time saving due to metro is very much diluted because of the problem of reaching the metro station and then to the platform to catch the metro.

For Nagpur also, average trip length will be around 7 kms. Hence Metro will definitely help in providing a balancing act.

## 17.5 TRANSPORT INTEGRATION BY DMRC

If we mean that transport integration is smooth transition from one mode (road based) to the other (metro rail) then it is important that the road based mode should reach the metro station in time, at regular interval so that passenger need not walk long distance to enter the station.

Several measures at Metro may be undertaken for smooth transition for the passengers using metro. Stations are designed user friendly, ambience is kept clean, cold and attractive. User needs like Snack bars, ATMs are available at many stations. Elevator and lift is provided at every station to avoid climbing through stair case. Parking facility, Feeder Bus & Bus stops are three most significant services given by DMRC. In addition, pilot projects for E-Rickshaws and cycle shelters have also been taken up.



The feeder buses, E-Rickshaws & cycle shahis would be expanded based on user demands, service ability and patronage.

The extent of need for above modes depends on the type of stations viz. Interchange Stations, stations with extensive Property Development/ close to Business Centers/ Activity Hubs, stations located on the road medians.

The need for provisioning bus stops/parking areas also differ in case of elevated/underground stations and at the terminal stations.

## 17.5 METRO FEEDER BUS SERVICE

In Delhi, up to Phase II DMRC will have a total of 236 stations out of which 21 are interchange stations. Many stations are with extensive property development near activity hubs or business centres and that are located on road medians or under the road. To cater to these stations, DMRC has so far deployed 117 feeder buses with a sitting capacity of 18 passengers and total capacity of 30 passengers. The present sanctioned routes are 98 which cover roughly 73 metro stations.

Additional 400 feeder buses have already been ordered through two selected bus operators and these mid buses will have a sitting capacity of 28 and total capacity of 50. The present peak ridership is 58,000 per day and monthly average of 50000 per day. The maximum revenue so far is 4.6 Lakhs per day with a monthly average revenue 4.6 Lakhs per day. It is expected that with additional buses the peak ridership per day will touch around 3.5 lakhs per day. For the stabling and maintenance of these buses a total of 8 feeder bus depots have been planned to keep the fleet run to the minimum and provide safe stabling and upkeep.



Existing Feeder Buses



New Feeder Buses Being Introduced

Fig. 17.2 - Modal of Feeder Buses



However, feeder bus service facility is still not attained perfection. Bus conditions are not good to travel; service headway is long as it is handled by private operators who would like to wait to fetch more passengers. Services at some routes are very irregular as not many passengers are available during non-peak hours. Passengers have to bank upon auto rickshaws. At some stations entry and exit gates are blocked by waiting buses, rickshaw pullers and vendors. This is irritating and some action is required.

Purchasing only one ticket for a complete journey by using any one or more transport mode is still a dream in India because of multiple ownership/agency control or lack of will to implement such systems. In Europe, USA this system is working very well and almost eliminated unhealthy competition. True transport integration will be possible when such system will be operational in Indian cities.

## 17.7 WAY FORWARD

In view of above deliberations in back ground, along with planning for Metro Rail System in any city, there is a need for providing a transportation system which is seamlessly integrated across all modes and provides first mile as well as last mile connectivity. It is also necessary that various public transportation modes including Inter-mediate Public Transport (IPT) and feeder buses etc. work together in order to facilitate increase in ridership to the Metro system and provide ease of using the Metro system by the public at large.

Therefore, there is a need for doing more scientific study exclusively for this. To achieve this goal, Metro Rail Stations influenced zone need to be defined which can be taken as approximately 5 kms for the motorized traffic and 1.5 km. for pedestrian/cyclists. Detailed Study is required to be done in this influenced zone of a Metro station for following aspects mainly:

- i) Availability and review of existing public and IPT facilities, in terms of motorized and non-motorized mode with main consideration of the streets/roads adjoining literally to the stations and also to examine adequacy of availability of pedestrian/cycle paths in the influenced zone.
- ii) Analysis and identification of gaps between supply and demand in terms of feeder facilities and other requirements for better first and last mile connectivity.



- ii) Proposal for introduction/enhancement of feeder buses and cycle/pedestrians tracks, bike sharing arrangement for each Metro station to be finalized.
- iv) Proposal for better integration of Metro station with other mode of transport, such as relocation of existing bus stop, introduction of new bus stop, bus lane etc.
- v) Cost of the requirements namely road widening including roads for pedestrian/cycle paths, feeder buses based on the outcome of the study.

The detailed study and requirement for providing first mile as well as last mile connectivity to the Metro users will be carried out separately and the same should be in place before the commercial operation of the Metro services for the benefit of the users as well as for better ridership and the financial viability of the project.

Since, it is envisaged that detailed study for provision of feeder buses, public bike sharing and pedestrianisation in the influence zone of metro stations will be done and put in place by the time commercial operation of the Metro services, a lump-sum cost of @ 2% of Total Cost of all items except Land has been considered sufficient and included in the project cost of proposed Metro Rail System of Nagpur Metro. If at any stage more feeder services etc. will be required, same can be augmented by concerned City transportation authorities.

# CHAPTER 18

## COST ESTIMATES



18.1	INTRODUCTION
18.2	CAPITAL COST ESTIMATE
18.3	LAND
18.4	FORMATION, ALIGNMENT
18.5	STATION BUILDINGS
18.6	PERMANENT WAY
18.7	DEPOT
18.8	UTILITY DIVERSIONS
18.9	ENVIRONMENTAL IMPACT ASSESSMENT
18.10	REHABILITATION & RESETTLEMENT
18.11	TRACTION & POWER SUPPLY
18.12	ELECTRICAL SERVICES AT STATIONS
18.13	SIGNALING & TELECOMMUNICATION WORKS
18.14	AUTOMATIC FARE COLLECTION
18.15	ROLLING STOCK
18.16	CAPITAL EXPENDITURE ON SECURITY
18.17	CAPITAL EXPENDITURE ON FEEDER BUSES
18.18	TAXES AND DUTIES

### TABLES

TABLE 18.1	CAPITAL COST ESTIMATE - NO CORRIDOR
TABLE 18.2	CAPITAL COST ESTIMATE - PM CORRIDOR
TABLE 18.3	DETAILS OF TAXES AND DUTIES - NO CORRIDOR
TABLE 18.4	DETAILS OF TAXES AND DUTIES - PM CORRIDOR


**CHAPTER - 10**
**COST ESTIMATES**
**10.1 INTRODUCTION**

Detailed cost estimates for Nagpur Metro Rail Project has been prepared corridor wise covering civil, electrical, signaling and telecommunication works, rising stack, environmental protection, rehabilitation, etc. considering 25 kv ac Overhead Traction System at June 2012 price level.

While preparing the capital cost estimates, various items have generally been grouped under three major heads on the basis of (i) route km length of alignment, (ii) number of units of that item, and (iii) item being an independent entity. All items related with alignment, whether elevated or at-grade or underground construction, permanent way, traction, signaling & telecommunication, whether in main line or in maintenance depot, have been estimated at rate per route km basis. Cost of station structures, other electrical services at these stations including Lifts & Escalators and Automatic Fire Detector (AFC) installations at all stations have been assessed in terms of each station as a unit. Similarly Rolling Stock costs have been estimated in terms of number of units required. In remaining items, viz. land, utility diversions, rehabilitation, etc. the costs have been assessed on the basis of each item, taken as an independent entity.

In order to arrive at realistic cost of various items, costs have been assessed on the basis of rates accepted for Delhi Metro. A suitable correction factor has been applied to bring these costs to June 2012 price level. The details of taxes and duties are worked out separately.

The capital cost has been worked out for Corridor-1: NORTH-SOUTH CORRIDOR (AUTOMOTIVE SQUARE TO KHAPRI) and Corridor-2: EAST-WEST CORRIDOR (LOKMANYA NAGAR TO PRAJAPATI NAGAR). One depot cum maintenance workshop in each corridor has been planned.



**10.2 CAPITAL COST ESTIMATE****CORRIDOR - I: NORTH-SOUTH CORRIDOR (AUTOMOTIVE SQUARE TO KHAPRI)**

The capital cost estimate is shown at Table 10.1

**Table 10.1**

NAGPUR METRO					
Capital Cost Estimate					
<i>June 2012 (Rs. in Cr.)</i>					
<b>CORRIDOR - I NORTH-SOUTH CORRIDOR (AUTOMOTIVE SQUARE TO KHAPRI)</b>					
Total length = 19.662 Km, Elev = 16.662 Km At Grade = 4.869 Km					
Total Stations = 17 nos, Elev = 16, At Grade = 2					

S. No.	Item	Unit	Rate	Qty.	Amount (Rs. in Cr.)
<b>Without taxes</b>					
1.0	<b>Land</b>				
1.1	Permanent				
a	Government	no	5.00	60,000	300.00
b	Private	no	24.42	2,000	134.94
1.2	Temporary				
a	Government	no	1.20	20,000	24.00
	Private	no			
	<b>Subtotal (1)</b>				<b>458.94</b>
2.0	<b>Alignment and Formation</b>				
2.1	Underground section by TBM including station length (200m each)	R. Km.	110.00	0.000	0.00
2.2	Underground section by Cut & Cover including Station length (200m each) RAMP PORTION	R. Km.	130.00	0.000	0.00
2.3	Divided section including station length	R. Km.	29.00	10,000	436.00
2.4	At Grade section including station length	R. Km.	2.00	4,000	13.38
2.5	Entry to depot	R. Km.	2.00	1,000	2.00
	<b>Subtotal (2)</b>				<b>451.38</b>
3.0	<b>Station Buildings</b>				
3.1	Underground Station (200m length) incl. EM works, lifts, escalators, VAC etc.	Each			
a	Underground Station- Civil works	Each	120.00	2	0.00
b	Underground Station- EM works etc.	Each	55.40	2	0.00



S. No.	Item	Unit	Rate	Qty	Amount (Rs. in Cr.)
<b>3.2</b>	<b>Elevated stations (including trashes)</b>	Each			
a	Type (A) way side-civil works	Each	17.00	10	170.00
b	Type (A) way side-EM works etc	Each	7.02	10	70.20
c	Type (B) Way side with signaling- civil works	Each	18.70	4	74.80
d	Type (B) Way side with signaling- EM works etc	Each	7.02	4	28.08
e	Type (C), Terminal station -civil works	Each	20.00	1	20.00
f	Type (C), Terminal station -EM works	Each	7.02	1	7.02
<b>3.3</b>	<b>At grade Stations (including finishes)</b>				
a	Type (A) way side-civil works	LS	13.600	2,000	27.20
b	Type (A) way side-EM works etc	LS	5.516	2,000	11.20
<b>3.3</b>	<b>Metro Station &amp; OCC Bldg.</b>	LS			
a	Metro Station & OCC bldg -civil works	LS			41.89
b	Metro Station & OCC Bldg-EM works etc	LS			7.23
	<b>Subtotal (3)</b>				<b>467.16</b>
<b>4.0</b>	<b>Depot</b>	LS			
a	Civil works	LS			16.40
b	EM works etc	LS			67.80
	<b>Subtotal (4)</b>				<b>148.89</b>
<b>5.0</b>	<b>P-Track</b>				
<b>5.1</b>	Ballastless track for elevated & underground Section	R. Km.	0.48	10,000	57.36
<b>5.2</b>	Ballast track for (a) at grade segment and (b) in depot	R. Km.	2.91	40,000	24.46
	<b>Subtotal (5)</b>				<b>122.88</b>
<b>6.0</b>	<b>Trackage &amp; power supply incl. OHE, ABB etc. Excl. lifts &amp; Escalators</b>				
<b>6.1</b>	UG Section	R.Km.	15.96	0,000	0.00
<b>6.1</b>	Elevated & at grade section	R.Km.	15.96	20,000	345.71
	<b>Subtotal (6)</b>				<b>345.71</b>
<b>7.0</b>	<b>Signalling and Telecom.</b>				
<b>7.1</b>	Sig. & Telecom.	R. Km.	14.00	20,000	280.07
<b>7.2</b>	Automatic fare collection	Stn.			
	At Grade Station	Each	5.00	2	10.00
	Elevated stations	Each	5.00	16	75.00
	<b>Subtotal (7)</b>				<b>375.07</b>
<b>8.0</b>	<b>M &amp; R incl. Materials etc.</b>	LS			60.00
	<b>Subtotal (8)</b>				<b>60.00</b>
<b>9.0</b>	<b>Misc. Utilities, roadworks, other civil works such as median etc. signages Environmental protection</b>	R. Km.			



S. No.	Item	Unit	Rate	Qty	Amount (Rs. in Cr.)
8	Civil works-BM works	R. Km.	4.85	21.058	99.92
	Subtotal (8)				99.92
10.8	Rolling Stock	Each	8.50	33.000	289.50
	Subtotal (10)				289.50
11.8	Capital expenditure on security	LS			
8	Civil works	LS			0.00
8	BM works etc.	LS			4.00
	Sub Total (11)				10.00
12.8	Capital expenditure on Feeder buses				
	Feeder Buses @ 2% of Total Cost of all items except Land	LS			47.91
13.8	Total of all items except Land				2080.52
	Total of all items except Land but including Feeder Buses				2087.94
14.8	General Charges Incl. Design charges @ 5 % on all items except land				119.87
16.8	Total of all items including G. Charges except land				2917.21
18.8	Contingencies @ 3 %				75.52
17.8	Gross Total				3598.25
	Cost without land	₹			3598
	Cost with land	₹			3618

**CORRIDOR - E: EAST WEST CORRIDOR (LOMBARDYA NAGAR TO PRAJAPATI NAGAR)**

The capital cost estimates is shown at Table 10.2

**Table 10.2**

NAOPUR METRO					
Capital Cost Estimate					
					June 2012 prices/yr
CORRIDOR - E EAST WEST CORRIDOR (LOMBARDYA NAGAR TO PRAJAPATI NAGAR)					
Total length = 10.967 Km, Bv = 10.967 Km					
Total Station = 16 nos, Bv = 16					
S. No.	Item	Unit	Rate	Qty	Amount (Rs. in Cr.)
<b>Without bus</b>					
1.0	Land				
1.1	Permanent				
8	Government	sq	5.00	27,460	137.30
8	Private	sq	26.82	1,400	52.32
1.2	Temporary				
8	Government	sq	1.20	20,900	24.30
	Private	sq			
	<b>Subtotal (1)</b>				<b>214.55</b>
2.0	Alignment and Formation				
2.1	Underground section by TBM excluding station length (263m BVT)	R. Km.	110.00	0.000	0.00
2.2	Underground section by Cut & Cover excluding Station length (263m each) - RAMP PORTION	R. Km.	100.00	0.000	0.00
2.3	Elevated section including station length	R. Km.	26.00	16.927	538.15
2.4	At Grade section including station length	R. Km.	2.90	0.000	0.00
2.5	Entry to dead	R. Km.	2.90	1.000	2.90
	<b>Subtotal (2)</b>				<b>541.05</b>
3.0	Station Buildings				
3.1	Underground Station 200 m length incl. RM works, lifts, escalators, VAC etc.	Each			
8	Underground Station, Civil works	Each	100.00	0	0.00
8	Underground Station, RM works etc.	Each	55.40	0	0.00



S. No.	Item	Unit	Rate	Qty	Amount (Rs. in Cr.)
<b>3.2</b>	<b>Elevated stations (including trusses)</b>	Each			
a	Type (A) way side-civil works	Each	17.00	13	221.00
b	Type (A) way side-EM works etc	Each	7.02	13	91.26
c	Type (B) Way side with signaling- civil works	Each	18.70	4	74.80
d	Type (B) Way side with signaling- EM works etc	Each	7.02	4	28.08
e	Type (C), Terminal station -civil works	Each	20.00	2	40.00
f	Type (C), Terminal station -EM works	Each	7.02	2	14.04
<b>3.3</b>	<b>At grade Stations (including finishes)</b>				
a	Type (A) way side-civil works	LS	12.600	0.000	0.00
b	Type (A) way side-EM works etc	LS	5.016	0.000	0.00
<b>3.4</b>	<b>Metro Station &amp; OCC Bldg.</b>	LS			
a	Metro Station & OCC bldg -civil works	LS			41.39
b	Metro Station & OCC Bldg-EM works etc	LS			7.29
	<b>Subtotal (3)</b>				<b>317.89</b>
<b>4.0</b>	<b>Depot</b>	LS			
a	Civil works	LS			16.41
b	EM works etc	LS			67.81
	<b>Subtotal (4)</b>				<b>144.89</b>
<b>5.0</b>	<b>P-Track</b>				
<b>5.1</b>	Ballastless track for elevated & underground Section	R. Km.	0.48	16.007	123.23
<b>5.2</b>	Ballast track in depot	R. Km.	2.91	0.693	11.55
	<b>Subtotal (5)</b>				<b>131.69</b>
<b>6.0</b>	<b>Traction &amp; power supply incl. OHE, ABB etc. Excl. lifts &amp; Escalators</b>				
<b>6.1</b>	UG Section	R.Km.	15.96	0.000	0.00
<b>6.1</b>	Elevated & at grade section	R.Km.	15.96	19.307	308.12
	<b>Subtotal (6)</b>				<b>308.12</b>
<b>7.0</b>	<b>Signalling and Telecom.</b>				
<b>7.1</b>	Sig. & Telecom.	R. Km.	14.00	16.307	216.30
<b>7.2</b>	Automatic fare collection	Stn.			
	At Grade Station	Each	0.00	3	0.00
	Elevated stations	Each	0.00	16	00.00
	<b>Subtotal (7)</b>				<b>216.30</b>
<b>8.0</b>	<b>M &amp; R incl. Materials etc.</b>	LS			60.00
	<b>Subtotal (8)</b>				<b>60.00</b>
<b>9.0</b>	<b>Misc. Utilities, roadworks, other civil works such as median etc. signages Environmental protection</b>	R. Km.			



S. No.	Item	Unit	Rate	Qty	Amount (Rs. in Cr.)
8	Civil works+EM works	R. No.	4.00	10.007	01.76
	Subtotal (8)				01.76
10.0	Rolling Stock	Each	9.50	36.000	309.00
	Subtotal (10)				309.00
11.0	Capital expenditure on security	LS			
8	Civil works	LS			6.00
0	EM works etc	LS			4.00
	Sub Total (11)				10.00
12.0	Capital expenditure on Feeder Buses				
	Feeder Buses @ 2% of Total Cost of all items except Land	LS			60.30
13.0	Total of all items except Land				268.06
	Total of all items except Land but including Feeder Buses				268.19
14.0	General Charges Incl. Design charges @ 5 % on all items except land				137.76
16.0	Total of all items including G. Charges except land				2602.06
16.0	Contingencies @ 2 %				90.49
17.0	Gross Total				2760.44
		Cost without land	=		2760
		Cost with land	=		2804

### 10.3 LAND

- i) Land requirements have been kept to the barest minimum & worked out on area basis. For underground and elevated alignment, no land is proposed to be acquired permanently, except small areas for locating entry/exit structures, traffic signals, etc. at stations, and wherever the alignment is off the road.
- ii) To work out cost of land its rates have been assumed as Rs. 1.00 Crore per hectare for government land and rates for private land have been taken as Rs. 35.52 Crore per hectare.
- iii) Land required for Property Development for funding the project after its commercial exploitation has not been taken in to account while working out project cost.

### 10.4 FORMATION, ALIGNMENT

- i) **Elevated Section:** The basis of rate is as accepted for Delhi Metro duly updated to June 2012 price level.

### 10.5 STATION BUILDINGS

- i) **Underground Stations:** The basis of rate is as accepted for Delhi Metro duly updated to June 2012 price level. The work cover U.G. alignment, as well as, other civil electrical works like ventilation, air-conditioning, lifts & escalators, but does not cover P-way, O.R.E. signaling and interlocking works, APC installations.
- ii) **Elevated Stations:** Rates are based on accepted rates of Delhi Metro, duly updated to June 2012 price level. The cost includes the general services of the stations but excludes the cost of viaduct, lifts & escalators, which have been considered separately under respective items. One station is planned at double height. The extra cost on double height accounts to be charged to contingency.

### 10.6 PERMANENT WAY

For elevated and underground sections, ballastless track and for at-grade section one Depot ballastless track has been planned. Rates are based on accepted rates of Delhi Metro, duly updated to June 2012 price level.

### 10.7 DEPOT

One Car Maintenance Depot-car-Workshop serving both the corridors have been proposed at KHAPRI (for N5 Corridor) and at Sushresh Nager (for B9 Corridor). The depot is planned at ground level. Costs have been worked out for various items of building, elevated structures, tracks, boundary wall & plants/machinery etc.



### 10.9 UTILITY DIVERSIONS

The costs of utility diversions involved in the station have been considered separately and provided for in the estimate. In addition to sewer/Drainage/water pipelines other important utilities works considered are road diversions, road restoration etc. Cost provision has been made on route by task based on experience of Delhi Metro.

### 10.8 ENVIRONMENTAL IMPACT ASSESSMENT

Provision for environmental impacts of the proposed two Corridors has been made to cover various protection works, additional compensatory measures, and compensation for loss of trees, compensatory afforestation and fencing, monitoring of water quality, air/noise pollution during construction, establishment of Environmental Division.

### 10.10 REHABILITATION & RESETTLEMENT

Provision towards compensation/rehabilitation of structures likely to be affected has been assessed. Sufficient provision is kept in the estimate to cover the cost of shifting of structures.

### 10.11 TRACTION & POWER SUPPLY

Provisions have been made to cover following subheads:

- OHE
- Receiving-cum-Traction Substations including cables
- AGS for elevated and at-grade stations.
- Service connection charges for Feeding Sub-stations.
- SCADA augmentation.
- Miscellaneous items e.g. Surveillance, lifting T&P, etc.

The rates adopted for various items are based on costs of works being done for Delhi Metro, duly updated to June 2012 level.

### 10.12 ELECTRICAL SERVICES AT STATIONS

These are included in estimated costs of stations. Cost of accessories for elevated stations have not been included in station costs, and therefore, are provided under electrical estimates & shown separately.

### 10.10 SIGNALLING & TELECOMMUNICATION WORKS

The rates adopted are based on assessment done considering rates of similar sub-system as accepted for Delhi Metro, duly updated to June 2012 price level and TPWB works. These rates include installation during manufacture & supply of equipment and their installation at site, but exclude CD and WT.

### 10.14 AUTOMATIC FARE COLLECTION

Adopted rates are based on assessment done considering rates of similar works in Delhi Metro other metro projects, duly updated to June 2012 price level. These rates exclude





CO & WT, but include excavation during the period of equipment manufacture and their supply, including installation.

#### 10.16 ROLLING STOCK

The estimated cost per coach at June 2012 price level exclusive of taxes and duties has been taken as Rs. 6.5 Crores per coach.

#### 10.16 CAPITAL EXPENDITURE ON SECURITY

A lump-sum cost of 10 crore has been considered for the purpose.

#### 10.17 CAPITAL EXPENDITURE ON FEEDER RUSES

A lump-sum cost of Feeder Ruses @ 2% of Total Cost of all items except Land has been considered.

#### 10.18 TAXES AND DUTIES

The component of Import Duty, Excise Duty and VAT is not included in the Capital cost estimated. The estimated taxes and duties for various materials are given in the following table.

Details of Taxes and duties for Carbons and Comdants are provided in table 10.3 and 10.4 respectively.



**TABLE 10.2**  
**Details of Taxes and Duties (NS CORRIDOR)**  
**Details of Taxes and Duties (NS CORRIDOR)**

S. No.	Description	Total cost without Taxes & Duties (Cr.)	Taxes and duties			Total taxes & duties (Cr.)
			custom duty (Cr.)	excise duty (Cr.)	VAT(Cr.)	
	Customs duty =	22,8531	%			
	Excise duty =	12.36	%			
	Sale tax =	6.25	%			
	Works tax =	6.25	%			
	VAT =	12.8	%			
<b>1</b>	<b>Alignment &amp; Formation</b>					
	Underground	6.89	0.35	6.89	1.00	6.90
	Excavated, at grade & entry to Depot	452.92		36.18	22.25	491.45
<b>2</b>	<b>Station Buildings</b>					
	a) Underground station-civil works	3.81	0.30	6.89	0.00	6.90
	a) Underground station-EM works	3.39	0.30	6.89	0.00	6.90
	Excavated station - civil works	276.91		25.28	14.35	316.63
	Excavated station-EM works	116.53	5.35	5.79	5.98	28.99
	a) Metro driver's & OCC dip-civil works	41.33		3.58	2.03	6.81
	1) Metro driver & OCC dip-EM works	7.29	0.35	6.81	0.39	1.29
<b>3</b>	<b>Depot</b>					
	Civil works	38.43	4.00	5.54	2.61	6.55
	EM works	57.83	4.00	7.36	4.18	16.56
<b>4</b>	<b>F-Way</b>	122.95	22.31	2.56	1.40	26.54
<b>5</b>	<b>Traction &amp; power supply</b>					
	Traction and power supply	348.71	31.89	21.98	12.43	66.30
<b>6</b>	<b>S &amp; T Works</b>					
	S & T	291.97	13.20	7.20	4.00	64.00
	NCC	60.30	14.57	2.63	1.48	18.68
<b>7</b>	<b>R &amp; R hutments</b>	60.93			3.75	5.76
<b>8</b>	<b>Misc.</b>					
	Civil works	72.89		6.25	3.57	6.90
	EM works	24.23		2.50	1.40	3.89
<b>9</b>	<b>Rolling stock</b>	290.30	30.41	2.75	1.54	66.86
<b>10</b>	<b>Security</b>					
	Civil works	6.90		0.22	0.36	6.90
	EM works	4.00		0.49	0.36	6.85
<b>11</b>	<b>Factor Rates</b>	47.31		5.61	4.23	16.84
	<b>Total</b>	<b>2287.34</b>	<b>180.36</b>	<b>147.68</b>		<b>419.47</b>
	<b>Total taxes &amp; Duties</b>					<b>420</b>



TABLE 10.4  
Details of Taxes and Duties (EW CORRIDOR)

Details of Taxes and Duties (NS CORRIDOR)						
S. No.	Description	Total cost without Taxes & Duties (Cr.)	Taxes and duties			Total taxes & duties (Cr.)
			custom duty (Cr.)	excise duty (Cr.)	VAT(Cr.)	
	Customs duty =	22.8331	%			
	Excise duty =	12.39	%			
	Sale tax =	6.23	%			
	Works tax =	6.23	%			
	vat =	12.8	%			
<b>1</b>	<b>Alignment &amp; Formation</b>					
	Underground	6.00	6.00	9.00	0.00	6.00
	Excavated, at grade & entry to Depot	541.05		45.61	20.00	76.61
<b>2</b>	<b>Station Buildings</b>					
	a) Underground station-civil works	0.00	0.00	0.00	0.00	0.00
	a) Underground station-EM works	0.00	0.00	0.00	0.00	0.00
	Excavated station - civil works	185.80		24.00	10.31	40.00
	Excavated station-EM works	135.58	8.30	11.21	6.37	36.00
	a) Metro station & OCC (sq)-civil works	41.33		9.98	2.09	6.00
	o Metro station & OCC (sq)-EM works	7.20	0.20	0.61	0.20	1.20
<b>3</b>	<b>Depot</b>					
	Civil works	30.40	4.00	3.54	2.31	9.00
	EM works	87.80	4.00	7.38	4.19	16.00
<b>4</b>	<b>P-Way</b>	131.00	24.40	2.77	1.37	28.54
<b>5</b>	<b>Traction &amp; power supply</b>					
	Traction and power supply	180.12	30.30	23.81	11.30	65.00
<b>6</b>	<b>S &amp; T Works</b>					
	S & T	275.34	10.36	6.81	3.87	17.00
	HT	30.00	16.28	2.54	1.97	20.00
<b>7</b>	<b>R &amp; H nutrients</b>	60.00			3.75	3.75
<b>8</b>	<b>Misc.</b>					
	Civil works	60.00		5.00	3.30	8.30
	EM works	22.94		2.41	1.37	4.78
<b>9</b>	<b>Rolling stock</b>	300.00	61.54	2.90	1.00	65.44
<b>10</b>	<b>Security</b>					
	Civil works	6.00		0.52	0.36	0.88
	EM works	4.00		0.48	0.36	0.94
<b>11</b>	<b>Header Rates</b>	93.10		6.18	4.50	10.78
	<b>Total</b>	<b>2968.18</b>	<b>198.81</b>	<b>164.61</b>		<b>442.22</b>
	<b>Total taxes &amp; Duties</b>					<b>442.22</b>

# CHAPTER 19

## FINANCING OPTIONS, FARE STRUCTURE AND FINANCIAL VIABILITY



19.1	INTRODUCTION
19.2	COSTS
19.3	REVENUES
19.4	FINANCIAL INTERNAL RATE OF RETURN (FIRR)
19.5	FINANCING OPTIONS
19.6	RECOMMENDATIONS

### TABLES

TABLE 19.1	COST TABLE
TABLE 19.2	YEAR 16 INFLATION
TABLE 19.3	ADDITIONAL INVESTMENT TOWARDS ROLLING STOCK
TABLE 19.4	OPERATION AND MAINTENANCE COSTS
TABLE 19.5	PROJECTED RISK/RSP
TABLE 19.6	TRIP DISTRIBUTION
TABLE 19.7	FARE STRUCTURE (M 2019 '0)
TABLE 19.8	INCOME ASSIGNED FROM ADDITIONAL TAXES
TABLE 19.9	FIRR - COST WITH CENTRAL TAXES
TABLE 19.10	FIRR SENSITIVITY
TABLE 19.11	FINDING PATTERN UNDER SPV MODEL (WITH TAXES & DUTIES)
TABLE 19.12	FINDING PATTERN UNDER BOT MODEL (WITH CENTRAL TAXES)
TABLE 19.13	FIND CONTRIBUTION OF COE & COM

### FIGURES

FIG. 19.1	TRIP DISTRIBUTION
FIG. 19.2	FINDING ESTIMATE - 0% INFL.



## CHAPTER 19

**FINANCING OPTIONS, FARE STRUCTURE  
AND FINANCIAL VIABILITY****19.1 INTRODUCTION**

The Noida Metro consisting of two corridors are proposed to be constructed with an estimated cost of Rs 6862.00 Crores with Central Taxes, State Taxes and land cost. The corridor-wise length estimated cost at June-2012 price level without taxes and with all taxes is placed in **Table 19.1** as under:

**Table 19.1**  
**Cost Details**

Corridor No.	Name of Corridor	Distance (KMs)	Rs. in Crores	
			Estimated Cost without Central taxes at June-2012 Price Level	Estimated Cost with all taxes at June-2012 Price Level
I	North-South Corridor	10.838	3612.00	3,420.00
II	East-West Corridor	10.557	2664.00	3,427.00
<b>Total</b>		<b>20.395</b>	<b>6276.00</b>	<b>6847.00</b>

The estimated cost at June-2012 price level includes Rs. 403.00 Crores and Rs.214.00 Crores as land cost respectively for Corridor I and II. The estimated cost at June-2012 price level also includes an amount of Rs.20 Crores as one-time charges of security personal benefits cost of weapons, barricades, and hind hold and door detector machine etc. However, the recurring cost towards salary and allowances of security personal have not been taken in to account in FIRR calculation with an assumption that the required police personnel will be provided free of cost by the state government since it is the state's subject.



## 18.2 COSTS

### 18.2.1 Investment Cost

For the purpose of calculating the Financial Internal Rate of Return (FIRR), the completion costs with central taxes & state taxes have been taken with an escalation factor @7.50% PA.

The construction work is expected to get completed by 31.03.2018. The Revenue Opening Date (ROD) has been assumed as 01.04.2018. The total completion costs duly escalated and shown in the table 18.2 have been taken as the initial investment. The year-wise cash outgo is shown in Table 18.2 as below.

**Table 18.2**  
Year-wise Investment

Financial Year	Cost at June 2012 Price Level	Rs. in Crore
		Completion Cost
2013-14	447.00	452.00
2014-15	344.00	1021.00
2015-16	1000.00	1074.00
2016-17	1865.00	2412.00
2017-18	1430.00	1080.00
2018-19	497.00	743.00
2019-20	134.00	188.00
<b>Total</b>	<b>6982.00</b>	<b>8980.00</b>

Although the construction is expected to get over by 31<sup>st</sup> March 2018, the cash flow left over up to March 2020 is necessary on account of payment normally required to be made to the various contractors up to that period necessitated by contractual clause.

The land cost is divided into two initial years during which it is expected that the land acquisition work would be over and related payments would have to be released. Therefore, no escalation has been considered on it.

### 18.2.2 Additional Investment

Total investment provided in the FIRR calculation towards requirement of additional rising stock to take care of incremental traffic, duly escalated @7% PA is placed in Table 18.3 as under: -

**Table 18.3**



**Additional investment towards Rolling Stock  
Rs. in Crore**

Year	No. of Cars	Amount with Taxes
2021-22	10	241.00
2026-27	9	194.00
2031-32	8	157.00
2036-37	12	400.00
2041-42	12	311.00

### 10.2.3 Operation & Maintenance (O&M) Costs

The Operation & Maintenance costs can be divided into three major parts: -

- Staff costs
- Maintenance cost which includes expenditure towards upkeep and maintenance of the system and consumables
- Energy costs

The staffs are assumed to be provided @ 35 persons per kilometre. The escalation factor used for staff costs is 5% per annum to provide for both escalation and growth in salaries.

The cost of other expenses is based on the actual O & M unit cost for the Delhi Metro Phase-I project. The average rate of electricity being paid by Delhi Metro for its Phase-I and Phase-II operations in Delhi is Rs. 5.80 per unit whereas in Nagpur the applicable rate is Rs. 5.00 per unit. The latter has been used for all calculations. The O&M cost (excluding staff cost) has been obtained by providing an escalation of 7.50% per annum. The O&M costs which has been calculated on life cycle cost basis is tabulated in Table 10.4 as below:-

**Table 10.4  
Operation and Maintenance Costs**

Rs. in crore					
YEAR	Staff	Maintenance Expenses	Energy	Total	
2016	21.4	11.34	41.52	74.26	138.52
2017	22.58	12.07	43.35	78.00	146.00
2018	23.81	12.82	45.23	81.86	153.72
2019	25.12	13.60	47.17	85.89	162.58
2020	26.51	14.41	49.17	90.09	172.18
2021	27.99	15.25	51.23	94.47	182.94
2022	29.56	16.13	53.36	99.05	194.90
2023	31.22	17.04	55.56	103.84	208.06
2024	32.97	18.00	57.82	108.79	222.56
2025	34.81	19.00	60.15	113.96	238.42
2026	36.74	20.04	62.55	119.34	255.63
2027	38.76	21.13	65.02	124.91	274.82
2028	40.87	22.27	67.57	130.71	296.41
2029	43.07	23.46	70.20	136.74	320.47
2030	45.36	24.70	72.91	143.01	347.98



YEAR	staff	Maintenance Expenses	Energy	Total
2015	277.73	66.71	165.26	509.70
2016	289.37	72.34	173.98	535.69
2017	301.70	87.26	187.87	576.83
2018	315.07	126.30	198.94	640.31
2019	329.30	167.29	217.94	714.53
2020	344.74	207.74	234.77	807.25
2021	361.71	257.27	250.30	919.28
2022	379.73	307.73	267.24	1054.70
2023	398.23	358.73	285.21	1212.17
2024	417.24	417.24	303.24	1397.72
2025	436.77	483.27	321.27	1601.31

#### 10.2.4 Depreciation

Although depreciation does not enter the PRR calculation (not being a cash outflow) unless a specific depreciation reserve fund has been provided, in the present calculator, depreciation calculations are placed for purpose of record.

#### 10.2.5 Replacement Cost

The replacement costs are provided for measuring the cost on account of replacement of equipment due to wear and tear. With the nature of equipment proposed to be provided, it is expected that only 30% of the Signalling and Telecom and 25% of electrical works would require replacement after 20 years. Further, 50% of the Signalling and Telecom and 25% of electrical works would require replacement after 30 years. These costs have been provided duly escalated @ 5% per annum.

### 10.3 REVENUES

The Revenue of Nagar Metro mainly consists of fare box collection and other incomes from property development, advertisement, parking etc.

#### 10.3.1 Fare box

The Fare box collection is the product of projected ridership per day and applicable fare structure based on assumed trip distribution of different distance zones.

#### 10.3.2 Traffic

The year-wise projected ridership figures are as indicated in **Table 10.3** as below :-

**Table 10.3**  
Projected Ridership

Year	Corridor-1 & 2 Trips Per Day (thous)
2014-15	3.67
2021-23	3.83
2025-27	4.13





Year	Corridor-1 & 2 Trac Per Day (Average)
2011-12	4.54
2016-17	5.09
2041-42	5.64

b. The growth rate for traffic is assumed at 2.10% Per Annum.

### 18.2.2 Trip Distribution


The trip distribution has been worked out by considering average load of 9.28 KM, which is placed in **Table 18.8** below: -

**Table 18.8**  
Trip Distribution

Distance in kms.	Percent distribution
0-2	11.00%
2-4	20.00%
4-6	20.50%
6-8	26.00%
8-12	7.00%
12-15	5.00%
15-18	3.00%
18-21	2.00%
>21	1.00%
Total	100.00%

The graphic presentation of the same is placed below in **Figure-18.5**.

**Figure 18.5 – Trip Distribution**





### 10.3.4 Fare structure

The Dahi Metro Fare structures laid by the fashion committee in 2009 have been assumed, which have been duly escalated @15% for every two years to arrive at the initial fare structure for Nagpur Metro, which is placed in Table 10.7.

**Table 10.7**  
Fare Structure in 2015-16

Distance in kms	DMRC Fare as Revised in 2009	Nagpur Metro Fare (Rs.) in 2015-16
0-2	8	15
2-4	10	18
4-8	12	20
6-9	15	28
9-12	16	30
12-15	18	34
15-18	19	30
18-21	21	39
>21	22	41

### 10.3.5 Other sources of revenues

**10.3.5.1 Property Business.** Other revenues from Property business i.e. advertisement, kiosk, ATM etc. have been estimated at 10% of the fare box revenues during operations. Apart from development of property on metro stations and depot it is possible to take resources through leasing of parking rights at stations, advertisement on trains and stadia, advertisements within stations and parking lots, advertisements on viaducts, columns and other metro structures, CO-branding rights to corporates, film shootings and special events on metro premises.

**10.3.5.2 Additional Taxes.** Income assumed from additional taxes i.e. FSI, Additional Stamp Duty, Development Fund as proposed by Nagpur Improvement Trust vide letter dated 26.09.2013 is placed at Table no. 10.8. The amount of taxes as provided by Nagpur Improvement Trust has been considered from 2015-16 for FIRR calculations.

**Table 10.8 : Income assumed from additional taxes**

Rs. in Crore

Year	FSI	Additional Stamp Duty@1%	Development Fund Revenue	Total
2015 - 2017	-	60.00	0.00	60.00
2017 - 2018	-	60.00	0.00	60.00
2018 - 2019	-61.00	-61.00	0.00	122.00
2019 - 2020	288.00	111.00	0.00	399.00
2020 - 2021	428.00	123.00	0.00	551.00
2021 - 2022	602.00	127.00	0.00	729.00
2022 - 2023	724.00	121.00	0.00	845.00
2023 - 2024	801.00	166.00	0.00	967.00



2024	-	2025	280.00	-81.00	0.00	-70.00
2025	-	2026	717.00	301.00	0.00	822.00
2026	-	2027	279.00	101.00	0.00	1120.00
2027	-	2028	1200.00	512.00	0.00	1200.00
2028	-	2029	211.00	267.00	0.00	765.00
2029	-	2030	519.00	361.00	0.00	805.00
2030	-	2031	748.00	312.00	0.00	1200.00
2031	-	2032	886.00	229.00	0.00	1200.00
2032	-	2033	1215.00	241.00	0.00	1200.00
2033	-	2034	-	101.00	0.00	100.00
2034	-	2035	-	174.00	0.00	174.00
2035	-	2036	-	311.00	0.00	311.00
2036	-	2037	-	371.00	0.00	371.00
2037	-	2038	-	329.00	0.00	329.00
2038	-	2039	-	361.00	0.00	361.00
2039	-	2040	-	761.00	0.00	761.00
2040	-	2041	-	876.00	0.00	876.00
2041	-	2042	-	811.00	0.00	811.00
2042	-	2043	-	1015.00	0.00	1015.00
<b>Total</b>			<b>14074.00</b>	<b>1325.00</b>	<b>-102.00</b>	<b>21100.00</b>

#### 10.4 FINANCIAL INTERNAL RATE OF RETURN (FIRR)

The Financial Internal Rate of Return (FIRR) and costs for 30 years business model including construction period is **10.30%**. The FIRR with all taxes is produced in **Table 10.9**.

**Table 10.9**  
FIRR (with all taxes)

Year	Rs. in Crore										
	Comp. Inv. Cost	Working Inv. Cost	Revenue & Outputs at	Right-of-use lease	Total Cost	Tax Sacr. Revenue &	PG & I&DT	Revenue after all taxes net Taxes	Total Revenue	Net Cash Flow for 30	
2012	-	2016	102						0	-102	
2014	-	2017	102						0	-102	
2015	-	2018	187						0	-187	
2016	-	2019	310						0	-310	
2017	-	2020	180						0	-180	
2018	-	2021	76	102	80	300	26	211	361	-108	
2019	-	2022	98		115	212	208	21	278	89	315
2020	-	2023	0		190	190	36	766	1196	816	
2021	-	2024	0	211	207	160	302	26	661	106	512
2022	-	2025	0	0	225	224	226	21	640	109	110
2023	-	2026	0	0	212	212	136	21	1102	379	1107
2024	-	2027	0	0	262	262	214	21	775	108	1175
2025	-	2028	0	0	286	286	229	21	812	109	1217



Year		Company Net Cost	Address Net Cost	Services & Utilities Net	Resale Net Cost	Other Costs	Tax Gains Services &	FD & R&D	Revenue from Operations Net Taxes	Tax Benefits &	Net Cost to the S&P
2008	-	4807	0	164	221	380	204	25	1162	1726	1361
2007	-	4928	0	0	247	217	217	22	1268	1668	1661
2006	-	3009	0	0	225	216	216	21	762	1076	1022
2005	-	3900	0	0	127	127	126	21	266	172	1116
2004	-	3801	0	0	112	112	268	27	1842	2207	1827
2003	-	3600	0	127	181	236	272	27	1227	2736	1512
2002	-	4202	0	0	221	221	1228	22	1717	2216	2221
2001	-	4206	0	0	206	204	1224	22	1726	1726	1726
2000	-	2222	0	0	212	212	1222	22	1726	1726	1726
1999	-	2226	0	0	221	221	1226	22	1726	1726	1726
1998	-	2007	0	222	222	1122	1222	22	222	2226	1671
1997	-	2228	0	0	222	222	1221	22	222	2227	1622
1996	-	2000	0	0	221	221	1221	22	222	2226	1726
1995	-	2222	0	0	222	222	1222	22	222	2226	1726
1994	-	2221	0	0	222	222	1221	22	222	2226	1726
1993	-	2222	0	211	212	212	1212	21	222	2226	1627
1992	-	2222	0	0	222	222	1222	22	222	2226	1726
<b>Total</b>		<b>562</b>	<b>1162</b>	<b>1212</b>	<b>222</b>	<b>1612</b>	<b>2226</b>	<b>222</b>	<b>2222</b>	<b>1676</b>	<b>10.25%</b>

The various sensitivities with regard to increase/decrease in capital costs, O&M costs and revenues are placed in Table 18.10 below :-

**Table 18.10**  
**FMR sensitivity**

CAPITAL COSTS with all Taxes			
10% increase in capital cost	20% increase in capital cost	10% decrease in capital cost	20% decrease in capital cost
9.44%	9.22%	11.20%	12.20%
REVENUE			
20% decrease in Traffic revenue	10% decrease in Traffic revenue	10% increase in Traffic revenue	20% increase in Traffic revenue
8.22%	9.27%	10.22%	11.22%
O&M COSTS			
10% increase in O&M cost		10% decrease in O&M cost	
10.22%		10.22%	

These sensitivities have been carried out independently for each factor.



## 10.6 FINANCING OPTIONS

### 10.6.1 Objectives of Funding

The objective of funding metro systems is not necessarily enabling the viability of funds for construction but coupled with the objective of financial closure are other concerns, which are of no less importance. -

1. Ensuring low project cost
2. Ensuring debt funds at low rates of interest
3. Creating self sustainable system in the long run by
  - Low infrastructure maintenance costs
  - Long life span
  - Setting fares which minimise dependence on subsidies
4. Recovering returns from both direct and indirect beneficiaries

Rail based mass transit systems are characterised by heavy capital investment coupled with long gestation period leading to low financial rates of return although the economic benefits to the society are immense. Such systems generate externalities, which do not get captured in monetary terms and, therefore, do not flow back to the system. However, experience all over the world reveals that both construction and operations of metro are highly subsidised. Government involvement in the funding of metro systems is a foregone conclusion. Singapore had a 100% equity contribution from the government, Hong Kong 78% for the first three lines and 85% for the later 2 lines. In India also, GOI & concerned state government have contributed entire equity capital and equally provided interest free sub-stribe debts for land and central taxes along with O&M support from JICA for Delhi, Chennai, and Bangalore metros.

### 10.6.2 Alternative Models Of Financing

The financing option shall depend upon selection of the dedicated agency created to implement the project. The prominent models are: -

- (i) Special Purpose Vehicle under the State Control (Delhi Metro Rail Corporation (DMRC) /Bangalore Metro Rail Corporation (BMRC) mode)
- (ii) Public-Private Partnership (PPP) mode
  - Build Operate and Transfer (BOT) model
  - Other PPP Model

### 10.6.3 DMRC/BMRC/CMRL, pattern of Financing

A Special Purpose Vehicle (SPV) is set up for the implementation of the project and for its subsequent Operation & Maintenance. Under this arrangement Government of India and Government of Maharashtra shall make equal equity contribution and run the SPV as a commercial enterprise as a joint venture of GOI & GOM. As per the prevalent practice, Central Government may be willing to contribute 15% to 20% of the project cost as their equity contribution. An equal amount can be contributed by Government of Maharashtra aggregating the total equity to 40%. With the equal ownership of the SPV, both the governments nominate their representatives as



members of the Board of Directors, which in turn select functional directors. Such a SPV has a benefit of independent management under the logic of Indian Companies Act, 1956. Delhi Metro Rail Corporation, Chennai & Bangalore metro corporations are striking example of success of such SPV. For the balance 60% funding requirement, options available are as follows:-

- (i) **Subordinate Debt** - For Delhi Metro, land and rehabilitation and resettlement cost have been borne by GOI & UNCTD equally as interest free subordinate debt. Now, MORD have changed the policy under which the cost of land for Bangalore Metro was borne by Government of Karnataka as interest free subordinate debt. Similarly, the cost of Land including rehabilitation and resettlement cost amounting to **Rs.944.10** Crore may be contributed as interest free subordinate debt by GOI. This mezzanine financing is of extreme help in quickening the pace of land acquisition, since the compensation amount is released to exchequer instantaneously. The loan is of longer duration and concessional repayable only after other long term loans raised for the project is repaid.
- (ii) **Debt** - The balance cost is to be met through loans from various institutions namely JICA, Local borrowing, loans from ADB/World Bank and Suppliers Credit.

**JICA Loan** - Overseas Development assistance from Japan International Cooperation Agency (JICA) may be availed of for metro rail projects with interest @ 1.40%PA and it is to be repaid on back to back basis. The loan is repayable in 30 years including moratorium period of 10 years. The loan is being provided by JICA to GOI which in turn releases the same to SPV under a Pass Through Assistance (PTA) mechanism. Normally, JICA funds for underground civil works, Electrical, Signalling & Telecom and Rolling Stock only. Since the loan will be in Japanese Yen, fluctuation in exchange rate at the time of repayment shall be borne by the Central Government and Government of Maharashtra in proportion to which their shares holding. Alternatively, JICA can release the loan to the SPV for which a sovereign guarantee will be required from Central Government. Foreign exchange variation in such eventually will be borne either by the SPV or GOI. In either case, loan shall be repaid by SPV from the income streams of metro operations.

**Loan from Asian Development Bank (ADB)/World Bank** - The Loan shall be available from ADB/World Bank, but as per the experience its processing and approval normally takes 8-12 months. The interest rate is fixed with periodically LIBOR. These bilateral funding institutions also charge some margin ranging from 200 basis points to 300 basis points. This may delay the implementation of the project resulting in avoidable increase in the completion cost. Recently, Bangalore Metro availed ADB loan.



**Loan from Bank and Financial Institutions:** - Funds can be arranged from domestic financial institutions like India Infrastructure Finance Company Limited (IFCL), India Development Financing Corporation (IDFC), Life Insurance Corporation of India (LIC), IDBI Bank, ICICI Bank Ltd etc. These institutions are increasingly engaged to fund infrastructure projects subject to their commercial viability against guarantees from GOI. There are many models available under which the funds can be arranged by these financial institutions with or without syndicating with other commercial banks. IFCL, e.g. fund 20% of the project cost and arrange balance through the syndication of commercial banks with a lead banker among the consortium of bankers. The loan can be given for a period of 20-30 years with interest rate ranging from 5.50% to 12% PA. IFCL can also provide 100% funding against GOI guarantee. They arrange EDB in the extent of foreign currency requirement at very competitive rate. The funding arrangement may require the central government guarantee as well. Since the rate of interest of these financial institutions is much higher than the interest rate of soft loan provided by JICA, GOI and GOM and have to bear the interest difference and provide suitable security to the SPV to make the project financially sustainable.

**Suppliers Credit:** - Suppliers Credit is an established method to secure funding of imports. It is backed by ECOM banks of exporting countries and is often a much better instrument than bilateral aid. While bilateral aid ties the borrowing entity, Suppliers Credit can be used intelligently and effectively to spur competition in competitive international tendering method. In case of floating bid, where market is truly competitive (under 55T) an attractive rate of interest for suppliers credit is possible. However, the supplier will load the amount of interest in the cost of supply, due to which the effective completion cost will be very high.

The funding pattern assumed under government owned SPV model is placed in Table 18.11 as under:-

**Table 18.11**  
Funding pattern under SPV model (with All Taxes & Duties)

Particulars	With Taxes & Duties	
	Amount (Rs/Crore)	% of contribution
Equity by GOI	1154.00	12.87%
Equity by GOM	1154.00	12.87%
SD by GOM to central Taxes (50%)	441.00	5.08%
SD by GOI for Central Taxes (50%)	441.00	5.08%
SD by GOM for State Taxes	200.00	2.28%
SD by GOM for Land	644.00	7.42%
Nagar Improvement Trust Contribution	421.00	4.85%
Nagar Municipal Corporation Contribution	421.00	4.85%
JICA Loan @ 1.40% P.A/Market Borrowing @ 12%	3826.00	44.08%
<b>Total</b>	<b>8986.00</b>	<b>100.00%</b>

**10.5.4 Public Private Partnership Mode**

Public Private Partnership (PPP) arrangements are steadily growing in use particularly in road, power, and telecom sectors which are more of commercial nature rather than in a social sector project. PPP models are arrayed across a spectrum ranging from BOT where the private sector has total involvement to other toll-raise models where both public and private sector assume separate responsibilities. A few alternatives which can be selected in this regard are:-

**BOT Model** – In this model, the private firm will be responsible for financing, designing, building, operating and maintaining of the entire project. The contribution of Government of Maharashtra will be limited to cost of land only. Such a project becomes eligible for Viability Gap Funding (VGF)- upto 20% from the Central Government provided the state government also contribute same amount towards the project. The metro being a social sector project may not attract much private parties. Besides quite expectedly the private operator may demand assured top or return in the range of 16% to 18% (Equity IRR) or a combine of guaranteed ownership etc.

The funding pattern assumed under this model is as per 16% as EIRR is placed in Table 10.12 tabulated as under:-

**Table 10.12**  
**Funding pattern under BOT model (with all taxes)**

Particulars	Amount (Rs/Crore)	% of contribution
VGF by GOI	1565.48	20.00%
VGF by GOM	824.63	6.70%
Equity by Concessionaire	1888.00	24.42%
Concessionaire's debt @ 12% Pd	3776.00	48.88%
<b>Total</b>	<b>7777.00</b>	<b>100.00%</b>
Land Free by GOM	844.00	
State Taxes by GOM	293.00	
IDC	443.00	
<b>Total including IDC</b>	<b>8126.00</b>	

**10.6. RECOMMENDATIONS**

The EIRR of subject metro with all taxes is **18.30%**, and therefore the corridors are recommended for implementation.

The total fund contribution of GOI & GOM under various alternatives is tabulated in table 10.13.





Table 18.11


Contributor	Rs. in crores	
	SPV Model	BOT
Government of India	1555.00	1555.40
Government of Maharashtra	2458.00	1427.60
<b>Total</b>	<b>4013.00</b>	<b>2983.00</b>

Considering the fact that the innovative financing from additional FAR, Stamp Duty, Development fund revenue provided by Nagar Improvement Trust shall flow only to the government instrumentalities and not to the private operator, it is recommended to implement the project under SPV model as per the funding pattern given in Table 18.11.

The details showing cash flow under JICA Loan, Market Borrowing, BOT model to ensure 10% EIRR when the project cost is with all taxes are shown respectively in Table 18.14, 18.15& 18.16.

The funding pattern assumed under SPV model is depicted in the pie chart i.e., Figure 18.2 as under :-

Figure 18.2  
Funding Pattern - SPV Model













# CHAPTER 20

## ECONOMIC APPRAISAL



20.1	INTRODUCTION
20.2	VALUES ADOPTED FOR SOME IMPORTANT VARIABLES
20.3	ECONOMIC BENEFIT STREAM
20.4	METRO CONSTRUCTION COST
20.5	ECONOMIC PERFORMANCE INDICATORS
20.6	SENSITIVITY ANALYSIS
20.7	QUALIFIED BENEFITS
20.8	TRANSPORT ORIENTED DEVELOPMENT (TOD) & DER

### TABLES

TABLE 20.1	BENEFIT COMPONENTS, DER TO MCVW
TABLE 20.2	VALUES ADOPTED FOR SOME IMPORTANT VARIABLES
TABLE 20.3	VEHICLE OPERATING COST IN RS
TABLE 20.4	VEHICLE EMISSIONS 2011, 2021 (CO <sub>2</sub> ) AND CO <sub>2</sub> IN RS
TABLE 20.5	ACCIDENT RATE AND COST IN RS
TABLE 20.6	TRAFFIC PARAMETER VALUES
TABLE 20.7	COMPONENT WISE BENEFIT VALUE STREAM
TABLE 20.8	AVERAGE MARGINAL WELFARE IN STUDY AREA
TABLE 20.9	ESTIMATED CAPITAL AND RECURRING COST INCLUDING CENTRAL TAX
TABLE 20.10	REVENUE DEDUCTION VALUES (WITH CENTRAL TAX)
TABLE 20.11	SENSITIVITY OF ERR
TABLE 20.12	ENVIRONMENTAL BENEFITS (QUANTIFIED)
TABLE 20.13	TRAVEL BENEFITS (QUANTIFIED)

### FIGURES

FIG. 20.1	PERCENT OF BENEFITS
-----------	---------------------

**Chapter - 20****ECONOMIC APPRAISAL****20.1 INTRODUCTION**

Economic benefits are social and environmental benefits which are quantified and then converted into money cost and discounted against the cost of construction and maintenance for deriving Economic Internal Rate of Return (EIRR). When actual revenue earned from fare collection, advertisement and property development are discounted against construction and maintenance cost, interest (to be paid) and depreciation cost, Financial Internal rate of Return (FIRR) is obtained. Therefore, EIRR is viewed from socio-economic angle while FIRR is an indicator of pure financial profitability and viability of any project.

20.1.1 Economic appraisal of a project starts from quantification of measurable economic benefits in economic money values, which are basically the savings of resource cost due to introduction of the metro line. Economic savings are derived from the difference of the cost of the same benefit components under 'with' and 'without' metro line. Total net savings or benefit is obtained by subtracting the economic cost of the project (incurred for construction (Capital) and maintenance (recurring) costs for the metro line) from the benefits out of the project in each year. The net benefit value which would be negative during initial years becomes positive as years pass. Internal rate of return and benefit cost ratio are derived from the stream.

20.1.2 The sources from where economic savings occur are identified first. Although there are many kinds of primary, secondary and tertiary benefits, only the quantifiable components can be taken to measure the benefits. These components are quantified by linking with the number of passengers shifted and the passenger km saved by the trips which are shifted from road/rail based modes to metro. It may be observed that first four benefit components given in **Table 20.1** are direct benefits due to shifting of trips to metro, but other benefit components are due to decongestion effect on the road. Benefit components were first estimated applying market values then were converted into respective



Economic values by using separate economic factors which are also given in table 20.1. Depending upon methodology of estimation, economic factors are ascertained. Overall economic value of benefit components is 93% of the market value. Similarly economic value of the cost components are 82% of the market cost.

**Table 20.1: Benefit Components due to Metro**

	Benefit Components	Economic Factors
1	Construction Cost	80%
2	Maintenance Cost	80%
3	Annual Time Cost Saved by Metro Passengers	90%
4	Annual Fuel Cost Saved by Metro Passengers	90%
5	Annual Vehicle Operating Cost Saved by Metro Passengers	90%
6	Emission Saving Cost	100%
7	Accident Cost	100%
8	Annual Time Cost Saved by Road Passengers	90%
9	Annual Fuel Cost Saved by Road Passengers	90%
10	Annual Infra Structure Maintenance Cost	80%
11	Overall economic factor for the benefit components	93%

## 20.2 VALUES ADOPTED FOR SOME IMPORTANT VARIABLES

Benefit components are converted (by applying appropriate unit cost) to money values (Rs.). Some of the values used for economic analysis are shown in Table 20.2.

**Table 20.2: Values adopted for some important variables**

	Values	Important variables
1	Rs. 2,791/min (2013)	Time Cost derived from passenger's journey time and fare paid (mode wise).
2	Market Rate (2012)	Fuel Cost (value of Petrol, Diesel and CNG)
3	Table 20.3	Vehicle Operating Cost (Derived from Life Cycle Cost of different passenger vehicles per km)
4	Table 20.4 (CPCB)	Emission (g/km as per CPCB and UK Norms) Emission Saving Cost (adopted for Indian conditions in Rs/ton)
5	Table 20.5 (Accident Rate & Cost)	Accident Rate (No of fatal and all accidents per one Cr KM). Accident costs are derived from published papers at current rate.
6	57.3%	Passenger km to Vehicle km conversion factor (derived from modal split within study area as reported in chapter 2)
7	Road User Cost Study Model (CRR)-2019)	Fuel Consumption of vehicles at a given speed is derived
8	Rs. 1.0/vehicle km	Infra Structure Maintenance Cost is derived from published values on annual expenditure on roads and traffic and

9	13.54 min	average vehicle km Average Journey Time Saved for average km journey after Shifting (Derived)
10	24.06 kmph	Average Journey Speed (Speed & Delay Study)

**Table 20.3: Vehicle Operating Cost in Rs.**

Per vehicle KM	Bus	4 Wh (Large)	4 Wh (Small)	2 Wh (MC)	2 Wh (SC)	3 Wh (Mini Bus)	Mini Bus
Maintenance Cost	5.94	3.31	2.01	0.57	0.72	2.26	2.75
Capital Cost	2.40	2.67	1.20	0.18	0.16	0.72	1.72
Total VOC	8.46	6.58	3.54	0.83	0.98	3.27	4.42

**Table 20.4: Vehicle Emission 2011-2021(GPCB) and Cost in Rs.**

VEHICLE	CO	HC	NOX	PM	CO	CO <sub>2</sub>
BUS	3.72	0.18	8.53	0.24	3.72	767.72
2W 3 STROKE	1.4	1.32	0.38	0.05	1.4	24.99
2W 4 STROKE	1.4	0.7	0.5	0.05	1.4	26.58
MINI BUS	2.48	0.83	8.26	0.58	2.48	360.96
4W SMALL	1.59	0.15	0.12	0.02	1.39	139.51
4W LARGE	0.58	0.05	0.45	0.05	0.58	166.95
TATA MAGIC	1.24	0.17	0.58	0.17	1.24	160
3W	2.45	0.75	0.12	0.08	2.45	77.89
Cost	RS. 10000 PER TON					800

**Table 20.5: Accident Rate<sup>3</sup> and Cost in Rs**

Accident Rate in the year 2010	Cr. Vehicle KM	Cost in Rs
All Types	3.0	566911
Fatal Accident	0.2	1892648

<sup>3</sup> 2011 figure of accidents in Nagpur is used

Traffic parameter values used for economic analysis are given in **Table 20.8**.

**Table 20.8: Traffic parameter values**

TRAFFIC INPUT	2014	2021	2028	2031	2034	2041
Trips/day NAGPUR METRO	352442	383439	419125	458800	508656	563735
Link Length (km)	39.5	39.5	39.5	39.5	39.5	39.5
Average Trip length (km)	8.42	8.45	8.49	8.53	8.52	8.52
Passenger km/km	37214	62641	89908	12997	63973	93284



Table 20.7: Average modal split in the study area

Vehicles	% Pass	% Vehicle
BUS	4.1%	16.4%
MTR/BUS	4.6%	4.9%
CAR	16.7%	36.4%
TAXI	4.3%	1.3%
2WH	10.2%	11.7%
AUTO	4.3%	22.9%
CYCLE	2.1%	2.1%

## 20.2 ECONOMIC BENEFIT STREAM

Benefits in terms of money value are estimated directly from the projected passenger km saved for the horizon years (2016, 2021, 2026, 2031 and 2041) and values for other years are interpolated on the basis of projected traffic. Market values are used for calculating costs and then appropriate economic factors (see table 20.1) are applied. For each year values of each benefit components are obtained and thus benefit stream is estimated. Benefit Components Stream for **Nagpur Metro Rail** is shown in **Table 20.8**.



Table 10.3: Comparison with Real-World Values (Contd.)

Year	Population (in lakhs)	Area (in sq. km)	Population Density (per sq. km)	Population (in lakhs)	Area (in sq. km)	Population Density (per sq. km)	Population (in lakhs)	Area (in sq. km)	Population Density (per sq. km)	Population (in lakhs)	Area (in sq. km)	Population Density (per sq. km)
1951	361	328727	1.1	361	328727	1.1	361	328727	1.1	361	328727	1.1
1961	426	328727	1.3	426	328727	1.3	426	328727	1.3	426	328727	1.3
1971	505	328727	1.5	505	328727	1.5	505	328727	1.5	505	328727	1.5
1981	597	328727	1.8	597	328727	1.8	597	328727	1.8	597	328727	1.8
1991	686	328727	2.1	686	328727	2.1	686	328727	2.1	686	328727	2.1
2001	786	328727	2.4	786	328727	2.4	786	328727	2.4	786	328727	2.4
2011	893	328727	2.7	893	328727	2.7	893	328727	2.7	893	328727	2.7
2021	1000	328727	3.0	1000	328727	3.0	1000	328727	3.0	1000	328727	3.0




Figure 20.1 Percent of Benefits

Total Benefit between the years 2010-2043 (Component wise) are shown in figure 20.1 which shows that benefits are mainly coming from saving of road line (metro and road) (44.25%), vehicle operation cost (VOC) (31.42%) and fuel cost (14.36%). Environmental benefit from emission reduction, accident reduction and road maintenance cost (sugarifer) is 0.97%. In this area (Majour City), personalized modes (cars, three and two wheelers) are dominant (37.07%) which have made vehicle by passenger ratio very high (51%). Average modal split obtained from the past study shows that about 10% passengers were using public bus within the city. Traffic volume count survey shows that 80.91% vehicle trips are by private modes as. Obviously presence of dependable mass transport system is not there.

**20.4 METRO CONSTRUCTION COST**

20.4.1 Total cost of metro construction (CAPITAL COST) is derived after considering cost of all major component such as Relocation and Rehabilitation(RR), Civil construction for underground and elevated portions, Stations and Depots, Track laying, Signalling and telecommunication, Power traction lines, Rolling stock, Man power etc. RECURRING COST includes energy cost, maintenance cost, and operation cost. Economic analysis period is taken from 2013-14 to 2042-43 out of which 6 years (2013-2018) are marked as construction period. Additional capital expenditure may be incurred in the years 2021-22 & 2025-27 (purchase of more rolling stock), 2031-32 and 2040-41. Operation is expected to start in 2018-2019 (Year 6). This cost stream is generated with Central taxes. Detail is shown in Table 20.8.

**Table 20.8: Estimated Capital and Recurring Cost including Central Tax**

Year	Year	Capital Cost	Recurring Cost
Start	Ending	Cr. Rs.	Cr. Rs.
2013	2014	447	0
2014	2015	995	0
2015	2016	1808	0
2016	2017	2334	0
2017	2018	1923	0
2018	2019	719	982
2019	2020	194	175
2020	2021	0	190
2021	2022	241	207
2022	2023	0	224
2023	2024	0	242
2024	2025	0	262
2025	2026	0	284
2026	2027	184	321
2027	2028	0	347
2028	2029	0	376
2029	2030	0	407
2030	2031	0	440
2031	2032	167	481
2032	2033	0	521
2033	2034	0	564
2034	2035	0	610
2035	2036	0	661



2036	2037	400	736
2037	2038	0	756
2038	2039	0	861
2039	2040	1700	932
2040	2041	1360	1006
2041	2042	511	1133
2042	2043	0	1226

### 20.6 ECONOMIC PERFORMANCE INDICATORS

After generating the cost and benefit stream table, values of economic indicators are derived and are presented in **table 20.10**. Project period is 2013-2043, ERR (with central tax) is found to be **17.76%** and B/C ratio as 3.45 and with 12 % discount, IRR is 5.06% and B/C ratio is 0.70. NPV without discount is Rs.51210 Cr. and with 12% discount rate, NPV is Rs.3404 Cr. which shows that the project is economically viable.

**Table 20.10. Economic Indicator Values (with Central Tax)**

Hagpur Metro Network	WITHOUT DISCOUNT	WITH DISCOUNT (12%)
Total cumulative cost	20014	6037
Total cumulative benefit	72126	4568
Benefit-Cost Ratio	3.45	0.70
NPV	51210	3404
ERR	17.76%	5.06%

### 20.6 SENSITIVITY ANALYSIS

Sensitivity analysis for ERR and B/C ratio is performed for both with and without discount and the output is given in the **table 20.11**. 2042-43 is taken for the year of comparison. ERR and B/C ratio after discount of 12% shows that the project is economically viable.

**Table 20.11 Sensitivity of ERR**

SENSITIVITY		WITHOUT DISCOUNT			WITH DISCOUNT (12%)		
TRAFFIC	COST	ERR	B/C	COST	ERR	B/C	COST
0%	0%	17.76%	3.45	20014	5.06%	1.52	6037
-10%	0%	17.06%	3.32	20014	4.52%	1.40	6037
-20%	0%	16.47%	3.19	20014	3.99%	1.40	6037
0%	10%	16.95%	3.34	23039	3.88%	1.38	7191
0%	20%	13.15%	2.87	25037	2.81%	1.27	7940
-10%	10%	15.78%	3.02	23006	3.26%	1.32	7191
-20%	20%	13.90%	2.88	25037	1.78%	1.10	7940



### 20.7 Quantified Benefits.

Benefits which are shown in previous tables are money value of the benefits. These benefits are estimated first and then converted into money value. For brevity, only 5 year estimates are shown in table 20.8 (Reduction of Vehicle gas Emission) and in table 20.12 (Reduction of Fuel, Time of Travel, Vehicle on Road etc).

**Table 20.12 Environmental Benefits Quantified**

Year/Year	2019	2020	2021	2022	2023
CO	1850.94	1484.86	1513.21	1540.71	1574.88
HC	980.89	746.29	790.52	775.86	791.52
NOx	235.39	238.00	241.12	242.96	230.90
PM	54.82	53.20	54.27	55.37	58.48
SO <sub>2</sub>	4.06	3.70	3.83	3.91	3.99
CO <sub>2</sub>	54621	60861	57108	58472	60854
Total Emission Saved	67789	68266	68691	73257	72511

From Table 20.12, it may be seen that in 2020, CO<sub>2</sub> reduction will be 65.66 thousand tons and reduction of other gases will be 3.168 thousand tons.

**Table 20.10 Travel Benefits Quantified**

Quantified Benefits in Horizon Years	2019	2020	2021	2022	2023
Annual Time Saved by Metro Passengers in Cr. Hr.	3.21	3.30	3.44	3.58	3.60
Annual Fuel Saved by Metro Passengers in Thousand Tons	46.77	48.17	49.83	51.19	52.82
Daily vehicles reduced (off the road)	50403	57036	52634	50817	51024
Reduced No. of Fatal Accidents in Year	19.38	19.61	20.24	20.70	21.18
Reduced No. of Other Accidents in year	174.40	178.27	182.16	186.30	190.08
Annual Vehicle km Reduced in Thousand Km.	26,344	28,545	27,362	27,314	26,477

Amount of travel in terms of vehicle reduced due to shifting of passengers to Metro Rail is equivalent to reduction of 57 thousand vehicles on the road in 2020. More than 19 fatal accidents and 182 other accidents may be avoided (approximately 4% of 2011 published figure). Hence it is expected that there will be some improvement of the overall ambience of the city.

### 20.8 Transport Oriented Development (TOD) & EIRR

There will be generation (addition of extra trips) of Ridership on Metro due to Transport Oriented Development. Introduction of Modern Mass Transit System (Metro) will have an impact on city's landuse in near future. Values of land which are closer to the metro line will increase very quickly, commercial activities near station areas will increase and people will not hesitate to live in remote areas of





the city (but near to metro station). Due to presence of metro existing bus routes may change, some old routes may stop operation and some new routes may be introduced. A detail study will be needed to identify, quantify and to estimate economic impact of such likely changes. Detail discussion and evaluation is beyond the scope within this chapter. Nevertheless, it will be interesting to know, for 10% increase of ridership, increase in EIRR value will be 6.57%, and for 20% increase EIRR will increase by 9.96%, keeping other traffic inputs unchanged.

□□□□□

# CHAPTER 21

## IMPLEMENTATION STRATEGY



21.1	INTRODUCTION
21.2	INSTITUTIONAL ARRANGEMENT
21.3	PROPOSED IMPLEMENTATION MODEL
21.4	ORGANIZATION SET-UP OF CMRC
21.5	HIGH POWER COMMITTEE
21.6	LEGAL COVER FOR NAGPUR METRO RAIL PROJECT
21.7	CONCESSION FROM GOVERNMENT

### FIGURES

FIGURE 21.1	PROPOSED CMRC ORGANIZATION STRUCTURE
ANNEXURE	METRO RAIL (AMENDMENT ACT) 2009

**Chapter - 21****IMPLEMENTATION STRATEGY****21.1 INTRODUCTION**

Nagpur city is having huge number of two wheelers and modal split towards public transport is very low. An effective public transport mode in the form of metro is expected to provide a fast, reliable, convenient and economical mode of transport to the Nagpur citizens and also the public commuting to Nagpur. It will also help in growth of the city and area as well. To ensure that the project is implemented on priority basis i.e., the project has to go through fast and a visible positive support from Nagpur Improvement Trust (NIT), GoM and GoI. Hence, a carefully drawn up implementation strategy is necessary for ensuring efficient execution of the metro project.

**21.2 INSTITUTIONAL ARRANGEMENT**

To enable Nagpur metro project to be implemented without any loss of time and cost over-run, effective institutional arrangements would need to be set up. Presently, Nagpur Improvement Trust (NIT) is dealing with the Project but there is need to have an SPV responsible entirely for this project.

**21.2.1 Special Purpose Vehicle**

This SPV should be on the same line as DMRC and may be named as 'Nagpur Metro Rail Corporation Ltd.' (NMRC). Equity of NMRC will be contributed by GoM and GoI thus the Directors on its Board will be nominees of Government of Maharashtra and Government of India. In order to avoid delays usually associated with bureaucratic process of decision making, the Board of Directors (BOD) of NMRC should be vested with full powers needed to implement the project. The BOD, in turn, should delegate adequate powers to the Managing Director to take all decisions in day to day matters. The Managing Director should be a technical of proven record and impeccable integrity. A railway background would be an added advantage. A metro background would be most desirable.



### 21.2.2 Implementation models

Once the SPV is created, there are different models which can be adopted for implementing the Nagpur metro project. Three models have been analyzed below.

#### a) Implementation through Government

Under this model, the entire project development, implementation and operation is undertaken and financed by the government authority. Some recent examples of metro rail projects implemented directly through Government agencies are as under:

- Delhi
- Bangalore
- Chennai
- Jaipur
- Kolkata

#### b) Implementation through BOT model

BOT approach assumes that the metro is given to a private partner (Concessionaire) to develop and operate over the concession period. The private partner brings requisite funds and the efficiency of private sector management in the implementation as well as operation of the project. NMRC's role in this option is limited to that of a regulatory authority. Thus NMRC would monitor the implementation of the project such as laying down the passenger fares, targets for the minimum number of services to be run by the private partner, frequency, punctuality and reliability of these services, etc. There cannot be any compromise on this and penalties for not achieving these targets will be spelt out in advance. The private partner would assume substantial financial, technical and operational risk in the project and upon expiration of the concession period hand back the project to the government. There are only two projects namely Hyderabad and Mumbai being implemented through BOT model. The success of this model in India is still to be known.

#### c) Implementation through PPP model

It has been experienced that developing metro rail projects through PPP is a slow and time consuming process. Transferring ROW clearance, utility diversions and other site related encumbrance responsibilities to the private sector results in higher time runs. As a result, a new hybrid model has been tried in which the site development and civil construction work is managed by the government agency while the operations and management is done by the private sector.





organization during various phases of the system. All Functional Directors will be full time members of the Management Board. The Directors will be assisted by Heads of Departments in each of the major disciplines and they in turn will be assisted by the requisite support staff.

Implementing a metro project in a congested metropolis is indeed a challenge. In sheer size, magnitude and technical complexity there are few parallels to metro projects. Further, these projects are to be carried out in difficult urban environment without disturbing city life, while at the same time preserving the environment. The project involves integration of a number of complex technical systems. Some of the technologies used in these systems are new to the country.

Since NMRC may not have the required expertise and experienced manpower to check and monitor the private partner's work, it may be necessary to engage General Consultants from the very start of the metro project, who will do this job on behalf of NMRC. Generally Consultants fee is about 3-4% of the project cost. For any expert opinion on the technically difficult matters, NMRC may also need Prime Consultants whose fee is about 0.5 - 1% of project cost.

#### **21.6 HIGH POWER COMMITTEE**

During the implementation of the project, issues with regard to acquisition of land, diversion of utilities, shifting of structures falling on the project alignment etc. are likely to arise. For expeditious resolution of these problems, an institutional mechanism needs to be set up at the State Government level. Towards this end, it is recommended that a High Power Committee under the chairmanship of Chief Secretary, Govt. of Maharashtra should be set up. Other members of this Committee should be Secretaries of the concerned Departments of the State Government who will be connected in one way or the other with the implementation of the project. This Committee should meet once a month or more frequently if required and sort out all problems brought before it by NMRC.

#### **21.8 LEGAL COVER FOR NAGPUR METRO RAIL PROJECT**

Government of India has passed Legislation as 'The Metro Railways (Amendment) Act 2009' for implementation of metro rail in any metropolitan area and NCR. Copy of the Act is attached as Annexure. The implementation of metro in Nagpur urban complex may be taken up under the cover of above Act.



### 21.7 CONCESSIONS FROM GOVERNMENT

Metro rail projects require heavy capital outlay. Loans have to be taken to fund a part of the capital cost of the project. These projects yield low financial internal rate of return though their economic internal rate of return is very high. With reasonable fare level, servicing of these loans often pose problems. Therefore, to make the project financially viable, the fares will have to be substantially increased, but this will result in their reaching socially un-acceptable levels. This will result in the ridership coming down significantly, as it is sensitive to increase in the fare levels. Thus the very objective of constructing the metro rail system to provide an affordable mode of mass travel for public is defeated. It, therefore, becomes necessary to keep the initial capital cost of a metro project as low as possible so that the fare level of the metro system can be kept at reasonable level.

Taxes and duties constitute about 16 – 18% of a metro rail projects capital cost. Following are the taxes and duties, which have to be borne by a metro project:

- Custom Duty on all imported rolling stock and other equipment needed for the project.
- Excise Duty on all indigenously manufactured rolling stock and other indigenously finished goods required for the project.
- Sales Tax on all purchases made for implementation of the project whether directly by the project implementation authority or by the contractors executing the project.
- Sales Tax on works contracts to be executed for the implementation of the project.
- Tax on electricity required for operation and maintenance of the metro system.

It is recommended that GoI to pay the Central taxes to the extent of 50% in the form of Subordinate debt as being agreed for the metro projects being sanctioned by GoI and 50% of taxes to be borne by State Government.



## Annexure - Metro Rail (Amendment Act) 2005











	THE GOVERNMENT OF INDIA	
	<p>18.1. The Government of India shall offer their students access to quality education through the provision of the following facilities in the following manner as may be determined by the Government:</p>	
18.2.	<p>(a) The Government of India shall offer the following facilities to students:</p>	Section 18, clause 1
	<p>(i) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(ii) "Career Counselling", to assist students in their selection of a career;</p>	
	<p>(iii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(iv) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(v) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(vi) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(vii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(viii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(ix) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(x) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xi) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xiii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xiv) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xv) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xvi) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xvii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xviii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xix) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xx) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxi) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxiii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxiv) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxv) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxvi) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxvii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxviii) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxix) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxx) "Career Guidance", to assist students in their selection of a career;</p>	
	<p>(xxxi) "Career Guidance", to assist students in their selection of a career;</p>	



\*\*\*\*\*

## CHAPTER 22

CONCLUSIONS





## Chapter – 22

### CONCLUSIONS

- 22.1** Nagpur Municipal Corporation (NMC) had awarded the project titled "Preparation of Master Plan/Prospective Plan for Transportation System of Nagpur City 2031" to **L&T-Ramboll Consulting Engineers Limited in June 2007**. The study aimed to update the long-term transportation strategy for NMC and identify a profitable and effective investment programme up to 2031. Consultants commenced the Study in the month of June,2007 and completed in June,2008. L&T Ramboll Consulting Engineers Limited had carried out the Comprehensive Traffic and Transportation Study and prepared Transportation Master Plan for Nagpur city commissioned by NMC. In their report, L&T-Ramboll recommended the under mentioned Metro Corridors:

- Alignment-1: Field Mills to Dehagun ( 24.34 km with 25 Stations)
- Alignment-2: Automotive Square to Dehagun ( 23.94 km with 24 Stations)
- Alignment-3: Transport Plaza to Dehagun predominantly on NH-7 ( 27.2 km with 26 Stations)
- Alignment-4: Transport Plaza to Dehagun partially on NH-7 ( 24.2 km with 24 Stations).

DMRC however found that the corridors recommended by L&T-Ramboll were not required in totality but some portions were kept as part of either recommended Metro Corridors proposed in Detailed Project Report submitted in July-2013. The corridors recommended in July DPR were namely:

- 1) North-South Corridor(21.833 km),
- 2) East-West Corridor (18.288 km)

### 22.2 FURTHER DEVELOPMENT

On 03.08.2013, a meeting presided by Shri S K Laha, JS-MoU/D,GoI was held at Nagpur to discuss the DPR. In that meeting, JS-MoU/D,GoI expressed that the FIRR of the project



should be at least 8%. Recently, MOUD has also issued advisory that FIRR of Metro Project should not be below 8%.

On 13.10.2013, a presentation on the DPR was made by M/s NIT to The Chief Minister, Government of Maharashtra. He was of the opinion to avoid underground alignment in MHAN and also construct Maintenance Depot in the land belonging to State Govt Land. Subsequently, on 21.10.2013, a joint inspection of the NS corridor was done by YCS&C-MADC, Chairman-NIT, and Director Business Development-DMRC.

The original alignment of Corridor-I proposed was passing through Khama Road, Airport Area after Sahakar Nagar and finally was ending at MHAN. The alignment up to Old Airport Station was elevated, then for a length of 3.20 km, it was underground with one underground station named as New Airport Station and again elevated in MHAN Area. Since the cost of underground section of the alignment is much more than the elevated section or the section at grade, alternative alignment was suggested for cost reduction, enhancement in R&POT and to increase FIRR so that project becomes financially and economically viable.

The new proposed alignment suggested in the above inspection, was to pass through a 24m wide road adjacent to London Street after Sahkar Nagar Junction and was proposed to be taken to the east along 24m wide road and London Street up to Wartha Road. From the intersection at Wartha road, the elevated alignment was proposed to be on the central divider on the Wartha Road. After crossing existing intersection point of Wartha Road & Airport Road, the alignment was to be shifted to the MHAN area. Alignment in this portion was proposed to be at grade and to run parallel to Wartha road upto ROB and sharing railway line thereafter upto proposed Car depot.

But, while working on the modification of alignment, it was noticed that a very large number of properties were falling along the alignment due to sharp curve at the junction of Sahakar Nagar & 24 m wide road and also at the junction of 24m wide road & Wartha Road. Acquiring of these properties will be very tough and may delay the whole project.

Hence to avoid all such situation, it has been decided to take the alignment on Wartha Road only without going on Khama Road.

Finally, NS Corridor will pass through Wartha Road after Congress Nagar Metro Station. After crossing existing intersection point of Wartha Road & Airport Road, the alignment will be shifted to the MHAN area. Alignment in this portion will be at grade and will run parallel to Wartha road upto ROB and parallel to railway line thereafter upto proposed Car depot. 5km wide stretch of land between the railway boundary line and the road near proposed Container Depot of Container Corporation of India Ltd. will be affected by the proposed alignment of the Metro Rail as the proposed alignment passes through this stretch of land.



7) Ho land is available on the west side of railway line and south of existing flyover near Khazan station. Average width of this land is about 80m and is about 1600m long. This MADC land may be utilized for Car Depot. Similarly, Depot of SW Corridor has also been allotted to SRP Land near proposed Lokmanya Nagar Metro Station.

This has caused station of few earlier proposed metro stations on NS Corridor and station of new stations on the same.

## 22.3 FINAL ALIGNMENT

Final alignment for both the corridors is as below.

Table 22.1 FINAL ALIGNMENT

Alignment	Detail Route
<b>Alignment-1</b> North-South Corridor (13.855 km, 17 Stations)	Admitted Square, along Kanchas Road, Wacha Road, Variety Square to Achyankar Road, along Nag River alignment will fall on Humpard Road, Ranote Colony Road, Wacha Road, Parallel to Railway Line, Khobli Station and finally in MHAFI Area near corridor depot
<b>Alignment-2</b> East - West Corridor (18.557 km, 19 Stations)	From Puzgal Nagar, along Centre Avenue Road, Railway Feeder Road, Mura Chowk, Jhand Ranao Chowk, North Ambaghar Road, Hingra Road, Lokmanya Nagar

- 22.4 From the Traffic Densities Forecast it can be seen that peak hour peak direction flow (PHPDF) on the North-South Corridor is 9085, 1936, 12634 and 11726 the year of 2016, 2021, 2031 and 2041 respectively. Similarly PHPDF on East-West corridor in the year of 2016, 2021, 2031 and 2041 is 7745, 8460, 9006 and 11882 respectively.

Real-based systems can optimally carry up to a maximum of 8,000 PHPDF. Since the PHPDF arrived on the above corridors exceed 8,000, there can be two options namely 1) Mono Rail and 2) Light Capacity Metro. Mono rail can carry the PHPDF projected but this technology is not a tested one. The operation and maintenance cost is much higher than that of Light metro. The capital cost of Mono rail is also almost same as that of Light Metro. Even in the other countries, the Mono rail is being adopted only for small lengths and as feeder to Metro. Hence, keeping in view the above disadvantages, it is recommended to adopt an stable, tested and reliable Metro technology. However, for Nagpur it will be Light Capacity Metro System.





- 22.6 After examining the various options for execution of Nagpur Metro Rail Project, it is recommended that the project be implemented through government funding through an SPV duly formed namely 'NMRC'. This SPV will be responsible for implementation and further operation, maintenance of Metro Network. NMRC will also examine the expansion of Metro Network further in the city and nearby urban areas.
- 22.8 Apart from nearby areas of Khasra (MIMM) and Nagpur Airport, Nagpur also has scope for property development as along the corridor. These areas will get boost in development once the implementation of Metro is taken up. The policy of bringing the cost increased cost of the land along the corridor to metro project, to be evolved. City Authorities should also create 'City Urban Transport Fund' for financing transport related Infrastructure Development.
- 22.7 For successful implementation of any metro project, which by its very nature is highly technical and complex and requires huge capital investment, there should be a political will and commitment. The decision making process has to be fast and the implementing agency must have the required work culture, commitment to targets, commitments to safety, quality and cost consciousness. Any time overrun will have adverse consequences by way of serious cost overruns.
- 22.8 To avoid delays in processing the clearance for the Project, it is suggested that immediately on receipt of the DPR, NIT should take the State Government's approval for the project.
- 22.9 SPV should be set up for Nagpur Metro and registered under the Companies Act, 1956. This SPV should be a PSU of GoM and GoI with its name as NMRC as suggested earlier.
- 22.10 After the approval of State Government, DPR to be sent to the Secretary, Ministry of Urban Development, Government of India, seeking GOI of the State Government's intention to take up the Project on government funding basis and requesting for the orders 'In Principle' clearance to go ahead with the Project.
- 22.11 Since NMRC will not have the required expertise to take forward the project, it is recommended that NMRC may engage Interim Consultants after getting in-principle approval of Ministry of Urban Development. Interim Consultants will transfer the alignment on ground, prepare land plans with the help of local authorities and also engage General Consultants for further implementation of project. To keep a check on the work of the General Consultants and to ensure that the Metro is being constructed in strict the appropriate specifications and safety standards, the SPV may also need to engage the services of Prime Consultants who will keep over-all watch over the execution of the project.

## APPENDIX-1



**APPROVAL BY GOVT. OF MAHARASHTRA WITH SPV  
MODAL FUNDING PATTERN (WITH MODIFICATION)**

**Nagpur Improvement Trust,**  
Station Road, Nadi, Nagpur

No. L.14000001/156

Nagpur, dated 24/11/2014

To,

Dear Mr. Subraman,  
Executive Engineer,  
IMRC,

**Subject: Approval of Copies of DTR of Nagpur Metro Rail Project.**

This is to inform you that Nagpur Metro Rail project is approved by cabinet of Government of Maharashtra on 26/01/2014. The final sharing of the project approved under SPV mode by the cabinet is per Annexure enclosed. You are requested to advise make the change in the DPR or endorse the change as an Addendum with the DPR. Also as per direction of State Government a total number of 30 copies (25 copies for Government of India and 5 Copies for Government of Maharashtra) is required. You are requested to get the same placed immediately as the same is to be forwarded to Government of India within two days.

Trusting you.

**Enclosure: As above.**

Executive Engineer (Project),  
Nagpur Improvement Trust,  
Nagpur.

**LETTER FROM NAGPUR IMPROVEMENT TRUST ABOUT  
APPROVAL BY GOVT. OF MAHARASHTRA**



Amount in

Particulars	With Taxes & Duties	
	Amount (Rs Crores)	% of contribution
Funding by GOI	172.00	20%
Contrib by OCM	1,02.00	20%
Major Improvement Fund Contribution	43.00	5%
Major Municipal Corporation Contribution	41.00	5%
SCA Loan @ 1.40% P.A Market Borrowing @ 12%	632.00	65%
<b>Total</b>	<b>860.00</b>	<b>100.00%</b>

**SPV MOBIL FUNDING PATTERN  
(WITH MODIFICATION)**